

N83447.AR.000638  
NAS FORT WORTH  
5090.3a

FINAL SITE INVESTIGATION FOR AREA OF CONCERN 19 WITH ATTACHED RESPONSE  
TO COMMENTS NAS FORT WORTH TX  
4/1/2002  
HYDROGEOLOGIC



**NAVAL AIR STATION  
FORT WORTH JRB  
CARSWELL FIELD  
TEXAS**

---

**ADMINISTRATIVE RECORD  
COVER SHEET**

AR File Number 724

**FINAL  
SITE INVESTIGATION REPORT  
AREA OF CONCERN 19  
NAS FORT WORTH JRB, TEXAS**



Prepared for

U.S. Air Force Center for Environmental Excellence  
Brooks AFB, Texas

Contract Number F41624-95-D-8005

Prepared by

HydroGeoLogic, Inc.  
1155 Herndon Parkway, Suite 900  
Herndon, VA 20170

April 2002

*This page was intentionally left blank.*





DEPARTMENT OF THE AIR FORCE  
HEADQUARTERS AIR FORCE CENTER FOR ENVIRONMENTAL EXCELLENCE  
BROOKS AIR FORCE BASE TEXAS


724

3

30 April, 2002

MEMORANDUM FOR RAY RISNER (TNRCC)

FROM: HQ AFCEE/ERD  
3207 Sidney Brooks  
Brooks AFB, TX 78235-5344



SUBJECT: Naval Air Station Joint Reserve Base  
Formerly Carswell AFB  
TNRCC Solid Waste Registration No. 65004  
TNRCC Hazardous Waste Permit No. HW-50289  
EPA ID No. TX0571924042  
Final Site Investigation Report, AOC 19

Dear Mr. Risner,

Two copies (one original and one copy) of the Final Site Investigation Report requesting closure of Area of Concern 19 are enclosed for your review per the TNRCC RCRA permit No. HW-50289 for NAS Fort Worth JRB. Additional copies of the Final Report are also being sent to the TNRCC Region 4 Office and to EPA Region 6.

Should you have any questions regarding this letter, please contact me at (210) 536-5290.

Sincerely,

Michael R. Dodyk, P.E.  
Restoration Team Chief  
NAS Fort Worth JRB



Printed on Recycled Paper

cc:

EPA Region VI  
Mr. Gary W. Miller  
1445 Ross Avenue, Suite 1200  
Dallas, TX 75202-2733

TNRCC Region 4 Office  
Mr. Sam Barrett, Waste Program Manager  
1101 East Arkansas Lane  
Arlington, TX 76010

TNRCC Region 4 Office (letter only)  
Mr. Tim Sewell  
1101 East Arkansas Lane  
Arlington, TX 76010

HQ AFCEE/ERD  
Mr. Don Ficklen  
3207 Sidney Brooks  
Brooks AFB, TX 78235-5344

Booz-Allen & Hamilton  
Ms. Audrie Medina  
300 Convent Street, Suite 1250  
San Antonio, TX 78205

**RESPONSES TO REVIEW COMMENTS  
DRAFT SITE INVESTIGATION REPORT  
AREA OF CONCERN 19, NAVAL AIR STATION  
JOINT RESERVE BASE, FORT WORTH, TEXAS**

**Comment 1**      *Page 1-1, Section 1.0, 2<sup>nd</sup> sentence. Please insert “as a voluntary action by the Air Force and was” after “The SI was conducted.”*

**Response**      **This change has been made as requested.**

**Comment 2**      *Page 1-3, Section 1.3, 4<sup>th</sup> paragraph, 4<sup>th</sup> sentence. Please explain the source(s) of the “existing medium specific concentrations (MSCs).”*

**Response**      **The sentence has been revised to read: “All analyte concentrations above the applicable RRS 1 value were compared to the applicable RRS 2 values, which are the medium-specific concentrations (MSCs) presented in 30 TAC §335.368. Those concentrations above RRS 2 pose a potential threat to shallow groundwater.”**

**Comment 3**      *Page 1-3, Section 1.3, 5<sup>th</sup> paragraph, 1<sup>st</sup> sentence. Please use either “Standard 2” or “RRS 2” consistently throughout the document.*

**Response**      **The explanation of RRS 1, RRS 2, Standard 1, Standard 2, and Standard 3 has been expanded in Section 1.3, and the document has been reviewed to ensure that the use of these terms is correct and consistent.**

**Comment 4**      *Page 1-4, Section 1.3, Please consider presenting the last two sentences in Section 4.0.*

**Response**      **The following text has been added as the 6<sup>th</sup> sentence of the 4<sup>th</sup> paragraph on page 1-3: “In some cases, a site-specific soil MSC was developed for an analyte by performing the synthetic precipitation leaching procedure (SPLP) and comparing the analytical results of the leachate to the applicable groundwater MSC (see Section 4.0).”**

- Comment 5**      *Page N/A, Section Figure 1.2. Please clearly indicate that the portion of solid waste management unit (SWMU) 25 that is across Perimeter Road is a part of SWMU 25. Also, include SWMU numbers for all SWMUs shown on the figure.*
- Response**      **Both portions of SWMU 25 have been indicated on the figure, and all SWMUs and AOCs shown on this figure have been identified.**
- Comment 6**      *Page N/A, Section Figure 2.1. Please add a legend to the figure that explains the various shadings on the drawing.*
- Response**      **The shading on this figure has been reproduced from the original USGS topological map; therefore, no change has been made.**
- Comment 7**      *Page 3-3, Section 3.4.1. Please change “Volatile” to “volatile” and “Semivolatile” to “semivolatile” here and throughout the document.*
- Response**      **The capitalization of these words has been corrected.**
- Comment 8**      *Page 3-4, Section 3.4.2.3. It is recommended that the section be reviewed for discrepancies in the total number of Phase II borings and monitoring wells.*
- Response**      **This section has been reviewed and discrepancies have been corrected. This section has also been revised to improve clarity.**
- Comment 9**      *Page 3-4, Section 3.4.2.3. 1<sup>st</sup> paragraph, 2<sup>nd</sup> sentence. Please reword the sentence for clarity.*
- Response**      **This sentence (as well as several subsequent sentences) has been revised for clarity.**
- Comment 10**      *Page 3-4, Section 3.4.2.3. 1<sup>st</sup> paragraph, 3<sup>rd</sup> sentence. Please indicate whether the Work Plan was revised to reflect the expanded scope of work and, if not, indicate whether AFCEE approval was obtained for the increased scope.*

- Response**                    The original Work Plan Addendum was not revised. The report text has been edited to indicate that the additional field work was performed after consultation with AFCEE and with AFCEE's concurrence.
- Comment 11**                *Page 3-4, Section N/A. Footnote 4 at the bottom of the page. Please insert "low TCE readings in" between "on" and "the."*
- Response**                    This footnote has been revised to include this information.
- Comment 12**                *Page 3-5, Section 3.4.2.3. 4<sup>th</sup> bullet. Please change "SW7471" to "SW7471A" and change "Amercury" to "mercury."*
- Response**                    This change has been made as requested.
- Comment 13**                *Page 3-5, 3.4.2.3, 1<sup>st</sup> paragraph on the page, 5<sup>th</sup> sentence. Please insert "analysis of" between "of" and "the."*
- Response**                    The text has been changed to read "Based on the analytical results of the sample collected from ..."
- Comment 14**                *Page 3-6, Section 3.4.2.3. 2<sup>nd</sup> paragraph on the page, 2<sup>nd</sup> sentence. Please rewrite the beginning of the sentence to read "A sample was collected from boring BHGLAOC1907 in August 2001."*
- Response**                    This sentence has been divided into two sentences that now read "One of the twelve Phase II borings, BHGLAOC1907, was advanced for confirmation purposes. The 10-foot interval of this confirmation boring was sampled in August 2001 in order to confirm a TCE detection in the 10-foot interval of BHGLAOC1901."
- Comment 15**                *Page 3-6, Section 3.4.2.4. 1<sup>st</sup> paragraph, 2<sup>nd</sup> sentence. Please show the piles of golf course construction debris on Figure 3.1.*
- Response**                    The debris pile is now shown on Figure 3.1.
- Comment 16**                *Page N/A, Figure 3.1. Please crosshatch the area that is part of both AOC 19 and SWMU 25 (also pertains to other figures). Please indicate that the blue hash marks indicate an aqueduct.*

**Response** SWMU 25 is now indicated by cross-hatching in the manner similar to that of Figure 6.1. Both figure legends now show that the hash marks indicate an underground aqueduct.

**Comment 17** *Page 4-1, Section 4.0. 2<sup>nd</sup> paragraph, 1<sup>st</sup> sentence. Please insert a comma after “previously.”*

**Response** This change has been made as requested.

**Comment 18** *Page 4-1, Section 4.0. 2<sup>nd</sup> paragraph, 3<sup>rd</sup> sentence. Please consider revising the sentence to read “Furthermore, all analytical results exceeding RRS 1 levels were compared to available MSCs.”*

**Response** This change has been made as requested.

**Comment 19** *Page 4-1, Section 4.0. 3<sup>rd</sup> paragraph, 1<sup>st</sup> sentence. Please consider revising this sentence if synthetic precipitation leaching procedure (SPLP) analysis was run on any samples for which there was no existing MSC.*

**Response** Standard 2 detections of analytes for which there are no RRS 2 values did not trigger SPLP extraction and analysis. No changes have been made.

**Comment 20** *Page 4-1, Section 4.1. 1<sup>st</sup> paragraph, last sentence. Please include the date that the RCRA Facility Investigation (RFI) was conducted at SWMU 25/Landfill 8.*

**Response** The dates of RFI activities conducted at SWMU 25/Landfill 8 have been added to footnote 6 on page 4-1.

**Comment 21** *Page 4-2, Section 4.1. 1<sup>st</sup> paragraph, 2<sup>nd</sup> sentence. Please include the waste manifest for the metal debris, if available, as an Appendix.*

**Response** No manifests were generated for this debris. The report has been revised to indicate that the metal debris was determined to be non-hazardous.

**Comment 22**      *Page 4-3, Section 4.1. 2<sup>nd</sup> paragraph on the page, last sentence. Please replace “native soil” with “the excavated soil.”*

**Response**      **This change has been made as requested.**

**Comment 23**      *Page 4-4, Section 4.2. 1<sup>st</sup> paragraph, 1<sup>st</sup> sentence. Please reference Figure 4.1 at the end of the sentence.*

**Response**      **This change has been made as requested.**

**Comment 24**      *Page 4-4, Section 4.2. 1<sup>st</sup> paragraph, 3<sup>rd</sup> sentence. Please locate the bermed area on the Figure 4.1.*

**Response**      **This change has been made as requested.**

**Comment 25**      *Page 4-4, Section 4.2. 1<sup>st</sup> paragraph, last sentence. Please indicate the contaminants for which delineation is necessary.*

**Response**      **The identification of contaminants for which delineation was necessary is a principal topic of Section 3.4.2.3, and this section is now referenced in Section 4.2.**

**Comment 26**      *Page 4-7, Section 4.4. 2<sup>nd</sup> paragraph on the page, 2<sup>nd</sup> sentence. Please spell out the acronym “MDL” and include it in the “Acronyms” section.*

**Response**      **The phrase “above the MDL” is redundant and has been removed from this sentence.**

**Comment 27**      *Page 4-11, Table 4.2. Please define “GW-Ind” in the “Notes” section below the table.*

**Response**      **This change has been made as requested.**

**Comment 28**      *Page 4-12, Table 4.3. Please globally (for all tables) remove the term “analyzed for , but” from the “Notes” section.*

**Response**      **This change has been made as requested.**

**Comment 29**      *Page 4-16, Table 4.4. Please remove the “2” following “NA= not analyzed.” Also, please use capitalization consistently in the “Notes” sections of the tables (e.g., text following “NA” begins with a lowercase letter, but text following “F” begins with an uppercase letter).*

**Response**      **This change has been made as requested. The table notes have been edited for consistency.**

**Comment 30**      *Page N/A, Figure 4.1. Please label Perimeter Road in the figure.*

**Response**      **This change has been made as requested.**

**Comment 31**      *Page N/A, Figure 4.3. Please describe the metal object in the right pictures in the appropriate section of the text.*

**Response**      **The text (page 4-2, third paragraph) describing the anomaly at THGLAOC1902 has been revised to include both metal objects shown in Figure 4.3.**

**Comment 32**      *Page N/A, Figure 4.8. Please consider indicating the extent of contamination delineation. Also, the legend points out that yellow shading indicates “proposed samples,” but there are no proposed samples. Please clarify.*

**Response**      **The text “proposed samples and” has been removed from the key for yellow headers. The extent of delineation for VOCs and SVOCs are depicted as the metes and bounds shown in Figure 6.1, and have not been placed on Figure 4.8.**

**Comment 33**      *Page 5-1, Section 5.3. Please reference Figure 4.8 in this section.*

**Response**      **This change has been made as requested.**

**Comment 34**      *Page 6-1, Section 6.0. 2<sup>nd</sup> paragraph, 1<sup>st</sup> sentence. Please insert “activities at” between “that” and “AOC 19.”*

**Response**      **This change has been made as requested, with the addition of the word “former” before “activities”.**



**Comment 35** *Page 6-1, Section 6.0. 2<sup>nd</sup> paragraph, 2<sup>nd</sup> sentence. Please insert “and delineated” between “identified” and “at.”*

**Response** **An additional sentence was added after the referenced sentence: “The SVOCs in this section of the site have been delineated.”**

**Comment 36** *Page 6-1, Section 6.0. 4<sup>th</sup> paragraph, 2<sup>nd</sup> sentence. Please insert a comma after the word “language.”*

**Response** **This change has been made as requested.**

**Comment 37** *Page N/A, Appendix E. The “Notes” sections of the tables contain a description of a “UJ” flag, but it does not appear that the “UJ” flag is used in the table. Typically, a result will be flagged as “U” or “J,” but not both. Please clarify.*

**Response** **UJ qualifiers are used in association with some AOC 19 data per the approved QAPP (e.g., the antimony result for BHGLAOC1903 00 ft on page E1-15). The definitions of data qualifiers in Appendix E have been edited for accuracy and clarity.**

**Comment 38** *Page N/A, Appendix H. Please ensure that the metes and bounds legal description is included in the next version of this report. Make the signature for Michael Dodyk, keeping the same address for AFCEE. Please change the date portion of the signature blocks to “2002.”*

**Response** **The legal description for metes and bounds at AOC 19 has been added to this report. The other changes have been made as requested.**

<b>REPORT DOCUMENTATION PAGE</b>			Form Approved	
QMB No 0704-0188				
Public reporting for this collection of information is estimated to average 1 hour per response, including the time for reviewing instruction, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1024, Arlington, VA 22202-1302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503				
1 AGENCY USE ONLY (Leave blank)		2 REPORT DATE  April 2002		3 REPORT TYPE AND DATES COVERED  Final
4 TITLE AND SUBTITLE  Final Site Investigation Report Area of Concern 19 NAS Fort Worth JRB, Texas			4 FUNDING NUMBERS  F41624-95-D-8005 Delivery Order 0026	
6 AUTHOR(S) HydroGeoLogic, Inc				
7 PERFORMANCE ORGANIZATION NAME(S) AND ADDRESS(S)  HydroGeoLogic, Inc. 1155 Herndon Parkway, Suite 900 Herndon, VA 20170			8 PERFORMANCE ORGANIZATION REPORT NUMBER  AFC001	
9 SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(S)  AFCEE/ERD Brooks AFB, Texas 78235-5328			10 SPONSORING/MONITORING AGENCY REPORT NUMBER  CDRL No. A007	
11 SUPPLEMENTARY NOTES				
12a DISTRIBUTION/AVAILABILITY STATEMENT  Unlimited			12b DISTRIBUTION CODE	
13 ABSTRACT (Maximum 200 words)  This document presents the Final Site Investigation (SI) Report for Area of Concern 19 located at the Naval Air Station Fort Worth Joint Reserve Base, Texas. Field observations and analytical results included in this SI Report indicate that there is some evidence that a release has occurred to the environment of hazardous constituents listed in 40 Code of Regulation Part 264, Appendix IX at AOC 19; however, analytical results indicate that this release poses no threat to human health or the environment. Based on this information, no further action is warranted, and the site is recommended for closure under Texas Natural Resources Conservation Commission Risk Reduction Standard 2.				
14 SUBJECT TERMS			15 NUMBER OF PAGES	
			16 PRICE CODE	
17 SECURITY CLASSIFICATION OF REPORT  Unclassified	18 SECURITY CLASSIFICATION OF THIS PAGE  Unclassified	18 SECURITY CLASSIFICATION OF ABSTRACT  Unclassified	20 LIMITATION OF ABSTRACT  Unlimited	

*This page was intentionally left blank.*

## PREFACE

This document contains the Final Site Investigation (SI) Report for area of concern (AOC) 19 at the Naval Air Station (NAS) Fort Worth Joint Reserve Base (JRB), Texas.

HydroGeoLogic, Inc. (HydroGeoLogic) prepared this report under contract to the U.S. Air Force (USAF) Center for Environmental Excellence (AFCEE), Contract No. F41624-95-D-8005, Delivery Order No. 0026, in support of the Air Force Installation Restoration Program (IRP).

Responsible key HydroGeoLogic personnel are as follows:

James P. Costello, P.G.	Program Manager
Miquette E. Rochford, P.G.	Deputy Program Manager / Project Manager

This contract will be administered by the Defense Contract Management Command (DCMC), 10500 Battleview Parkway, Suite 200, Manassas, Virginia 22110. The Contracting Officer is Mr. David Miller. The Contracting Officer's Representative is Mr. Don Ficklen (210/536-5290), representing the AFCEE Environmental Restoration Division (ERD), located at Headquarters AFCEE, 3207 Sidney Brooks, Brooks Air Force Base (AFB), Texas 78235-5363.

*This page was intentionally left blank.*

## TABLE OF CONTENTS

		Page
1.0	INTRODUCTION.....	1-1
1.1	PROJECT BACKGROUND .....	1-1
1.2	SITE IDENTIFICATION AND DESCRIPTION .....	1-2
1.3	REGULATORY REQUIREMENTS .....	1-3
1.4	INVESTIGATION STRATEGY .....	1-4
1.5	DATA QUALITY OBJECTIVES .....	1-5
1.6	REPORT ORGANIZATION .....	1-6
2.0	SUMMARY OF EXISTING INFORMATION .....	2-1
2.1	INSTALLATION ENVIRONMENTAL SETTING .....	2-1
2.1.1	Physiographic Province .....	2-1
2.1.2	Regional Geology .....	2-1
2.1.3	Groundwater .....	2-1
2.1.3.1	Alluvial Terrace Deposits .....	2-2
2.1.3.2	Goodland/Walnut Aquitard.....	2-2
2.1.3.3	Paluxy Aquifer .....	2-3
2.1.3.4	Glen Rose Aquitard.....	2-3
2.1.3.5	Twin Mountains Aquifer .....	2-4
2.1.3.6	Water Well Survey Results.....	2-4
2.1.4	Surface Water .....	2-4
2.1.5	Climate .....	2-5
2.1.6	Biology .....	2-6
2.1.7	Demographics .....	2-6
2.1.7.1	Regional Demographics .....	2-6
2.1.7.2	Site-Specific Demographics.....	2-7
2.2	SITE-SPECIFIC ENVIRONMENTAL SETTING .....	2-7
2.2.1	Site-Specific Soils .....	2-7
2.2.2	Site-Specific Geology .....	2-8
3.0	SUMMARY OF INVESTIGATION ACTIVITIES .....	3-1
3.1	SWMU 25 RCRA FACILITY INVESTIGATION .....	3-1
3.2	BASEWIDE TCE PLUME .....	3-1
3.3	SITE RECONNAISSANCE AND UTILITY CLEARANCE .....	3-2
3.4	AOC 19 SITE INVESTIGATION ACTIVITIES .....	3-2
3.4.1	Phase I - Site Investigation Activities .....	3-2
3.4.2	Phase II - Site Investigation Activities .....	3-3
3.4.2.1	Geophysical Survey .....	3-3
3.4.2.2	Exploratory Excavations.....	3-4
3.4.2.3	Soil Boring Installation/Soil Characterization.....	3-4

## TABLE OF CONTENTS (continued)

	Page
3.4.2.4 Monitoring Well Installation/Groundwater Characterization .....	3-6
3.5 ELEVATION AND LOCATION SURVEY .....	3-7
4.0 INVESTIGATION RESULTS .....	4-1
4.1 GEOPHYSICAL AND EXPLORATORY EXCAVATION FINDINGS.....	4-1
4.2 LITHOLOGIC FINDINGS .....	4-4
4.3 SURFACE SOIL DETECTIONS .....	4-6
4.3.1 Inorganic Constituents .....	4-6
4.3.2 Organic Constituents.....	4-6
4.4 SUBSURFACE SOIL DETECTIONS.....	4-6
4.4.1 Inorganic Constituents .....	4-7
4.4.2 Organic Constituents.....	4-7
4.5 GROUNDWATER DETECTIONS .....	4-8
5.0 DISCUSSION OF ANALYTICAL RESULTS .....	5-1
5.1 GEOPHYSICAL SURVEY .....	5-1
5.2 SURFACE SOIL .....	5-1
5.3 SUBSURFACE SOIL.....	5-1
5.3.1 Inorganic Constituents.....	5-1
5.3.2 Organic Constituents.....	5-2
5.4 GROUNDWATER.....	5-3
6.0 CONCLUSIONS .....	6-1
7.0 REFERENCES .....	7-1
APPENDIX A	AREAS OF CONCERN 17, 18, AND 19 IDENTIFICATION LETTER
APPENDIX B	DATA QUALITY ASSESSMENT
APPENDIX C	GEOPHYSICAL SURVEY REPORT
APPENDIX D	SURVEY DATA
APPENDIX E	ANALYTICAL DATA SUMMARY TABLES
APPENDIX F	FIELD FORMS
APPENDIX G	DATA VALIDATION REPORTS
APPENDIX H	METES AND BOUNDS

## LIST OF TABLES

---

Table 4.1	Excavation Results—AOC 19—NAS Fort Worth JRB, Texas
Table 4.2	Site-Specific MSCs—AOC 19—NAS Fort Worth JRB, Texas
Table 4.3	Surface Soil Detections—AOC 19—NAS Fort Worth JRB, Texas
Table 4.4	Subsurface Soil Detections—AOC 19—NAS Fort Worth JRB, Texas
Table 4.5	Groundwater Sampling Results—AOC 19—NAS Fort Worth JRB, Texas

## LIST OF FIGURES

---

Figure 1.1	Location of AOC 19—NAS Fort Worth JRB, Texas
Figure 1.2	Historic Location of AOC 19—Suspected Former Fire Training Area B—December 3, 1958
Figure 1.3	Photos and Location Map—AOC 19—Suspected Former Fire Training Area B
Figure 2.1	Lake Worth Topographic Map
Figure 2.2	Generalized Geologic Cross Section of NAS Fort Worth JRB, Texas
Figure 2.3	Areal Distribution of Geologic Units of NAS Fort Worth JRB, Texas
Figure 2.4	Cross Section Location Map
Figure 2.5	Cross Sections A-A', A'-A'', and A'-A'''
Figure 2.6	Cross Section B-B'
Figure 2.7	Cross Section B'-B''
Figure 2.8	Stratigraphic Column Correlating Hydrogeologic and Geologic Units
Figure 2.9	Water Level Elevations, Terrace Alluvium, April 2001
Figure 2.10	Water Level Elevations, Terrace Alluvium, October 2001
Figure 2.11	Water Well Receptor Survey Within 1 Mile of NAS Fort Worth JRB
Figure 2.12	Soil Association Map, NAS Fort Worth JRB, Texas
Figure 3.1	Site Map and Sampling Locations—AOC 19—Suspected Former Fire Training Area B
Figure 3.2	Trichloroethene Concentrations, Terrace Alluvium, April 1 through July 2001
Figure 4.1	Geophysical Results and Excavation Locations—AOC 19—Suspected Former Fire Training Area B
Figure 4.2	Photo and Exploratory Excavation Dimensions—THGLAOC1901
Figure 4.3	Photos and Exploratory Excavation Dimensions—THGLAOC1902
Figure 4.4	Photos and Exploratory Excavation Dimensions—THGLAOC1903
Figure 4.5	Photos and Exploratory Excavation Dimensions—THGLAOC1904
Figure 4.6	Photos and Exploratory Excavation Dimensions—THGLAOC1905
Figure 4.7	AOC 19 Lithologic Cross Section—A-A' and B-B'
Figure 4.8	Analyte Concentrations in Soil Above RRS 1—AOC 19—Suspected Former Fire Training Area B



**LIST OF FIGURES (continued)**

- 
- Figure 4.9     Analyte Concentrations in Groundwater Above RRS 1—AOC 19—Suspected Former Fire Training Area B
- Figure 6.1     Proposed Area for RRS 2 Closure—AOC 19—Suspected Former Fire Training Area B

## LIST OF ACRONYMS AND ABBREVIATIONS

---

AFB	Air Force Base
AFCEE	U.S. Air Force Center for Environmental Excellence
AFP 4	Air Force Plant 4
AGE	aerospace ground equipment
AOC	area of concern
ASTM	American Society for Testing and Materials
bgs	below ground surface
BTEX	benzene, toluene, ethylbenzene, and xylenes
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	Code of Federal Regulations
COPCs	contaminants of potential concern
cm/sec	centimeters per second
DCMC	Defense Contract Management Command
DPT	direct push technology
DQE	data quality evaluation
EDD	electronic data deliverable
EM	electromagnetic
ERA	Environmental Restoration Account
ERD	Environmental Restoration Division
ERPIMS	Environmental Resources Program Information Management System
ESE	Environmental Science and Engineering, Inc.
ft/d	feet per day
°F	degrees Fahrenheit
gpd/ft <sup>2</sup>	gallons per day per square foot
GSAP	Groundwater Sampling and Analysis Program
HSA	hollow stem auger
HW	hazardous waste
HydroGeoLogic	HydroGeoLogic, Inc.
IRA	Interim Remedial Action
IRP	Installation Restoration Program
IT	International Technologies Corporation

---

## LIST OF ACRONYMS AND ABBREVIATIONS (continued)

---

JRB	Joint Reserve Base
LCS	laboratory control sample
mg/kg	milligrams per kilogram
MQL	method quantitation limit
MSC	medium-specific concentration
MS/MSD	matrix spike/matrix spike duplicate
NAS	Naval Air Station
NFA	no further action
NGVD	National Geodetic Vertical Datum
NPDES	National Pollution Discharge Elimination System
NPL	National Priority List
OVM	organic vapor monitor
OVS	oil/water separator
PAH	polynuclear aromatic hydrocarbon
QAPP	quality assurance project plan
QA	quality assurance
QC	quality control
RCRA	Resource Conservation and Recovery Act
RFI	RCRA Facility Investigation
RRS	risk reduction standard
SDG	sample delivery group
SI	Site Investigation
SPLP	synthetic precipitation leaching procedure
SVOC	semivolatile organic compound
SWMU	solid waste management unit
TAC	Texas Administrative Code
TCE	trichloroethene
TNRCC	Texas Natural Resource Conservation Commission
TWC	Texas Water Commission
USAF	U.S. Air Force
USEPA	U.S. Environmental Protection Agency
USGS	U.S. Geological Survey

---

**LIST OF ACRONYMS AND ABBREVIATIONS (continued)**

---

VOC	volatile organic compound
WP	Work Plan
WPA	Work Plan Addendum

*This page was intentionally left blank.*

# TAB

*SECTION 1.0*

---

**FINAL  
SITE INVESTIGATION REPORT  
AREA OF CONCERN 19  
NAS FORT WORTH JRB, TEXAS**

## **1.0 INTRODUCTION**

The Air Force Center for Environmental Excellence (AFCEE) contracted HydroGeoLogic, Inc. (HydroGeoLogic) to perform a Site Investigation (SI) at Area of Concern (AOC) 19 located at Naval Air Station (NAS) Fort Worth Joint Reserve Base (JRB), Texas (formerly Carswell Air Force Base [AFB]). This SI was conducted as a voluntary action by the Air Force and was based on historic aerial photographic evidence that suggested that possible fire training activities had occurred at this location. The investigation was conducted under the auspices of, but not at the request of, the Texas Natural Resource Conservation Commission (TNRCC) to determine whether any hazardous constituents had been released into the environment from AOC 19. The first phase of the SI field work was conducted in May 2000. Based on the results of the Phase I investigation, further investigation at AOC 19 was necessary. The second phase of the SI was conducted in 2001. The results of field investigation activities at AOC 19 revealed some evidence of release to soils at AOC 19; however analytical results indicate that this release poses no threat to human health or the environment. Based on this information, no further action (NFA) is warranted and AOC 19 is recommended for closure under TNRCC Risk Reduction Standard 2 (RRS 2) (30 Texas Administrative Code [TAC] 335.554).

### **1.1 PROJECT BACKGROUND**

Carswell AFB was officially closed on September 30, 1993. A significant portion of the former base, now known as NAS Fort Worth JRB, has been transferred from the U.S. Air Force (USAF) to U.S. Navy management. Before complete property transfer can be accomplished, required environmental investigations of potential contamination related to USAF activities occurring prior to September 30, 1993 on NAS Fort Worth JRB property are to be completed, and contaminated sites remediated.

On February 7, 1991, the former Carswell AFB (NAS Fort Worth JRB) was issued a Resource Conservation and Recovery Act (RCRA) hazardous waste (HW) permit (HW-50289) by the Texas Water Commission (TWC). This permit requires a RCRA Facilities Investigation (RFI) of all solid waste management units (SWMUs) and AOCs listed in Permit Provision VIII, as well as those SWMUs and AOCs subsequently added to the list, in order to determine if any of the hazardous constituents listed in 40 Code of Federal Regulations (CFR) Part 264, Appendix IX have been released into the environment.

In accordance with permit HW-50289, an RFI/SI was conducted at four SWMUs and three AOCs at NAS Fort Worth JRB in May 2000 (HydroGeoLogic, 2000a). The SWMUs and AOCs included in the RFI/SI served mainly as fire training areas, suspected former landfills, and a storm water drainage system. The AOCs included in the SI are not listed in permit HW-50289, nor were they added at a later date. The SI was performed as a proactive measure under the initiative and direction of AFCEE.

The initial phase of the RFI/SI was conducted at the subject SWMUs and AOCs during May 2000, in an effort to obtain closure under the TNRCC RRS program. As a result of the initial field investigation AOCs 17 and 18 received closure under RRS 1 in a letter from the TNRCC dated March 7, 2001. The remaining five of the seven sites required further investigation and/or remediation before closure could be requested. Consequently, a Phase II investigation was conducted at SWMUs 19, 20, 21, and 53, and AOC 19 in 2001 (HydroGeoLogic, 2000b). SWMU 53 received closure under RRS 1 by the TNRCC in a letter dated July 18, 2001. Investigations continue at SWMUs 19, 20, and 21, the results of which will be presented under a separate RFI report at a later date. The remaining site, AOC 19, is the subject of this SI Report.

This SI Report demonstrates that AOC 19 poses no significant risk to human health or the environment and provides justification for NFA and closure under RRS 2 for soil. This investigation was managed by the USAF under the Environmental Restoration Account (ERA). The lead regulatory agency that governs this SI and closure of this site is the TNRCC.

## 1.2 SITE IDENTIFICATION AND DESCRIPTION

The area of interest for this SI Report is AOC 19 located on the NAS Fort Worth JRB installation. AOC 19 was one of three AOCs identified in the February 17, 1998, letter from HydroGeoLogic to AFCEE detailing findings from historic aerial photographs (Appendix A). The location of AOC 19 in relation to the base is presented on Figure 1.1.

As illustrated in Figure 1.1, AOC 19 is located south of taxiway Charlie, and adjacent to the base boundary. Activity at this site was identified on aerial photographs of Carswell AFB during the period of February 3, 1954 through August 22, 1962 (U.S. Geological Survey [USGS], 1954; National Archives, 1962). Figure 1.2 shows the current location of AOC 19 superimposed on a historical aerial photograph.

The operational history of AOC 19 is unknown. However, as the site was suspected to have operated as a fire training area during the 1950s and early 1960s, wastes received may have consisted of various waste oils, recovered fuels, and spent solvents and cleaners. Currently, the AOC 19 area is covered by grass, with a bermed area at the north and partially down the western boundary of the site. Current photographs of AOC 19 are shown in Figure 1.3. A fence marks the NAS Fort Worth JRB boundary at the south and eastern boundaries of AOC 19, with an escarpment immediately to the south of AOC 19 leading into Farmers Branch Creek. Immediately east and adjacent to AOC 19 is the Carswell golf course. The western



portion of AOC 19 (approximately one-third of AOC 19's area) overlaps SWMU 25/Landfill 8 (Figure 1.3). SWMU 25/Landfill 8 received closure in June 2001 under RRS 2.

### 1.3 REGULATORY REQUIREMENTS

SI field activities were initiated at AOC 19 in May 2000, and continued through 2001. Although AOC 19 is not a RCRA-permitted site, the SI was designed to meet the requirements of Provision VIII of RCRA permit HW-50289. The RFI/SI Work Plans (WPs) and this SI Report have been prepared using guidance documents from the Installation Restoration Program (IRP), RCRA, the U.S. Environmental Protection Agency (USEPA), and the TNRCC RRS program.

Phase I of this SI was conducted in accordance with the RFI/SI WPs prepared by HydroGeoLogic dated April 2000 (HydroGeoLogic, 2000a). The RFI/SI WPs contain the Field Sampling Plan, which was followed during all sampling activities. Phase II of this SI was conducted in accordance with the Final Phase II RFI/SI Work Plans Addendum (WPA) prepared by HydroGeoLogic dated November 2000 (HydroGeoLogic, 2000b). Exploratory excavation activities were performed in accordance with the Final Excavation Work Plan for SWMUs 19 and 64, and AOC 19 (HydroGeoLogic, 2001a). In addition, the 2000 Basewide Quality Assurance Project Plan (QAPP) was used as guidance for managing specific quality assurance (QA) and quality control (QC) procedures as well as analytical data generated from the RFI and SI. Analytical data generation and assessment were designed to achieve data quality goals in accordance with the 2000 Basewide QAPP (HydroGeoLogic, 2000c).

The overall objective of the RFI/SI is to obtain closure of the subject SWMUs and AOCs under the guidelines of the TNRCC RRS program. An overview of the RRS program is presented in Section 4.1 of the RFI/SI WPs (HydroGeoLogic, 2000a).

To determine if a release has occurred at AOC 19, the results from site samples were compared to predetermined RRS 1 values. For inorganic constituents, the RRS 1 values were obtained from the base-specific background values for surface and subsurface soils as presented in the Final Basewide Background Study (Jacobs, 1998). For organic analytes, RRS 1 values were determined using compound-specific method quantitation limits (MQLs), as defined in the TNRCC Interoffice Consistency Memorandum (TNRCC, 1998a) and its Erratum Sheet (TNRCC, 1998b). All analyte concentrations above the applicable RRS 1 value were compared to the applicable RRS 2 values, which are the medium-specific concentrations (MSCs) presented in 30 TAC §335.368. Those concentrations above RRS 2 pose a potential threat to shallow groundwater. In some cases, a site-specific soil MSC was developed for an analyte by performing the synthetic precipitation leaching procedure (SPLP) and comparing the analytical results of the leachate to the applicable groundwater MSC (see Section 4.0). Note that analyte concentrations at or below the RRS 1 value are referred to as Standard 1 concentrations, analyte concentrations above the RRS 1 value and at or below the RRS 2 value are referred to as Standard 2 concentrations, and analyte concentrations above the RRS 2 value are referred to as Standard 3 concentrations.

Closure may be requested under the provisions of RRS 2 when it is established that the subject site does not contain contaminant concentrations greater than RRS 2 in any contaminated media of concern. In addition, contamination must be delineated to Standard 1 concentrations. Attainment of closure under RRS 2 is demonstrated by sufficient sample collection and analysis from the contaminated media of concern using the procedures outlined in Subchapter S of the TNRCC Risk Reduction Rules and the TNRCC Interoffice Memorandum. A document stating the responsible persons intention to fulfill deed certification requirements outlined in subsection 335.560 of the Risk Reduction Rules, Subchapter S must also be prepared and approved.

Evaluation of the Phase I and II SI results against the above criteria indicated that there may be a release to the soils at AOC 19. This potential release has been delineated and poses no significant risk to human health or the environment. As a result, AOC 19 is recommended for closure under Standard 2 (RRS 2).

#### **1.4 INVESTIGATION STRATEGY**

The SI was designed and conducted to achieve the following objectives:

- Determine if a release from AOC 19 has occurred.
- Characterize the nature and extent of any contamination encountered.
- Utilize the Synthetic Precipitation Leaching Procedure (SPLP) to provide site-specific MSCs, if necessary.

Field tasks used to characterize AOC 19 included the advancement of soil borings, conducting a geophysical survey, excavation of geophysical anomalies, monitoring well installation, and groundwater monitoring.

During Phase I of the SI, a total of 4 continuous core characterization soil borings were advanced using direct push technology (DPT) within the boundaries of AOC 19. Soil samples were collected from each characterization soil boring in 5-foot intervals from the ground surface to the top of the water table or refusal. This soil sampling method was used to determine the lithology of native soils and the nature and extent of any surface and subsurface contamination at AOC 19.

During Phase II of the SI a geophysical survey was conducted at AOC 19. Following the geophysical survey, exploratory excavations and confirmation soil sampling were conducted to investigate the potential existence of subsurface anomalies at the site. Following the geophysical activities, additional characterization soil borings along with delineation borings were advanced at the site. These borings provided additional site data to confirm Phase I detections or to delineate specific contaminants of potential concern (COPCs) to RRS 1 concentrations. Phase II delineation and conformation soil samples were collected at the depth intervals associated with the corresponding Phase I detections.

Also during Phase II of the SI, three monitoring wells were installed using a hollow-stem auger (HSA). Soil samples were collected during the installation of each monitoring well and analyzed for COPCs associated with Phase I detections. Three rounds of groundwater samples were collected from both new and existing wells at the site. Groundwater samples were analyzed for those COPCs identified in the Phase I soils.

As previously noted, AOC 19 was identified as a potential former fire training area by aerial photo interpretation only. No actual records of fire training activities at AOC 19 were confirmed. In order to determine if AOC 19 presents a threat to human health or the environment, essential information regarding the site was obtained. This information includes:

- The nature of wastes potentially generated at AOC 19.
- The lithology of soils to the top of the water table or refusal beneath AOC 19.
- An assessment of potential contaminant impacts on the quality of soil and groundwater within and around AOC 19.

## 1.5 DATA QUALITY OBJECTIVES

The data generated by this project are of sufficient quality and quantity to meet the overall project objective to request closure of AOC 19 under the TNRCC RRS program. Data from the following categories were required for this study:

**Site Characterization** - Data were used to evaluate physical and chemical properties of soil and groundwater. The data were also used to characterize the nature and extent of any contaminants detected.

**Health and Safety** - Data were used to establish the level of protection needed for the sampling team and other site-related personnel. These data were gathered by the use of organic vapor monitors (OVMs) during intrusive activities.

A combination of screening level data and definitive level data was used during this SI. Health and safety data were collected as screening data. All soil samples were analyzed following USEPA SW-846 protocols. The definitions of screening data and definitive data, as established by the Data Quality Objectives Process for Superfund Interim Final Guidance (USEPA/540/G-93/071, 1993) are described below:

- Screening Data with Definitive Confirmation - Screening data can be generated by rapid, less precise methods of analysis with less rigorous sample preparation. Sample preparation steps may be restricted to simple procedures such as dilution with a solvent, instead of elaborate extraction/digestion and cleanup. Screening data provides analyte identification and quantification. Although the quantification may be determined using analytical methods with QA/QC procedures and criteria associated with definitive data,

screening data without associated confirmation data are not considered to be data of known quality.

- **Definitive Data** - Definitive data were generated using rigorous analytical criteria, such as approved USEPA reference methods. Data are analyte-specific, with confirmation of analyte identity and concentration. These methods produce tangible raw data (e.g., chromatograms, spectra, digital values) in the form of paper printouts or computer-generated electronic files. Data may be generated at the site or at an off-site location, as long as the QA/QC requirements are satisfied. For the data to be definitive, either analytical or total measurement error must be determined.

The methods of analysis selected for samples collected from NAS Fort Worth JRB produced screening as well as definitive data. The data generated by the laboratory analysis of samples were sufficiently sensitive to allow comparison of the results to the TNRCC RRS. The 2000 Basewide QAPP (HydroGeoLogic, 2000c) describes each method that was performed as part of the investigation and outlines the QA measures followed by the contract laboratory. A data quality assessment of the analytical data collected during the AOC 19 SI is presented as Appendix B.

## **1.6 REPORT ORGANIZATION**

The remainder of this document is divided into the following sections:

Section 2.0 summarizes the installation and site-specific environmental settings for this SI.

Section 3.0 summarizes previous investigations as well as the activities that were conducted during this SI.


Section 4.0 presents the results of the SI and the potential releases to the environment.

Section 5.0 presents a discussion and analysis of the results presented in Section 4.0.

Section 6.0 presents the conclusions and recommendations for closure based on the results presented in Section 4.0.

Section 7.0 presents the references associated with the preparation of this report.

**FIGURES**



Filename X:\AFC001\26\ao19\_site\_investigation\Report\  
 aoc\_locations.apr  
 Project AFC001-026-20  
 Created 10/18/00 jbelcher  
 Revised 02/27/02 jb  
 Source HydroGeoLogic, Inc—GIS Database

**HYDRO**  
**Geologic**

#### Legend


- NAS Fort Worth JRB Boundary
- Former Carswell AFB Boundary
- Area of Concern 19

**Figure 1.1**

**Location of AOC 19  
 NAS Fort Worth JRB, Texas**



File: 17A-83-2  
 D.E.

File: 17A-83-2  
D.E.



**Figure 1.2**  
**Historic Location of AOC 19**  
**Suspected Former Fire Training**  
**Area B**  
**December 3, 1958**

**Legend**

- |   |      |   |                             |
|---|------|---|-----------------------------|
|  | SWMU |  | Surface Water               |
|  | AOC  |  | NAS Fort Worth JRB Boundary |

Filename X:\af001\26\ao19\_site\_investigation\Report\photo\_areas.apr  
Project AFC001-026-20  
Created 07/21/99 th  
Revised 04/22/02 tbrswell  
Photo Source National Archives  
Record Group 373  
Roll X380 18TRS  
Frame 24, 26

**HYDRO**  
**Geologic**

File: 17A-83-2  
D.E.




Photo taken at Point A. 09/99





Photo taken at Point B. 09/99



Filename X:\AFC001\26\ac19\_site\_investigation\

Report\photo\_locations.apr

Project AFC001-026-20

Created 08/25/99 jbelcher

Revised 02/27/02 jb

Map Source HGL GIS Database



**HYDRO**  
**Geologic**

### Legend

Solid Waste Management Unit 25

Area of Concern 19

Monitoring Well



Figure 1.3

**Photos and Location Map**  
**AOC 19**  
**Suspected Former Fire Training**  
**Area B**



# TAB

*SECTION 2.0*

---

## 2.0 SUMMARY OF EXISTING INFORMATION

The climate, physiography, geology, hydrology, biology, and demographics of the NAS Fort Worth JRB area are described in the following sections.

### 2.1 INSTALLATION ENVIRONMENTAL SETTING

#### 2.1.1 Physiographic Province

NAS Fort Worth JRB is located along the border zone between two physiographic provinces. The southeastern part of the base is situated within the Grand Prairie section of the Central Lowlands Physiographic Province. Most of NAS Fort Worth JRB is located within this province. This region is characterized by broad, eastward-sloping terrace surfaces that are interrupted by westward-facing escarpments. The land surface is typically grass covered and treeless except for isolated stands of upland timber. The northwestern part of the NAS Fort Worth JRB area is situated within the Western Cross Timbers Physiographic Province. This area is characterized by rolling topography and a heavy growth of post and blackjack oaks (Radian, 1989a,b). Surface elevations for this region range from about 850 feet above National Geodetic Vertical Datum (NGVD) west of the base to approximately 550 feet above NGVD along the eastern side of the base. Figure 2.1 is a section of the Lake Worth, Texas, U.S. Geological Survey topographic map showing the relief of the NAS Fort Worth JRB/Air Force Plant 4 (AFP 4) region.

#### 2.1.2 Regional Geology

The geologic units of interest for the region, from youngest to oldest, are as follows: (1) the Quaternary Alluvium (including fill material and terrace deposits), (2) the Cretaceous Goodland Limestone, (3) the Cretaceous Walnut Formation, (4) the Cretaceous Paluxy Formation, (5) the Cretaceous Glen Rose Formation, and (6) the Cretaceous Twin Mountains Formation. A generalized cross section of the geology beneath NAS Fort Worth JRB is presented in Figure 2.2 (Radian, 1989a,b). The areal limits of surface exposure of these units at NAS Fort Worth JRB are shown in Figure 2.3. Cross section locations and individual cross sections at NAS Fort Worth JRB are presented in Figures 2.4 through 2.7 (CH2M HILL, 1996). The regional dip of the stratigraphic units beneath NAS Fort Worth JRB is between 35 and 40 feet per mile in an easterly to southeasterly direction. NAS Fort Worth JRB is located on the relatively stable Texas Craton, west of the faults that lie along the Ouachita Structural Belt. No major faults or fracture zones have been mapped near the base.

#### 2.1.3 Groundwater

The water-bearing geologic formations located in the NAS Fort Worth JRB area may be divided into the following five hydrogeologic units, listed from the shallowest to the deepest: (1) an upper perched-water zone occurring in the alluvial terrace deposits associated with the Trinity River, (2) an aquitard of predominantly dry limestone of the Goodland and Walnut

Formations, (3) an aquifer in the Paluxy Sand, (4) an aquitard of relatively impermeable limestone in the Glen Rose Formation, and (5) a major aquifer in the sandstone of the Twin Mountains Formation. Each of these units is examined more explicitly in the following paragraphs. The relationship between these hydrogeologic units and geologic units is illustrated in Figure 2.8 (Radian, 1989a,b).

#### **2.1.3.1 Alluvial Terrace Deposits**

The uppermost groundwater in the area occurs within the pore space of the grains of coarse sand and gravels deposited by the Trinity River. In some parts of Tarrant County, primarily in those areas adjacent to the Trinity River, groundwater from the terrace deposits is used for irrigation and residential use. Groundwater from the terrace deposits is rarely used as a source of potable water due to its limited distribution and susceptibility to surface/storm water pollution (CH2M HILL, 1984).

Recharge to the water-bearing deposits occurs through infiltration from precipitation and from surface water bodies. Extensive on-site pavement and construction restricts this recharge. Additional recharge, however, comes from leakage in water supply lines, sewer systems, storm drains, and cooling water systems. In 1991, this leakage was calculated to be in excess of approximately 115.5 million gallons for NAS Fort Worth JRB and AFP 4 (General Dynamics Facility Management, 1992). This inflow of water to the shallow aquifer effects local groundwater flow patterns and contamination transport, along with increasing hydraulic head, which acts as the force to potentially drive water into lower aquifer systems. The estimated hydraulic conductivity of the alluvial aquifer is 4.57 gallons per day per square foot (gpd/ft<sup>2</sup>) (Radian, 1989a,b).

This flow between aquifers is restricted by the Goodland/Walnut Formations; therefore, the alluvial terrace groundwater is not hydraulically connected to the underlying aquifers at NAS Fort Worth JRB. The primary water flow in the terrace deposits is generally eastward toward the West Fork Trinity River, although localized variations exist across the entire site. The hydraulic gradient across the base is variable, reflecting variations in the flow direction and localized recharge. Discharge from the aquifer occurs into surface water on-site, specifically Farmers Branch Creek.

Potentiometric surface maps of NAS Fort Worth JRB and AFP 4 alluvial terrace groundwater are presented as Figure 2.9 and Figure 2.10 for April 2001 and October 2001 groundwater elevation data, respectively. Both maps show an easterly trend in groundwater flow over the area of NAS Fort Worth JRB toward the West Fork Trinity River (HydroGeoLogic, 2001c).

#### **2.1.3.2 Goodland/Walnut Aquitard**

The groundwater within the terrace deposits is isolated from groundwater within the lower aquifers by the low permeability of the Goodland Limestone and Walnut Formations. The primary inhibitors to vertical groundwater movement within these units are the fine-grained

clay and shale layers that are interbedded with layers of limestone. Some groundwater movement does occur between the individual bedding planes of both of these units, but the vertical hydraulic conductivity has been calculated to range between  $1.2 \times 10^{-9}$  centimeters per second (cm/sec) to  $7.3 \times 10^{-11}$  cm/sec for the NAS Fort Worth JRB and AFP 4 area. This corresponds to a vertical flow rate that ranges between  $1.16 \times 10^{-3}$  feet per day (ft/d) to  $5.22 \times 10^{-3}$  ft/d (Environmental Science and Engineering Incorporated [ESE], 1994).

At the AFP 4 “window area,” the Goodland/Walnut aquitard is breached, and the alluvial terrace groundwater is in direct contact with the groundwater in the Paluxy aquifer. Several wells and borings have been advanced at NAS Fort Worth JRB to the Goodland/Walnut aquitard. There is no evidence that a similar window exists on the base property. All five monitoring wells that fully penetrate the Paluxy aquifer on NAS Fort Worth JRB property are represented in cross sections (Figures 2.5 through 2.7). These wells are USGS01P, USGS05P, USGS06P, USGS07P, and Paluxy 1 (P1).

#### **2.1.3.3 Paluxy Aquifer**

The Paluxy aquifer is an important source of potable groundwater for the Fort Worth area. Many of the surrounding communities, particularly White Settlement, obtain their municipal water supplies from the Paluxy aquifer. Groundwater from the Paluxy is also used in some of the surrounding farms and ranches for agricultural purposes. Due to the extensive use of the Paluxy aquifer, water levels have declined significantly over the years. Water levels in the NAS Fort Worth JRB vicinity have not decreased as much as in the Fort Worth area due to its proximity to the Lake Worth recharge area and the fact that the base does not obtain water from the Paluxy aquifer. Drinking water at the base is supplied by the city of Fort Worth, which uses Lake Worth as its water source. The groundwater of the Paluxy aquifer is contained within the openings created by gaps between bedding planes, cracks, and fissures in the sandstones of the Paluxy Formation. Just as the Paluxy Formation is divided into upper and lower sand members, the aquifer is likewise divided into upper and lower aquifers. The upper sand is finer grained and contains a higher percentage of shale than the lower sand. In 1989, Radian estimated the hydraulic conductivity and transmissivity to be 130 to 140 gpd/ft<sup>2</sup> and 1,263 to 13,808 gallons per day per foot (gpd/ft), respectively.

#### **2.1.3.4 Glen Rose Aquitard**

Below the Paluxy aquifer are the fine-grained limestone, shale, marl, and sandstone beds of the Glen Rose Formation. The thickness of the formation ranges from 250 to 450 feet. Although the sands in the Glen Rose Formation yield small quantities of groundwater in the area, the relatively impermeable limestone acts as an aquitard, restricting water movement between the Paluxy aquifer above and the Twin Mountains aquifer below.

### **2.1.3.5 Twin Mountains Aquifer**

The Twin Mountains Formation is the oldest and deepest water supply source used in the NAS Fort Worth JRB area. The Twin Mountains Formation occurs approximately 600 feet below NAS Fort Worth JRB, with a thickness of between 250 to 430 feet. Recharge to the Twin Mountains aquifer occurs west of NAS Fort Worth JRB, where the formation out crops. Groundwater movement is eastward in the downdip direction. The Twin Mountains groundwater occurs under unconfined conditions in the recharge area and becomes confined as it moves downdip. Transmissivities in the Twin Mountains aquifer range from 1,950 to 29,700 gpd/ft and average 8,450 gpd/ft in Tarrant County. Hydraulic conductivities range from 8 to 165 gpd/ft<sup>2</sup> and average 68 gpd/ft<sup>2</sup> in Tarrant County (CH2M HILL, 1984).

### **2.1.3.6 Water Well Survey Results**

An inventory of water supply wells within a one-half-mile radius of the NAS Fort Worth JRB boundary was conducted by HydroGeoLogic in 1997. Figure 2.11 illustrates the locations of 59 wells that were identified from TWC records. All of these wells were installed and completed in the Paluxy aquifer or the Twin Mountains aquifer. No active water wells are located on NAS Fort Worth JRB property. Water is supplied to the base by the city of Fort Worth, which obtains water from Lake Worth.

### **2.1.4 Surface Water**

The topography of NAS Fort Worth JRB is fairly flat except for the lower lying areas along the tributaries of the Trinity River. The land surface slopes gently northeastward toward Lake Worth and eastward toward the West Fork Trinity River. Surface elevations range from about 690 feet above NGVD at the southwest corner of the base to approximately 550 feet above NGVD, along the eastern side of the base.

NAS Fort Worth JRB is located within the Trinity River Basin, adjacent to Lake Worth. The lake is a man-made reservoir created by damming the Trinity River at a point just northeast of the base. The surface area of the lake is approximately 2,500 acres. Lake Worth receives a limited amount of storm water runoff from NAS Fort Worth JRB during and immediately after rainfall events. Elevation of the water surface is fairly consistent at approximately 594 feet above NGVD, the fixed elevation of the dam spillway. Part of the eastern boundary of NAS Fort Worth JRB is defined by the West Fork Trinity River. River flow is towards the southeast into the Gulf of Mexico. Because the Trinity River has been dammed, the 100- and 500-year flood plains do not extend more than 400 feet from the center of the river or any of its tributaries.

Surface drainage is mainly east towards the West Fork Trinity River. The base is partly drained by Farmers Branch Creek, a tributary of the West Fork Trinity River. Farmers Branch Creek begins within the community of White Settlement and flows eastward. Just south of AFP 4, Farmers Branch Creek flows under the runway within two large culverts

identified as an aqueduct. Most of the base drainage is intercepted by a series of storm drains and culverts, directed to oil/water separators (OWSs), and discharged to the West Fork Trinity River downstream of Lake Worth. A small portion of the north end of the base drains directly into Lake Worth.

NAS Fort Worth JRB currently has three storm water discharge points that are subject to National Pollution Discharge Elimination System (NPDES) requirements. Each discharge point is monitored weekly for chemical oxygen demand, oil and grease, and pH. The permit has been violated on numerous occasions. In 1979, these violations prompted the USEPA to formally demand a corrective action (CH2M HILL, 1984). Several additional sampling points were established to determine the flow of pollutants onto and off of the base. Samples were collected for a variety of parameters as circumstances (spills, fish kills, odors, and oil sheen) dictated (Radian, 1989a,b).

### 2.1.5 Climate

The climate in the Fort Worth area is classified as sub-humid with hot summers and dry winters. Tropical maritime air masses control the weather during much of the year, but the passage of polar cold fronts and continental air masses can create large variations in winter temperatures (TNRCC, 1996b). In the Dallas-Fort Worth area, daily mean temperatures range from 43.4 degrees Fahrenheit (°F) in January to 85.3 °F in July. The highest recorded temperature is 113 °F, and the lowest temperature is 2 °F. Freezing temperatures occur on average of 25 days in the year (National Climatic Data Center (NCDC), 2000).

Average relative humidity (after noon) ranges from 51 percent (September and October) to 62 percent (January) (NCDC, 2000). Mean annual precipitation recorded at the base is approximately 34.73 inches. The wettest months are May and October, with a secondary maximum in June. The period from November to March is generally dry, with a secondary minimum in August. Snowfall accounts for a small percentage of the total precipitation between November and March. Thunderstorm activity occurs at the base an average of 45 days per year, with the majority of the activity between April and June. Hail may fall 2 to 3 days per year. The maximum precipitation ever recorded in a 24-hour period is 1.49 inches. On the average, measurable snowfall occurs 5 days per year.

During 2001, the average annual temperature in the area was 65.6 °F, and monthly mean temperatures varied from 42.7 °F in January to 86.7 °F in July. The average daily minimum temperature in January was 33 °F, and the lowest recorded temperature was 19 °F. The average daily maximum temperature was 96.7 °F, and highest temperature recorded at the base during 2001 was 100 °F in the month of July. Freezing temperatures occur at NAS Fort Worth JRB an average of 11 days per year. (National Weather Service, 2002).

Lake evaporation near NAS Fort Worth JRB is estimated to be approximately 57 inches per year. Evapotranspiration over land areas may be greater or less than lake evaporation depending on vegetative cover type and moisture availability. Average net precipitation is

expected to be equal to the difference between average total precipitation and average lake evaporation, or approximately minus 25 inches per year. Mean cloud cover averages 50 percent at NAS Fort Worth JRB, with clear weather occurring frequently during the year. Some fog is present an average of 83 days per year. Wind speed averages 7 knots; however, a maximum of 80 knots has been recorded. Predominant wind direction is from the south-southwest throughout the year (TNRCC, 1996b).

#### **2.1.6 Biology**

Approximately 374 acres, or 14 percent, of NAS Fort Worth JRB is considered unimproved, indicating the presence of seminatural to natural biological/ecological conditions. The base lies in the Cross Timbers and Prairies Regions of Texas, where native vegetation is characterized by alternating bands of prairies and woodlands. The higher elevations on the base are covered by native and cultivated grasses such as little bluestem, Indian grass, big bluestem, side oats, grama, and buffalo grass. Forested areas occur primarily on the lower land and along the banks of streams. Common wood species include oak, elm, pecan, hackberry, and sumac. Several non-native species such as catalpa and chinaberry are common (Radian, 1989a,b).

Typical wildlife on the base includes black-tailed jackrabbits in grassy areas along the runway. In addition, there are cottontail rabbits, gray squirrels, and opossums in the wooded areas. Common birds include morning doves, meadowlarks, grackles, and starlings. Hunting and trapping are not allowed on the base, but in the nearby rural areas they are a very popular form of recreation (Radian, 1989a,b).

Reported game fish include black bass, sunfish, and catfish, all of which can be found in Lake Worth, Farmers Branch Creek, and one small pond located on base near the golf course equipment shed. According to the Texas Department of Parks and Wildlife and the U.S. Fish and Wildlife Service, there are no threatened or endangered species known to occur on NAS Fort Worth JRB. None of the federally listed endangered plant species for Texas are known to occur within 100 miles of Tarrant County. Of the federally listed endangered animals species, only the peregrine falcon and the whooping crane are known to occasionally inhabit the area; however, none of these is suspected to reside in the vicinity of NAS Fort Worth JRB (Radian, 1989a,b).

#### **2.1.7 Demographics**

The following sections describe the regional and site-specific demographics as they relate to the Fort Worth, Texas area and NAS Fort Worth JRB.

##### **2.1.7.1 Regional Demographics**

Approximately 1,278,606 people reside within Tarrant County, Texas (U.S. Department of Commerce, 1996). Of this population, 485,650 reside within the city limits of Fort Worth.

Several smaller cities and villages make up the remainder of the population. The communities of White Settlement, Lake Worth, Westworth Village, River Oaks, and Sansom Park lie within a 3-mile radius of NAS Fort Worth JRB. The following populations that reside in the cities and villages are based on 1994 census data: White Settlement (city) 16,502; Lake Worth (city) 4,694; Westworth Village (town) 2,502; River Oaks (city) 6,747; and Sansom Park (city) 4,136 (U.S. Department of Commerce, 1994). Six schools are within a 2-mile radius of NAS Fort Worth JRB; the closest is 0.5 miles south (Rust, 1995).

The area surrounding NAS Fort Worth JRB is highly urbanized due to its proximity to the city of Fort Worth. The area is composed of a combination of residential, commercial, and light industrial properties that employ the majority of local residents (Rust, 1995).

#### **2.1.7.2 Site-Specific Demographics**

The current full-time population at NAS Fort Worth JRB is approximately 3,600 people, comprising 400 officers, 1,400 civilians, and 1,800 active reservists. Part-time military reservists will increase this population to over 6,000 military personnel (CH2M HILL, 1996).

Approximately 86 percent of NAS Fort Worth JRB has been developed by way of buildings, roads, parking lots, runways, and housing and recreational areas. On-site activities include various maintenance, inspection, and support activities for fuel systems, weapons, jet engines, aerospace ground equipment (AGE), and specialized ground equipment (HydroGeoLogic, 1999).

## **2.2 SITE-SPECIFIC ENVIRONMENTAL SETTING**

The following sections describe the site-specific environmental setting of NAS Fort Worth JRB.

### **2.2.1 Site-Specific Soils**

The U.S. Soil Conservation Service has identified four major soil associations in the area of NAS Fort Worth JRB. The first association is the surficial soils of the nearly level to gently sloping clayey soils of the Sanger-Purves-Slidell Association. Second is the Aledo-Bolar-Sanger Association, which is located within the southwestern portion of the Sanger-Purves-Slidell Association and is characterized as an increasingly loamy clayey soil of gentle to moderate slope. The third association, the Bastisil-Silawa Association separates the Sanger-Purves-Slidell Association from the Frio-Trinity Association. The Bastisil-Silawa Association is characterized as a sandy clay loam of nearly level slope (ESE, 1994). The clayey soils of the Frio-Trinity Association make up the fourth soil association and are located along the flood plain of the West Fork Trinity River. The areal limits of each of these soil associations and their occurrence on-site are shown in Figure 2.12.



### 2.2.2 Site-Specific Geology

The majority of NAS Fort Worth JRB is covered by alluvium deposited by the Trinity River during flood stages. The Quaternary Period alluvium (Holocene Epoch) occurs downstream from the Lake Worth Dam in the current flood plain of the West Fork Trinity River, on the east side of the facility. Older alluvial deposits and terrace deposits (Pleistocene Epoch) also occur on-site. The alluvium is composed of gravel, sand, silt, and clay of varying thicknesses and lateral extent. The thickness of these materials ranges from 0 to 60 feet. Fill material is also included within these deposits where landfills, waste pits, excavation sites, and other construction activities have altered the original land surface. This fill material is made up of clay, silt, sand, and gravel mixtures, but may also contain debris and other waste (Radian, 1989a,b).

Below the alluvial terrace deposits are the Cretaceous-age Goodland and Walnut Formations, which form the bedrock surface beneath NAS Fort Worth JRB. Both formations consist of interbedded, fossiliferous, hard limestone and calcareous shale. The upper formation, the Goodland Limestone, is exposed on the southern portion of the base, south of White Settlement Road. The Goodland is a chalky-white, fossiliferous limestone and marl. The thickness of the Goodland Limestone ranges from 20 to 25 feet. Below the Goodland Formation is the Walnut Formation (or Walnut Clay). The Walnut Formation is exposed in a small area along the shores of Lake Worth and Meandering Road Creek. This formation is a shell agglomerate limestone with varying amounts of clay and shale. It ranges in thickness from 25 to 35 feet throughout the site except where erosion has produced a few thinner areas. Subsurface investigations have located troughs and paleochannels that are eroded into the top of the bedrock at NAS Fort Worth JRB. These paleochannels are typical of an erosional surface modified by fluvial processes and are filled with sand and gravel deposits ranging in thickness from 15 to 35 feet (CH2M HILL, 1996).

Below the Walnut Formation is the Paluxy Formation (or Paluxy Sand). The Paluxy Formation underlies all of NAS Fort Worth JRB. The formation consists of several thick sandstone layers that are separated by thin, discontinuous shale and claystone layers. Sandstones in the formation are primarily a fine-to coarse-grained sand with minor amounts of clay, sandy clay, pyrite, lignite, and shale. The lower section of the Paluxy is generally coarser-grained than the upper section (CH2M HILL, 1996). Total formation thickness ranges from 130 to 175 feet, with variable thickness and occurrence of individual layers across the site. Only one unit in this formation, a shale/silty shale, can be extensively mapped across the base.

The older Glen Rose and Twin Mountains Formations are not exposed at NAS Fort Worth JRB. The Glen Rose Formation consists primarily of calcareous sedimentary rock and some sands, clays, and anhydrite. The Glen Rose caps the Twin Mountain Formation, which is the oldest Cretaceous Formation in the NAS Fort Worth JRB area. The Twin Mountain Formation consists of a basal conglomerate of chert and quartz, grading upward into coarse- to fine-grained sand interspersed with varicolored shale.

**FIGURES**

Figure 2.1

Lake Worth Topographic Map




U.S. Air Force Center for  
Environmental Excellence

Legend

○ Area of Concern 19

Site Location



File: 17A-83-2  
D.E.



Filename X:\AFC001\26aoc19\_site\_investigation\

Report\topo.cdr

Project AFC001-026-20

Created by cflamer 05/27/99


Revised 02/28/02 asp

Map Source USGS


Maps Lake Worth and Benbrook, TX

Dates Photorevised 1981, 1982



**NOTES**

- 1 STRATIGRAPHIC CONDITIONS ARE KNOWN ONLY AT THE MONITORING WELLS AND BORINGS; CONTACTS ARE INTERPOLATED BETWEEN CONTROL POINTS
- 2 WITH THE EXCEPTION OF THE AREA BETWEEN USGS07P AND CAR-P2, THE CONTACT BETWEEN THE GOODLAND WALNUT AND PALUXY FORMATIONS DISPLAYS THE REGIONAL DIP OF 35-40 FEET PER MILE

**Legend**

**Figure 2.2**  
**Generalized Geologic Cross Section of**  
**NAS Fort Worth JRB, Texas**

Filename: X:\AFC001\26\AOC19\_site\_investigation\Report1

Geo-x-section.dwg


Created: 06/02/99 jbelcher

Revised: 02/11/02 asp

Project: AFC001-026-20

Source: Radon, 1986; HGL, 1999

**HYDRO**  
**Geologic**



### Figure 2.4

## Cross Section Location Map



### Legend

USGS01P

## Boring Location

A A' Cross Section Line

Area of Concern 19

File: 17A-83-2  
D.E.



Age Group	Number of people
0-14	~1000
15-24	~1250
25-34	~1500
35-44	~1750
45-54	~2000
55-64	~2250
65-74	~2500
75-84	~2750
85+	~2500

SCALE IN FEET

Filename X:\AFC001\26\loc19\_site\_investigation\Report\1x-sect-loc.dwg  
Project AFC001-026-20  
Created by jbelcher 06/09/99  
Revised 02/28/02 asp  
Map Source JACOBS, 1996













### Figure 2.5

### Cross Sections A-A', A'-A", and A'-A'''



### Legend

- | Stratigraphic Contact   | Inferred Stratigraphic Contact                                       |
|---|--|
|    | Fine- to Coarse-Grained Sand, Clayey Sand, Silty Sand, Gravelly Sand |
|    | Clay, Silty Clay, Sandy Clay   |
|   | Silt, Clayey Silt, Sandy Silt  |
|  | Gravelly Clay or Clay w/Limestone                                    |
|  | Fill, Soil, Gravel, Rock   |
|  | Coarse Gravel, Silty Gravel, Sandy Gravel                            |
|  | Limestone  |
|  | Claystone/Mudstone/Shale   |
|  | Sandstone  |



Filename X AFC001\26\aoac19\_sie\_investigation\1  
Report\A-A\_x-sections.cdr  
Project AFC001-026-20  
Revised 02/11/02.asp  
Source CH2M HILL, 1996 b








Figure 2.6

Cross Section B-B'



Legend

- Stratigraphic Contact
- Inferred Stratigraphic Contact
- Fine- to Coarse-Grained Sand, Clayey Sand, Silty Sand, Gravelly Sand
- Clay, Silty Clay, Sandy Clay
- Silt, Clayey Silt, Sandy Silt
- Gravelly Clay or Clay w/Limestone
- Fill, Soil, Gravel, Rock
- Coarse Gravel, Silty Gravel, Sandy Gravel
- Limestone
- Claystone/Mudstone/Shale
- Sandstone



NOTE

- 1) SEE FIGURE 2.4 FOR THE CROSS SECTION LOCATION AND BORING LOG REFERENCES
- 2) THE LITHOLOGIC LOGS FOR CERTAIN USGS BORINGS (USGS, 1996) CHARACTERIZE THESE SEQUENCES AS "SANDSTONE" WHICH, WHEN COMPARED WITH OTHER LOGS IN THIS AREA, SEEMS UNEXPECTED AT THIS ELEVATION IN THE SECTION. THEREFORE, HYDROGEOLOGIC HAS CORRELATED THESE UNITS WITH THE TERRACE ALLUVIAL SANDS

Filename X:\AFC001\26\laoc19\_site\_investigation\ Report\B-B' x-section.cdr  
Project AFC001-026-20  
Revised 02/11/02 asp  
Source CH2M HILL, 1996 b






Figure 2.7  
Cross Section B'-B''



Legend

- Stratigraphic Contact
- Inferred Stratigraphic Contact
- Fine- to Coarse-Grained Sand, Clayey Sand, Silty Sand, Gravelly Sand
- Clay, Silty Clay, Sandy Clay
- Silt, Clayey Silt, Sandy Silt
- Gravelly Clay or Clay w/Limestone
- Fill, Soil, Gravel, Rock
- Coarse Gravel, Silty Gravel, Sandy Gravel
- Limestone
- Claystone/Mudstone/Shale
- Sandstone




NOTE

- 1) SEE FIGURE 2.4 FOR THE CROSS SECTION LOCATION AND BORING LOG REFERENCES
- 2) THE LITHOLOGIC LOGS FOR CERTAIN USGS BORINGS (USGS, 1996) CHARACTERIZE THESE SEQUENCES AS "SANDSTONE" WHICH, WHEN COMPARED WITH OTHER LOGS IN THIS AREA, SEEMS UNEXPECTED AT THIS ELEVATION IN THE SECTION. THEREFORE, HYDROGEOLOGIC HAS CORRELATED THESE UNITS WITH THE TERRACE ALLUVIAL SANDS

Filename X:\AFC001\26laoc19\_site\_investigation\Report18'-B''\_x-section.cdr  
Project AFC001-026-20  
Revised 02/11/02 asp  
Source CH2M HILL, 1996






Filename X:\AFC001\26\loc19\_site\_investigation\  
Report\Strat\_column.cdr  
Project AFC001-026-20  
Revised 02/11/02 asp  
Map Source Radian, 1989



#### Legend



**Figure 2.8**  
**Stratigraphic Column Correlating**  
**Hydrogeologic and Geologic Units**

Figure 2.9

Water Level Elevations  
Terrace Alluvium  
April 2001



Legend


- NAS Fort Worth JRB (Carswell Field)
- Former Carswell Air Force Base
- 600 - Groundwater Elevation Contour (ft msl)
- Monitoring Well  
533 76
- AOC 19
- Building/Structure

File: 17A-83-2  
D.E.



SCALE IN FEET

Filename X:\AFC001\26\aac19\_site\_investigation\Report\groundwater elev apr 2001 apr  
Project AFC001-026-22  
Created 07/05/01 jbelcher  
Revised 05/01/02 thraswell  
MapSource HydroGeoLogic, Inc  
ArcView GIS Database, 2001



HydroGeoLogic, Inc. --Site Investigation Report, AOC 19  
NAS Fort Worth JRB, Texas

Figure 2.10

Water Level Elevations  
Terrace Alluvium  
October 2001



Legend

- NAS Fort Worth JRB (Carswell Field)
- Former Carswell Air Force Base
- 600 - Groundwater Elevation Contour (ft msl)

Monitoring Well  
608 99

AOC 19

Building/Structure

File: 17A-83-2  
D.E.



SCALE IN FEET

Filename X:\AFC001\26\aoe19\_site\_investigation\ Report\groundwater elev\_oct2001.apr  
Project AFC002-026-20  
Created 07/03/01 Belcher  
Revised 02/26/02 j  
MapSource HydroGeoLogic, Inc  
ArcView GIS Database, 2002






Figure 2.11

Water Well Receptor Survey  
Within 1 Mile of  
NAS Fort Worth JRB



U.S. Air Force Center for  
Environmental Excellence

Legend


- Area of Concern 19 D.E.
- Water Well Location

MAP ID	STATE	WELL ID	WELL TYPE
1	Unnumbered	32-13-5	Domestic
2	32-13-811	32-13-5U	Domestic
3	32-13-808	32-13-5U	Domestic
4	32-13-808	32-24-4	Industrial
5	32-13-7K	Unnumbered	Domestic
6	32-13-806	32-13-3	Domestic
7	32-13-805	Unnumbered	Domestic
8	32-13-8	32-13-5	Domestic
9	32-13-8	32-13-5K	Domestic
10	32-13-816	32-13-5K	Domestic
11	32-13-7X	32-13-5	Domestic
12	32-13-8	32-13-5B	Domestic
13	32-13-8	32-13-5	Domestic
14	Unnumbered	32-13-5	Domestic
15	32-21-2	32-13-8H	Domestic
16	32-13-8	32-13-5	Domestic
17	32-13-814	32-13-5	Domestic
18	32-13-819	32-13-5F	Domestic
19	32-13-804	32-13-5F	Domestic
20	32-20-6	32-13-5	Domestic
21	32-13-822	32-13-5	Domestic
22	32-13-815	32-13-5	Domestic
23	32-13-821	32-13-5	Domestic
24	32-13-5	32-13-5	Domestic
25	32-13-5	32-13-5	Domestic
26	32-13-818	32-13-5	Domestic
27	G2200324A	32-13-5M	Domestic
28	32-13-817	32-13-810	Public Supply
29	32-13-8	32-13-809	Domestic
30	32-13-8	32-13-8	Domestic
31	32-13-7G	32-13-8	Domestic
32	32-21-205	32-13-8	Domestic
33	32-21-206	32-13-8	Domestic
34	32-21-207	32-13-8	Domestic
35	32-21-208	32-13-8	Domestic
36	32-13-8C	32-13-8	Domestic
37	32-13-807	32-13-912	Public Supply
38	32-13-803	32-13-9A	Domestic
39	32-13-812	32-13-917	Public Supply
40	32-13-801	32-13-9	Public Supply
41	32-13-802	32-14-7	Domestic
42	32-13-5C	32-14-7	Domestic
43	Unnumbered	32-14-7	Domestic
44	32-13-5	32-13-9	Domestic
45	32-13-7	32-13-9	Domestic
46	32-21-2B	32-13-9	Domestic
47	32-13-5	32-13-9A	Domestic
48	32-13-5	32-13-9	Domestic
49	32-13-5	32-31-1N	Irrigation
50	32-13-5	32-13-5	Domestic
51	32-13-5U	32-13-5	Domestic
52	32-24-4	32-13-5	Domestic
53	Unnumbered	32-13-5	Domestic
54	32-13-3	32-13-5	Domestic
55	Unnumbered	32-13-5	Domestic
56	32-13-5	32-13-5	Domestic
57	32-13-5K	32-13-5	Domestic
58	32-13-5K	32-13-5	Domestic
59	32-13-5	32-13-5	Domestic
60	32-13-5B	32-13-5	Domestic
61	32-13-5	32-13-5	Domestic
62	32-13-5	32-13-5	Domestic
63	32-13-5	32-13-5	Domestic
64	32-13-5	32-13-5	Domestic
65	32-13-5	32-13-5	Domestic
66	32-13-5F	32-13-5	Domestic
67	32-13-5F	32-13-5	Domestic
68	32-13-5F	32-13-5	Domestic
69	32-13-5	32-13-5	Domestic
70	32-13-5	32-13-5	Domestic
71	32-13-5	32-13-5	Domestic
72	32-13-5	32-13-5	Domestic
73	32-13-5S	32-13-5	Domestic
74	32-13-5	32-13-5	Domestic
75	32-13-5	32-13-5	Domestic
76	32-13-5M	32-13-5	Domestic
77	32-13-810	32-13-810	Public Supply
78	32-13-809	32-13-809	Domestic
79	32-13-8	32-13-8	Domestic
80	32-13-8	32-13-8	Domestic
81	S2200012A	32-13-8	Domestic
82	S2200012B	32-13-8	Domestic
83	S2200068A	32-13-8	Domestic
84	32-14-7	32-14-7	Domestic
85	32-13-911	32-13-911	Domestic
86	32-13-912	32-13-912	Domestic
87	32-13-9A	32-13-9A	Domestic
88	32-13-917	32-13-917	Domestic
89	32-13-9	32-13-9	Domestic
90	32-14-7	32-14-7	Domestic
91	32-14-7	32-14-7	Domestic
92	32-14-7	32-14-7	Domestic
93	32-13-9	32-13-9	Domestic
94	32-13-9	32-13-9	Domestic
95	32-13-9A	32-13-9A	Domestic
96	32-13-9	32-13-9	Domestic
97	32-31-1N	32-31-1N	Irrigation



Filename X:\AFC001\26\loc19 site\_investigation\1  
Report\water\_well\_receptor.apr  
Project AFC001-026-20  
Created by: cfarmer 01/17/01  
Revised: 02/28/02 asp  
Maps Lake Worth and Benbrook TX  
Dates Photorevised 1981, 1982






Filename X\AFC001\26\aoe19\_site\_investigation\  
Report\Soil\_Association.cdr  
Project AFC001-026-20  
Revised 02/28/02 asp  
Map Source Radian, 1989



#### Legend



**Figure 2.12**  
**Soil Association Map**  
**NAS Fort Worth JRB, Texas**

# TAB

*SECTION 3.0*

---

### 3.0 SUMMARY OF INVESTIGATION ACTIVITIES

This section provides a summary of previous/ongoing investigations in the AOC 19 area and describes activities conducted as part of this investigation. Preliminary activities conducted for the site characterization included aerial photo interpretation, site reconnaissance, and utility clearance. Chemical characterization activities included surface and subsurface soil sample collection and groundwater sample collection. In addition, a geophysical survey was performed to identify subsurface anomalies, and exploratory excavations were completed to characterize those anomalies identified by the geophysical survey.

#### 3.1 SWMU 25 RCRA FACILITY INVESTIGATION

Prior to the current SI, HydroGeoLogic conducted an RFI at SWMU 25/Landfill 8 which extends over the western third of AOC 19. The overlapping boundaries of SWMU 25/Landfill 8 and AOC 19 are depicted in Figure 3.1. RFI activities at SWMU 25/Landfill 8 began in August 1997, and continued until June 2000. The results of the RFI showed concentrations of several constituents above RRS 1 and 2 within the AOC 19 boundary. However most of these concentrations were removed during the interim remedial action (IRA) at SWMU 25/Landfill 8 conducted by International Technologies Corporation (IT) in July and August 2000. The remaining constituents of concern were delineated or eliminated as statistically probable deviations of background concentrations. A full discussion of the SWMU 25/Landfill 8 RFI is presented in the *Final RCRA Facility Investigation Report, Solid Waste Management Units 22, 23, 24, and 25, NAS Fort Worth JRB, Texas* (HydroGeoLogic, 2001b). Based on the conclusions of the RFI Report, TNRCC granted closure of SWMU 25/Landfill 8 under RRS 2 in June 2001.

#### 3.2 BASEWIDE TCE PLUME

A basewide groundwater sampling and analysis program (GSAP) was initiated for NAS Fort Worth JRB in April 1995 to address groundwater contamination associated with various SWMUs and AOCs identified on the base. Twenty-two rounds of quarterly or semi-annual sampling have been implemented to date. The major source of the trichloroethene (TCE) plume is from the upgradient site AFP 4. AFP 4 was placed on the National Priority List (NPL) in August 1990 because of a large release of TCE arising from past disposal practices. While the source areas are currently being remediated under Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), the dissolved TCE plume appears to have migrated east of AFP 4, extending under NAS Fort Worth JRB. The regional TCE plume can be subdivided into northern and southern lobes (HydroGeoLogic, 2000e).

AOC 19 is located in the vicinity of the southern lobe of the TCE plume, as shown in Figure 3.2. The concentrations of TCE upgradient of AOC 19 from April to July 2001 ranged from 3.800 J mg/L (HM-112) to 0.280 mg/L (HM-126), as depicted in Figure 3.2.



### **3.3 SITE RECONNAISSANCE AND UTILITY CLEARANCE**

Prior to mobilizing to the field, HydroGeoLogic conducted site reconnaissance to select sample locations and to assess requirements for site preparation and clearance of underground utilities. Proposed drilling locations were determined and marked within the area of AOC 19 based on accessibility, utility locations, site extent identified in aerial photographs, results of the SWMU 25 RFI, and topography, which slopes downward toward Farmer's Branch Creek in a southerly direction.

As this SI involved multiple phases, the Navy Public Works office issued an individual dig permit for each phase of site activities that involved subsurface work at AOC 19. Each dig permit was valid for 30 days, and the corresponding HydroGeoLogic field effort was conducted during this 30-day window.

Prior to initiating subsurface activities, HydroGeoLogic marked the boring locations with stakes and notified the Navy Public Works Office regarding the intended field investigations and sampling activities. A local utility company marked and cleared all subsurface utilities within a 50-foot radius of the proposed AOC 19 boring/excavation locations. The Phase I utility clearance was requested on April 28, 2000 and was received on May 8, 2000 (permit call number 534). Phase II utility clearances were requested on August and December 3, 2001, and received on August 12, 2001 and December 3, 2001 (permit call numbers 012151081 and 013375126, respectively).

### **3.4 AOC 19 SITE INVESTIGATION ACTIVITIES**

The following sections describe activities conducted as part of this SI. As stated previously in Section 1.0, all sampling activities were conducted in accordance with the RFI/SI WPs (HydroGeoLogic, 2000a) along with planning documents specifically developed for each subsequent phase of field activities referenced in the subsections below.

#### **3.4.1 Phase I – Site Investigation Activities**

Phase I of the SI at AOC 19 was initiated on May 12, 2000 and was completed on May 15, 2000. A total of four soil borings were advanced at AOC 19 using DPT during Phase I. Figure 3.1 illustrates the Phase I soil boring locations, depicted in blue. Soil boring BHGLAOC1901 was advanced in the north central area of AOC 19. Soil borings BHGLAOC1902 and BHGLAOC1903 were advanced along the eastern boundary of AOC 19. Soil boring BHGLAOC1904 was advanced along the south central boundary of AOC 19. The purpose of these borings was to identify and characterize potential contamination associated with AOC 19. Continuous cores were used to sample and evaluate the physical characteristics of the soil. Soil samples were collected at 5-foot intervals from the ground surface to the water table or refusal, and submitted for analysis. Based on the potential wastes handled at AOC 19 (Section 1.2), soil samples were analyzed for the following reduced list of Appendix IX analytes:

## Appendix IX

- SW8260B - VOCs
- SW8270C - semivolatile organic compounds (SVOCs)
- SW6010B - trace elements (metals)
- SW7471A - mercury

During Phase I, a total of five surface (four samples and one duplicate) and five subsurface soil samples were submitted for chemical analysis<sup>1</sup>. Results of the AOC 19 Phase I soil investigation are presented in Section 4.0.

- SW7471A - mercury

### **3.4.2 Phase II – Site Investigation Activities**

The second phase of SI field activities at AOC 19 was conducted in various stages throughout 2001. All field work associated with the Phase II activities was performed in accordance with the *Phase II Work Plan Addendum, RCRA Facility Investigation of SWMUs 19, 20, 21, and 53; and Site Investigation of AOC 19* (HydroGeoLogic, 2000b). Phase II investigation activities consisted of the following:

- geophysical survey
- exploratory excavations
- soil boring installation/soil characterization
- monitoring well installation/groundwater characterization

#### **3.4.2.1 Geophysical Survey**

Due to the proximity of AOC 19 to SWMU 25/Landfill 8, a geophysical survey was performed by a HydroGeoLogic subcontractor in February 2001. This survey was performed using magnetic, time-domain electromagnetic (EM) induction, and frequency-domain EM induction techniques. The instrumentation consisted of a Geometrics G-858G magnetic gradiometer for survey data acquisition, a Geonics EM61 high-sensitivity metal detector for the time-domain EM survey, and a Geonics EM31 terrain conductivity meter for the frequency-domain survey. Both Geonics units were coupled to an Omnidata DL720 digital data logger when in use.

The results of this survey were reported in *Surface Geophysical Survey Report, AOC 19 Site/SWMUs 19 & 20 Site* (IT, 2001). The geophysical report is included as Appendix C and the results are discussed in Section 4.1.

---

<sup>1</sup> Due to a sample delivery problem, the VOCs fraction was recollected from the surface and subsurface intervals of BHGLAOC1901 on May 26, 2000.

### 3.4.2.2 Exploratory Excavations

Based on the results of the geophysical survey, five anomalies, THGLAOC1901 through THGLAOC1905, were investigated by exploratory excavations in August 2001. All work was performed in accordance with the *Excavation Work Plan, SWMUs 19, 64, and AOC 19*<sup>2</sup> (HydroGeoLogic, 2001a). The locations of the Phase II exploratory excavations are shown on Figure 3.1, along with the locations of three test pits completed within the boundary of AOC 19 during the SWMU 25/Landfill 8 RFI in 1997. The Phase II excavation activities at AOC 19 were initiated and completed in August 2001. One soil sample was collected from the floor of exploratory excavation THGLAOC1905 due to the uncovering of three crushed 55-gallon drums. This sample, THGLAOC1905-02, was analyzed for Appendix IX VOCs (SW8260B), SVOCs (SW8270C), and metals/mercury (SW6010B/SW7000A series/SW7141A)<sup>3</sup>. Excavation findings and analytical results are presented in Section 4.1.

### 3.4.2.3 Soil Boring Installation/Soil Characterization

A total of 12 soil borings were advanced at AOC 19 during Phase II of the SI, 3 of which were completed as monitoring wells. As stated in the Phase II WP Addendum (HydroGeoLogic, 2000b), the purpose of the Phase II investigation was twofold: to sample selected soil intervals for analysis of TCE by method SW8260B in order to confirm or delineate the results of the Phase I soil investigation, and to install and sample groundwater monitoring wells immediately downgradient from the site. Six Phase II borings were originally planned; three of these borings (BHGLAOC1905, BHGLAOC1906, and BHGLAOC1907) would be advanced and sampled for confirmation/delineation, and three others (WHGLTA050, WHGLTA051, and WHGLTA052) would be advanced and sampled for delineation purposes, and then completed as groundwater monitoring wells (see Section 3.4.2.4). Based on geophysical investigation results and the analytical results from subsequent exploratory excavations (see Sections 3.2.4.1 and 3.2.4.2 above), the SI was expanded to include borings BHGLAOC1908, BHGLAOC1909, and BHGLAOC1910. Based on the August 2001 Phase II results, three additional soil borings, BHGLAOC1911, BHGLAOC1912, and BHGLAOC1913 were advanced in December 2001. These additional borings were advanced after consultation with AFCEE and with AFCEE's concurrence. All Phase II soil boring locations are depicted in red in Figure 3.1. The analytical results from the Phase II investigation are presented in Section 4.0. All soil sampling activities were performed in accordance with the project WPs (HydroGeoLogic, 2000a and 2000b). The rationale for Phase II boring locations and the analytes requested for analysis are presented in the following paragraphs.

---

<sup>2</sup> Although not identified in the original geophysical survey, THGLAOC1902 was excavated based upon a high magnetic locator reading at the time the exploratory excavations were being conducted at the site.

<sup>3</sup> This sample was analyzed for a broader list of analyses than proposed in the Excavation WP based on the materials revealed in excavation THGLAOC1905.

One of the twelve Phase II borings, BHGLAOC1907, was advanced for confirmation purposes. The 10-foot interval of this confirmation boring was sampled in August 2001 in order to confirm a TCE detection in the 10-foot interval of BHGLAOC1901.

Two of the twelve Phase II soil borings were advanced for additional site characterization purposes. These characterization borings, BHGLAOC1905<sup>4</sup> and BHGLAOC1908, were advanced in order to further characterize the bermed area southwest of THGLAOC1905, where road construction debris was uncovered. These borings were installed in order to evaluate whether any possible landfill material from SWMU 25/Landfill 8 within AOC 19 did not pose a threat to human health or the environment. Soil samples were collected from borings BHGLAOC1905 and BHGLAOC1908 every 5 feet from the ground surface to the top of the water table, or refusal, whichever occurred first. The following methods were used to analyze the Phase II characterization borings:

#### Appendix IX

- SW8260B - VOCs
- SW8270C - SVOCs
- SW6010B - trace elements (metals)
- SW7471A - mercury

A total of nine delineation borings (including the three borings completed as monitoring wells) were advanced during Phase II. In August 2001, three soil borings, BHGLAOC1906, BHGLAOC1909, and BHGLAOC1910, were advanced within and around the perimeter of AOC 19 in order to delineate concentrations detected in Phase I and excavation THGLAOC1905 (Figure 3.1). Based upon the August 2001 analytical results, it was necessary to advance three additional soil borings, BHGLAOC1911 through BHGLAOC1913, in December 2001 for delineation. Based on the results of the Phase I and II soil samples, the samples from the following borings were analyzed for TCE by method SW8260B: BHGLAOC1906, BHGLAOC1913, and WHGLTA050 through WHGLTA052. Based on the analytical results of the sample collected from exploratory excavation THGLAOC1905, the samples from the following borings were analyzed for polynuclear aromatic hydrocarbons (PAHs) by method SW8270C: BHGLAOC1909, BHGLAOC1910, BHGLAOC1911, and BHGLAOC1912. Additional detail on the Phase II delineation borings is provided in the following paragraphs.

Soil boring BHGLAOC1906 was installed in order to delineate TCE in the subsurface soil south of BHGLAOC1904 in accordance with the Phase II WPs (HydroGeoLogic, 2000b). Soil borings BHGLAOC1909 and BHGLAOC1910 were added during the field effort to delineate the detections of PAHs in the soil sample collected from floor of excavation THGLAOC1905. Soil boring BHGLAOC1909 was sampled at the 5-foot interval for southwestern delineation of

<sup>4</sup> BHGLAOC1905 was originally planned as a eastern delineation boring for TCE; however, based on low TCE concentrations in the soil samples collected during monitoring well installation, this was no longer necessary.

THGLAOC1905, and BHGLAOC1910 was sampled at the surface, 5-foot, and 10-foot intervals for western delineation of THGLAOC1905. A total of 3 surface and 11 subsurface (10 samples and one duplicate) soil samples were submitted for chemical analysis in August 2001.

Three delineation soil borings, BHGLAOC1911 through BHGLAOC1913, were advanced within and around the perimeters of AOC 19 in December 2001. Based on the August 2001 analytical results, a vertical delineation boring (BHGLAOC1911) and a northern delineation boring (BHGLAOC1912) for the samples collected from the exploratory excavation were necessary. The 10-foot interval from boring BHGLAOC1911 and the 5- and 10-foot intervals for BHGLAOC1912 were sampled and analyzed for PAHs using method SW8270C; the 5- and 10-foot intervals of boring BHGLAOC1913 were sampled and analyzed for TCE by method SW8260B. In December 2001, six subsurface soil samples (five samples and one duplicate) were submitted for chemical analysis.

The remaining three delineation soil borings were completed as monitoring wells in February 2001: WHGLTA050, WHGLTA051, and WHGLTA052. Based on the results of the Phase I soil investigation, soil samples were collected from the surface and 5-foot intervals of monitoring wells WHGLTA050 and WHGLTA051. In addition, a soil sample was collected from the 5-foot interval of monitoring well WHGLTA052. All soil samples collected during the installation of the AOC 19 monitoring wells were analyzed for TCE by method SW8260B. A total of two surface and three subsurface soil samples were submitted for chemical analysis in February 2001.

#### **3.4.2.4 Monitoring Well Installation/Groundwater Characterization**

Monitoring wells WHGLTA050, WHGLTA051, and WHGLTA052 were installed down- and crossgradient of AOC 19 in February 2001. Monitoring wells WHGLTA050 and WHGLTA051 were installed further east of the fence than preferred due to piles of golf course construction rubble that restricted rig access near the NAS Fort Worth boundary. Delineation soil samples collected during monitoring well installation are discussed in Section 3.4.2.3.

Three rounds of groundwater sampling were conducted two months apart according to the RCRA permit. Sampling occurred in February, April, and June 2001. In addition to the three wells installed for this investigation, existing upgradient monitoring well WHGLTA004 and existing crossgradient monitoring well WHGLTA801 were sampled for TCE by method SW8260B<sup>5</sup>.

---

<sup>5</sup> Groundwater samples were analyzed for the full suite of VOCs listed in the 2000 Basewide QAPP (HydroGeoLogic, 2000b) in conjunction with the April 2001 Semi-Annual Sampling Event conducted in support of the Basewide Groundwater Sampling and Analysis Program (GSAP). Only the TCE results for the April 2001 samples are relevant to the SI. The full set of analytical results for the April 2001 sampling event is presented in *Basewide Groundwater Sampling and Analysis Program, April 2001 Semi-Annual Report* (HydroGeoLogic, 2001c).

The analytical results from the groundwater samples are intended to determine if the soil at AOC 19 is impacting groundwater at the site. Results of the AOC 19 groundwater investigation are presented in Section 4.5 of this SI.


### **3.5 ELEVATION AND LOCATION SURVEY**

All sampling points including soil borings, monitoring wells, and excavations were surveyed by Baird, Hampton & Brown, Inc., of Fort Worth, Texas. In addition, the corners of the geophysical grids were also surveyed. Vertical and horizontal measurements were collected in accordance with the RFI WPs (HydroGeoLogic, 2000a). Surveying data are provided in Appendix D.

*This page was intentionally left blank.*

## FIGURES







# TAB

*SECTION 4.0*

---

## 4.0 INVESTIGATION RESULTS

This section presents the results from the investigation activities conducted during the AOC 19 SI. The findings from the exploratory excavations are presented in Table 4.1 and the analytical results are summarized in Tables 4.2 through 4.5. All soil and groundwater samples were analyzed in accordance with the rationale presented in the RFI/SI WPs (HydroGeoLogic, 2000a) and Phase II WPs Addendum (HydroGeoLogic, 2000b).

As stated previously, analytical results were compared to the applicable RRS 1 values in order to determine if a release has occurred at AOC 19. The results from samples collected and analyzed for trace metals were compared to the approved base-specific background values as presented in the Final Basewide Background Study (Jacobs, 1998). The results from samples collected and analyzed for organic compounds were compared to respective MQLs. Furthermore, all analytical results exceeding RRS 1 values were compared to available MSCs. All AOC 19 soil detections are presented in tabular form in this section. Complete analytical data summaries for soil samples are presented in Appendix E. As the complete analytical data for all Phase II groundwater samples are presented in Table 4.5 in this section, these data are not included in Appendix E.

The SPLP extraction method was used in order to possibly provide a site specific MSC if analytes were detected above the applicable MSC in the original sample. When an SPLP extraction and analysis was performed, the result was compared to the applicable industrial groundwater MSC. If the result in the extract was below this groundwater MSC, then the corresponding soil MSC was adjusted to the highest soil value that is associated with a “passing” SPLP result, provided that there is no soil result at the site with a lower detection for the same analyte that “failed” subsequent SPLP analysis.

### 4.1 GEOPHYSICAL AND EXPLORATORY EXCAVATION FINDINGS

A total of eight test pits were excavated at SWMU 25/Landfill 8 in 1997, three of which (THGLTA026, THGLTA027, and THGLTA028) are within the AOC 19 boundary (Figure 3.1). The contents of the three SWMU 25/Landfill 8 test pits are described in Table 4.1. The results of the geophysical survey conducted as part of the AOC 19 SI revealed 15 distinct anomalies, as depicted in Figure 4.1. However, all the anomalies, with the exception of A-14, are located along the perimeter road and/or the boundary of SWMU 25/Landfill 8<sup>6</sup>. The anomalies along the road are attributed to road fill and construction debris from the adjacent landfill, such as found in THGLTA026 (Table 4.1). Based on the results of the geophysical survey and the SWMU 25/Landfill 8 RFI, exploratory excavations were conducted at the southeastern anomaly (A-14), the northern anomaly (A-4), and the south central anomaly (A-13) as depicted in Figure 4.1 (HydroGeoLogic, 2001a).

---

<sup>6</sup> HydroGeoLogic performed an RFI at SWMU 25/Landfill 8 in several phases from August 1997 through June 2000, and an interim remedial action was performed by IT in July and August 2000. SWMU25/Landfill 8 received closure in June 2001 under RRS 2 based on the findings presented in the Final RFI Report (HydroGeoLogic, 2001b).

The exploratory excavations were advanced over anomalies that were not within the boundary of SWMU 25/Landfill 8. A total of five exploratory excavations were advanced in August 2001 (THGLAOC1901 through THGLAOC1905). A magnetic locator was used in the field to confirm the location and removal of the anomalies. All metal debris removed from the excavations at AOC 19 was determined to be non-hazardous and was taken to a recycling facility off base for disposal. Photographs and schematics of each exploratory excavation conducted during the AOC 19 SI are presented as Figures 4.2 through 4.6. Table 4.1 presents a description of the materials encountered in both the exploratory excavations completed at AOC 19 and the three relevant test pits from the 1997 SWMU 25/Landfill 8 RFI.

Excavation THGLAOC1901 was located in the area of anomaly A-14, in the southeast corner of AOC 19 (Figure 4.1). Excavation THGLAOC1901 measured 6-feet long by 5-feet wide by 1-foot deep. The source of the geophysical anomaly at THGLAOC1901 was a 2-feet wide by 2.5-feet long by 0.25-inch thick steel plate, depicted in Figure 4.2. No staining, odor, nor PID detections were observed in the soil within the excavation; as a result exploratory excavation THGLAOC1901 was immediately backfilled with the excavated soil in the order that it was removed.

Excavation THGLAOC1902 was located in the area of anomaly A-13, in the south central portion of AOC 19 (Figure 4.1). The magnetic locator used prior to all excavations, identified potential buried metal approximately 20 feet east of the area where A-13 was located on Figure 4.1. Therefore an additional exploratory excavation to the four proposed in the Excavation WP (HydroGeoLogic, 2001a) was advanced in this area. Excavation THGLAOC1902 measured 9-feet long by 15-feet wide by 3-feet deep. The source of the anomaly at THGLAOC1902 consisted of a 20-foot long, 2-inch steel pipe and an approximately 1.5 x 2.5 foot piece of sheet steel, depicted in Figure 4.3. No staining, odor, nor PID detections were observed in the soil within the excavation; as a result exploratory excavation THGLAOC1902 was immediately backfilled with native soil in the order that it was removed.

Excavation THGLAOC1903 was located over anomaly A-13 (Figure 4.1). Excavation THGLAOC1903 measured 10-feet long by 7-feet wide by 2.5-feet deep. The magnetic locator received weak signals in this area, and only reinforced concrete, barbwire, and pieces of wire cable were found within the excavation. THGLAOC1903 is depicted in Figure 4.4. No staining, odor, nor PID detections were observed in the soil within the excavation; as a result exploratory excavation THGLAOC1903 was immediately backfilled with native soil in the order that it was removed.

Although two exploratory excavations were planned within anomaly A-4 in the Excavation WPs (HydroGeoLogic, 2001a), only one of the two planned excavations (THGLAOC1905) was advanced in the area of anomaly A-4 (Figure 4.1). This change was based on the visual observation of concrete at the top of the berm in the proposed area and the proximity of the proposed location to SWMU 25/Landfill 8. Therefore the second excavation proposed within anomaly A-4 (THGLAOC1904) was alternatively advanced in the central portion of AOC 19 over anomaly A-5 (Figure 4.1). The new location of excavation THGLAOC1904 was based

on anomalous readings at the base of the berm by the magnetic locator used in the field. Excavation THGLAOC1904 measured 15-feet long by 9-feet wide by 4.5-feet deep. The only items unearthed in excavation THGLAOC1904 consisted of a piece of scrap metal and wire cable, shown in Figure 4.5. No staining, odor, nor PID detections were observed in the soil within the excavation; as a result exploratory excavation THGLAOC1904 was immediately backfilled with native soil in the order that it was removed.

THGLAOC1905 was excavated in the area of anomaly A-4 in the north central area of AOC 19. Excavation THGLAOC1905 measured 13-feet long by 21-feet wide by 3-feet deep. The source of the geophysical anomaly at THGLAOC1905 was construction debris which included 3 crushed, rusted, and empty 55-gallon drums; 2 crushed, rusted, and empty 5-gallon buckets; nails; a large amount of reinforced concrete; roofing tar; resin; glass; metal wire; and wood. The excavation and objects removed are depicted in Figure 4.6. No staining, odor, nor PID detections were observed in the soil within the excavation, stockpile, or around and inside the drums and buckets. However, based on the contents of the unearthed materials, two soil samples were collected to characterize the soil within the excavation. Soil sample THGLAOC1905-02 was collected from the excavation floor (3-feet below ground surface [bgs]) beneath the location where the drums were discovered. This sample was analyzed for Appendix IX VOCs (SW8260B), SVOCs (SW8270C), and metals/mercury (SW6010B/7000)<sup>7</sup>. The second soil sample was collected from the stockpile for waste characterization and analyzed for reactivity (SW846, Chapter 7), ignitability (SW1020A), corrosivity (SW1110), total petroleum hydrocarbons (TNRCC method TX1005), VOCs (SW8260B), and metals (SW6010B/7000A). The analysis of these samples was expedited by the analytical laboratory. The stockpiled soil was covered and the open excavation was secured until the results were received. Based on the analytical results of the stockpiled soil, the excavation was backfilled with the excavated soil in the order that it was removed.

No concentrations of metals or VOCs were detected above RRS 1 values in the soil samples collected at THGLAOC1905. The following SVOC constituents were detected above RRS 1 concentrations in the subsurface soil sample collected from the floor of THGLAOC1905:

- **bis(2-Ethylhexyl)phthalate** was detected at 0.66 milligrams per kilogram (mg/kg) in the soil sample collected from the floor of test pit THGLAOC1905. This result is above the RRS 1 of 0.33 mg/kg and the MSC of 0.6 mg/kg. Analyzing an SPLP extract of sample THGLAOC1905-02 developed a site-specific MSC of 0.66 mg/kg. The site-specific MSCs for AOC 19 are listed in Table 4.2.
- **PAHs** are a class of compounds represented by 16 analytes on the SVOC analyte list. Twelve of these compounds were detected above RRS 1 in the sample collected from the floor of test pit THGLAOC1905. Anthracene; benzo[*g,h,i*]perylene; chrysene; fluoranthene; phenanthrene; and pyrene were detected above the associated RRS 1 values, but below the associated RRS 2 values. Benzo[*a*]anthracene; benzo[*a*]pyrene;

<sup>7</sup> Additional analyses were added to those proposed in the Excavation WP in order to more completely characterize the soil beneath the materials uncovered in THGLAOC1905.

benzo[*b*]fluoranthene; benzo[*k*]fluoranthene; dibenzo[*a,h*]anthracene; and indeno[1,2,3-*cd*]pyrene were detected above the associated RRS 2 values. Site-specific MSCs were developed for these six compounds by analyzing an SPLP extract of this sample (Table 4.2).

The analytical results of sample THGLAOC1905-02 are listed in Table 4.4 and discussed in Section 4.4.

## 4.2 LITHOLOGIC FINDINGS

A total of four soil borings, BHGLAOC1901 through BHGLAOC1904, were initially advanced at AOC 19 (Figure 4.1). Based on the results of Phase I and following completion of the geophysical survey in August 2001, six additional soil borings, BHGLAOC1905 through BHGLAOC1910, were advanced at AOC 19. BHGLAOC1905 and BHGLAOC1908 were characterization borings added to the Phase II sampling plan based upon the excavation findings in order to ensure that any construction debris within the bermed area along the road did not pose a threat to human health or the environment. Borings BHGLAOC1909 and BHGLAOC1910 were added to the sampling plan in order to delineate the constituents detected in the floor sample from THGLAOC1905, and three additional borings (BHGLAOC1911 through BHGLAOC1913) were added in December 2001 in order to achieve delineation of the August 2001 analytical results (see Section 3.2.4.3).

As previously mentioned in Section 3.0, drilling locations were determined based on accessibility, utility locations, geophysical survey results, and topography, which slopes downward toward Farmer's Branch Creek in a southerly direction. The placement of down- and crossgradient monitoring wells WHGLTA050, WHGLTA051, and WHGLTA052, was constrained by a debris area that did not allow for drill rig access near the NAS Fort Worth JRB fence line, depicted in Figure 3.1. The debris was a result of ongoing construction and renovation activities at the Carswell golf course.

No debris or suspected landfill materials were encountered in any of the AOC 19 soil borings. The only construction debris encountered was within exploratory excavation THGLAOC1905 (August 2001), and THGLTA026, THGLTA027, and THGLTA028 from the SWMU 25/Landfill 8 RFI investigation in 1997. Boring logs are presented as Appendix F, and the contents of the exploratory excavations are presented in Table 4.1.

The surface of AOC 19 is covered by grass with a bermed area at the north and northwestern edge that follows the curve of Perimeter Road, and then levels out to the south and to the east. South of AOC 19 beyond the NAS Fort Worth JRB fence line, the ground surface drops off into Farmers Branch Creek. The depth to bedrock at AOC 19 ranges from 7 feet to 12.5 feet bgs. Water table elevations ranged from 5.5 feet to 11 feet bgs.

The lithology of AOC 19 was analyzed using a southwest-northeast transect along borings WHGLTA801, BHGLAOC1905, BHGLAOC1908, and BHGLAOC1910, depicted as cross-

section A-A' in Figure 4.7. Boring WHGLTA801 exhibited fill material to a depth of 3 feet bgs, overlying silty clay between 3 and 7 feet bgs. A clayey gravel layer was encountered between 7 and 11 feet, overlying clayey sandy gravel between 11 and 14 feet bgs. Refusal at bedrock was reached at 14.5 feet bgs. Boring BHGLAOC1905 exhibited a layer of concrete and fill material from the surface to a depth of 3 feet bgs followed by a layer of silty clay between 3 and 6 feet bgs. A sand and gravel layer was encountered between 6 and 8 feet bgs, overlying clayey gravelly sand between 8 and 10.5 feet bgs, with refusal at 10.5 feet bgs. Boring BHGLAOC1908 also exhibited fill material from the ground surface to a depth of 3 feet bgs followed by silty clay from 3 to 6 feet bgs, overlying clay between 6 and 12 feet bgs, and weathered limestone from 12 and 12.5 feet bgs, reaching refusal at 12.5 feet bgs. Boring BHGLAOC1910 exhibited fill material from the ground surface to a depth of 8 feet bgs, overlying silty clay with limestone gravel between 8 and 9 feet bgs, transitioning to silty sand and gravel from 9 to 12 feet bgs. Boring BHGLAOC1910 was terminated at 12 feet bgs since it was advanced as a delineation boring for the 5- and 10-foot intervals of sample THGLAOC1905. Boring logs are presented in Appendix F.

The lithology at AOC 19 was analyzed using a west-east transect along borings BHGLTA812, BHGLAOC1905, BHGLTA814, BHGLAOC1902, and WHGLTA050, depicted by cross-section B-B' in Figure 4.7. Boring BHGLTA812 exhibited fill material from the ground surface to a depth of 11 feet bgs overlying silty clay between 11 and 13 feet bgs. A gravelly clay layer was encountered between 13 and 17 feet, which overlies a layer of sandy clay between 17 and 21 feet bgs, with silty gravel from 21 to 23 feet bgs. Boring BHGLTA812 was terminated at 23 feet bgs when the water table was encountered. Boring BHGLAOC1905 similarly exhibited a layer of concrete and fill material from the surface to a depth of 3 feet bgs overlying silty clay between 3 and 6 feet bgs. This layer is overlying sand and gravel between 6 and 8 feet bgs and clayey gravelly sand between 8 and 10.5 feet bgs, reaching refusal at 10.5 feet bgs. Boring BHGLTA814 also exhibited fill material from the ground surface to a depth of 4 feet bgs and silty clay between 4 and 10 feet bgs, however, a layer of gravelly clay was encountered from 10 to 11 feet bgs before refusal was reached at 11 feet bgs. Boring BHGLAOC1902 exhibited fill material from the ground surface to a depth of 2.5 feet bgs overlying a thick layer of sandy clayey silt between 2.5 and 8 feet bgs. This layer is overlying silty sand with clay and gravel from 8 to 11 feet bgs. Boring BHGLAOC1902 was terminated at 11 feet bgs as the water table was reached at 9.5 feet bgs. WHGLTA050 was a shallow boring with a layer of fill material from the ground surface to a depth of 2 feet bgs overlying silty clay with gravel between 2 and 4 feet bgs followed by a layer of clayey sand from 4 to 5.5 feet bgs. Saprolite was encountered from 5.5 to 7 feet bgs, with refusal in limestone bedrock at 7 feet bgs. Boring logs are included in Appendix F.

Groundwater was encountered from approximately 5.5 to 11 feet bgs at AOC 19. Groundwater flow direction across the site trends to the south-southeast towards Farmers Branch Creek.



### 4.3 SURFACE SOIL DETECTIONS

Surface soil samples were collected for characterization purposes from Phase I borings BHGLAOC1901 through BHGLAOC1904, and Phase II borings BHGLAOC1905 and BHGLAOC1908. All characterization samples were analyzed for the list of analyses presented in Section 3.2.2. As described below, boring BHGLAOC1902 contained the only surface soil sample with an analyte concentration above the associated RRS 1 value. There were no inorganic analytes detected above background in any surface soil characterization samples, and TCE was the only organic constituents detected above RRS 1. Soil sampling locations are depicted in Figure 4.8. Soil sampling results are listed in Table 4.3.

The surface soil samples were collected for delineation purposes from boring BHGLAOC1910, and the borings advanced to install monitoring wells WHGLTA050 and WHGLTA051. The delineation surface soil sample collected at BHGLAOC1910 was analyzed for PAHs by method SW8270C; the delineation surface soil samples collected at WHGLTA050 and WHGLTA051 were analyzed for TCE by method SW8260B. There were no analytes detected above RRS 1 in the delineation surface soil samples. All analytes detected in surface soil samples are presented in Table 4.3. Analytes detected above RRS 1 concentrations are depicted in Figure 4.8.

#### 4.3.1 Inorganic Constituents

No concentrations of metals were detected above RRS 1 in any of the surface soil samples collected at AOC 19.

#### 4.3.2 Organic Constituents

No concentrations of SVOCs were detected above RRS 1 in surface soils at AOC 19. The following VOC was detected above RRS 1 in the surface soil samples collected at AOC 19:

- TCE was detected at 0.019 mg/kg in the surface soil sample collected from boring BHGLAOC1902. This result is only slightly above the RRS 1 concentration (0.005 mg/kg) and well below the MSC (0.5 mg/kg) for this analyte.

### 4.4 SUBSURFACE SOIL DETECTIONS

Characterization subsurface soil samples were collected for chemical analysis at seven locations at AOC 19: Phase I borings BHGLAOC1901 through BHGLAOC1904; Phase II borings BHGLAOC1905 and BHGLAOC1908; and from the bottom of exploratory excavation THGLAOC1905. All characterization samples were analyzed for the list of analyses presented in Section 3.2.2.

Delineation subsurface soil samples were collected from borings BHGLAOC1906, BHGLAOC1909, BHGLAOC1910, and BHGLAOC1911 through BHGLAOC1913.

Delineation subsurface soil samples were also collected from the borings advanced to install monitoring wells WHGLTA050 through WHGLTA052. The delineation subsurface soil samples collected at borings BHGLAOC1906, BHGLAOC1913, and well installation borings WHGLTA050 through WHGLTA052 were analyzed for TCE by method SW8260B. The delineation subsurface soil samples collected at BHGLAOC1909 through BHGLAOC1912 were analyzed for SVOCs by method SW8270C. All analytes detected in subsurface soil samples are presented in Table 4.4, and those analytes detected above RRS 1 are depicted in Figure 4.8. Analytical results indicate concentrations of two metals (arsenic and chromium), two VOCs (*cis*-1,2-dichloroethene and TCE), and several SVOCs (bis(2-ethylhexyl)phthalate and PAHs) were detected above RRS 1 in the subsurface soils at AOC 19.

One confirmation sample, BHGLAOC1907, was collected in order to confirm the TCE detection at the 10-foot interval of BHGLAOC1901. TCE was not detected in this confirmation sample. This soil sampling location is depicted in Figure 4.8, and the result is listed in Table 4.4.

#### 4.4.1 Inorganic Constituents

The following metals were detected above RRS 1 concentrations in the subsurface soil samples collected at AOC 19:

- **Arsenic** was detected at 6.7 mg/kg in the subsurface soil sample collected from the 10-foot interval of boring BHGLAOC1901; this detection of arsenic is slightly above both the background value and the MSC (6.58 mg/kg).
- **Chromium** was detected at 17.7 mg/kg in the subsurface soil sample collected from the 5-foot interval of boring BHGLAOC1908; this detection of chromium is slightly above both the background value and the MSC (16.31 mg/kg).

#### 4.4.2 Organic Constituents

The following organic constituents were detected above RRS 1 concentrations in the subsurface soil samples collected at AOC 19:

- ***cis*-1,2-Dichloroethene** was detected at 0.007 mg/kg in the soil sample collected from the 10-foot interval of boring BHGLAOC1908. This result is only slightly above the RRS 1 concentration (0.005 mg/kg) and well below the MSC (7 mg/kg) for this analyte.
- **Trichloroethene** was detected in the following subsurface soil samples: the 10-foot interval of boring BHGLAOC1901 (0.019 mg/kg); the 5-foot interval of boring BHGLAOC1902 (0.008 mg/kg); the 5-foot interval of boring BHGLAOC1904 (0.009); the 5-foot interval of boring BHGLAOC1905 (0.006 mg/kg); the 5- and 10-foot intervals of boring BHGLAOC1906 (0.033 mg/kg and 0.008 J mg/kg, respectively);

the 10-foot interval of boring BHGLAOC1908 (0.030 mg/kg); and the 5- and 10-foot intervals of boring BHGLAOC1913 (0.051 J mg/kg and 0.036 mg/kg, respectively). Most of these results are only slightly above the RRS 1 concentration (0.005 mg/kg). All concentrations are well below the MSC (0.5 mg/kg) for this analyte.

- **bis(2-Ethylhexyl)phthalate** was detected at a concentration of 0.42 mg/kg in the soil sample collected from the 10-foot interval of boring BHGLAOC1905 and at 0.66 mg/kg in the soil sample collected from the floor of test pit THGLAOC1905 (Section 4.1). These results are above the RRS 1 of 0.33 mg/kg. Although the result from BHGLAOC1905 is below the MSC (0.6 mg/kg) for this analyte, the result from THGLAOC1905 exceeded the RRS 2 value. As a result, an SPLP extract of sample THGLAOC1905 was analyzed and a site-specific MSC of 0.66 mg/kg was developed. Site-specific MSCs for AOC 19 are listed in Table 4.2.
- **PAHs** were detected above RRS 1 in the 10-foot interval (or its duplicate) of boring BHGLAOC1911. Benzo[*g,h,i*]perylene; chrysene; fluoranthene; phenanthrene; and pyrene were detected above the associated RRS 1 values, but below the associated RRS 2 values, at BHGLAOC1911. Benzo[*a*]anthracene; benzo[*a*]pyrene; benzo[*b*]fluoranthene; benzo[*k*]fluoranthene; dibenzo[*a,h*]anthracene; and indeno[1,2,3-*cd*]pyrene were detected above the RRS 2 value at exploratory excavation THGLAOC1905, and site-specific MSCs were developed for these six compounds by analyzing an SPLP extract of this sample. These compounds were detected above RRS 1 but below the site-specific MSC in the sample from boring BHGLAOC1911, with the exception of dibenzo[*a,h*]anthracene (which was below RRS 1). Site-specific MSCs for AOC 19 are listed in Table 4.2.

#### 4.5 GROUNDWATER DETECTIONS

Groundwater samples were collected for chemical analysis from five monitoring wells at AOC 19: WHGLTA004, WHGLTA050, WHGLTA051, WHGLTA052, and WHGLTA801. Monitoring wells WHGLTA050, WHGLTA051, and WHGLTA052 were installed as part of Phase II of the SI for cross- and downgradient groundwater characterization. WHGLTA004 and WHGLTA801 are pre-existing monitoring wells located upgradient and within AOC 19 (and also within SWMU 25/Landfill 8), respectively. Three rounds of groundwater sampling were conducted in February, April, and June 2001. All groundwater samples were analyzed for TCE (SW8260B) based on the soil sampling results from Phase I. Analytical results from the groundwater investigation are presented in Table 4.5. The groundwater sampling locations and results above the RRS 1 for TCE are depicted in Figure 4.9. These results indicate the highest concentrations of TCE were detected in the upgradient monitoring well (WHGLTA004) at AOC 19.

The following concentrations of TCE were detected above RRS 2 in the groundwater samples collected at AOC 19:

- TCE was detected in all five wells in concentrations above RRS 2 during all three rounds of sampling. The highest detections of TCE were detected in WHGLTA004, the upgradient well located in SWMU 25, at concentrations of 0.53 mg/L in February 2001; 0.45 mg/L in April 2001; and 0.66 mg/L in June 2001. The lowest detections of TCE were detected in WHGLTA050, a cross- and downgradient monitoring well, at concentrations of 0.15 J mg/L in February 2001; 0.17 mg/L in April 2001; and 0.26 mg/L in June 2001. WHGLTA051, another downgradient monitoring well, had the second lowest detections of TCE at 0.19 mg/L in February 2001; 0.17 mg/L in April 2001; and 0.31 mg/L in June 2001. WHGLTA801, a monitoring well within AOC 19 (and within SWMU 25/Landfill 8), had detections of 0.36 mg/L in February 2001; 0.15 mg/L in April 2001; and 0.34 mg/L in June 2001. WHGLTA052, the downgradient monitoring well between AOC 19 and Farmers Branch Creek, had detections of 0.3 mg/L in February 2001 and April 2001; and 0.57 mg/L in June 2001.

*This page was intentionally left blank.*

**TABLES**

**Table 4.1**  
**Excavation Results**  
**AOC 19**  
**NAS Fort Worth JRB, Texas**

<b>Excavation Location</b>	<b>Excavation Dimensions</b>	<b>Contents</b>
THGLAOC1901	6' x 5' x 1'	A 2' x 2.5' x 0.25" steel plate. No staining, odor, or elevated PID readings were encountered. Excavation was backfilled with native soil.
THGLAOC1902	9' x 15' x 3'	A 20' long 2" pipe. No staining, odor, or elevated PID readings were encountered. Excavation was backfilled with native soil.
THGLAOC1903	10' x 7' x 2.5'	Reinforced concrete, barbwire, and wire cable. No staining, odor, or elevated PID readings were encountered. Excavation was backfilled with native soil.
THGLAOC1904	15' x 9' x 4.5'	Scrap metal and wire cable. No staining, odor, or elevated PID readings were encountered. Excavation was backfilled with native soil.
THGLAOC1905	13' x 21' x 3'	Various construction type debris consisting of three crushed and empty drums, a crushed and empty paint can, nails, reinforced concrete, roofing tar, resin, glass, metal wire, and wood. No odor, staining, or elevated PID readings were detected around or inside the excavation or its contents. A soil sample was collected and analyzed for VOCs (SW8260B), SVOCs (SW8270C), and metals/mercury (SW6010B/7000) from the excavation floor beneath where the crushed drums were located. After analytical results were received, the excavation was backfilled with native soil.
THGLTA026*	40' x 3' x 6'	Construction debris, large pieces of asphalt and concrete, and the footing of an old building.
THGLTA027*	40' x 2' x 2'	Concrete at surface and sand encountered at 2 feet bgs.
THGLTA028*	40' x 2' x 9'	No waste materials were encountered.

## Notes:

\*Advanced in 1997 as part of the SWMU 25/Landfill 8 RFI

bgs = below ground surface

Table 4.2  
Site-Specific MSCs  
AOC 19  
NAS Fort Worth JRB, Texas

Location	Depth	Method	Analyte	RRS 1 (mg/kg)	RRS 2 (mg/kg)	Result (mg/kg)	GW-Ind (mg/L)	SPLP Result (mg/L)	Revised MSC (mg/kg)
THGLAOC1905	2.5'	SW8270C	Benzo[a]anthracene	0.33	0.33	[(2)]	0.01	ND	2
THGLAOC1905	2.5'	SW8270C	bis(2-Ethylhexyl)phthalate	0.33	0.6	[(0.66)]	0.01	ND	0.66
THGLAOC1905	2.5'	SW8270C	Benzo[k]fluoranthene	0.33	0.39	[(1.4)]	0.01	ND	1.4
THGLAOC1905	2.5'	SW8270C	Benzo[a]pyrene	0.33	0.33	[(1.8)]	0.01	ND	1.8
THGLAOC1905	2.5'	SW8270C	Indeno[1,2,3-c,d]pyrene	0.33	0.33	[(1.1)]	0.01	ND	1.1
THGLAOC1905	2.5'	SW8270C	Dibenz[a,h]anthracene	0.33	0.33	[(0.43)]	0.01	ND	0.43
THGLAOC1905	2.5'	SW8270C	Benzo[b]fluoranthene	0.33	0.33	[(2.2)]	0.01	ND	2.2

## Notes

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

GW-Ind = TNRCC Groundwater MSC for Industrial Use

MSC = medium-specific concentration

Values above RRS 1 are bold and enclosed in ( )

Values above RRS 2 are bold and enclosed in [( )]

ND = analyte not detected

SPLP = synthetic precipitation leaching procedure



**Table 4.3**  
**Surface Soil Detections**  
**AOC 19**  
**NAS Fort Worth JRB, Texas**

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1901 00 ft 2000-05-12	BHGLAOC1901 00 ft 2000-05-26	BHGLAOC1902 00 ft 2000-05-15
SW6010B	Arsenic	5.85	5.85	mg/kg	4.9 F	NA	4.9
SW6010B	Barium	233	233	mg/kg	44.6	NA	75 J
SW6010B	Beryllium	1.02	1.02	mg/kg	0.84	NA	1
SW6010B	Cadmium	0.556	0.556	mg/kg	--	NA	0.24 F
SW6010B	Chromium, total	25.86	25.86	mg/kg	12.8	NA	20.3 J
SW6010B	Cobalt	11.05	613.2	mg/kg	4.6 F	NA	5.5 F
SW6010B	Copper	17.37	130	mg/kg	7.4 F	NA	10.5
SW6010B	Nickel	14.6	204.4	mg/kg	10 F	NA	13.2 J
SW6010B	Tin	10	6132	mg/kg	1.2 F	NA	--
SW6010B	Vanadium	46.3	71.54	mg/kg	31.1 F	NA	36.8 J
SW6010B	Zinc	38.8	3066	mg/kg	22.7 F	NA	36.2
SW7041	Antimony	0.56	0.6	mg/kg	--	NA	--
SW7421	Lead	30.97	30.97	mg/kg	14.9 F	NA	10.4
SW7471A	Mercury	0.14	0.151	mg/kg	--	NA	--
SW8260B	Trichloroethene (TCE)	0.005	0.5	mg/kg	NA	--	(0.019)
SW8270C	Benzyl alcohol	0.33	3066	mg/kg	--	NA	--
SW8270C	Benzyl butyl phthalate	0.33	2044	mg/kg	0.28 F	NA	--

## Notes:

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 1 are bold and enclosed in ( )

-- = analyte not detected

NA = not analyzed

F = estimated value below the reporting limit

J = estimated value above the reporting limit

Table 4.3 (continued)  
Surface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1903 00 ft 2000-05-15	BHGLAOC1903 00 ft 2000-05-15 Dup	BHGLAOC1904 00 ft 2000-05-15	BHGLAOC1905 00 ft 2001-08-20
SW6010B	Arsenic	5.85	5.85	mg/kg	3 F	4	2.8 F	4.9
SW6010B	Barium	233	233	mg/kg	66.1 J	70.5 J	81.1 J	78.1
SW6010B	Beryllium	1.02	1.02	mg/kg	0.44 J	0.84	0.6	0.92
SW6010B	Cadmium	0.556	0.556	mg/kg	0.21 F	0.29 F	0.27 F	--
SW6010B	Chromium, total	25.86	25.86	mg/kg	12.8 J	14.9 J	13.1 J	16.3
SW6010B	Cobalt	11.05	613.2	mg/kg	3.3 F	4.9	3 F	5.3 F
SW6010B	Copper	17.37	130	mg/kg	5.4 F	10.2	5.7 F	10.9
SW6010B	Nickel	14.6	204.4	mg/kg	8.1 F	10.7 J	8 J	11.5
SW6010B	Tin	10	6132	mg/kg	--	--	--	--
SW6010B	Vanadium	46.3	71.54	mg/kg	26.5 F	29.1 J	25.5 J	31.5
SW6010B	Zinc	38.8	3066	mg/kg	17.2 F	26.2 J	17.7 F	--
SW7041	Antimony	0.56	0.6	mg/kg	--	--	--	--
SW7421	Lead	30.97	30.97	mg/kg	5.6	8.9	6.9 J	12.7
SW7471A	Mercury	0.14	0.151	mg/kg	--	--	--	--
SW8260B	Trichloroethene (TCE)	0.005	0.5	mg/kg	--	--	0.005 J	--
SW8270C	Benzyl alcohol	0.33	3066	mg/kg	--	--	--	--
SW8270C	Benzyl butyl phthalate	0.33	2044	mg/kg	--	--	--	--

## Notes:

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 1 are bold and enclosed in ( )

-- = analyte not detected

NA = not analyzed

F = estimated value below the reporting limit

J = estimated value above the reporting limit

Table 4.3 (continued)  
Surface Soil Detections  
AOC 19

NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1908 00 ft 2001-08-21	BHGLAOC1910 00 ft 2001-08-22	WHGLTA050 00 ft 2001-02-07	WHGLTA051 00 ft 2001-02-07
SW6010B	Arsenic	5.85	5.85	mg/kg	4 2 F	NA	NA	NA
SW6010B	Barium	233	233	mg/kg	80.3	NA	NA	NA
SW6010B	Beryllium	1.02	1.02	mg/kg	0 79	NA	NA	NA
SW6010B	Cadmium	0 556	0 556	mg/kg	--	NA	NA	NA
SW6010B	Chromium, total	25.86	25.86	mg/kg	12.8	NA	NA	NA
SW6010B	Cobalt	11.05	613.2	mg/kg	5 4 F	NA	NA	NA
SW6010B	Copper	17.37	130	mg/kg	8.6 F	NA	NA	NA
SW6010B	Nickel	14.6	204.4	mg/kg	10 8	NA	NA	NA
SW6010B	Tin	10	6132	mg/kg	--	NA	NA	NA
SW6010B	Vanadium	46.3	71 54	mg/kg	25 1 F	NA	NA	NA
SW6010B	Zinc	38.8	3066	mg/kg	--	NA	NA	NA
SW7041	Antimony	0.56	0.6	mg/kg	0 43 F	NA	NA	NA
SW7421	Lead	30 97	30 97	mg/kg	11 1	NA	NA	NA
SW7471A	Mercury	0 14	0 151	mg/kg	0.013 F	NA	NA	NA
SW8260B	Trichloroethene (TCE)	0.005	0 5	mg/kg	--	NA	--	--
SW8270C	Benzyl alcohol	0.33	3066	mg/kg	--	--	NA	NA
SW8270C	Benzyl butyl phthalate	0.33	2044	mg/kg	--	--	NA	NA

Notes

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 1 are bold and enclosed in ( )

-- = analyte not detected

NA = not analyzed

F = estimated value below the reporting limit

J = estimated value above the reporting limit

Table 4.4  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1901 05 ft 2000-05-12	BHGLAOC1901 05 ft 2000-05-26	BHGLAOC1901 10 ft 2000-05-12
SW6010B	Arsenic	6.58	6.58	mg/kg	4.4 F	NA	[(6.7)]
SW6010B	Barium	128.1	200	mg/kg	80.9	NA	33.3 F
SW6010B	Beryllium	1.13	1.13	mg/kg	--	NA	--
SW6010B	Cadmium	0.59	0.59	mg/kg	0.07 F	NA	0.13 F
SW6010B	Chromium, total	16.31	16.31	mg/kg	12.8	NA	7.4 F
SW6010B	Cobalt	6.19	613.2	mg/kg	5.2 F	NA	2.9 F
SW6010B	Copper	13.72	130	mg/kg	5.3 F	NA	4.2 F
SW6010B	Nickel	19.76	204.4	mg/kg	11.1	NA	7.6 F
SW6010B	Tin	10	6132	mg/kg	1.6 F	NA	1 F
SW6010B	Vanadium	37.4	71.54	mg/kg	29.5 F	NA	22.6 F
SW6010B	Zinc	31.3	3066	mg/kg	21 F	NA	9.8 F
SW7041	Antimony	0.712	0.712	mg/kg	--	NA	--
SW7421	Lead	12.66	12.66	mg/kg	8.8	NA	4.7
SW7471A	Mercury	0.035	0.1513	mg/kg	--	NA	--
SW8260B	cis-1,2-Dichloroethene	0.005	7	mg/kg	NA	--	NA
SW8260B	Trichloroethene (TCE)	0.005	0.5	mg/kg	NA	0.004 F	NA
SW8270C	Acenaphthene	0.33	613.2	mg/kg	--	NA	--
SW8270C	Anthracene	0.33	3066	mg/kg	--	NA	--
SW8270C	Benzo[a]anthracene	0.33	0.33	mg/kg	--	NA	--
SW8270C	Benzo[a]pyrene	0.33	0.33	mg/kg	--	NA	--
SW8270C	Benzo[b]fluoranthene	0.33	0.33	mg/kg	--	NA	--
SW8270C	Benzo[g,h,i]perylene	0.33	306.6	mg/kg	--	NA	--
SW8270C	Benzo[k]fluoranthene	0.33	0.392	mg/kg	--	NA	--
SW8270C	Benzyl alcohol	0.33	3066	mg/kg	--	NA	--

**Table 4.4 (continued)**  
**Subsurface Soil Detections**  
**AOC 19**  
**NAS Fort Worth JRB, Texas**

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1901 05 ft 2000-05-12	BHGLAOC1901 05 ft 2000-05-26	BHGLAOC1901 10 ft 2000-05-12
SW8270C	bis(2-Ethylhexyl)phthalate	0.33	0.6	mg/kg	--	NA	--
SW8270C	Chrysene	0.33	3.92	mg/kg	--	NA	--
SW8270C	Dibenz[a,h]anthracene	0.33	0.33	mg/kg	--	NA	--
SW8270C	Dibenzofuran	0.33	40.88	mg/kg	--	NA	--
SW8270C	Fluoranthene	0.33	408.8	mg/kg	--	NA	--
SW8270C	Fluorene	0.33	408.8	mg/kg	--	NA	--
SW8270C	Indeno[1,2,3-c,d]pyrene	0.33	0.33	mg/kg	--	NA	--
SW8270C	Naphthalene	0.33	204.4	mg/kg	--	NA	--
SW8270C	Phenanthrene	0.33	306.6	mg/kg	--	NA	--
SW8270C	Pyrene	0.33	306.6	mg/kg	--	NA	--

## Notes.

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 1 are bold and enclosed in ( )

Values above RRS 2 are bold and enclosed in [ ( ) ]

-- = analyte not detected

NA = not analyzed

F = estimated value below the reporting limit

J = estimated value above the reporting limit

Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	UNIT	BHGLAOC1901 10 ft 2000-05-26	BHGLAOC1902 05 ft 2000-05-15	BHGLAOC1903 05 ft 2000-05-15
SW6010B	Arsenic	6.58	6.58	mg/kg	NA	5.5	2.5 F
SW6010B	Barium	128.1	200	mg/kg	NA	62 J	45.3 J
SW6010B	Beryllium	1.13	1.13	mg/kg	NA	0.35 J	0.38 J
SW6010B	Cadmium	0.59	0.59	mg/kg	NA	0.26 F	0.18 F
SW6010B	Chromium, total	16.31	16.31	mg/kg	NA	10.5 J	10.3 J
SW6010B	Cobalt	6.19	613.2	mg/kg	NA	3.9 F	2 F
SW6010B	Copper	13.72	130	mg/kg	NA	4.1 F	3.8 F
SW6010B	Nickel	19.76	204.4	mg/kg	NA	7.9 F	6.7 F
SW6010B	Tin	10	6132	mg/kg	NA	--	--
SW6010B	Vanadium	37.4	71.54	mg/kg	NA	28.9 J	27 J
SW6010B	Zinc	31.3	3066	mg/kg	NA	13.5 F	13.5 F
SW7041	Antimony	0.712	0.712	mg/kg	NA	--	--
SW7421	Lead	12.66	12.66	mg/kg	NA	4.9	5.9
SW7471A	Mercury	0.035	0.1513	mg/kg	NA	--	--
SW8260B	cis-1,2-Dichloroethene	0.005	7	mg/kg	0.005	--	--
SW8260B	Trichloroethene (TCE)	0.005	0.5	mg/kg	(0.019)	(0.008)	0.005
SW8270C	Acenaphthene	0.33	613.2	mg/kg	NA	--	--
SW8270C	Anthracene	0.33	3066	mg/kg	NA	--	--
SW8270C	Benzo[a]anthracene	0.33	0.33	mg/kg	NA	--	--
SW8270C	Benzo[a]pyrene	0.33	0.33	mg/kg	NA	--	--
SW8270C	Benzo[b]fluoranthene	0.33	0.33	mg/kg	NA	--	--
SW8270C	Benzo[g,h,i]perylene	0.33	306.6	mg/kg	NA	--	--
SW8270C	Benzo[k]fluoranthene	0.33	0.392	mg/kg	NA	--	--
SW8270C	Benzyl alcohol	0.33	3066	mg/kg	NA	--	--
SW8270C	bis(2-Ethylhexyl)phthalate	0.33	0.6	mg/kg	NA	--	--

Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	UNIT	BHGLAOC1901 10 ft 2000-05-26	BHGLAOC1902 05 ft 2000-05-15	BHGLAOC1903 05 ft 2000-05-15
SW8270C	Chrysene	0.33	3.92	mg/kg	NA	--	--
SW8270C	Dibenz[ <i>a,h</i> ]anthracene	0.33	0.33	mg/kg	NA	--	--
SW8270C	Dibenzofuran	0.33	40.88	mg/kg	NA	--	--
SW8270C	Fluoranthene	0.33	408.8	mg/kg	NA	--	--
SW8270C	Fluorene	0.33	408.8	mg/kg	NA	--	--
SW8270C	Indeno[1,2,3- <i>c,d</i> ]pyrene	0.33	0.33	mg/kg	NA	--	--
SW8270C	Naphthalene	0.33	204.4	mg/kg	NA	--	--
SW8270C	Phenanthrene	0.33	306.6	mg/kg	NA	--	--
SW8270C	Pyrene	0.33	306.6	mg/kg	NA	--	--

## Notes

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 1 are **bold** and enclosed in ( )Values above RRS 2 are **bold** and enclosed in [ ( ) ]

-- = analyte not detected

NA = not analyzed

F = estimated value below the reporting limit

J = estimated value above the reporting limit

Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1904 05 ft 2000-05-15	BHGLAOC1905 05 ft 2001-08-20	BHGLAOC1905 10 ft 2001-08-20
SW6010B	Arsenic	6.58	6.58	mg/kg	2.4 F	3.9 F	5.2
SW6010B	Barium	128.1	200	mg/kg	59.1 J	76.2	47.4
SW6010B	Beryllium	1.13	1.13	mg/kg	0.45 J	0.63	0.55
SW6010B	Cadmium	0.59	0.59	mg/kg	0.23 F	--	--
SW6010B	Chromium, total	16.31	16.31	mg/kg	11.8 J	12.3	11.8
SW6010B	Cobalt	6.19	613.2	mg/kg	3 F	2 F	2.9 F
SW6010B	Copper	13.72	130	mg/kg	5.1 F	5.2 F	5.4 F
SW6010B	Nickel	19.76	204.4	mg/kg	8.7 J	7.4 F	7.4 F
SW6010B	Tin	10	6132	mg/kg	--	--	--
SW6010B	Vanadium	37.4	71.54	mg/kg	29.8 J	22.9 F	28.2
SW6010B	Zinc	31.3	3066	mg/kg	16.2 F	--	--
SW7041	Antimony	0.712	0.712	mg/kg	--	--	--
SW7421	Lead	12.66	12.66	mg/kg	6.4	7.1	6.6
SW7471A	Mercury	0.035	0.1513	mg/kg	--	--	--
SW8260B	cis-1,2-Dichloroethene	0.005	7	mg/kg	--	--	--
SW8260B	Trichloroethene (TCE)	0.005	0.5	mg/kg	(0.009)	(0.006)	--
SW8270C	Acenaphthene	0.33	613.2	mg/kg	--	--	--
SW8270C	Anthracene	0.33	3066	mg/kg	--	--	--
SW8270C	Benzo[a]anthracene	0.33	0.33	mg/kg	--	--	--
SW8270C	Benzo[a]pyrene	0.33	0.33	mg/kg	--	--	--
SW8270C	Benzo[b]fluoranthene	0.33	0.33	mg/kg	--	--	--
SW8270C	Benzo[g,h,i]perylene	0.33	306.6	mg/kg	--	--	--
SW8270C	Benzo[k]fluoranthene	0.33	0.392	mg/kg	--	--	--
SW8270C	Benzyl alcohol	0.33	3066	mg/kg	--	--	--
SW8270C	bis(2-Ethylhexyl)phthalate	0.33	0.6	mg/kg	--	--	(0.42)



Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1904 05 ft 2000-05-15	BHGLAOC1905 05 ft 2001-08-20	BHGLAOC1905 10 ft 2001-08-20
SW8270C	Chrysene	0.33	3.92	mg/kg	--	--	--
SW8270C	Dibenz[ <i>a,h</i> ]anthracene	0.33	0.33	mg/kg	--	--	--
SW8270C	Dibenzofuran	0.33	40.88	mg/kg	--	--	--
SW8270C	Fluoranthene	0.33	408.8	mg/kg	--	--	--
SW8270C	Fluorene	0.33	408.8	mg/kg	--	--	--
SW8270C	Indeno[1,2,3- <i>c,d</i> ]pyrene	0.33	0.33	mg/kg	--	--	--
SW8270C	Naphthalene	0.33	204.4	mg/kg	--	--	--
SW8270C	Phenanthrene	0.33	306.6	mg/kg	--	--	--
SW8270C	Pyrene	0.33	306.6	mg/kg	--	--	--

## Notes.

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 1 are **bold** and enclosed in ( )Values above RRS 2 are **bold** and enclosed in [ ( ) ]

-- = analyte not detected

NA = not analyzed

F = estimated value below the reporting limit

J = estimated value above the reporting limit

**Table 4.4 (continued)**  
**Subsurface Soil Detections**  
**AOC 19**  
**NAS Fort Worth JRB, Texas**

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1906 05 ft 2001-08-20	BHGLAOC1906 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20
SW6010B	Arsenic	6.58	6.58	mg/kg	NA	NA	NA
SW6010B	Barium	128.1	200	mg/kg	NA	NA	NA
SW6010B	Beryllium	1.13	1.13	mg/kg	NA	NA	NA
SW6010B	Cadmium	0.59	0.59	mg/kg	NA	NA	NA
SW6010B	Chromium, total	16.31	16.31	mg/kg	NA	NA	NA
SW6010B	Cobalt	6.19	613.2	mg/kg	NA	NA	NA
SW6010B	Copper	13.72	130	mg/kg	NA	NA	NA
SW6010B	Nickel	19.76	204.4	mg/kg	NA	NA	NA
SW6010B	Tin	10	6132	mg/kg	NA	NA	NA
SW6010B	Vanadium	37.4	71.54	mg/kg	NA	NA	NA
SW6010B	Zinc	31.3	3066	mg/kg	NA	NA	NA
SW7041	Antimony	0.712	0.712	mg/kg	NA	NA	NA
SW7421	Lead	12.66	12.66	mg/kg	NA	NA	NA
SW7471A	Mercury	0.035	0.1513	mg/kg	NA	NA	NA
SW8260B	cis-1,2-Dichloroethene	0.005	7	mg/kg	NA	NA	NA
SW8260B	Trichloroethene (TCE)	0.005	0.5	mg/kg	(0.033)	(0.008 J)	--
SW8270C	Acenaphthene	0.33	613.2	mg/kg	NA	NA	NA
SW8270C	Anthracene	0.33	3066	mg/kg	NA	NA	NA
SW8270C	Benzo[a]anthracene	0.33	0.33	mg/kg	NA	NA	NA
SW8270C	Benzo[a]pyrene	0.33	0.33	mg/kg	NA	NA	NA
SW8270C	Benzo[b]fluoranthene	0.33	0.33	mg/kg	NA	NA	NA
SW8270C	Benzo[g,h,i]perylene	0.33	306.6	mg/kg	NA	NA	NA
SW8270C	Benzo[k]fluoranthene	0.33	0.392	mg/kg	NA	NA	NA
SW8270C	Benzyl alcohol	0.33	3066	mg/kg	NA	NA	NA
SW8270C	bis(2-Ethylhexyl)phthalate	0.33	0.6	mg/kg	NA	NA	NA

Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1906-05 ft 2001-08-20	BHGLAOC1906 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20
SW8270C	Chrysene	0.33	3.92	mg/kg	NA	NA	NA
SW8270C	Dibenz[ <i>a,h</i> ]anthracene	0.33	0.33	mg/kg	NA	NA	NA
SW8270C	Dibenzofuran	0.33	40.88	mg/kg	NA	NA	NA
SW8270C	Fluoranthene	0.33	408.8	mg/kg	NA	NA	NA
SW8270C	Fluorene	0.33	408.8	mg/kg	NA	NA	NA
SW8270C	Indeno[1,2,3- <i>c,d</i> ]pyrene	0.33	0.33	mg/kg	NA	NA	NA
SW8270C	Naphthalene	0.33	204.4	mg/kg	NA	NA	NA
SW8270C	Phenanthrene	0.33	306.6	mg/kg	NA	NA	NA
SW8270C	Pyrene	0.33	306.6	mg/kg	NA	NA	NA

## Notes:

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 1 are **bold** and enclosed in ( )Values above RRS 2 are **bold** and enclosed in [( )]

-- = analyte not detected

NA = not analyzed

F = estimated value below the reporting limit

J = estimated value above the reporting limit

**Table 4.4 (continued)**  
**Subsurface Soil Detections**  
**AOC 19**  
**NAS Fort Worth JRB, Texas**

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1907 10 ft 2001-08-20 Dup	BHGLAOC1908 05 ft 2001-08-21	BHGLAOC1908 10 ft 2001-08-21
SW6010B	Arsenic	6.58	6.58	mg/kg	NA	2.7 F	3.7 F
SW6010B	Barium	128.1	200	mg/kg	NA	92	53.5
SW6010B	Beryllium	1.13	1.13	mg/kg	NA	0.86	0.64
SW6010B	Cadmium	0.59	0.59	mg/kg	NA	--	--
SW6010B	Chromium, total	16.31	16.31	mg/kg	NA	[(17.7)]	13
SW6010B	Cobalt	6.19	613.2	mg/kg	NA	3.3 F	2.9 F
SW6010B	Copper	13.72	130	mg/kg	NA	8.9 F	4.4 F
SW6010B	Nickel	19.76	204.4	mg/kg	NA	9.4 F	7.6 F
SW6010B	Tin	10	6132	mg/kg	NA	--	--
SW6010B	Vanadium	37.4	71.54	mg/kg	NA	25 F	25 F
SW6010B	Zinc	31.3	3066	mg/kg	NA	--	--
SW7041	Antimony	0.712	0.712	mg/kg	NA	0.23 F	--
SW7421	Lead	12.66	12.66	mg/kg	NA	10.1	6.4
SW7471A	Mercury	0.035	0.1513	mg/kg	NA	--	--
SW8260B	cis-1,2-Dichloroethene	0.005	7	mg/kg	NA	--	(0.007)
SW8260B	Trichloroethene (TCE)	0.005	0.5	mg/kg	--	--	(0.03)
SW8270C	Acenaphthene	0.33	613.2	mg/kg	NA	--	--
SW8270C	Anthracene	0.33	3066	mg/kg	NA	--	--
SW8270C	Benzo[a]anthracene	0.33	0.33	mg/kg	NA	--	--
SW8270C	Benzo[a]pyrene	0.33	0.33	mg/kg	NA	--	--
SW8270C	Benzo[b]fluoranthene	0.33	0.33	mg/kg	NA	--	--
SW8270C	Benzo[g,h,i]perylene	0.33	306.6	mg/kg	NA	--	--
SW8270C	Benzo[k]fluoranthene	0.33	0.392	mg/kg	NA	--	--
SW8270C	Benzyl alcohol	0.33	3066	mg/kg	NA	--	--
SW8270C	bis(2-Ethylhexyl)phthalate	0.33	0.6	mg/kg	NA	--	--

Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1907 10 ft 2001-08-20 Dup	BHGLAOC1908 05 ft 2001-08-21	BHGLAOC1908 10 ft 2001-08-21
SW8270C	Chrysene	0.33	3.92	mg/kg	NA	--	--
SW8270C	Dibenz[ <i>a,h</i> ]anthracene	0.33	0.33	mg/kg	NA	--	--
SW8270C	Dibenzofuran	0.33	40.88	mg/kg	NA	--	--
SW8270C	Fluoranthene	0.33	408.8	mg/kg	NA	--	--
SW8270C	Fluorene	0.33	408.8	mg/kg	NA	--	--
SW8270C	Indeno[1,2,3- <i>c,d</i> ]pyrene	0.33	0.33	mg/kg	NA	--	--
SW8270C	Naphthalene	0.33	204.4	mg/kg	NA	--	--
SW8270C	Phenanthrene	0.33	306.6	mg/kg	NA	--	--
SW8270C	Pyrene	0.33	306.6	mg/kg	NA	--	--

## Notes:

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 1 are bold and enclosed in ( )

Values above RRS 2 are bold and enclosed in [ ( ) ]

-- = analyte not detected

NA = not analyzed

F = estimated value below the reporting limit

J = estimated value above the reporting limit

**Table 4.4 (continued)**  
**Subsurface Soil Detections**  
**AOC 19**  
**NAS Fort Worth JRB, Texas**

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1909 05 ft 2001-08-22	BHGLAOC1910 05 ft 2001-08-22	BHGLAOC1910 10 ft 2001-08-22
SW6010B	Arsenic	6.58	6.58	mg/kg	NA	NA	NA
SW6010B	Barium	128.1	200	mg/kg	NA	NA	NA
SW6010B	Beryllium	1.13	1.13	mg/kg	NA	NA	NA
SW6010B	Cadmium	0.59	0.59	mg/kg	NA	NA	NA
SW6010B	Chromium, total	16.31	16.31	mg/kg	NA	NA	NA
SW6010B	Cobalt	6.19	613.2	mg/kg	NA	NA	NA
SW6010B	Copper	13.72	130	mg/kg	NA	NA	NA
SW6010B	Nickel	19.76	204.4	mg/kg	NA	NA	NA
SW6010B	Tin	10	6132	mg/kg	NA	NA	NA
SW6010B	Vanadium	37.4	71.54	mg/kg	NA	NA	NA
SW6010B	Zinc	31.3	3066	mg/kg	NA	NA	NA
SW7041	Antimony	0.712	0.712	mg/kg	NA	NA	NA
SW7421	Lead	12.66	12.66	mg/kg	NA	NA	NA
SW7471A	Mercury	0.035	0.1513	mg/kg	NA	NA	NA
SW8260B	cis-1,2-Dichloroethene	0.005	7	mg/kg	NA	NA	NA
SW8260B	Trichloroethene (TCE)	0.005	0.5	mg/kg	NA	NA	NA
SW8270C	Acenaphthene	0.33	613.2	mg/kg	--	--	--
SW8270C	Anthracene	0.33	3066	mg/kg	--	--	--
SW8270C	Benzo[a]anthracene	0.33	0.33	mg/kg	--	--	--
SW8270C	Benzo[a]pyrene	0.33	0.33	mg/kg	--	0.077 F	--
SW8270C	Benzo[b]fluoranthene	0.33	0.33	mg/kg	--	--	--
SW8270C	Benzo[g,h,i]perylene	0.33	306.6	mg/kg	--	--	--
SW8270C	Benzo[k]fluoranthene	0.33	0.392	mg/kg	--	--	--
SW8270C	Benzyl alcohol	0.33	3066	mg/kg	--	--	--
SW8270C	bis(2-Ethylhexyl)phthalate	0.33	0.6	mg/kg	--	--	--

Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1909 05 ft 2001-08-22	BHGLAOC1910 05 ft 2001-08-22	BHGLAOC1910 10 ft 2001-08-22
SW8270C	Chrysene	0.33	3.92	mg/kg	--	--	--
SW8270C	Dibenz[a,h]anthracene	0.33	0.33	mg/kg	--	--	--
SW8270C	Dibenzofuran	0.33	40.88	mg/kg	--	--	--
SW8270C	Fluoranthene	0.33	408.8	mg/kg	--	--	--
SW8270C	Fluorene	0.33	408.8	mg/kg	--	--	--
SW8270C	Indeno[1,2,3-c,d]pyrene	0.33	0.33	mg/kg	--	--	--
SW8270C	Naphthalene	0.33	204.4	mg/kg	--	--	--
SW8270C	Phenanthrene	0.33	306.6	mg/kg	--	--	--
SW8270C	Pyrene	0.33	306.6	mg/kg	--	--	--

## Notes:

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 1 are bold and enclosed in ( )

Values above RRS 2 are bold and enclosed in [( )]

-- = analyte not detected

NA = not analyzed

F = estimated value below the reporting limit

J = estimated value above the reporting limit

Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1911 10 ft 2001-12-05	BHGLAOC1911 10 ft 2001-12-05 Dup	BHGLAOC1912 05 ft 2001-12-05
SW6010B	Arsenic	6.58	6.58	mg/kg	NA	NA	NA
SW6010B	Barium	128.1	200	mg/kg	NA	NA	NA
SW6010B	Beryllium	1.13	1.13	mg/kg	NA	NA	NA
SW6010B	Cadmium	0.59	0.59	mg/kg	NA	NA	NA
SW6010B	Chromium, total	16.31	16.31	mg/kg	NA	NA	NA
SW6010B	Cobalt	6.19	613.2	mg/kg	NA	NA	NA
SW6010B	Copper	13.72	130	mg/kg	NA	NA	NA
SW6010B	Nickel	19.76	204.4	mg/kg	NA	NA	NA
SW6010B	Tin	10	6132	mg/kg	NA	NA	NA
SW6010B	Vanadium	37.4	71.54	mg/kg	NA	NA	NA
SW6010B	Zinc	31.3	3066	mg/kg	NA	NA	NA
SW7041	Antimony	0.712	0.712	mg/kg	NA	NA	NA
SW7421	Lead	12.66	12.66	mg/kg	NA	NA	NA
SW7471A	Mercury	0.035	0.1513	mg/kg	NA	NA	NA
SW8260B	cis-1,2-Dichloroethene	0.005	7	mg/kg	NA	NA	NA
SW8260B	Trichloroethene (TCE)	0.005	0.5	mg/kg	NA	--	NA
SW8270C	Acenaphthene	0.33	613.2	mg/kg	0.13 F	--	--
SW8270C	Anthracene	0.33	3066	mg/kg	0.23 F	[(0.64)]	--
SW8270C	Benzo[a]anthracene	0.33	0.33	mg/kg	[(0.65)]	[(0.82 J)]	--
SW8270C	Benzo[a]pyrene	0.33	0.33	mg/kg	[(0.58 J)]	[(0.91)]	--
SW8270C	Benzo[b]fluoranthene	0.33	0.33	mg/kg	[(0.67)]	(0.52 J)	--
SW8270C	Benzo[g,h,i]perylene	0.33	306.6	mg/kg	0.3 F	[(0.62)]	--
SW8270C	Benzo[k]fluoranthene	0.33	0.392	mg/kg	[(0.47)]	--	--
SW8270C	Benzyl alcohol	0.33	3066	mg/kg	--	0.16 F	--
SW8270C	bis(2-Ethylhexyl)phthalate	0.33	0.6	mg/kg	--	(0.72)	--



Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1911 10 ft 2001-12-05	BHGLAOC1911 10 ft 2001-12-05 Dup	BHGLAOC1912 05 ft 2001-12-05
SW8270C	Chrysene	0.33	3.92	mg/kg	(0.74)	0.17 F	--
SW8270C	Dibenz[a,h]anthracene	0.33	0.33	mg/kg	--	(1.1)	--
SW8270C	Dibenzofuran	0.33	40.88	mg/kg	--	0.17 F	--
SW8270C	Fluoranthene	0.33	408.8	mg/kg	(2.1 J)	[(0.5 J)]	--
SW8270C	Fluorene	0.33	408.8	mg/kg	0.27 F	--	--
SW8270C	Indeno[1,2,3-c,d]pyrene	0.33	0.33	mg/kg	0.31 F	(0.55 J)	--
SW8270C	Naphthalene	0.33	204.4	mg/kg	0.082 F	(1.2)	--
SW8270C	Phenanthrene	0.33	306.6	mg/kg	(1.6 J)		--
SW8270C	Pyrene	0.33	306.6	mg/kg	(1.3)		--

## Notes:

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 1 are bold and enclosed in ( )

Values above RRS 2 are bold and enclosed in [( )]

-- = analyte not detected

NA = not analyzed

F = estimated value below reporting limit

J = estimated value above the reporting limit

Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1912 10 ft 2001-12-05	BHGLAOC1913 05 ft 2001-12-05	BHGLAOC1913 10 ft 2001-12-05
SW6010B	Arsenic	6.58	6.58	mg/kg	NA	NA	NA
SW6010B	Barium	128.1	200	mg/kg	NA	NA	NA
SW6010B	Beryllium	1.13	1.13	mg/kg	NA	NA	NA
SW6010B	Cadmium	0.59	0.59	mg/kg	NA	NA	NA
SW6010B	Chromium, total	16.31	16.31	mg/kg	NA	NA	NA
SW6010B	Cobalt	6.19	613.2	mg/kg	NA	NA	NA
SW6010B	Copper	13.72	130	mg/kg	NA	NA	NA
SW6010B	Nickel	19.76	204.4	mg/kg	NA	NA	NA
SW6010B	Tin	10	6132	mg/kg	NA	NA	NA
SW6010B	Vanadium	37.4	71.54	mg/kg	NA	NA	NA
SW6010B	Zinc	31.3	3066	mg/kg	NA	NA	NA
SW7041	Antimony	0.712	0.712	mg/kg	NA	NA	NA
SW7421	Lead	12.66	12.66	mg/kg	NA	NA	NA
SW7471A	Mercury	0.035	0.1513	mg/kg	NA	NA	NA
SW8260B	cis-1,2-Dichloroethene	0.005	7	mg/kg	NA	NA	NA
SW8260B	Trichloroethene (TCE)	0.005	0.5	mg/kg	NA	(0.051 J)	(0.036)
SW8270C	Acenaphthene	0.33	613.2	mg/kg	--	NA	NA
SW8270C	Anthracene	0.33	3066	mg/kg	--	NA	NA
SW8270C	Benzo[a]anthracene	0.33	0.33	mg/kg	--	NA	NA
SW8270C	Benzo[a]pyrene	0.33	0.33	mg/kg	--	NA	NA
SW8270C	Benzo[b]fluoranthene	0.33	0.33	mg/kg	--	NA	NA
SW8270C	Benzo[g,h,i]perylene	0.33	306.6	mg/kg	--	NA	NA
SW8270C	Benzo[k]fluoranthene	0.33	0.392	mg/kg	--	NA	NA
SW8270C	Benzyl alcohol	0.33	3066	mg/kg	--	NA	NA
SW8270C	bis(2-Ethylhexyl)phthalate	0.33	0.6	mg/kg	--	NA	NA

Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	BHGLAOC1912 10 ft 2001-12-05	BHGLAOC1913 05 ft 2001-12-05	BHGLAOC1913 10 ft 2001-12-05
SW8270C	Chrysene	0.33	3.92	mg/kg	--	NA	NA
SW8270C	Dibenz[a,h]anthracene	0.33	0.33	mg/kg	--	NA	NA
SW8270C	Dibenzofuran	0.33	40.88	mg/kg	--	NA	NA
SW8270C	Fluoranthene	0.33	408.8	mg/kg	--	NA	NA
SW8270C	Fluorene	0.33	408.8	mg/kg	--	NA	NA
SW8270C	Indeno[1,2,3-c,d]pyrene	0.33	0.33	mg/kg	--	NA	NA
SW8270C	Naphthalene	0.33	204.4	mg/kg	--	NA	NA
SW8270C	Phenanthrene	0.33	306.6	mg/kg	--	NA	NA
SW8270C	Pyrene	0.33	306.6	mg/kg	--	NA	NA

## Notes:

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 1 are bold and enclosed in ( )

Values above RRS 2 are bold and enclosed in [ ( ) ]

-- = analyte not detected

NA = not analyzed

F = estimated value below reporting limit

J = estimated value above the reporting limit

Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	THGLA0C1905 05 ft 2001-08-15	WHGLTA050 05 ft 2001-02-07	WHGLTA051 05 ft 2001-02-07	WHGLTA052 05 ft 2001-02-07
SW6010B	Arsenic	6.58	6.58	mg/kg	3.5 F	NA	NA	NA
SW6010B	Barium	128.1	200	mg/kg	61.2	NA	NA	NA
SW6010B	Beryllium	1.13	1.13	mg/kg	0.28	NA	NA	NA
SW6010B	Cadmium	0.59	0.59	mg/kg	0.28 F	NA	NA	NA
SW6010B	Chromium, total	16.31	16.31	mg/kg	7.2 F	NA	NA	NA
SW6010B	Cobalt	6.19	613.2	mg/kg	2.4 F	NA	NA	NA
SW6010B	Copper	13.72	130	mg/kg	3.3 F	NA	NA	NA
SW6010B	Nickel	19.76	204.4	mg/kg	4.3 F	NA	NA	NA
SW6010B	Tin	10	6132	mg/kg	1.1 F	NA	NA	NA
SW6010B	Vanadium	37.4	71.54	mg/kg	15 F	NA	NA	NA
SW6010B	Zinc	31.3	3066	mg/kg	17 F	NA	NA	NA
SW7041	Antimony	0.712	0.712	mg/kg	--	NA	NA	NA
SW7421	Lead	12.66	12.66	mg/kg	7.9	NA	NA	NA
SW7471A	Mercury	0.035	0.1513	mg/kg	0.0092 F	NA	NA	NA
SW8260B	cis-1,2-Dichloroethene	0.005	7	mg/kg	--	NA	NA	NA
SW8260B	Trichloroethene (TCE)	0.005	0.5	mg/kg	--	0.002 F	0.001 F	--
SW8270C	Acenaphthene	0.33	613.2	mg/kg	0.17 F	NA	NA	NA
SW8270C	Anthracene	0.33	3066	mg/kg	(0.38)	NA	NA	NA
SW8270C	Benzo[a]anthracene	0.33	0.33	mg/kg	[(2)]	NA	NA	NA
SW8270C	Benzo[a]pyrene	0.33	0.33	mg/kg	[(1.8)]	NA	NA	NA
SW8270C	Benzo[b]fluoranthene	0.33	0.33	mg/kg	[(2.2)]	NA	NA	NA
SW8270C	Benzo[g,h,i]perylene	0.33	306.6	mg/kg	(1.3)	NA	NA	NA
SW8270C	Benzo[k]fluoranthene	0.33	0.392	mg/kg	[(1.4)]	NA	NA	NA
SW8270C	Benzyl alcohol	0.33	3066	mg/kg	--	NA	NA	NA
SW8270C	bis(2-Ethylhexyl)phthalate	0.33	0.6	mg/kg	[(0.66)]	NA	NA	NA

Table 4.4 (continued)  
Subsurface Soil Detections  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	RRS 1	RRS 2	Unit	THGLA0C1905 05 ft 2001-08-15	WHGLTA050 05 ft 2001-02-07	WHGLTA051 05 ft 2001-02-07	WHGLTA052 05 ft 2001-02-07
SW8270C	Chrysene	0.33	3.92	mg/kg	(2)	NA	NA	NA
SW8270C	Dibenz[ <i>a,h</i> ]anthracene	0.33	0.33	mg/kg	[(0.43)]	NA	NA	NA
SW8270C	Dibenzofuran	0.33	40.88	mg/kg	0.077 F	NA	NA	NA
SW8270C	Fluoranthene	0.33	408.8	mg/kg	(3.5)	NA	NA	NA
SW8270C	Fluorene	0.33	408.8	mg/kg	0.14 F	NA	NA	NA
SW8270C	Indeno[1,2,3- <i>c,d</i> ]pyrene	0.33	0.33	mg/kg	[(1.1)]	NA	NA	NA
SW8270C	Naphthalene	0.33	204.4	mg/kg	--	NA	NA	NA
SW8270C	Phenanthrene	0.33	306.6	mg/kg	(2.1)	NA	NA	NA
SW8270C	Pyrene	0.33	306.6	mg/kg	(3.6)	NA	NA	NA

## Notes:

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 1 are bold and enclosed in ( )

Values above RRS 2 are bold and enclosed in [( )]

-- = analyte not detected

NA = not analyzed

F = estimated value below reporting limit

J = estimated value above the reporting limit

**Table 4.5**  
**Groundwater Sampling Results**  
**AOC 19**  
**NAS Fort Worth JRB, Texas**

Monitoring Well	RRS 1	RRS 2	Unit	TCE FEB. 2001	TCE APR. 2001	TCE JUNE 2001
WHGLTA004	0.0005	0.005	mg/L	[(0.530)]	[(0.45)]	[(0.66)]
WHGLTA050	0.0005	0.005	mg/L	[(0.15 J)]	[(0.17)]	[(0.26)]
WHGLTA051	0.0005	0.005	mg/L	[(0.19)]	[(0.17)]	[(0.31)]
WHGLTA052	0.0005	0.005	mg/L	[(0.3)]	[(0.3)]	[(0.57)]
WHGLTA801	0.0005	0.005	mg/L	[(0.36)]	[(0.15)]	[(0.32)]
WHGLTA801 Duplicate	0.0005	0.005	mg/L	[(0.26)]	[(0.17)]	[(0.34)]

## Notes:

TCE - trichloroethene

RRS 1 = Risk Reduction Standard 1

RRS 2 = Risk Reduction Standard 2

Values above RRS 2 are bold and enclosed in [( )]


J = estimated value above the reporting limit

## FIGURES


Figure 4.1  
Geophysical Results and  
Excavation Locations  
AOC 19 - Suspected Former Fire  
Training Area B



- Legend
- NAS Fort Worth JRB (Carswell Field) Boundary
  - Geophysical Boundary
  - SWMU 25 Test pit (1997)
  - Edge of Berm (Approximate)
  - AOC 19 Exploratory Excavation (2001)
  - Soil Boring Location
  - Monitoring Well Location
  - Solid Waste Management Unit 25 (Landfill 8)
  - Area of Concern 19
  - High Concentration of Buried Metal
  - Moderate Concentration of Buried Metal
  - Low Concentration of Buried Metal





Filename X:\AFC001\26\aac19\_site\_investigation\  
Report\fig1\_aoc19.apr  
Created 04/11/01 jbelcher  
Revised 02/27/02 jb  
Project AFC001-026-20  
Map Source HydroGeoLogic, Inc.,  
ArcView GIS Database, 2001  
IT Corporation, 2001




Farmers Branch

Perimeter Road





PLAN VIEW

CROSS-SECTION  
(from the west)

Filename X\AFC001\26\aac19\_site\_investigation\  
Report\aac\_19\_as-built.cdr  
Project AFC001-026-20  
Created by cfarmer 10/01/01  
Revised 02/22/02 asp  
Source





## Legend


1 Grid Cell = 1 Foot



**Figure 4.2**  
**Photo and Exploratory**  
**Excavation Dimensions**  
**THGLAOC1901**



PLAN VIEW

CROSS-SECTION  
(from the west)

Filename X:\AFC001\26\aac19\_site\_investigation\  
Report\aac\_19\_as-built.cdr  
Project AFC001-026-20  
Created by cfarmer 10/01/01  
Revised 02/22/02 asp  
Source




## Legend


1 Grid Cell = 1 Foot



**Figure 4.3**  
**Photos and Exploratory**  
**Excavation Dimensions**  
**THGLAOC1902**



PLAN VIEW

CROSS-SECTION  
(from the west)

Filename X:\AFC001\26\loc19\_site\_investigation\  
Report\loc19\_as-buils cdr  
Project AFC001-026-20  
Created by cfarmer 10/01/01  
Revised 02/22/02 asp  
Source




## Legend


1 Grd Cell = 1 Foot



**Figure 4.4**  
**Photos and Exploratory**  
**Excavation Dimensions**  
**THGLAOC1903**



PLAN VIEW

CROSS-SECTION  
(from the west)

Filename X\AFC001\26\loc19\_site\_investigation\  
Report\loc\_19\_as-built.cdr  
Project AFC001-026-20  
Created by cfarmer 10/01/01  
Revised 02/22/02 asp  
Source




## Legend


1 Grid Cell = 1 Foot



**Figure 4.5**  
**Photos and Exploratory**  
**Excavation Dimensions**  
**THGLAOC1904**



PLAN VIEW



CROSS-SECTION  
(from the west)

Filename X\AFC001\26\loc19\_site\_investigation\  
Report\loc\_19\_as-buils cdr  
Project AFC001-026-20  
Created by cfarmer 10/01/01  
Revised 02/22/02 asp  
Source



Legend

1 Grd Cell = 1 Foot





Figure 4.6  
Photos and Exploratory  
Excavation Dimensions  
THGLAOC1905

Figure 4.7  
AOC 19  
Lithologic Cross Sections  
A - A' and B - B'



Legend

- Fill
- Silty Sandy Clay
- Clayey Sandy Gravel
- Bedrock
- Elevation of Bottom of Borings
- Groundwater Elevation (October 2001)
- AOC
- SWMU
- NAS Fort Worth Boundary
- Monitoring Well
- Boring Location

B'

WHGLTA050

B



BHGLTA812

BHGLAOC1905 BHGLTA814

BHGLAOC1902

A'

WHGLTA801 BHGLAOC1905 BHGLAOC1908 BHGLAOC1910



Vertical Exaggeration = 5x

Filename X:\AFC001\26\AOC\_19\_Site\_Investigation\Report\AOC\_19\_draft.dwg  
Project AFC001-026-20  
Created by jrths 11/02/01  
Revised 02/25/02 asp  
Map Source

**Figure 4.8**  
**Analyte Concentrations in Soil**  
**Above RRS1**  
**AOC 19**



**U.S. Air Force Center for  
Environmental Excellence**

### Legend

- - - - - NAS Fort Worth JRB (Carswell Field)  
 Groundwater Elevation Contour (April 2001)  
 Area of Concern (AOC)  
 Solid Waste Management Unit (SWMU)  
 Debris Area (No Rig Access)  
 Monitoring Well  
 Phase I Soil Boring  
 Phase II Soil Boring  
 SWMU 25 Test Pit (1997)  
 AOC 19 Exploratory Excavation (2001)  
 Generalized Groundwater Flow

Gold	Headers indicate characterization/confirmation samples
Grey	Headers indicate delineation samples
Yellow	Headers indicate data screening values

### Color Codes

	Analyte detected above RRS-2
	Analyte detected above RRS-2, but below site-specific MSC
	Analyte detection above RRS-1 or RRS-2, but not confirmed
	Analyte not detected or detected below RRS-1

All results in mg/kg.

MSC - Media Specific Concentration GWP-Ind

na - Not Analyzed

### RRS-I - Risk Reduction Standard I

## RRS-2 - Risk Reduction Standard 2

031



Filename: X:\AFC001\26\doc19 site investigation\Report\

analyte in soil and

Project AFC001-026-20

Created: 09/20/00 ASP

Revised 02/27/02 bh

File: 17A-83-2  
D.E.

**D.F.**

Map Source: HGL GIS Database




Figure 4.9  
Analyte Concentrations  
in Groundwater Above RRS1  
AOC19  
Suspected Former Fire Training Area B




Legend


- Solid Waste Management Unit (SWMU)
- Area of Concern (AOC)
- Debris Area (No Rig Access)
- Monitoring Well Location
- 600— Groundwater Contour (April 2001)

	Data Screening Values
	Groundwater Results in mg/L
	Analyte detected above MSC
	Analyte not detected, or detected below the MSC.

File: 17A-83-2  
D.E.



Filename X:\AFC001\26\aac19\_site\_investigation\Report\gw\_results\_aoc19.apr  
Project AFC001-026-20  
Created 09/20/00 ASP  
Revised 02/27/02 jb  
Map Source: HGL GIS Database





# TAB

*SECTION 5.0*

---

## 5.0 DISCUSSION OF ANALYTICAL RESULTS

### 5.1 GEOPHYSICAL SURVEY

The geophysical survey and subsequent exploratory excavations conducted at AOC 19 revealed the source of the metallic anomalies to be consistent with material found in a landfill, and not a fire training area. The analytical results of the surface and subsurface soil sampling within and around the anomalies likewise were not indicative of a former fire training area. As a result, the subsurface materials found at AOC 19 are most likely to be an extension of the former landfill SWMU 25/Landfill 8.

### 5.2 SURFACE SOIL

No concentrations of any inorganic constituents were detected above RRS 1 in any of the surface soil samples collected as part of the SI at AOC 19. The only analyte detected above RRS 1 in the surface soil at AOC 19 was TCE. Figure 4.8 depicts the relevant surface soil results for AOC 19.

- TCE was detected at 0.019 mg/kg in the surface soil sample collected from boring BHGLAOC1902. The concentration is an isolated detection in the surface soil, slightly exceeding the RRS 1 (0.005 mg/kg), and well below the MSC (0.5 mg/kg) for this analyte. This low concentration of TCE is delineated in the surface soil by WHGLTA050 (east), BHGLAOC1903 (south), BHGLAOC1908 (west), BHGLAOC1901 (north), and vertically by a lower concentration at the 5-foot interval. Based on this information, TCE does not warrant further investigation in the surface soils at AOC 19.

### 5.3 SUBSURFACE SOIL

Concentrations of both inorganic and organic analytes were found in the subsurface soil at AOC 19. Figure 4.8 depicts the relevant subsurface soil results for AOC 19. These constituents are discussed in the following subsections.

#### 5.3.1 Inorganic Constituents

The following inorganic constituents were detected at concentrations slightly above their corresponding background values in samples collected in the subsurface at AOC 19: arsenic and chromium.

- Arsenic was detected at 6.7 mg/kg in the soil sample collected from the 10-foot interval of BHGLAOC1901. This result was isolated and only slightly exceeds both the background and MSC value of 6.58 mg/kg. No pattern of occurrence can be established for this compound. Therefore, this detection of arsenic most likely

represents a natural variation of background concentrations. Based on this information, this constituent does not warrant further investigation at AOC 19.

- **Chromium** was detected at 17.7 mg/kg in the soil sample collected from BHGLAOC1908 in the 5-foot interval. The concentration was only slightly above the background value of 16.31 mg/kg. No pattern of occurrence can be established for this compound. Therefore, this inorganic constituent is likely to represent a natural variation of background concentrations and is not indicative of a release of hazardous constituents from AOC 19. Based on this information, this constituent does not warrant further consideration at AOC 19.

### 5.3.2 Organic Constituents

Several organic constituents were detected in the subsurface soil at AOC 19. A total of two VOCs were detected at concentrations above their corresponding RRS 1 values: *cis*-1,2-dichloroethene and TCE. The following SVOC constituents were detected at concentrations exceeding RR1 and or RRS 2 values in the subsurface at AOC 19: bis(2-ethylhexyl)phthalate and various PAHs [anthracene, benzo[*a*]anthracene, benzo[*a*]pyrene, benzo[*b*]fluoranthene, benzo[*g,h,i*]perylene, benzo[*k*]fluoranthene, chrysene, dibenz[*a,h*]anthracene, fluoranthene, indeno[1,2,3-*c,d*]pyrene, phenanthrene, and pyrene].

- ***cis*-1,2-Dichloroethene** was detected at 0.007 mg/kg in boring BHGLAOC1908 at the 10-foot interval. *Cis*-1,2-dichloroethene was detected only once, the result was slightly above RRS 1 (0.005 mg/kg) and well below the MSC (7 mg/kg), and the analyte is delineated. As a result, no pattern of occurrence can be established for this analyte. Based on this information, this constituent does not warrant further investigation at AOC 19.
- **Trichloroethene** was detected in the following soil samples: the 10-foot interval of boring BHGLAOC1901 (0.019 mg/kg); the 5-foot interval of boring BHGLAOC1902 (0.008 mg/kg); the 5-foot interval of boring BHGLAOC1904 (0.009); the 5-foot interval of boring BHGLAOC1905 (0.006 mg/kg); the 5- and 10-foot intervals of boring BHGLAOC1906 (0.033 mg/kg and 0.008 J mg/kg, respectively); the 10-foot interval of boring BHGLAOC1908 (0.030 mg/kg); and the 5- and 10-foot intervals of boring BHGLAOC1913 (0.051 J mg/kg and 0.036 mg/kg, respectively). TCE was detected at low concentrations above RRS 1 (0.005 mg/kg) and well below RRS 2 (7 mg/kg) throughout the site. The TCE concentrations in the subsurface soils at AOC 19 do not appear to be associated with a release from the site. The bedrock and water table at AOC 19 is shallow, therefore the low concentrations of TCE in the soil are most likely attributed to a smear zone created by seasonal fluctuations in the water table from the basewide TCE plume previously mentioned in Section 3.2. In addition, all TCE concentrations in the subsurface soils at AOC 19 have been delineated to decreasing concentrations and/or RRS 1. As a result, further investigation of TCE in the soil at AOC 19 is not warranted.

- **bis(2-Ethylhexyl)phthalate** was detected at 0.42 mg/kg in the soil sample collected from the 10-foot interval of boring BHGLAOC1905 and at 0.66 mg/kg in the soil sample collected from the bottom of THGLAOC1905. Both of these results are above the RRS 1 of 0.33 mg/kg. However, BHGLAOC1905 was below the MSC (0.6 mg/kg) and THGLAOC1905-02 exceeded the MSC. An SPLP extract of THGLAOC1905-02 was analyzed and a site-specific MSC of 0.66 mg/kg was developed. Bis(2-ethylhexyl)phthalate is delineated and based on the SPLP extraction result, shows no impact on groundwater. As a result, this constituent does not warrant further investigation at AOC 19.
- **PAHs** were detected in THGLAOC1905 and BHGLAOC1911. Twelve of the sixteen PAH compounds were detected above RRS 1 in the sample collected from the floor sample from THGLAOC1905, and ten were detected above RRS 1 in the 10-foot interval (or its duplicate) of boring BHGLAOC1911. Soil sample THGLAOC1905-02 was extracted for SPLP and the resulting water sample was a non-detect for all of the PAHs above RRS 2. These results established new site-specific MSCs and showed that the concentrations of these analytes in the soil are protective of groundwater. These analytes are fully delineated horizontally and vertically at AOC 19. Therefore further investigation of PAHs in the subsurface soil at AOC 19 is not warranted.

## 5.4 GROUNDWATER

Three rounds of groundwater sampling were conducted at cross- and downgradient monitoring wells WHGLTA050, WHGLTA051, WHGLTA052, WHGLTA801, and upgradient monitoring well WHGLTA004. Groundwater samples from all five monitoring wells were analyzed for TCE, the only COPC identified in soil during Phase I. TCE was detected above RRS 2 in all five wells during the three rounds of sampling. The upgradient well, WHGLTA004, consistently had the highest detections of TCE, with concentrations decreasing down- and crossgradient from AOC 19. As a result, concentrations of TCE in the groundwater beneath AOC 19 appear to be attributed to the basewide TCE plume (Section 3.2) and do not appear to be a result of a release from AOC 19. Therefore, it is recommended that the groundwater at AOC 19 be addressed with the basewide TCE plume under a separate and ongoing environmental restoration project.

*This page was intentionally left blank.*

# TAB

*SECTION 6.0*

---

## 6.0 CONCLUSIONS

This SI of AOC 19 has been conducted in accordance with Chapter 335, Subchapter S of the TNRCC Risk Reduction Rules and NAS Fort Worth JRB Hazardous Waste Permit, HW-50289. Evidence resulting from past fire training activities typically includes elevated PID readings and odors due to high concentrations of flammable compounds such as waste oils and solvents that might have been used to ignite a training fire. In addition, stained soil is often present in conjunction with odors and organic vapor readings. The physical characteristics observed during the SI at AOC 19 were not indicative of typical fire training activities. No elevated PID readings, staining, or odors were observed in site soils and analytical results did not indicate the presence of organic constituents typically found at fire training areas. Therefore, it is unlikely that significant fire training exercises were conducted historically at AOC 19.

Although physical observations and analytical data support the conclusion that AOC 19 was not utilized extensively as a fire training area, the analytical results indicate that former activities at AOC 19 may have had an impact on a small area of subsurface soil. SVOC contaminated soil was identified in the north central section of the site relating to the buried debris unearthed during the exploratory excavations. The SVOCs in this section of the site have been delineated. Due to this small area of SVOC contamination in soil, closure under RRS 2 is recommended for AOC 19.


TCE was detected in soil and groundwater samples collected as part of the AOC 19 SI. However, these concentrations are likely attributable to the basewide TCE plume rather than to historical site activities. This conclusion is supported by the migration of the TCE plume beneath AOC 19 and that concentrations of TCE are consistently higher upgradient of AOC 19. As TCE concentrations in groundwater do not increase downgradient of AOC 19, it can be concluded that AOC 19 is not a source of TCE contamination in groundwater. Groundwater contamination in the vicinity of AOC 19 will continue to be addressed by the ongoing investigation of the basewide TCE plume. Nonetheless, as RRS 2 concentrations of TCE exist in site soils, the deed certification language will identify TCE as a contaminant left in place as part of this investigation.

Pursuant with Chapter 335, Subchapter S, and Sections 335.555 through 335.560 of the TNRCC RRS, this SI demonstrates that attainment of RRS 2 (Closure/Remediation to health-based standards and criteria) has been achieved and closure of AOC 19 is recommended. The proposed deed certification language, including the metes and bounds survey, is presented in Appendix H.

*This page was intentionally left blank.*




**FIGURE**



**Figure 6.1**  
**Proposed Area for**  
**RRS 2 Closure**  
**AOC 19—Suspected Former**  
**Fire Training Area B**

- Legend**
- Area of Concern (AOC)
  - Solid Waste Management Units (SWMU)
  - Fences
  - SWMU 25/ Landfill 8
  - Metes and Bounds
  - Monitoring Well
  - Phase I Soil Boring Location
  - Phase II Soil Boring Location
  - Metes and Bounds (SVOC's)
  - Metes and Bounds (TCE)

  
 Filename X:\AFC001\26\AOC19\_site\_investigation\report\AOC19\_closure\_area-final.apr  
 Project AFC001-026-20  
 Created 07/20/99 jbelcher  
 Revised 04/29/02 apassarelli  
 Source HGL ArcView Database

# TAB

*SECTION 7.0*

---

## 7.0 REFERENCES

- A.T. Kearney, Inc., 1989, RCRA Facility Assessment PR/VSI Report.
- CH2M HILL, 1984, Installation Restoration Program Records Search for Carswell Air Force Base, Texas
- CH2M HILL, Inc., 1996, Site Characterization Summary Informal Technical Information Report.
- Environmental Science and Engineering Incorporated, 1994, Summary of Remediation Projects at Air Force Plant 4 and Carswell Air Force Base.
- General Dynamics Facility Management, 1992, Memorandum of Telephone Conversation Regarding AFP 4 Water Balance Between General Dynamics Facility Management and Chem-Nuclear Geotech. Memorandum dated December 15, 1992.
- HydroGeoLogic, Inc., 1999, Draft Basewide Groundwater Sampling and Analysis Program, January 1999 Quarterly Report, NAS Fort Worth JRB, Texas.
- HydroGeoLogic, Inc., 2000a, Final Work Plans, RCRA Facility Investigation of SWMUs 19, 20, 21, and 53; and Site Investigation of AOCs 17, 18, and 19 at NAS Fort Worth JRB, Texas.
- HydroGeoLogic, Inc., 2000b, Final Phase II Work Plan Addendum, RCRA Facility Investigation of SWMUs 19, 20, 21, and 53; and Site Investigation of AOC 19, NAS Fort Worth JRB, Texas.
- HydroGeoLogic, Inc., 2000c, Final 2000 Basewide Quality Assurance Project Plan, NAS Fort Worth JRB, Texas.
- HydroGeoLogic, Inc., 2000d, Final Summary Report, Southern Lobe TCE Groundwater Plume Delineation, NAS Fort Worth JRB, Texas.
- HydroGeoLogic, Inc., 2001a, Final Excavation Work Plan, SWMUs 19, 64, and AOC 19, NAS Fort Worth JRB, Texas.
- HydroGeoLogic, Inc., 2001b, Final RCRA Facility Investigation, SWMUs 22, 23, 24, and 25, NAS Fort Worth JRB, Texas.
- HydroGeoLogic, Inc., 2001c, Final Basewide Groundwater Sampling and Analysis Program, April 2001 Semi-Annual Report, NAS Fort Worth JRB, TX

International Technologies Corporation (IT), 2001, Draft Surface Geophysical Survey Report; AOC 19 Site, SWMU 19 & 20 Site; NAS Fort Worth JRB, Texas.

Jacobs Engineering Group, Inc., 1998, NAS Fort Worth JRB, Texas - Final Basewide Background Study.

Radian Corporation, 1989a, Installation Restoration Program RI/FS, Stage 2 Draft Final Technical Report, Carswell Air Force Base, Volume 1.

Radian Corporation, 1989b, Installation Restoration Program RI/FS, Stage 2 Draft Final Appendices A-E, Carswell Air Force Base, Volume 2.

Rust Geotech, 1995, Remedial Investigation and Preliminary Assessment/Site Inspection Report, Air Force Plant 4.

Texas Natural Resource Conservation Commission (TNRCC), 1996a, Texas Administrative Code, Environmental Quality, Chapter 335 Industrial Solid Waste and Municipal Hazardous Waste, Risk Reduction Standards.

TNRCC, Office of Air Quality, 1996b, Air Quality in Texas: Dallas/Fort Worth, Obtained from TNRCC Internet Home Page.

TNRCC, 1998a, Interoffice Memorandum, Implementation of the Existing Risk Reduction Rule, July 23.

TNRCC, 1998b, Erratum Sheet to the July 23, 1998 Memorandum, September 11.

Texas Water Commission (TWC), 1991, Permit Number HW-50289, EPA I.D. Number 0571924042.

U.S. Department of Commerce, 1994, 1990 Census of Population, Cities and Villages in Tarrant County, Texas, Bureau of the Census, Washington, D.C.

U.S. Department of Commerce, 1996, 1990 Census of Population, Tarrant County, Texas, Bureau of the Census, Washington, D.C.

U.S. Environmental Protection Agency (USEPA), 1993, Data Quality Objectives Process for Superfund Interim Final Guidance.

U.S. Geological Survey (USGS), 1981, Soil Survey of Tarrant County, Texas, pps. 202-203.

# TAB

*APPENDIX A*

---

**APPENDIX A**

**AREAS OF CONCERN 17, 18, AND 19 IDENTIFICATION LETTER**

February 17, 1998

AFCEE/ERD

Attn. Mr. Joseph Dunkle

3207 North Road

Brooks Air Force Base, Texas 78235-5363

**Re: Contract No. F41624-95-D-8005-0005**

**Identification of Possible SWMUs at NAS Fort Worth JRB**

Dear Mr. Dunkle:

The purpose of this letter is to notify you of the possibility of three additional sites at Naval Air Station Fort Worth Joint Reserve Base (NAS Fort Worth JRB) - two fire training areas and a landfill. We identified these possible sites during our review of aerial photographs for our ongoing Resource Conservation and Recovery Act (RCRA) Facility Investigation (RFI) activities at the base. Our findings are summarized below with the supporting visual evidence provided in Figures 1 through 9. A base map is provided as Figure 10 showing the location of these sites based on the current configuration of the Base

### ***Suspected Fire Training Area A***

On April 10, 1952 (Figure 1), just north of Phillips Circle and south of Hobby Shop Road, is a single plane located on what appears to be open ground. The area directly beneath the plane is dark in color while the perimeter of the area appears white. This discoloration could be the result of charring from fire training exercises.

The time period at which this area may have been used as a fire training area is unknown. A review of aerial photographs, however, before and after 1952 indicates this site existed as early as December 31, 1950 (Figure 2) and no later than January 4, 1953 (Figure 3). No planes were visible in this area as early as September 1946. Figure 2 shows two airplanes located at the site in question. The second plane is located just west of the plane identified in Figure 1. The area beneath each of these planes shows a slight discoloration (darkening) indicating the possibility of fire training exercises. The area outside the adjacent perimeter of the suspected fire training area appears white in color. Figure 3 no longer shows any visible evidence of using this site as a fire training area, and the planes are no longer located at this site. In addition, the land appears to have been re-engineered, potentially for future construction activities. Figure 4 indicates that by February 1954, a parking area had been constructed over the site.



*Suspected Fire Training Area B*

A single plane located in a cleared triangular shaped area south of taxiway Charlie and east of taxiway 35R was identified from a December 3, 1958 (Figure 5) aerial photograph of the base. The plane is parked on what appears to be open ground. The two planes located immediately southwest of this plane are parked in the area of SWMU 18 (Fire Training Area I). Because the single plane is located at a distance from taxiway Charlie, we suspect that this area may have served as a fire training area similar to the adjacent site located immediately southwest.

Although the time period at which this area may have been used as a possible fire training area is unknown, it did not exist on February 3, 1954 (Figure 6) and is no longer visible after August 22, 1962 (Figure 7). Aerial photographs later than 1954 and earlier than 1962 were not available for this review to further quantify the time period at which a plane(s) may have been located at this site.

*Suspected Landfill A*

On April 10, 1942, just west of the most western section of the West Fork Trinity River (prior to rerouting the river), are 8-10 trench like areas (Figure 8). These trenches are located approximately 290 feet from the roadway that runs in a north-south direction along the eastern part of the base boundary. Each "trench" is estimated to occupy an area approximately 65 feet long by 35 feet wide. The trenches are oriented in an northeast-southwest direction. Combined, the trenches occupy an area of about 30,000 ft<sup>2</sup>, or 0.69 acres. Trenches like these were often used by the military for the burial of facility refuse ranging from construction debris to industrial waste. Other base landfills were located along the river, east of this site, during the late 1940s, 1950s, 1970s, and 1980s (e.g., SWMU Nos. 28 and 30).

On April 4, 1944, (Figure 9) there is no longer any visual evidence of the trenches at this location. The area appears to have been leveled and covered with grass. In 1997, it appears that a building is being constructed over the suspected site.

Please contact me at 703-736-4507, if there is anything else we can do for you regarding these possible sites.

Sincerely,



James P. Costello, P.G.  
Project Manager

Attachments (Figures 1-10)


**Location of Suspected  
Fire Training Area A**



Drawn/Scanned by: C. Farmer	Date: 12/31/97
Checked by: M. Rodtang	Date: 01/08/98
Filename: AFCEE\Fire_Training_Area\ FTA_fig1 cdr	




**Figure 1**  
**Aerial Photograph**  
**April 10, 1952**



Approximate Scale  
1:8,500


**Location of Suspected  
Fire Training Area A**



Drawn/Scanned by: C. Farmer	Date: 12/31/97
Checked by: M. Rodtang	Date: 01/08/98
Filename: AFCEE\Fire_Training_Area\ FTA_fig2.cdr	




**Figure 2**  
**Aerial Photograph**  
**December 31, 1950**



Approximate Scale  
1:10,000


# Former Location of Suspected Fire Training Area A



Drawn/Scanned by: C Farmer	Date: 12/31/97
Checked by: M Rodtang	Date: 01/08/98
Filename: AFCEE\Fire_Training_Area\ FTA_fig3.cdr	



**Figure 3**  
**Aerial Photograph**  
**January 4, 1953**



Approximate Scale  
~1:17,000


### Former Location of Suspected Fire Training Area A



Drawn/Scanned by. C. Farmer	Date: 12/31/97
Checked by M. Rodtang	Date: 01/08/98
Filename: AFCEE\Fire_Training_Area\ FTA_fig4.cdr	




**Figure 4**  
**Aerial Photograph**  
**February 3, 1954**



Approximate Scale  
1 12,000


# Location of Suspected Fire Training Area B



Drawn/Scanned by. C Farmer	Date: 12/31/97
Checked by M Rodtang	Date: 01/08/98
Filename: AFCEE\Fire_Training_Area\ FTA_fig5 cdr	




**Figure 5**  
**Aerial Photograph**  
**December 3, 1958**



Approximate Scale  
1:8,600


# **Future Location of Suspected Fire Training Area B**



Drawn/Scanned by: C Farmer	Date: 12/31/97
Checked by: M Rodtang	Date: 01/08/98
Filename: AFCEE\Fire_Training_Area\ FTA_fig6.cdr	



**Figure 6**  
**Aerial Photograph**  
**February 3, 1954**



Approximate Scale  
1 12,000


**Former Location of Suspect d  
Fire Training Area B**



Drawn/Scanned by C. Farmer	Date 12/31/97
Checked by M. Rodtang	Date 01/08/98
Filename. AFCEE\Fire_Training_Area\ FTA_fig7 cdr	




**Figure 7**  
**Aerial Photograph**  
**August 22, 1962**



Approximate Scale  
1:12,300




# Location of Suspected Landfill



Drawn/Scanned by. C Farmer	Date 12/31/97
Checked by: M. Rodtang	Date. 01/08/98
Filename. AFCEE\Fire_Training_Area\ FTA_fig8.cdr	




**Figure 8**  
**Aerial Photograph**  
**April 10, 1942**



Approximate Scale  
1:10,000


Former Location of Suspected Landfill



Drawn/Scanned by C Farmer	Date: 12/31/97
Checked by. M. Rodtang	Date: 01/08/98
Filename: AFCEE\Fire_Training_Area\ FTA_fig9.cdr	



**Figure 9**  
**Aerial Photograph**  
**April 4, 1944**




Approximate Scale  
1:10,000

HydroGeologic, Inc.  
Former Carswell Air Force Base

Figure 10  
NAS Fort Worth, JRB  
Base Location Map


LEGEND

- NAS Fort Worth JRB
- Former Carswell Air Force Base
- Surface Water



**HYDRO**  
**Geologic** INC.

Filename: AFCEE\NAS Ft Worth\BaseLcm.dwg  
Revised: 02/12/98  
Project: AF0001-DO5  
Map Source: Jacobs, 1996



# TAB

*APPENDIX B*

---

**APPENDIX B**  
**DATA QUALITY ASSESSMENT**

**DATA QUALITY ASSESSMENT  
SITE INVESTIGATION REPORT  
AREA OF CONCERN 19  
NAS FORT WORTH JRB, TEXAS**

## **1.0 FIELD QUALITY ASSURANCE/QUALITY CONTROL**

Field quality control samples were collected as described in the following sections.

### **1.1 AMBIENT BLANK**

Ambient blanks consist of American Society for Testing and Materials (ASTM) Type II reagent grade water poured into a VOC sample vial at a sampling site (in the same vicinity as the associated samples). Ambient blanks are used to assess the potential introduction of contaminants from ambient sources (e.g., active runways, engine test cells, gasoline motors in operation) to the samples during sample collection. Ambient blanks are handled like environmental samples and transported to the laboratory for analysis. Depending on the analytes of interest at the associated site(s), ambient blanks are analyzed for VOCs, benzene, toluene, ethylbenzene, and xylenes (BTEX), or methane. No ambient blanks were collected in association AOC 19 samples.

### **1.2 EQUIPMENT BLANK**

An equipment blank is a sample of ASTM Type II reagent grade water poured over the sampling device, collected in a sample container, and transported to the laboratory for analysis. Equipment blanks are used to assess the effectiveness of equipment decontamination procedures. Equipment blanks are collected immediately after equipment has been decontaminated. Each blank is analyzed for all laboratory analyses requested for the environmental samples collected at the site. One equipment blank was collected per day for each type of sampling equipment used. Twelve equipment blanks were collected in association with AOC 19 samples; eight associated with soil samples and four associated with groundwater samples.

### **1.3 TRIP BLANK**

A trip blank consists of a VOC sample vial filled at the laboratory with ASTM Type II reagent grade water, transported to the sampling site, handled like an environmental sample, and returned to the laboratory for analysis. Trip blanks are not opened in the field. Trip blanks are prepared only when samples are collected and analyzed for VOC analytes. Trip blanks are used to assess the potential introduction of contaminants from sample containers or during the transportation and storage procedures. One trip blank accompanied each cooler of samples sent to the laboratory for analysis of VOCs. Twelve trip blanks were collected in association

with AOC 19 samples; eight associated with soil samples and four associated with groundwater samples.

## 1.4 FIELD DUPLICATES

Duplicate sample results are used to assess precision of the sample collection process. Precision of soil samples to be analyzed for VOCs is assessed from collocated samples because the compositing process required to obtain uniform samples could result in loss of the compounds of interest.

Duplicate samples are collected simultaneously, or in immediate succession, using identical recovery techniques, and treated in an identical manner during storage, transportation, and analysis. The sample containers are assigned an identification number in the field so that they cannot be identified (blind duplicate) as duplicate samples by laboratory personnel performing the analysis. Specific locations were designated for collection of field duplicate samples prior to the beginning of sample collection. One duplicate sample was collected for every 10 field samples collected. Six field duplicates were collected during AOC 19 SI activities; three for soil samples and three for groundwater.

## 1.5 SAMPLE TRACKING PROTOCOL

Each sample was assigned a unique identification number that describes where and what type of sample was collected. The number that was used in the field consisted of a maximum 15 digit alphanumeric code. The alphanumeric code was truncated to 10 digits once the data was ready to be entered into the Environmental Resources Program Information Management System (ERPIMS) database. This system is explained in detail as follows:

abbccccdd-ee

where:

- a represents the medium (e.g., W=monitoring well, P = wipe sample, R = rinse sample, B = soil boring, U = surface water sample, or E = sediment sample).
- bbb represents HydroGeoLogic, Inc. designation (e.g., HGL)
- cccccc represents the AOC number (e.g., AOC 19.)
- dd represents the location identification (LOCID) (e.g., 01, 02)
- ee represents the order that the sample was obtained within the soil boring; i.e., a surface soil sample would be 01, a 5- to 7-foot sample would be 02, etc. These two digits will dropped once the data are entered into the ERPIMS database.

For example, the surface soil sample collected from the first boring advanced at AOC 19 was identified as “BHGLAOC1901-01.” The sample collected from the 5 foot interval of the first soil boring advanced at AOC 19 was identified as “BHGLAOC1901-02”.

Duplicate samples were submitted to the laboratory blind. In order to ensure that field duplicates were analyzed “blind” by the laboratory, each field duplicate sample was assigned a unique sample identification number that did not associate the duplicate with its parent sample. Duplicate sample numbering format is “DUPxx”, where xx is a sequential number. The locations from which field duplicate samples were to be collected were determined prior to mobilization. Documentation was maintained in the field sampling logbook, and on the sample collection log, to track these field duplicate samples.

QC samples were identified by use of a similar system of identifiers with a maximum of 10 characters. The QC sampling number system is summarized below:

xyyyyyyy

where:

xx represents the blank type (EB for equipment blank, TB for trip blank, AB for ambient blank)

yyyyyy represents the date (month, day, year)

For example, an equipment blank obtained on May 1, 2000, would be identified as EB050100. When multiple field blanks of a particular type were collected on the same day, alphabetical suffixes (A, B, C, and so forth) were attached to the identification numbers.

The Project Geologist/Field Coordinator maintained a list detailing the connection between each QC sample and specific environmental samples. For instance, each trip blank was correlated with a particular set of samples shipped to the laboratory, and each equipment blank was correlated to those samples collected using a particular set of sampling tools on a specific date.

After the laboratory data were received and validated, data entry and QC operations were performed on the laboratory’s electronic data deliverables (EDDs) to ensure that each EDD was complete, correct, and compatible with the ERPIMS format. An EDD report in the ERPIMS format will be provided to AFCEE.

## 2.0 LABORATORY ANALYSIS

Samples collected from AOC 19 were analyzed for a reduced list of 40 CFR 264 Appendix IX constituents, comprising VOCs, SVOCs, and metals/mercury as in accordance with the 2000 Basewide QAPP (HydroGeoLogic, 2000c). Specific sampling parameters for each site are listed in Section 3.0 of the SI Report.



## 2.1 ANALYTICAL PROGRAM

The data generated by this project is of sufficient quality and quantity to meet the overall project objective, which is closure of AOC 19 under the TNRCC RRS program. Data from the following categories were required for this study:

**Site Characterization** - Data were used to evaluate physical and chemical properties of soil. The data were also used to characterize the nature and extent of any contaminants detected.

**Health and Safety** - Data were used to establish the level of protection needed for the sampling team and other site-related personnel. These data were gathered by the use of organic vapor monitors during intrusive activities.

A combination of screening level data and definitive level data was used during this SI. Health and safety data were collected as screening data. All soil and water samples were analyzed following USEPA SW846 protocols. The definitions of screening data and definitive data, as established by the Data Quality Objectives Process for Superfund Interim Final Guidance (USEPA/540/G-93/071, 1993) are described below:

- Screening Data with Definitive Confirmation - Screening data can be generated by rapid, less precise methods of analysis with less rigorous sample preparation. Sample preparation steps may be restricted to simple procedures such as dilution with a solvent, instead of elaborate extraction/digestion and cleanup. Screening data provides analyte identification and quantification. Although the quantification may be determined using analytical methods with QA/QC procedures and criteria associated with definitive data, screening data without associated confirmation data are not considered to be data of known quality.
- Definitive Data - Definitive data were generated using rigorous analytical methods, such as approved USEPA reference methods. Data are analyte-specific, with confirmation of analyte identity and concentration. These methods produce tangible raw data (e.g., chromatograms, spectra, digital values) in the form of paper printouts or computer-generated electronic files. Data may be generated at the site or at an off-site location, as long as the QA/QC requirements are satisfied. For the data to be definitive, either analytical or total measurement error must be determined.

The data generated by the laboratory analysis of samples were sufficiently sensitive to allow comparison of the results to the TNRCC RRS. The 2000 Basewide QAPP (HydroGeoLogic, 2000c) describes each method that was performed as part of the investigation and outlines the quality assurance measures the contract laboratory must follow. The methods of analysis selected for samples collected from NAS Fort Worth JRB produced screening as well as definitive data.

## 2.2 QUALITY ASSURANCE/QUALITY CONTROL PROGRAM

The primary project QA/QC document is the 2000 Basewide QAPP (HydroGeoLogic, 2000c). This document was originally released in 1998 and was based on versions 1.1 and 2.0 of AFCEE's Model QAPP, with some base-specific modifications and updates. The 2000 version of the QAPP incorporates elements of the AFCEE Modal QAPP, version 3.0, and updates to SW-846 methods. This document is supplemented by the laboratory's Quality Assurance Plan. Together, these two documents detail the requirements that must be followed in order to generate data of the level of quality required to support the project decision-making process. Among the requirements contained in these documents is the requirement for review of the data at several levels at the laboratory. Each benchtop chemist is responsible for a 100 percent review of all data generated, as is each laboratory section manager (or designee). Subsequent to analyst review, 10 percent of data are reviewed by the laboratory QA department prior to assembly of each data report. Each final data report is reviewed by the laboratory project manager prior to release from the laboratory.

### 2.2.1 Laboratory QA/QC Program

The laboratory QA/QC program was maintained in overall accordance with the 2000 Basewide QAPP. Where the laboratory performance was not in accordance with the QAPP criteria, the affected data were qualified in the data validation process. The Data Validation Reports are presented in Appendix G. In order to provide data meeting the requirements for definitive data, the following QC elements were used by the laboratory to provide QC data applicable to the analytical results: laboratory control samples (LCSs), matrix spike/matrix spike duplicate (MS/MSD) samples, surrogate recoveries, internal standard performance, method blanks and calibration, instrument tuning and calibration, second source calibration checks, confirmation columns/detectors, interference check samples, recovery tests, laboratory duplicates, and serial dilutions. A description of each laboratory QC element can be found in Section 4.0 of the 2000 Basewide QAPP (HydroGeoLogic, 2000c). The frequency and acceptance criteria for each laboratory QC element are described in general in Sections 4.0 and 8.0 of the 2000 Basewide QAPP, and in the method-specific subsections of Section 7.0 of the 2000 Basewide QAPP (HydroGeoLogic, 2000c).

### 2.2.2 QA/QC Program Performance

Evaluation of the QC and analytical data provided by the laboratory showed that there was general compliance with the QA/QC program. There were cases where individual analytes or QC elements did not meet program criteria. If these QC failures were serious enough, the laboratory performed re-analysis after attempting corrective action. Where re-analysis was not performed or corrective action was not successful, the data were qualified in accordance with the method-specific requirements of Section 7.0 and the general requirements of Section 8.0 of the 2000 Basewide QAPP (HydroGeoLogic, 2000c).

A total of 4076 data points were generated by the analyses of AOC 19 soil samples. This number includes the results from 33 field samples and 3 field duplicates. Of the data points

reported, 94 were rejected due to failure to achieve QA/QC program requirements. Total AOC 19 soil data completeness is calculated to be 97.69 percent, which exceeds the soil data completeness goal of 90 percent. The soil data set obtained for AOC 19 in May 2000, February 2001, August 2001, and December 2001 is judged to be sufficiently complete, from a QC standpoint, to be used in any subsequent decision-making process.

A total of 18 data points were generated by the analyses of AOC 19 groundwater samples. This number includes the results from 15 field samples and 3 field duplicates. Of the data points reported, none were rejected due to failure to achieve QA/QC program requirements. Total AOC 19 groundwater data completeness is calculated to be 100 percent, which exceeds the groundwater data completeness goal of 95 percent. The groundwater data set obtained for AOC 19 in February 2001, April 2001, and June 2001 is judged to be sufficiently complete, from a QC standpoint, to be used in any subsequent decision-making process.

### **2.2.3 QA Activities**

On March 25 and 26, 1998, the HydroGeoLogic project chemist, assisted by a Law Engineering project chemist, performed a QA audit of the facilities and practices of the analytical laboratory, at Recra Labnet<sup>1</sup> in University Park, Illinois. The auditors reviewed the laboratory's Quality Assurance Plan, evaluated the laboratory's recent state certification performance evaluation sample results, reviewed the laboratory's standard operating procedures, and conducted an on-site inspection of the laboratory's facility. The laboratory was found to have sufficient expertise, resources, and procedures to generate definitive and legally defensible data.

## **3.0 DATA QUALITY EVALUATION**

This section describes the analytical methods and quality control program utilized for the SI of AOC 19 at NAS Fort Worth JRB. The analytical methods used for the analysis of the field samples are described in the 2000 Basewide QAPP (HydroGeoLogic, 2000c).

### **3.1 DATA QUALITY EVALUATION OBJECTIVE**

The objective of the Data Quality Evaluation (DQE) is to provide a professional review of the analytical data packages submitted by the laboratory. The DQE consists of a review of laboratory QC data and field QC data. This review is performed to indicate which data are usable, usable with qualification, or unusable. The analytical procedures used to generate field sample data are evaluated in accordance with the general and method-specific QC criteria listed in Sections 5.0, 6.0, 7.0, and 8.0 of the 2000 Basewide QAPP (HydroGeoLogic, 2000c).

---

<sup>1</sup> RCRA Labnet was acquired by Severn Trent Laboratories in January 1999.

The following items of laboratory QC data are reviewed:

- Sample integrity
- Sample completeness
- Preparation and analysis holding times
- Laboratory preparation and analysis methods
- Method accuracy and precision (e.g., MS/MSDs, dilution tests)
- Laboratory performance criteria (e.g., blanks, LCS recoveries, surrogates, internal standards)
- Instrument initial and continuing calibration checks

Field QC performance is evaluated through evaluating field duplicates, field blanks, field documentation, and shipping criteria.

### 3.2 METHODOLOGY FOR DATA QUALITY ASSESSMENT

Environmental Data Services, Inc. and HydroGeoLogic validated the results for AOC 19 samples. The data were evaluated in accordance with the procedures and acceptance criteria contained in the 2000 Basewide QAPP. All results from all analytical methods were evaluated with respect to the requirements of definitive data at the equivalent of a USEPA level III review. The data review identified those data that were unusable due to serious QC deficiencies, as well as other data that were affected by QC problems but not of sufficient severity to warrant rejection. Rejected data were qualified 'R', while qualifiers of lesser severity were applied to usable data where necessary. The level III validation reports for each sample delivery group (SDG) are included in Appendix G.

Subsequent to the data validation process, the required data validation qualifiers were entered into the project database. The accuracy the validation and data entry process was checked at all stages. The "as received" accuracy of each EDD for each data package was verified by comparing the contents of each EDD to the hardcopy of that data package at a 10 percent rate. The accuracy of the validation qualifiers was also checked on the final database output at a rate of 10 percent.

*This page was intentionally left blank.*

# TAB

*APPENDIX C*

---

**APPENDIX C**  
**GEOPHYSICAL SURVEY REPORT**

**DRAFT**

**SURFACE GEOPHYSICAL SURVEY REPORT**

**AOC 19 Site and  
SWMUs 19 & 20 Site**

**NAS Ft. Worth JRB (Formerly Carswell AFB)  
Fort Worth, Texas**

**Prepared For:  
HydroGeoLogic Inc.  
1155 Herndon Parkway, Suite 900  
Herndon, Virginia, 20170**

**Prepared By:  
IT Corporation  
312 Directors Drive  
Knoxville, Tennessee, 37923**

**AFCEE Contract No. 41624-95-D-8005  
Delivery Order 0026 & 0029  
IT Project No. 800870**

**March 2001**



## **Table of Contents**

---

List of Acronyms .....	iii
1.0 Introduction.. .....	1-1
2.0 Field Procedures .....	2-1
2.1 Survey Control .. .....	2-1
2.2 Geophysical Survey Design and Instrumentation. . . . .	2-1
2.3 Anomaly Verification .....	2-3
3.0 Data Processing .. .....	3-1
4.0 Geophysical Survey Results.....	4-1
4.1 Interpretation Methods.....	4-1
4.2 Data Interpretation .. . . .	4-2
4.2.1 AOC 19 Anomalies .....	4-2
4.2.2 SWMUs 19 & 20 Anomalies .....	4-6
5.0 Conclusions and Recommendations .....	5-1
Site Maps With Geophysical Interpretation	
Appendix A – AOC 19 Site Map with Geophysical Interpretation and Data Contour Maps	
Appendix B – SWMUs 19 & 20 Site Map with Geophysical Interpretation and Data Contour Maps	
Appendix C – Magnetic Base Station Plots	
Appendix D – Theoretical Background	

## List of Acronyms

---

AFB	Air Force Base
AFCEE	Air Force Center for Environmental Excellence
BGS	below ground surface
CD	Compact Disk
E-W	east-to-west
EM	electromagnetic induction
EM31	Geonics Limited EM31 Terrain Conductivity Meter
EM61	Geonics Limited EM61 High-Resolution Metal Detector
G-856AX	Geometrics, Inc. G-856 Magnetometer
G-858G	Geometrics, Inc. G-858G Magnetic Gradiometer
IT	IT Corporation
JRB	joint reserve base
mS/m	milliSiemens per meter
mV	milliVolts
ppt	parts per thousand
N-S	north-to-south
NAS	Naval Air Station
nT	nanoTeslas
SWMU	solid waste management unit
UST	underground storage tank
UXO	unexploded ordnance

## 1.0 Introduction

---

IT Corporation (IT) performed surface geophysical surveys at the AOC 19 and Solid Waste Management Unit (SWMU) 19 & 20 sites at Naval Air Station (NAS) Ft. Worth Joint Reserve Base (JRB) (Formerly Carswell Air Force Base (AFB)) from February 12 through 16, 2001. The surveys were conducted for HydroGeoLogic under the Air Force Center for Environmental Excellence (AFCEE) Contract No. 41624-95-D-8005, Delivery Orders 0026 and 0029.

The objective of the survey at the AOC 19 site was to locate buried metal objects potentially representing drums. The objectives of the survey at the SWMUs 19 & 20 site were to locate buried metal objects potentially representing drums and a 10,000-gallon underground storage tank (UST). The total area investigated was approximately 189,950 square feet (approximately 4.36 acres).

To accomplish the objectives of the surveys, the geophysical surveys were designed using magnetic, time-domain electromagnetic (EM), and frequency-domain EM techniques. The site maps with geophysical interpretation (Figures A-1 and B-1) show the survey areas relative to permanent site features and the locations of significant anomalies that were identified in the data.

The AOC 19 site encompasses an irregular-shaped area with topography that slopes up to the north and west. The AOC 19 survey area was bounded on the south and east by a chain link fence and on the west and north by a road, as shown on the site map with geophysical interpretation (Figure A-1). The SWMUs 19 & 20 site is grass covered and has a gently sloped mound, which covers most of the site.

Field procedures used to conduct the survey are described in Section 2.0. Data processing methods used for the survey are presented in Section 3.0. The geophysical survey results are presented in Section 4.0. Conclusions derived from the geophysical survey are presented in Section 5.0.

- Appendices A and B: Site Maps showing the Geophysical Interpretation and data contour maps for the sites investigated.
- Appendix C: Magnetic Base Station Plots
- Appendix D: Theoretical Background of the geophysical techniques used in this investigation.

## **2.0 Field Procedures**

---

This section describes the field procedures and instruments used to conduct the geophysical surveys.

### **2.1 Survey Control**

Initially, the geophysics crew established base grids on 100-foot centers throughout the sites. Using the base grid as a reference, the crew marked control points on 10-foot centers with surveyors' paint to provide the required resolution for the investigation. Due to the uncertainty of true field positions inherent when establishing a survey area using 300-foot fiberglass tapes in the presence of wind and surface obstructions (e.g. utility poles, monitoring wells), the lateral precision for the survey areas and anomalies is believed to be within +/- 2 feet

Detailed, hand-sketched site maps were drawn in the field. The maps included any surface cultural features within the survey areas, or near their perimeters that could potentially affect the geophysical data (e.g., overhead utilities, manhole covers, monitoring wells). The maps also show reference features, such as roads and fences that could later aid in reconstructing the site boundaries. All reference information documented on the hand-sketched site maps was translated to the site interpretation maps.

### **2.2 Geophysical Survey Design and Instrumentation**

**Survey Equipment.** Magnetic instruments used during the investigation consisted of a Geometrics G-858G magnetic gradiometer (G-858G) for survey data acquisition, and Geometrics G-856AX magnetometer (G-856AX) for collecting base station data. Time-domain EM equipment used to conduct the investigation consisted of a Geonics EM61 high sensitivity metal detector (EM61) coupled to an Omnidata DL720 digital data logger. Frequency-domain EM equipment used to conduct the investigation consisted of a Geonics EM31 terrain conductivity meter (EM31) coupled to an Omnidata DL720 digital data logger. Where required, a Metrotech 9860-BRL EM utility locator was used to verify that linear anomalies seen in the EM31/EM61 data were caused by subsurface pipelines.

All geophysical data were collected in accordance with the methods and procedures outlined in the following IT Standard Operating Procedures:

- ITGP-001: Surface Magnetic Surveys
- ITGP-002: Surface Frequency-Domain Electromagnetic Surveys
- ITGP-004: Surface Time-Domain Electromagnetic Surveys
- ITGP-012: Geophysical Data Management.

**Field Instrument Base Station.** A field instrument base station was established at each site to provide quality assurance/quality control of the geophysical data. Prior to collecting the base station data, the instruments were used to determine that the location was clear of surface and subsurface cultural interference (e.g., fences, utilities, and surface/buried metal objects). Standard field procedures were used to take readings at the base station with each instrument (G-858G, EM61, and EM31) before and after each data collection session. These opening and closing base station files were reviewed as the survey progressed to assure proper instrument operation during each survey period. Average readings for each base station file were recorded on the base station summary form and are contained in project files.

**Magnetic Base Station.** A magnetic base station was used to record the diurnal variation in the Earth's magnetic field during the G-858G magnetic gradiometer survey. The magnetic base station was established at a location determined to be clear of surface and subsurface cultural interference (e.g., fences, utilities, and surface/buried metal objects). The G-856AX base station magnetometer was time-synchronized with the G-858G field survey instrument and programmed to record the Earth's background magnetic field at 10-second intervals during magnetic survey. These base station data were later used during data processing to "drift-correct" the G-858G survey data for variations in the Earth's magnetic field. Plots of the base station data are presented in Appendix C.

**G-858G Data Collection.** Prior to and immediately following each survey session, 60 readings of total magnetic field data were recorded with the G-858G at the field instrument base station. Evaluation of the base station data indicates the instrument was operating properly during the survey and that instrument drift was within acceptable limits. The spacing between the two G-858G sensors was 2.5 feet (0.76 meters) during the investigation, with the lower sensor at approximately 2.0 feet and the upper sensor at approximately 4.5 feet above the ground surface. Magnetic survey data were collected at 0.5-second (approximately 2.0- to 2.5-foot) intervals along north to south (N-S) oriented survey lines, spaced 5 feet apart, for a total of

approximately 39,210 linear feet of survey coverage. Magnetic data were stored in the internal memory of the G-858G, along with corresponding line and station numbers and the time of acquisition. Field and magnetic base station data were downloaded to a personal computer, backed up on Iomega® compatible zip disks, copied to compact disc (CD), and are retained in project files.

**EM61 Survey.** Prior to and immediately following each survey session, 20 readings of the potential difference were recorded from the top and bottom coils of the EM61 at the field instrument base station. Evaluation of the base station data indicates the instrument was operating properly during the survey and that instrument drift was within acceptable limits. EM61 data were collected in the wheel mode at 2.5-foot station intervals along N-S and east to west (E-W) oriented survey lines, spaced 5 feet apart, for a total of approximately 79,230 linear feet of survey coverage. Data were stored in the digital data logger programmed with corresponding line and station numbers. EM61 data were downloaded to a personal computer, backed up on Iomega® compatible zip disks, copied to CD, and are retained in project files.

**EM31 Survey.** Prior to each survey session, the EM31 was calibrated, the in-phase component was zeroed, and 20 readings of conductivity and in-phase component data were collected at the field instrument base station. Following each survey session, EM31 closing base station data were collected to verify that the EM31 was operating properly and to provide a quantitative record of instrument variation, or drift, during the survey period. Evaluation of the EM31 base station data indicates the instrument was operating properly during the survey period. The EM31 survey was conducted in the vertical dipole mode and data were collected at 5-foot intervals along N-S and E-W oriented survey lines, spaced 10 feet apart, for a total of approximately 39,090 linear feet of survey coverage. Data were stored in the digital data logger programmed with corresponding line and station numbers. EM31 data were downloaded to a personal computer, backed up on Iomega® compatible zip disks, copied to CD, and are retained in project files.

### **2.3 Anomaly Verification**

Following the field surveys, preliminary color-contour maps of magnetic, EM61, and EM31 data representing the site were plotted and field-checked to differentiate between anomalies caused by known surface features and those caused by subsurface source materials.

### 3.0 Data Processing

---

Contour maps of magnetic, EM61, and EM31 data were generated using the OASIS Montaj® geophysical mapping system from Geosoft, Inc. These maps were color-enhanced to aid with interpreting subtle anomalies. Select contour maps data are presented as Figures A-2 through A-10 and B-2 through B-10.

A series of data processing steps were required to generate the contour maps. G-858G magnetic gradiometer data were downloaded from the field instrument, corrected for diurnal drift, and then converted to an ASCII format file using the Geometrics, Inc. MAGMAP 2000® program. EM61 and EM31 data were downloaded from the data loggers and converted to ASCII format files using DAT61® and DAT31® software from Geonics, Inc. The ASCII data files were then reviewed so that line numbers, station ranges, and overall data quality could be assessed. Field data file names and corresponding base station data files were recorded on the data file tracking form. Data screening results were recorded on the base station summary form. Following data quality assessment, geometry corrections to field data files were made, if necessary, using a text editor and recorded on the Geophysical Data Editing Form.

Final, corrected magnetic and EM data files containing local geophysical station coordinates (X,Y) and the geophysical measurement (Z) were converted to OASIS Montaj® .XYZ format and imported into the geophysical mapping software. The data were bi-directionally gridded with an Akima spline. The grid cell size was 1.25 feet for the magnetic and EM61 data, and 2.5 feet for the EM31 data. The names of files generated and processing parameters used were recorded on data processing forms. All completed forms of magnetic and EM data collected during the investigation are retained in project files.

Due to the complexity of some magnetic anomalies, enhanced data processing was conducted on the Pre-Removal survey magnetic field data using the Geosoft UX Detect® interpretation software. The UX Detect® software performs inverse modeling by calculating 3-dimensional gradients of the magnetic data, determining the peak gradient locations, and then performing Euler deconvolution to solve for the apparent depth of the source material of the anomaly. The contour map of 3-dimensional magnetic gradient is most useful in reducing the complex magnetic response seen in total field magnetic data to a likely source area.

Enhanced data processing was performed on the EM61 data to aid with the depth determination of geophysical anomalies and provide for more accurate interpretations of metal concentrations. The UX-Detect® program, as applied to EM61 data, performs modeling by calculating the

difference in the data response between the top and bottom coils, determining the peak locations, then applying depth algorithms that use ratio response curves for both receivers to solve for the apparent depth of the source material.



## **4.0 Geophysical Survey Results**

---

This section describes the methods used to interpret the magnetic and EM data collected at NAS Ft. Worth JRB (Formerly Carswell AFB). The geophysical interpretation maps (Figures A-1 and B-1) are based on the combined results of the instruments used to conduct the surveys.

Interpreted contour maps of the geophysical data are presented in Appendices A and B. The theoretical background section (Appendix D) describes the factors influencing the observed geophysical response for the various methods used

### **4.1 Interpretation Method**

Anomalies shown on the magnetic and EM contour maps range from high to low values and from negative to positive, depending on the type of data displayed. The observed anomalies in the contour map of total magnetic field for the upper sensor have values above and below the average magnetic field intensity of 50,600 nanoTeslas (nT) for north central Texas during the survey periods. The typical magnetic data response to near-surface ferrous metallic debris is an asymmetric south high/north low signature. The shape and amplitude of an induced magnetic anomaly over a ferromagnetic object depend on the geometry, size, depth, orientation, and magnetic susceptibility of the object. The upper sensor is generally more useful for interpreting larger source objects such as landfill areas, underground storage tanks, and drums. The lower sensor is generally more useful for interpreting small, near-surface source objects, such as scrap metal and unexploded ordnance (UXO). Used together, both are diagnostic for estimating the size and depth characteristics of ferrous source materials. Typically, an increase in total magnetic field, particularly in the upper sensor, indicates an increase in the volume of ferromagnetic materials in the study area. However, this increase in field intensity can also be caused by source materials located closer to the surface. To better understand G-858G upper sensor magnetic field variations, other data such as the G-858G lower sensor, EM61 and EM31 data were also analyzed. Although contour maps of the G-858G lower sensor and vertical magnetic gradient were interpreted, only the map of upper sensor data are presented since it is the most useful for locating drum-sized objects.

The characteristic EM61 response over a buried metal object shows a positive-amplitude signal, with the amplitude being dependent on the size of the object, distance from the transmitter/receiver coils, and the type of metal. Upper and lower receiver coil readings are processed to determine a differential value that can be used to estimate the depth of source objects. Although all EM61 data were evaluated during interpretation, only the bottom coil EM61 data are presented, since the bottom coil is most sensitive to buried metal objects.

The characteristic EM31 anomaly over a near-surface metallic conductor consists of a narrow zone having strong negative amplitude centered over the target and a broader lobe of weaker, positive amplitude on either side of the target. As the depth of the target feature increases, the characteristic EM31 response often changes to a positive amplitude centered over the target. For this type of investigation, EM31 data are generally more useful for interpreting small pits containing more than one drum.

## **4.2 Data Interpretation**

This section discusses the general characteristics of the geophysical data and describes the geophysical characteristics specific to each anomaly identified on the magnetic and EM contour maps.

The site maps with geophysical interpretation (Figures A-1 and B-1) contain detailed information about known surface features. The information contained on the site maps was translated from the hand-sketched site maps generated in the field. The anomalies shown on the site interpretation maps correspond to those shown on the data contour maps.

The magnetic and EM data contour maps show several low- to high-amplitude anomalies throughout the sites. Some of these anomalies are caused by known surface features (i.e., fences and manhole covers) and subsurface pipelines/utilities and are indicated as such on the data contour maps.

The anomalies observed in the contour map G-858G total magnetic field data and the analytic signal best depict the relative concentrations of metal at the site. The EM61 potential difference data most accurately show the boundaries and relative depth of the near-surface metallic source objects. The EM31 conductivity and in-phase component data are useful in distinguishing pipeline trends and determining whether anomalies seen in EM61 data represent continuous or nearly continuous source objects (i.e., small pit containing more than one drum-sized object) or simply a large number of point sources.

### **4.2.1 AOC 19 Anomalies**

The geophysical anomalies identified in the data are indicated on the data maps and interpretation map as Anomalies A-1 through A-15. These anomalies are interpreted to be caused by buried metal objects large enough to represent individual drums or pits containing more than one drum. Ten of the anomalies are contained within the AOC 19 site boundaries, while the remaining five are perimeter anomalies, which trend offsite. The site map with

geophysical interpretation (Figure A-1) shows the boundaries and relative concentrations of buried metal at the site.

**Anomaly A-1.** Anomaly A-1 consists of two individual anomalies that occur at (365N, 177E) and (341N, 157E). Anomaly A-1 occurs as multiple magnetic anomalies with responses, which vary from 350 to 1,500 nT (Figure A-2). Anomaly A-1 is interpreted as moderate concentrations of buried metal at depth.

**Anomaly A-2.** Anomaly A-2 is a perimeter anomaly located at approximately (365N, 123E). Anomaly A-2 occurs as a low-amplitude anomaly in the magnetic data with a response of approximately 193 nT (Figure A-2). Anomaly A-2 has a moderate-amplitude response in the EM61 data of approximately 237 milliVolts (mV) (Figures A-4 and A-5). EM61 UX-detect depth modeling indicates that the source objects are approximately 1 to 2 feet below ground surface (bgs) (Figure A-6). Anomaly A-2 extends beyond the western boundary of the survey area, therefore the lateral extents of the anomaly cannot be determined. Anomaly A-2 is interpreted as a low concentration of buried metal.

**Anomaly A-3.** Anomaly A-3 is located at approximately (337N, 226E). Anomaly A-3 occurs primarily as a high-amplitude magnetic anomaly with a response of approximately 1,300 nT (Figure A-2). Anomaly A-3 also has a subtle response in the N-S EM31 inphase component data of approximately 0.7 parts per thousand (ppt) above background (Figure A-7). Anomaly A-3 is interpreted to be a low concentration of buried metal, not likely a buried drum(s).

**Anomaly A-4.** Anomaly A-4 consists of multiple features in the north-central portion of the site centered at approximately (295N, 135E). Anomaly A-4 occurs in the magnetic data with responses, that vary from 1,500 to 3,300 nT (Figure A-2) and in the EM61 data with responses, that vary from 100 to 3,000 mV (Figures A-4 and A-5). EM61 UX-detect depth modeling indicates that the source objects are located between 1 to 5 feet bgs (Figure A-6). Anomaly A-4 has a moderate amplitude EM31 conductivity response approximately 15 milliSiemens per meter (mS/m) below background (Figures A-8 and A-10). Anomaly A-4 occurs in the EM31 inphase component data as a moderate- to high-amplitude anomaly with a response varying from 4 ppt above background to 10 ppt below background (Figures A-7 and A-9). Portions of Anomaly A-4 extend beyond the boundaries of the survey area, therefore the lateral extents of the anomaly cannot be determined. Anomaly A-4 is interpreted to be caused by a high concentration of buried metal, possibly representing buried drums.

**Anomaly A-5.** Anomaly A-5 consists of two individual features that are centered at approximately (255N, 170E) and (256N, 190E). Anomaly A-5 occurs as two high-amplitude magnetic anomalies with responses, which vary from 2,600 to 3,100 nT (Figure A-2). Anomaly A-5 is interpreted to be caused by a low concentration of buried metal, possibly representing deeply buried metal objects.

**Anomaly A-6.** Anomaly A-6 is a perimeter anomaly located at approximately (240N, 50E). Anomaly A-6 occurs as a moderate-amplitude anomaly with a magnetic response of approximately 900 nT and an EM61 response of approximately 220 mV (Figures A-2, A-4, and A-5). EM61 UX-detect depth modeling indicates that the source objects are located within 3 feet of ground surface (Figure A-6). Anomaly A-6 extends beyond the western boundary of the survey area, therefore the lateral extents of the anomaly cannot be determined. Anomaly A-6 is interpreted to be caused by a moderate concentration of buried metal, possibly representing buried drums.

**Anomaly A-7.** Anomaly A-7 is located at approximately (190N, 60E). Anomaly A-7 occurs as a high-amplitude anomaly in the magnetic data with a response exceeding 3,700 nT (Figure A-2). Anomaly A-7 has a subtle response of approximately 75 mV in the EM61 data (Figures A-4 and A-5). EM61 UX-detect depth modeling indicates that the source objects are located within 3 feet of ground surface (Figure A-6). Anomaly A-7 is interpreted to be caused by a moderate concentration of buried metal, possibly representing buried drums.

**Anomaly A-8.** Anomaly A-8 is located at approximately (160N, 130E). Anomaly A-8 occurs as high-amplitude anomalies in the magnetic data (Figure A-2) and the EM31 data sets (Figures A-7 through A-10). The magnitude of Anomaly A-8's response cannot be determined due to the anomaly's proximity to a nearby pipeline. Anomaly A-8 is likely a utility vault or valve box, however, the possibility remains that it could be caused by buried drums.

**Anomaly A-9.** Anomaly A-9 consists of multiple features in the southwestern portion of the site centered at approximately (135N, 80E). Anomaly A-9 occurs in the magnetic data as several moderate- to high-amplitude anomalies with responses ranging from 600 to 1,500 nT (Figure A-2). Anomaly A-9 occurs in the EM61 data as a broad distribution of anomalies with responses in the range of 60 to 200 mV with isolated sources exceeding 1,500 mV (Figures A-4 and A-5). EM61 UX-detect depth modeling indicates that the source objects are located between 1 to 3 feet bgs (Figure A-6). Anomaly A-9 occurs in the EM31 inphase component data as a low that exceeds 3.1 ppt below background (Figures A-7 and A-9). The EM31 inphase low corresponds

with high-amplitude magnetic and EM61 anomalies indicating a high concentration of buried metal, possibly representing buried drums.

**Anomaly A-10.** Anomaly A-10 is located at approximately (100N, 15E) and (75N, 25E).

Anomaly A-10 occurs as two moderate-amplitude magnetic anomalies with responses that range from approximately 450 to 820 nT (Figure A-2). Anomaly A-10 occurs in the EM61 data as multiple low-amplitude anomalies with responses of approximately 25 mV (Figures A-4 and A-5). EM61 UX-detect depth modeling indicates that the source objects are located between 3 to 4 feet bgs (Figure A-6). Anomaly A-10 is interpreted to be moderate concentrations of buried metal, possibly representing buried drums.

**Anomaly A-11.** Anomaly A-11 is a perimeter anomaly located at approximately (45N, 12E)

Anomaly A-11 occurs only in the magnetic data as a high-amplitude anomaly exceeding 1,500 nT (Figure A-2). A portion of Anomaly A-11 extends beyond the boundary of the survey area, therefore the lateral extents of the anomaly cannot be determined. Anomaly A-11 is interpreted as a low concentration of buried metal trending offsite to the west.

**Anomaly A-12.** Anomaly A-12 is located at approximately (38N, 75E). Anomaly A-12 occurs in the magnetic data as a high-amplitude anomaly with a response of approximately 1,000 nT (Figures A-2). Anomaly A-12 occurs as a low-amplitude anomaly in the EM61 data with a response of approximately 170 mV (Figures A-4 and A-5). EM61 UX-detect depth modeling indicates that the source objects are located within 1 foot of ground surface (Figure A-6). Anomaly A-12 is interpreted as a high concentration of buried metal, not likely a buried drum(s).

**Anomaly A-13.** Anomaly A-13 is located at approximately (50N, 130E). Anomaly A-13 occurs as a high-amplitude magnetic dipole with a response exceeding 1,300 nT (Figure A-2). Anomaly A-13 has a moderate-amplitude response in the EM61 data of approximately 350 mV (Figure A-4 and Figure A-5). EM61 UX-detect depth modeling indicates that the source object is located between 1 to 2 feet bgs (Figure A-6). Anomaly A-13 occurs in the EM31 inphase component data as a moderate-amplitude anomaly with a response of approximately 4 ppt (Figures A-7 and A-9). Anomaly A-13 is interpreted as a high-concentration of buried metal, possibly representing a pit of buried drums.

**Anomaly A-14.** Anomaly A-14 is located at approximately (92N, 260E). Anomaly A-14 occurs as a low-amplitude magnetic anomaly with a response of approximately 200 nT (Figure A-2). Anomaly A-14 has moderate- to high-amplitude responses in the EM61 data ranging from approximately 500 to 2,800 mV (Figures A-4 and A-5). EM61 UX-detect depth modeling

indicates that the source objects are located between 2 to 3 feet bgs (Figure A-6). Anomaly A-14 occurs as an EM31 inphase component anomaly with a response of approximately 2.2 ppt below background. The magnetic and EM data responses for Anomaly A-14 may be partially masked by the nearby metal fence. Anomaly A-14 is interpreted as a high concentration of buried metal, possibly representing a buried drum(s).

**Anomaly A-15.** Anomaly A-15 is a perimeter anomaly located at approximately (18N, 50E). Anomaly A-15 occurs in the magnetic data as a moderate-amplitude monopole with a response of approximately 900 nT below background (Figure A-2). Anomaly A-15 has a moderate-amplitude EM61 response of 300 mV (Figures A-4 and A-5). EM61 UX-detect depth modeling indicates that the source objects are located between 1 to 2 feet bgs (Figure A-6). The magnetic and EM data responses for Anomaly A-15 may be partially masked by the nearby metal fence. Anomaly A-15 extends beyond the boundary of the survey area, therefore the lateral extents of the anomaly cannot be determined. Anomaly A-15 is interpreted to be caused by a high concentration of buried metal possibly trending offsite to the south.

#### **4.2.2 SWMUs 19 & 20 Anomalies**

The geophysical anomalies identified in the data are indicated on the data maps and interpretation map as Anomalies B-1 through B-7. These anomalies are interpreted to be caused by buried metal objects large enough to represent individual drums, USTs or pits containing more than one drum. The site map with geophysical interpretation (Figure B-1) shows the boundaries and relative concentrations of buried metal at the site.

**Anomaly B-1.** Anomaly B-1 is located at approximately (307N, 177E). It occurs as a high-amplitude anomaly in both the magnetic and EM data. Anomaly B-1 has a response of approximately 2,700 nT in the magnetic data (Figure B-2) and 1,300 mV in the EM61 data (Figures B-4 and B-5). EM61 UX-detect depth modeling indicates that the source object is approximately 2 to 3 feet bgs (Figure B-6). Anomaly B-1 has a high-amplitude response in the EM31 inphase component data of 6 ppt below background (Figures B-7 and B-9) and in the conductivity data of approximately 30 mS/m below background (Figures B-8 and B-10). Anomaly B-1 is interpreted as a high concentration of buried metal possibly representing a UST or a pit of buried drums.

**Anomaly B-2.** Anomaly B-2 is located at approximately (265N, 205E). Anomaly B-2 has a low-amplitude magnetic response of approximately 120 nT (Figure B-2). Anomaly B-2 has an EM61 response of that exceeds 800mV (Figures B-4 through B-6). EM61 UX-detect depth

modeling indicates that the source object is approximately 1 to 2 feet bgs. Anomaly B-2 has an EM31 conductivity response approximately 10 mS/m below background and occurs in the EM31 inphase component data with a response of 3.6 ppt below background (Figures B-7 through B-10). Anomaly B-2 is interpreted as a moderate concentration of buried metal possibly representing a valve box, a utility vault, a UST or a pit of buried drums.

**Anomaly B-3.** Anomaly B-3 is located at approximately (33N, 0E). Anomaly B-3 occurs only in the EM61 data with a response exceeding 250 mV (Figures B-4 through B-6). EM61 UX-detect depth modeling indicates that the source object is within 1 foot of the surface. Anomaly B-3 is interpreted as a low concentration of non-ferrous buried metal, not likely a buried drum(s).

**Anomaly B-4.** Anomaly B-4 is located at approximately (25N, 25E). Anomaly B-4 occurs only in the EM61 data with a response that exceeds 500 mV (Figures B-4 through B-6). EM61 UX-detect depth modeling indicates that the source object is within 1 foot of the surface. Anomaly B-4 is interpreted as a low concentration of non-ferrous buried metal not likely a buried drum(s).

**Anomaly B-5.** Anomaly B-5 is located at approximately (40N, 25E). Anomaly B-5 occurs only in the magnetic data with a response of 550 nT (Figure B-2). Anomaly B-5 is interpreted to be caused by a low concentration of ferrous metal, not likely a buried drum(s).

**Anomaly B-6.** Anomaly B-6 is located at approximately (0N, 220E). It occurs as a high-amplitude anomaly in both the magnetic and EM data. Anomaly B-6 occurs in the magnetic data with a response of approximately 1,100 nT (Figure B-2) and in the EM61 data with a response of approximately 70 mV with an isolated source exceeding 1,700 mV (Figures B-4 and B-5). EM61 UX-detect depth modeling indicates that the source object is approximately 1 to 3 feet bgs (Figure B-6). Anomaly B-6 occurs as a high-amplitude anomaly in the E-W EM31 inphase data with a response of approximately 7 ppt below background (Figure B-9). Anomaly B-6 has an EM31 conductivity data response that varies from 12 mS/m below background to 14 mS/m above background (Figures B-8 and B-10). This signature is characteristic of shallow buried metal. The linear nature of Anomaly B-6 indicates the possibility that it could be caused by a section of pipeline/utility. Anomaly B-6 is interpreted as a high concentration of buried metal possibly representing a section of pipe, a small UST, or a pit of buried drums.

*Anomaly B-7.* Anomaly B-7 is located at approximately (20N, 265E). It occurs as a high-amplitude anomaly in both the magnetic and EM data. Anomaly B-7 occurs in the magnetic data with a response of approximately 2,700 nT (Figure B-2) and in the EM61 data with a response of approximately 1,300 mV (Figures B-4 and B-5). EM61 UX-detect depth modeling indicates that the source object is within approximately 2 feet of the surface (Figure B-6). Anomaly B-7 occurs in the EM31 conductivity data as a high-amplitude response that varies from 80 mS/m below background to 50 mS/m above background (Figures B-8 and B-10). This signature is typical of shallow buried metal. The linear nature of Anomaly B-7 indicates the possibility that it could be caused by a section of pipe. Anomaly B-7 is interpreted as a high concentration of buried metal possibly a section of pipe or a trench/pit of buried drums.



## 5.0 Conclusions and Recommendations

---

Surface geophysical surveys using magnetic and EM methods were conducted at the AOC 19 and SWMUs 19 & 20 sites at NAS Ft. Worth JRB (Formerly Carswell AFB) from February 12 through 16, 2001. The objective of the survey at the AOC 19 site was to locate buried metal objects potentially representing drums. The objectives of the survey at the SWMUs 19 & 20 site were to locate buried metal objects potentially representing drums and a 10,000-gallon UST. The total area investigated was approximately 189,950 square feet (approximately 4.36 acres).

Twenty-two geophysical anomalies caused by buried metal are identified on the data maps. The site maps with geophysical interpretation (Figures A-1 and B-1) show the boundaries and relative concentrations of buried metal at the sites. At the AOC 19 site, five anomalies are caused by source anomalies that extend offsite. In order to fully delineate these anomalies site expansions are recommended at the western and southern boundaries. Intrusive investigation is recommended at all anomaly locations to identify the source objects.

Detailed hand sketches were drawn in the field to document all permanent site reference features and to provide a basis for future reconstruction of the survey areas. Due to the uncertainty of true field positions inherent when establishing survey areas using a 300-foot fiberglass tapes in the presence of wind and surface obstructions (e.g., fences, monitoring wells and surface metal), the lateral precision for the survey areas and anomalies is believed to be within +/- 2 feet.

Pipelines are indicated on the site interpretation maps where evident in the geophysical data. However, the utilities shown on the maps should not be used to preclude proper geophysical clearance work at those exploratory trenching locations where buried utilities are suspect. Proper geophysical clearance work typically involves obtaining available utility maps and conducting "point" clearances with an EM utility locator and ground penetrating radar.




To relocate the survey areas and anomalies, IT recommends using the detailed information contained on the site interpretation maps (Figures A-1 and B-1).

## APPENDIX A

### AOC 19 Site


Site Map with Geophysical Interpretation  
G-858G Total Magnetic Field Upper Sensor Contour Map  
G-858G Total Magnetic Field Analytic Signal Map  
EM61 Potential Difference Contour Maps  
EM61 Target Depth Estimate Map  
EM31 In-Phase Component Contour Maps  
EM31 Conductivity Contour Maps





LEGEND

- GEOPHYSICAL SURVEY LINES
- A-1 ANOMALY DISCUSSED IN TEXT
- BM ANOMALY CAUSED BY BURIED METAL OBJECT
- SM ANOMALY CAUSED BY SURFACE METAL
- F ANOMALY CAUSED BY FENCE
- ANOMALY CAUSED BY BURIED PIPE OR UTILITY



Minimum Contour Interval 100 nanoTeslas


FIGURE A-2

G-858G TOTAL MAGNETIC FIELD  
UPPER SENSOR (4 5 FT ABOVE GROUND SURFACE)  
NORTH-SOUTH SURVEY LINES



AOC 19  
NAS FT WORTH JRB (FORMERLY CARSWELL AFB)  
FORT WORTH, TEXAS

IT GEOPHYSICS GROUP KNOXVILLE, TENNESSEE

NAME	DATE
M. L. M. L.	February 20, 2001
PROJECT NUMBER	LOCATION
800870	C:\projects\carwell\AOC19\MAGTOP map






Target ID ●



- LEGEND
- GEOPHYSICAL SURVEY LINES
  - A-1 ANOMALY DISCUSSED IN TEXT
  - BM ANOMALY CAUSED BY BURIED METAL OBJECT
  - SM ANOMALY CAUSED BY SURFACE METAL
  - F ANOMALY CAUSED BY FENCE
  - ANOMALY CAUSED BY BURIED PIPE OR UTILITY

FIGURE A-3	
G-858G TOTAL MAGNETIC FIELD ANALYTIC SIGNAL (3D MAGNETIC GRADIENT) NORTH-SOUTH SURVEY LINES	
NAS FT WORTH JRB (FORMERLY CARSWELL AFB) FORT WORTH, TEXAS	AOC 19
IT GEOPHYSICS GROUP KNOXVILLE, TENNESSEE	

NAME	DATE
Media Media	February 20, 2001
PROJECT NUMBER	LOCATION
800870	C:\projects\carwell\AOC19\AOC19MAGTARGST2.msp



LEGEND

- GEOPHYSICAL SURVEY LINES
- ANOMALY DISCUSSED IN TEXT
- A-1 ANOMALY CAUSED BY SURFACE METAL
- SM ANOMALY CAUSED BY BURIED METAL OBJECT
- BM ANOMALY CAUSED BY FENCE
- F ANOMALY CAUSED BY BURIED PIPE OR UTILITY

Scale 1:720






FIGURE A-4

EM61 POTENTIAL DIFFERENCE  
BOTTOM COIL (1.5 FT ABOVE GROUND SURFACE)  
NORTH-SOUTH SURVEY LINES

AOC 19  
NAS FT WORTH JRB (FORMERLY CARSWELL AFB)  
FORT WORTH, TEXAS

IT GEOPHYSICS GROUP KNOXVILLE, TENNESSEE

NAME	McGILL	DATE	February 20, 2001
PROJECT NUMBER	800870	LOCATION	C:\projects\carwell\AOC19\EM61\NB2.map



**LEGEND**

GEOPHYSICAL SURVEY LINES

- A-1 ANOMALY DISCUSSED IN TEXT
- SM ANOMALY CAUSED BY SURFACE METAL
- BM ANOMALY CAUSED BY BURIED METAL OBJECT
- F ANOMALY CAUSED BY FENCE
- ANOMALY CAUSED BY BURIED PIPE OR UTILITY





FIGURE A-5

EM61 POTENTIAL DIFFERENCE  
BOTTOM COIL (1.5 FT ABOVE GROUND SURFACE)  
EAST-WEST SURVEY LINES


AOC 19  
NAS FT WORTH JRB (FORMERLY CARSWELL AFB)  
FORT WORTH, TEXAS

IT GEOPHYSICS GROUP KNOXVILLE, TENNESSEE

NAME	Mike Mado	DATE	February 20, 2001
PROJECT NUMBER	800870	LOCATION	C:\project\carswell2\AOC 19\EM61EB2.map










**FIGURE A-7**

EM31 INPHASE COMPONENT  
VERTICAL DIPOLE (3 0 FT ABOVE GROUND SURFACE)  
NORTH-SOUTH SURVEY LINES

AOC 19  
NAS FT WORTH JRB (FORMERLY CARSWELL AFB)  
FORT WORTH, TEXAS

IT GEOPHYSICS GROUP KNOXVILLE, TENNESSEE

NAME	Media Map	DATE	February 20, 2001
PROJECT NUMBER	800870	LOCATION	C:\projects\carswell\20AOC19\EM31\IN1.map



- LEGEND
- GEOPHYSICAL SURVEY LINES
- A-1 ANOMALY DISCUSSED IN TEXT
  - SM ANOMALY CAUSED BY SURFACE METAL
  - F ANOMALY CAUSED BY FENCE
  - ANOMALY CAUSED BY BURIED PIPE OR UTILITY





FIGURE A-8

EM31 CONDUCTIVITY	
VERTICAL DIPOLE (3.0 FT ABOVE GROUND SURFACE)	
NORTH-SOUTH SURVEY LINES	
AOC 19	
NAS FT WORTH JRB (FORMERLY CARSWELL AFB)	FORT WORTH, TEXAS
IT GEOPHYSICS GROUP KNOXVILLE, TENNESSEE	

NAME	DATE
Nicki Maki	February 20, 2001
PROJECT NUMBER	LOCATION
80870	C:\projects\carw\2\AOC19\EM31\NC map



### LEGEND

GEOPHYSICAL SURVEY LINES  
B-1 ANOMALY DISCUSSED IN TEXT  
SM ANOMALY CAUSED BY SURFACE METAL  
F ANOMALY CAUSED BY FENCE  
ANOMALY CAUSED BY BURIED PIPE OR UTILITY

Scale 1 720

1 foot  
Minimum Contour Interval 1 ppt Secondary to Primary Field



FIGURE A-9

EM31 INPHASE COMPONENT  
VERTICAL DIPOLE (3.0 FT ABOVE GROUND SURFACE)  
EAST-WEST SURVEY LINES

NAS FT WORTH JRB (FORMERLY CARSWELL AFB)  
FORT WORTH, TEXAS

IT GEOPHYSICS GROUP KNOXVILLE, TENNESSEE

NAME	DATE
Micki Maki	February 20, 2001
PROJECT NUMBER	LOCATION
800870	C:\projects\camwell\AOC19\EM31\EL.map



LEGEND

GEOPHYSICAL SURVEY LINES

A-1 ANOMALY DISCUSSED IN TEXT

SM ANOMALY CAUSED BY SURFACE METAL

F ANOMALY CAUSED BY FENCE

ANOMALY CAUSED BY BURIED PIPE OR UTILITY

FIGURE A-10

EM31 CONDUCTIVITY

VERTICAL DIPOLE (30 FT ABOVE GROUND SURFACE)

EAST-WEST SURVEY LINES

AOC 19

NAS FT. WORTH JRB (FORMERLY CARSWELL AFB)

FORT WORTH, TEXAS

IT GEOPHYSICS GROUP KNOXVILLE, TENNESSEE

NAME	Micki Maki	DATE	February 20, 2001
PROJECT NUMBER	800870	LOCATION	C:\projects\carwell\2AOC19\EM31\EC map

## APPENDIX B

### SWMUs 19 & 20 Site

Site Map with Geophysical Interpretation  
G-858G Total Magnetic Field Upper Sensor Contour Map  
G-858G Total Magnetic Field Analytic Signal Map  
EM61 Potential Difference Contour Maps  
EM61 Target Depth Estimate Map  
EM31 In-Phase Component Contour Maps  
EM31 Conductivity Contour Maps

**(NOT INCLUDED)**

## APPENDIX C

### Magnetic Base Station Plots

Figure C-1  
Magnetic (G-856) Base Station  
February 12, 2001  
NAS Ft Worth JRB (Formerly Carswell AFB)  
Project No 800870




Figure C-2  
 Magnetic (G-856) Base Station  
 February 12, 3, 2001  
 NAS Ft Worth JRB (Formerly Carswell AFB)  
 Project No 800870






Figure C-3  
Magnetic (G-856) Base Station  
February 14, 2001  
NAS Ft Worth JRB (Formerly Carswell AFB)  
Project No 800870





Figure C-4  
Magnetic (G-856) Base Station  
February 15, 2001  
NAS Ft Worth JRB (Formerly Carswell AFB)  
Project No 800870



# TAB

APPENDIX A: THEORETICAL BACKGROUND

## APPENDIX D

### THEORETICAL BACKGROUND

## ***Table of Contents***

---

List of Acronyms.....	D-ii
D.1.0 Magnetic Method. ....	D-1
D 2.0 Frequency-domain Electromagnetic Induction Method.....	D-3
D.3.0 Time-domain Electromagnetic Induction Method ...	D-5
D.4.0 References .....	D-6

## ***List of Acronyms***

---

EM	electromagnetic induction
EM31	Geonics Limited EM31 Terrain Conductivity Meter
EM61	Geonics Limited EM61 High-Resolution Metal Detector
G-856	Geometrics Inc. G-856 Magnetometer
G-858G	Geometrics Inc. G-858G Magnetic Gradiometer
9860-BRL	Metrotech Inc 9860-BRL EM utility locator
JRB	Joint Reserve Base
mV	millivolts
mS/m	milliSiemens/meter
NAS	Naval Air Station
nT	nanoTeslas
nT/m	nanoTeslas/meter
ppt	parts per thousand
RF	radiofrequency
UXO	unexploded ordnance

## ***D.1.0 Magnetic Method***

---

The magnetic instruments used during the Naval Air Station (NAS) Ft Worth Joint Reserve Base (JRB) surface geophysical surveys were a Geometrics, Inc., G-858G "walking mode" magnetic gradiometer (G-858G) for acquiring survey data and a Geometrics, Inc., G-856 for collecting magnetic base station data.

The G-858G, which is an optically-pumped cesium vapor instrument, measures the intensity of the Earth's magnetic field in nanoTeslas (nT) and the vertical gradient of the magnetic field in nanoTeslas per meter (nT/m). The vertical gradient is measured by simultaneously recording the magnetic field with two sensors at different heights. To determine the vertical magnetic gradient, the upper sensor reading is subtracted from the lower sensor reading, and the result is then divided by the distance between the sensors. The distance between sensors for this investigation was 2.5 feet (0.76 meters). The vertical magnetic gradient measurement allows for better definition of shallower anomalies.

During operation of the G-858G magnetic gradiometer, a direct current is used to generate a polarized monochromatic light. Absorption of the light occurs within the naturally precessing cesium atoms found in the instrument's two vapor cells or sensors. When absorption is complete, the precessing atoms become a transfer mechanism between light and a transverse radiofrequency (RF) field at a specific frequency of light known as the Larmor frequency. The light intensity is used to monitor the precession and adjusts the RF allowing for the determination of the magnetic field intensity (Sheriff, 1991)

The Earth's magnetic field is believed to originate in currents in the Earth's liquid outer core. The magnetic field varies in intensity from approximately 25,000 nT near the equator, where it is parallel to the Earth's surface, to approximately 70,000 nT near the poles, where it is perpendicular to the Earth's surface. In Texas, the intensity of the Earth's magnetic field varies from 50,000 nT to 51,000 nT and has an associated inclination of approximately 54 degrees.

Anomalies in the Earth's magnetic field are caused by induced or remnant magnetism. Remnant magnetism is caused by naturally occurring magnetic materials. Induced magnetic anomalies result from the induction of a secondary magnetic field in a ferromagnetic material (e.g., pipelines, drums, tanks, or well casings) by the Earth's magnetic field. The shape and amplitude of an induced magnetic anomaly over a ferromagnetic object depend on the geometry, size,

depth, and magnetic susceptibility of the object and on the magnitude and inclination of the Earth's magnetic field in the study area (Dobrin, 1976; Telford, et al , 1976) Induced magnetic anomalies over buried objects such as drums, pipes, tanks, and buried metallic debris generally exhibit an asymmetrical, south high/north low signature (maximum amplitude on the south side and minimum on the north). Magnetic anomalies caused by buried metallic objects generally have dimensions much greater than the dimensions of the objects themselves. As an extreme example, a magnetometer may begin to sense a buried oil well casing at a distance of greater than 50 feet.

The magnetic method is not effective in areas with ferromagnetic material at the surface because the signal from the surface material obscures the signal from any buried objects. Also, the presence of an alternating current electrical power source can render the signal immeasurable because of the high precision required in the measurement of the frequency at which the protons precess (Breiner, 1973). The precession signal may also be sharply degraded in the presence of large magnetic gradients (exceeding approximately 600 nT/m).

The magnetic field measured at any point on the Earth's surface undergoes low-frequency diurnal variation, called magnetic drift, associated with the Earth's rotation. The source of magnetic drift is mainly within the ionosphere, and its magnitude is sometimes large enough to introduce artificial trends in survey data. The G-856 base station magnetometer was used to record this drift for removal from the G-858G survey data during processing.

Applications of the magnetic method include delineating old waste sites and mapping unexploded ordnance (UXO), drums, tanks, pipes, abandoned wells, and buried metallic debris. The method also is useful in searching for magnetic ore bodies, delineating basement rock, and mapping subsurface geology characterized by volcanic or mafic rocks.



## ***D.2.0 Frequency-Domain EM Induction Method***

---

Frequency-domain electromagnetic induction equipment used during this investigation consisted of a Geonics EM31 terrain conductivity meter (EM31) coupled to an Omnidata DL720 digital data logger. The EM31 consists of a 12-foot-long plastic boom with a transmitter coil mounted at one end and a receiver coil at the other. An alternating current is applied to the transmitter coil, causing the coil to radiate a primary EM field. As described by Faraday's law of induction, this time-varying magnetic field generates eddy currents in conductive subsurface materials. These eddy currents have an associated secondary magnetic field with a strength and phase shift (relative to the primary field) that are dependent on the conductivity of the medium. The combined effect of the primary and secondary fields is measured by the receiver coil in-phase (in-phase) and 90 degrees out-of-phase (quadrature) with the primary field. Most geologic materials are poor conductors. Current flow through geologic materials takes place primarily in the pore fluids (Keller and Frischknecht, 1966), as such, conductivity is predominantly a function of soil type, porosity, permeability, pore fluid ion content, and degree of saturation. The EM31 is calibrated so that the out-of-phase component is converted to electrical conductivity in units of millisiemens per meter (mS/m) (McNeill, 1980), and the in-phase component is converted to parts per thousand (ppt) of the secondary field to the primary EM field. The in-phase component is a relative value that is generally set to zero over background materials at each site.

The depth of penetration for EM induction instruments depends on the transmitter/receiver separation and coil orientation (McNeill, 1980). The EM31 has an effective exploration depth of approximately 18 feet when operating in the vertical dipole mode (horizontal coils). In this mode, the maximum instrument response results from materials at a depth of approximately two-fifths the coil spacing (or, approximately 2 feet below ground surface with the instrument at the normal operating height of approximately 3 feet), providing that no large metallic features such as tanks, drums, pipes, and reinforced concrete are present. Single buried drums typically can be located to depths of approximately 5 feet, whereas clusters of drums can be located to significantly greater depths if background noise is limited or negligible. In the horizontal dipole mode (vertical coils), the EM31 has an effective exploration depth of approximately 9 feet and is most sensitive to materials immediately beneath the ground surface.

The EM31 generally must pass over or very near a buried metallic object to detect it. Both the out-of-phase and in-phase components exhibit a characteristic anomaly over near-surface metallic conductors. This anomaly consists of a narrow zone having strong negative amplitude

centered over the target and a broader lobe of weaker, positive amplitude on either side of the target. For long, linear conductors such as pipelines, the characteristic anomaly is as described when the axis of the coil (instrument boom) is at an angle to the conductor. However, when the instrument boom is oriented parallel to the conductor, a positive amplitude anomaly is obtained.

The application of frequency-domain EM techniques includes mapping conductive groundwater contaminant plumes in very shallow aquifers, delineating oil brine pits, landfill boundaries and pits and trenches containing buried metallic and nonmetallic debris, and locating buried pipes, cables, drums, and tanks

### ***D.3.0 Time-Domain EM Induction Method***

---

Time-domain electromagnetic induction equipment used during this investigation consisted of a Geonics EM61 high-resolution metal detector (EM61) coupled to an Omnidata DL720 digital data logger. The EM61 consists of one transmitter and two receiver coils each 1-meter square. The transmitter and one receiver coil are co-incident within the instrument, the second receiver coil is separated by 0.5 meters (m). Comparison of the readings in the two receiver coils allows for discrimination between shallow and deeply buried metal objects. In operation, a pulse of current in the transmitter coil generates a primary magnetic field that induces eddy currents in nearby metallic conductors, as described by Faraday's law of induction. These eddy currents produce secondary magnetic fields that are measured by the time-dependant, decaying voltage they produce in the receiver coils. The internal electronics of the EM61 are designed such that readings are taken in a very narrow time window following transmitter turn-off. The measurement secondary fields in the absence of a primary field allows for the high sensitivity measurements obtained with the system. Since the current ring diffuses down and outward, readings taken immediately after current shut-off are most affected by near-surface conditions and the later readings by the electrical properties of the deeper subsurface.

The EM61 is generally adjusted in the field to have a zero millivolts (mV) response over background conditions.

The EM61 depth of penetration depends primarily on the size of the target, and to a lesser degree on the type of metal (Geonics, 1997). The EM61 has an effective exploration depth in excess of 10 feet for locating large conductive features, such as tanks.

The EM61 generally must pass over, or very near a buried metallic object to detect it. The EM61 characteristic anomaly consists of readings elevated 10 to 20 mV above background for small conductors and up to several thousand mV for large conductors, such as tanks. For mapping long, linear conductors, the EM61 data is most useful when measurements are taken perpendicular to the orientation of the conductor.

The application of near-surface time-domain EM techniques with instruments such as the EM61, includes detecting and mapping metallic objects (buried pipes, cables, drums, and tanks), and mapping the boundaries of landfill, pits or trenches containing buried metallic debris.

## D.4.0 References

---

- Breiner, S., 1973, *Applications Manual for Portable Magnetometers*, Geometrics, Sunnyvale, California
- Dobrin, M. B., 1976, *Introduction to Geophysical Prospecting*, MacGraw-Hill, New York, New York.
- Geonics, 1997, *EM61 High Sensitivity Metal Detector Operating Manual*, Geonics Limited, Mississauga, Ontario, Canada.
- Keller, G. V. and F. C. Frischknecht, 1966, *Electrical Methods in Geophysical Prospecting*, International Series in Electromagnetic Waves, Volume 10, Pergamon Press, Oxford, England.
- McNeill, J. D., 1980, *Electromagnetic Terrain Conductivity Measurement at Low Induction Numbers*, Geonics Limited, Technical Note TN-6, Ontario, Canada, October.
- Sheriff, R. E., 1991, *Encyclopedic Dictionary of Exploration Geophysics*, Society of Exploration Geophysicists, Tulsa, Oklahoma
- Telford, W. M., L. P. Geldart, R. E. Sheriff, and D. A. Keys, 1976, *Applied Geophysics*, Cambridge University Press, Cambridge, England.
- Ulriksen, C. P. F., 1982, *Application of Impulse Radar to Civil Engineering*, Department of Engineering Geology, Lund University of Technology, Sweden.

# TAB

APPENDIX D: SURVEY DATA

**APPENDIX D**  
**SURVEY DATA**

## AOC 19 Site Investigation Survey Points

724 201

HydroGeoLogic, Inc.  
 Prime Contract No. F41624-95-D-8005  
 Delivery Order No. 26

Subcontractor:  
 Baird, Hampton, Brown, Inc.

LOCATION	NORTHING	EASTING	GROUND ELEVATION	RIM ELEVATION	DESCRIPTION
BHGLAOC1901	6963046.00	2296012.77	604.11		Boring
BHGLAOC1902	6963004.26	2296068.64	601.90		Boring
BHGLAOC1903	6962822.45	2296067.10	598.80		Boring
BHGLAOC1904	6962771.02	2296001.22	599.62		Boring
BHGLAOC1905	6962878.146	2295904.4	601.995		Boring
BHGLAOC1906	6962761.843	2295999.03	599.593		Boring
BHGLAOC1907	6963045.976	2296012.44	604.084		Boring
BHGLAOC1908	6962977.164	2295949.6	603.08		Boring
BHGLAOC1909	6963052.561	2295993.92	606.541		Boring
BHGLAOC1910	6963080.138	2295977.25	612.536		Boring
BHGLAOC1911	6963066.96	2296003.74	606.64		Boring
BHGLAOC1912	6963113.19	2296037.66	611.10		Boring
BHGLAOC1913	6962755.91	2295995.23	599.54		Boring
THGLAOC1901A	6962827.984	2296060.22	599.157		Exploratory Excavation
THGLAOC1901B	6962822.256	2296060.09	598.923		Exploratory Excavation
THGLAOC1901C	6962822.503	2296064.91	598.905		Exploratory Excavation
THGLAOC1901D	6962828.711	2296065.08	599.09		Exploratory Excavation
THGLAOC1902A	6962804.601	2295958.24	600.356		Exploratory Excavation
THGLAOC1902B	6962794.309	2295957.2	600.522		Exploratory Excavation
THGLAOC1902C	6962792.534	2295972.45	599.863		Exploratory Excavation
THGLAOC1902D	6962801.215	2295972.6	599.948		Exploratory Excavation
THGLAOC1903A	6962801.471	2295927.57	600.846		Exploratory Excavation
THGLAOC1903B	6962794.982	2295927.83	600.617		Exploratory Excavation
THGLAOC1903C	6962793.89	2295939.11	600.341		Exploratory Excavation
THGLAOC1903D	6962801.87	2295938.04	600.569		Exploratory Excavation
THGLAOC1904A	6963002.676	2295961.44	603.789		Exploratory Excavation
THGLAOC1904B	6962993.997	2295958.32	603.498		Exploratory Excavation
THGLAOC1904C	6962987.722	2295971.89	603.057		Exploratory Excavation
THGLAOC1904D	6962997.141	2295975.24	603.162		Exploratory Excavation
THGLAOC1905A	6963048.419	2296001.75	604.2		Exploratory Excavation
THGLAOC1905B	6963063.039	2296011.86	605.034		Exploratory Excavation
THGLAOC1905C	6963075.995	2295999.69	609.063		Exploratory Excavation
THGLAOC1905D	6963060.529	2295988.61	608.708		Exploratory Excavation
WHGLTA050	6963013.36	2296420.09	599.19	599.08	Monitoring Well
WHGLTA051	6962894.90	2296247.12	598.37	598.30	Monitoring Well
WHGLTA052	6962769.45	2296098.07	597.12	597.00	Monitoring Well

# TAB

*APPENDIX E*

---



**APPENDIX E**

**ANALYTICAL DATA SUMMARY TABLES**

## NOTES FOR TABLES E.1 AND E.2

Sample date format: “YYYY-MM-DD”

F = The analyte was detected, but the associated numerical value is a concentration below the reporting limit.

J = The analyte was detected; the associated numerical value is an estimated concentration.

R = The data are unusable due to QC deficiencies.

U = The analyte was not detected. The associated value is the reporting limit.

UJ = The analyte was not detected. The associated value is the reporting limit, which may be inaccurate due to associated QC deficiencies.

NA = Not analyzed

*This page was intentionally left blank.*

**TABLES**

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1901 00 ft 2000-05-12	BHGLAOC1901 00 ft 2000-05-26	BHGLAOC1901 05 ft 2000-05-12	BHGLAOC1901 05 ft 2000-05-26
SW6010B	Arsenic	mg/kg	4.9 F	NA	4.4 F	NA
SW6010B	Barium	mg/kg	44.6	NA	80.9	NA
SW6010B	Beryllium	mg/kg	0.84	NA	0.6 U	NA
SW6010B	Cadmium	mg/kg	0.54 U	NA	0.07 F	NA
SW6010B	Chromium, total	mg/kg	12.8	NA	12.8	NA
SW6010B	Cobalt	mg/kg	4.6 F	NA	5.2 F	NA
SW6010B	Copper	mg/kg	7.4 F	NA	5.3 F	NA
SW6010B	Nickel	mg/kg	10 F	NA	11.1	NA
SW6010B	Tin	mg/kg	1.2 F	NA	1.6 F	NA
SW6010B	Vanadium	mg/kg	31.1 F	NA	29.5 F	NA
SW6010B	Zinc	mg/kg	22.7 F	NA	21 F	NA
SW7041	Antimony	mg/kg	0.56 UJ	NA	0.51 UJ	NA
SW7421	Lead	mg/kg	14.9 F	NA	8.8	NA
SW7471A	Mercury	mg/kg	0.04 U	NA	0.04 U	NA
SW7740	Selenium	mg/kg	0.34 UJ	NA	1.5 U	NA
SW7761	Silver	mg/kg	0.22 UJ	NA	0.2 UJ	NA
SW7841	Thallium	mg/kg	1.1 U	NA	1 UJ	NA
SW8260B	1,1,1,2-Tetrachloroethane	mg/kg	NA	0.002 U	NA	0.003 U
SW8260B	1,1,1-Trichloroethane	mg/kg	NA	0.003 U	NA	0.004 U
SW8260B	1,1,2,2-Tetrachloroethane	mg/kg	NA	0.002 UJ	NA	0.002 U
SW8260B	1,1,2-Trichloroethane	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	1,1-Dichloroethane	mg/kg	NA	0.002 U	NA	0.002 U
SW8260B	1,1-Dichloroethene	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	1,2,3-Trichloropropane	mg/kg	NA	0.004 UJ	NA	0.004 U
SW8260B	1,2-Dibromo-3-chloropropane	mg/kg	NA	0.004 UJ	NA	0.004 U
SW8260B	1,2-Dibromoethane (Ethylene dibromide)	mg/kg	NA	0.002 U	NA	0.003 U
SW8260B	1,2-Dichloroethane	mg/kg	NA	0.002 U	NA	0.003 U
SW8260B	1,2-Dichloropropane	mg/kg	NA	0.002 U	NA	0.002 U
SW8260B	2-Chloro-1,3-butadiene	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	2-Hexanone	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Acetone	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Acetonitrile	mg/kg	NA	0.033 U	NA	0.037 U
SW8260B	Acrolein	mg/kg	NA	0.082 U	NA	0.092 U
SW8260B	Acrylonitrile	mg/kg	NA	0.033 U	NA	0.037 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1901 00 ft 2000-05-12	BHGLAOC1901 00 ft 2000-05-26	BHGLAOC1901 05 ft 2000-05-12	BHGLAOC1901 05 ft 2000-05-26
SW8260B	Allyl chloride (3-Chloropropene)	mg/kg	NA	0.008 U	NA	0.009 U
SW8260B	Benzene	mg/kg	NA	0.002 U	NA	0.002 U
SW8260B	Bromodichloromethane	mg/kg	NA	0.003 U	NA	0.004 U
SW8260B	Bromoform	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Bromomethane	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Carbon disulfide	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Carbon tetrachloride	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Chlorobenzene	mg/kg	NA	0.002 U	NA	0.002 U
SW8260B	Chloroethane	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Chloroform	mg/kg	NA	0.002 U	NA	0.002 U
SW8260B	Chloromethane	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	cis-1,2-Dichloroethene	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	cis-1,3-Dichloropropene	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Dibromochloromethane	mg/kg	NA	0.002 U	NA	0.003 U
SW8260B	Dibromomethane	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Dichlorodifluoromethane	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Ethyl methacrylate	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Ethylbenzene	mg/kg	NA	0.002 U	NA	0.003 U
SW8260B	Iodomethane (Methyl iodide)	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Isobutanol	mg/kg	NA	0.16 U	NA	0.18 U
SW8260B	m,p-Xylene (sum of isomers)	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Methyl ethyl ketone (2-Butanone)	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Methyl isobutyl ketone (4-Methyl-2-pentanone)	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Methyl methacrylate	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Methylacrylonitrile	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Methylene chloride	mg/kg	NA	0.002 U	NA	0.002 U
SW8260B	o-Xylene (1,2-Dimethylbenzene)	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Pentachloroethane	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Propane nitrile (Propionitrile)	mg/kg	NA	0.016 U	NA	0.018 U
SW8260B	Styrene	mg/kg	NA	0.002 U	NA	0.002 U
SW8260B	Tert-Butyl Methyl Ether	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Tetrachloroethene (PCE)	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Toluene	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Trans-1,2-Dichloroethene	mg/kg	NA	0.002 U	NA	0.003 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1901 00 ft 2000-05-12	BHGLAOC1901 00 ft 2000-05-26	BHGLAOC1901 05 ft 2000-05-12	BHGLAOC1901 05 ft 2000-05-26
SW8260B	Trans-1,3-Dichloropropene	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Trans-1,4-Dichloro-2-Butene	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Trichloroethene (TCE)	mg/kg	NA	0.004 U	NA	0.004 F
SW8260B	Trichlorofluoromethane	mg/kg	NA	0.003 U	NA	0.004 U
SW8260B	Vinyl acetate	mg/kg	NA	0.004 U	NA	0.004 U
SW8260B	Vinyl chloride	mg/kg	NA	0.004 U	NA	0.004 U
SW8270C	1,2,4,5-Tetrachlorobenzene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	1,2,4-Trichlorobenzene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	1,2-Dichlorobenzene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	1,3,5-Trinitrobenzene	mg/kg	1.6 U	NA	1.5 U	NA
SW8270C	1,3-Dichlorobenzene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	1,3-Dinitrobenzene	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	1,4-Dichlorobenzene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	1,4-Dioxane (p-Dioxane)	mg/kg	1.6 U	NA	1.5 U	NA
SW8270C	1,4-Naphthoquinone	mg/kg	2 R	NA	1.9 R	NA
SW8270C	1-Naphthylamine	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	2,2'-Oxybis(1-chloropropane)	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	2,3,4,6-Tetrachlorophenol	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	2,4,5-Trichlorophenol	mg/kg	2 U	NA	1.9 U	NA
SW8270C	2,4,6-Trichlorophenol	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	2,4-Dichlorophenol	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	2,4-Dimethylphenol	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	2,4-Dinitrophenol	mg/kg	2 R	NA	1.9 R	NA
SW8270C	2,4-Dinitrotoluene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	2,6-Dichlorophenol	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	2,6-Dinitrotoluene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	2-Acetylaminofluorene	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	2-Aminonaphthalene (beta-Naphthylamine)	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	2-Chloronaphthalene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	2-Chlorophenol	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	2-Methylnaphthalene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	2-Methylphenol (o-Cresol)	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	2-Nitroaniline	mg/kg	2 U	NA	1.9 U	NA
SW8270C	2-Nitrophenol	mg/kg	0.39 U	NA	0.38 U	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1901 00 ft 2000-05-12	BHGLAOC1901 00 ft 2000-05-26	BHGLAOC1901 05 ft 2000-05-12	BHGLAOC1901 05 ft 2000-05-26
SW8270C	2-Picoline (alpha-Picoline)	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	3,3'-Dichlorobenzidine	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	3,3'-Dimethylbenzidine	mg/kg	2 U	NA	1.9 U	NA
SW8270C	3-Methylcholanthrene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	3-Nitroaniline	mg/kg	2 U	NA	1.9 U	NA
SW8270C	4,6-Dinitro-2-methylphenol	mg/kg	2 U	NA	1.9 U	NA
SW8270C	4-Aminobiphenyl (4-Biphenylamine)	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	4-Bromophenyl phenyl ether	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	4-Chloro-3-methylphenol	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	4-Chloroaniline	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	4-Chlorophenyl phenyl ether	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	4-Methylphenol (P-Cresol)	mg/kg	NA	NA	NA	NA
SW8270C	4-Nitroaniline	mg/kg	2 U	NA	1.9 U	NA
SW8270C	4-Nitrophenol	mg/kg	2 U	NA	1.9 U	NA
SW8270C	4-Nitroquinoline-1-oxide	mg/kg	2 R	NA	1.9 R	NA
SW8270C	5-Nitro-o-toluidine	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	7,12-Dimethylbenzo(a)anthracene	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	Acenaphthene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Acenaphthylene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Acetophenone	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	alpha, alpha-Dimethylphenethylamine	mg/kg	2 U	NA	1.9 U	NA
SW8270C	Aniline (Phenylamine, Aminobenzene)	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Anthracene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Aramite (total)	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	Benzo(a)anthracene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Benzo(a)pyrene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Benzo(b)fluoranthene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Benzo(g,h,i)perylene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Benzo(k)fluoranthene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Benzoic acid	mg/kg	2 U	NA	1.9 U	NA
SW8270C	Benzyl alcohol	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Benzyl butyl phthalate	mg/kg	0.28 F	NA	0.38 U	NA
SW8270C	bis(2-Chloroethoxy)methane	mg/kg	0.39 U	NA	0.38 U	NA



Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1901 00 ft 2000-05-12	BHGLAOC1901 00 ft 2000-05-26	BHGLAOC1901 05 ft 2000-05-12	BHGLAOC1901 05 ft 2000-05-26
SW8270C	bis(2-Chloroethyl)ether (2-Chloroethyl ether)	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	bis(2-Ethylhexyl)phthalate	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Chlorobenzilate	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Chrysene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Cresols, m & p	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Diallate (total of cis and trans isomers)	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Dibenz(a,h)anthracene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Dibenzofuran	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Diethyl phthalate	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Dimethyl phthalate	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Di-n-butyl phthalate	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Di-n-octyl phthalate	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Dinoseb	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	Diphenylamine	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Ethyl methanesulfonate	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Fluoranthene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Fluorene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Hexachlorobenzene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Hexachlorobutadiene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Hexachlorocyclopentadiene	mg/kg	0.39 R	NA	0.38 R	NA
SW8270C	Hexachloroethane	mg/kg	5.9 R	NA	5.7 R	NA
SW8270C	Hexachlorophene	mg/kg	2 U	NA	1.9 U	NA
SW8270C	Hexachloropropene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Indeno(1,2,3-c,d)pyrene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Isophorone	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Isosafrole	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Methapyriline	mg/kg	2 U	NA	1.9 U	NA
SW8270C	Methyl methanesulfonate	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	Naphthalene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Nitrobenzene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	N-Nitrosodimethylamine	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	N-Nitrosodimethylamine	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	N-Nitrosodi-n-butylamine	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	N-Nitrosodi-n-propylamine	mg/kg	0.39 U	NA	0.38 U	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1901 00 ft 2000-05-12	BHGLAOC1901 00 ft 2000-05-26	BHGLAOC1901 05 ft 2000-05-12	BHGLAOC1901 05 ft 2000-05-26
SW8270C	N-Nitrosodiphenylamine	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	N-Nitrosomethylethylamine	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	N-Nitrosomorpholine	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	N-Nitrosopiperidine	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	N-Nitrosopyrrolidine	mg/kg	2 U	NA	1.9 U	NA
SW8270C	o-Toluidine	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	p-Dimethylaminoazobenzene	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	Pentachlorobenzene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Pentachloronitrobenzene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Pentachlorophenol	mg/kg	2 U	NA	1.9 U	NA
SW8270C	Phenacetin	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	Phenanthrene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Phenol	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	p-Phenylenediamine	mg/kg	1.6 U	NA	1.5 U	NA
SW8270C	Pronamide	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	Pyrene	mg/kg	0.39 U	NA	0.38 U	NA
SW8270C	Pyridine	mg/kg	0.79 U	NA	0.76 U	NA
SW8270C	Safrole	mg/kg	0.39 U	NA	0.38 U	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1901 10 ft 2000-05-12	BHGLAOC1901 10 ft 2000-05-26	BHGLAOC1902 00 ft 2000-05-15	BHGLAOC1902 05 ft 2000-05-15
SW6010B	Arsenic	mg/kg	6.7	NA	4.9	5.5
SW6010B	Barium	mg/kg	33.3 F	NA	75 J	62 J
SW6010B	Beryllium	mg/kg	0.31 U	NA	1	0.35 J
SW6010B	Cadmium	mg/kg	0.13 F	NA	0.24 F	0.26 F
SW6010B	Chromium, total	mg/kg	7.4 F	NA	20.3 J	10.5 J
SW6010B	Cobalt	mg/kg	2.9 F	NA	5.5 F	3.9 F
SW6010B	Copper	mg/kg	4.2 F	NA	10.5	4.1 F
SW6010B	Nickel	mg/kg	7.6 F	NA	13.2 J	7.9 F
SW6010B	Tin	mg/kg	1 F	NA	9.1 UJ	8.2 UJ
SW6010B	Vanadium	mg/kg	22.6 F	NA	36.8 J	28.9 J
SW6010B	Zinc	mg/kg	9.8 F	NA	36.2	13.5 F
SW7041	Antimony	mg/kg	0.43 UJ	NA	0.53 UJ	0.48 UJ
SW7421	Lead	mg/kg	4.7	NA	10.4	4.9
SW7471A	Mercury	mg/kg	0.04 U	NA	0.04 U	0.03 U
SW7740	Selenium	mg/kg	1.3 U	NA	0.32 UJ	1.4 UJ
SW7761	Silver	mg/kg	0.17 UJ	NA	0.21 UJ	0.19 UJ
SW7841	Thallium	mg/kg	0.86 UJ	NA	1.1 U	4.8 UJ
SW8260B	1,1,1,2-Tetrachloroethane	mg/kg	NA	0.002 U	0.003 U	0.003 U
SW8260B	1,1,1-Trichloroethane	mg/kg	NA	0.003 U	0.004 U	0.004 U
SW8260B	1,1,2,2-Tetrachloroethane	mg/kg	NA	0.002 U	0.002 UJ	0.002 U
SW8260B	1,1,2-Trichloroethane	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	1,1-Dichloroethane	mg/kg	NA	0.002 U	0.002 U	0.002 U
SW8260B	1,1-Dichloroethene	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	1,2,3-Trichloropropane	mg/kg	NA	0.004 U	0.005 UJ	0.004 U
SW8260B	1,2-Dibromo-3-chloropropane	mg/kg	NA	0.004 U	0.005 UJ	0.004 U
SW8260B	1,2-Dibromoethane (Ethylene dibromide)	mg/kg	NA	0.002 U	0.003 U	0.003 U
SW8260B	1,2-Dichloroethane	mg/kg	NA	0.002 U	0.003 U	0.003 U
SW8260B	1,2-Dichloropropane	mg/kg	NA	0.002 U	0.002 U	0.002 U
SW8260B	2-Chloro-1,3-butadiene	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	2-Hexanone	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Acetone	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Acetonitrile	mg/kg	NA	0.032 U	0.04 U	0.036 U
SW8260B	Acrolein	mg/kg	NA	0.079 U	0.1 U	0.089 U
SW8260B	Acrylonitrile	mg/kg	NA	0.032 U	0.04 U	0.036 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1901 10 ft 2000-05-12	BHGLAOC1901 10 ft 2000-05-26	BHGLAOC1902 00 ft 2000-05-15	BHGLAOC1902 05 ft 2000-05-15
SW8260B	Allyl chloride (3-Chloropropene)	mg/kg	NA	0.008 U	0.01 U	0.009 U
SW8260B	Benzene	mg/kg	NA	0.002 U	0.002 U	0.002 U
SW8260B	Bromodichloromethane	mg/kg	NA	0.003 U	0.004 U	0.004 U
SW8260B	Bromoform	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Bromomethane	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Carbon disulfide	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Carbon tetrachloride	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Chlorobenzene	mg/kg	NA	0.002 U	0.002 U	0.002 U
SW8260B	Chloroethane	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Chloroform	mg/kg	NA	0.002 U	0.002 U	0.002 U
SW8260B	Chloromethane	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	cis-1,2-Dichloroethene	mg/kg	NA	0.005	0.005 U	0.004 U
SW8260B	cis-1,3-Dichloropropene	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Dibromochloromethane	mg/kg	NA	0.002 U	0.003 U	0.003 U
SW8260B	Dibromomethane	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Dichlorodifluoromethane	mg/kg	NA	0.004 U	0.006 U	0.004 U
SW8260B	Ethyl methacrylate	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Ethylbenzene	mg/kg	NA	0.002 U	0.003 U	0.003 U
SW8260B	Iodomethane (Methyl iodide)	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Isobutanol	mg/kg	NA	0.16 U	0.2 U	0.18 U
SW8260B	m,p-Xylene (sum of isomers)	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Methyl ethyl ketone (2-Butanone)	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Methyl isobutyl ketone (4-Methyl-2-pentanone)	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Methyl methacrylate	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Methylacrylonitrile	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Methylene chloride	mg/kg	NA	0.002 U	0.002 U	0.002 U
SW8260B	o-Xylene (1,2-Dimethylbenzene)	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Pentachloroethane	mg/kg	NA	0.004 U	0.01 U	0.004 U
SW8260B	Propane nitrile (Propionitrile)	mg/kg	NA	0.016 U	0.02 U	0.018 U
SW8260B	Styrene	mg/kg	NA	0.002 U	0.002 U	0.002 U
SW8260B	Tert-Butyl Methyl Ether	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Tetrachloroethene (PCE)	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Toluene	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Trans-1,2-Dichloroethene	mg/kg	NA	0.002 U	0.003 U	0.003 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1901 10 ft 2000-05-12	BHGLAOC1901 10 ft 2000-05-26	BHGLAOC1902 00 ft 2000-05-15	BHGLAOC1902 05 ft 2000-05-15
SW8260B	Trans-1,3-Dichloropropene	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Trans-1,4-Dichloro-2-Butene	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Trichloroethene (TCE)	mg/kg	NA	0.019	0.019	0.008
SW8260B	Trichlorofluoromethane	mg/kg	NA	0.003 U	0.004 U	0.004 U
SW8260B	Vinyl acetate	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8260B	Vinyl chloride	mg/kg	NA	0.004 U	0.005 U	0.004 U
SW8270C	1,2,4,5-Tetrachlorobenzene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	1,2,4-Trichlorobenzene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	1,2-Dichlorobenzene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	1,3,5-Trinitrobenzene	mg/kg	1.4 U	NA	1.5 U	1.4 U
SW8270C	1,3-Dichlorobenzene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	1,3-Dinitrobenzene	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	1,4-Dichlorobenzene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	1,4-Dioxane (p-Dioxane)	mg/kg	1.4 U	NA	1.5 U	1.4 U
SW8270C	1,4-Naphthoquinone	mg/kg	1.8 R	NA	1.9 R	1.8 R
SW8270C	1-Naphthylamine	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	2,2'-Oxybis(1-chloropropane)	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	2,3,4,6-Tetrachlorophenol	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	2,4,5-Trichlorophenol	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	2,4,6-Trichlorophenol	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	2,4-Dichlorophenol	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	2,4-Dimethylphenol	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	2,4-Dinitrophenol	mg/kg	1.8 R	NA	1.9 U	1.8 U
SW8270C	2,4-Dinitrotoluene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	2,6-Dichlorophenol	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	2,6-Dinitrotoluene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	2-Acetylaminofluorene	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	2-Aminonaphthalene (beta-Naphthylamine)	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	2-Chloronaphthalene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	2-Chlorophenol	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	2-Methylnaphthalene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	2-Methylphenol (o-Cresol)	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	2-Nitroaniline	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	2-Nitrophenol	mg/kg	0.35 U	NA	0.38 U	0.35 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1901 10 ft 2000-05-12	BHGLAOC1901 10 ft 2000-05-26	BHGLAOC1902 00 ft 2000-05-15	BHGLAOC1902 05 ft 2000-05-15
SW8270C	2-Picoline (alpha-Picoline)	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	3,3'-Dichlorobenzidine	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	3,3'-Dimethylbenzidine	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	3-Methylcholanthrene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	3-Nitroaniline	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	4,6-Dinitro-2-methylphenol	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	4-Aminobiphenyl (4-Biphenylamine)	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	4-Bromophenyl phenyl ether	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	4-Chloro-3-methylphenol	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	4-Chloroaniline	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	4-Chlorophenyl phenyl ether	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	4-Methylphenol (P-Cresol)	mg/kg	NA	NA	NA	NA
SW8270C	4-Nitroaniline	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	4-Nitrophenol	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	4-Nitroquinoline-1-oxide	mg/kg	1.8 R	NA	1.9 R	1.8 R
SW8270C	5-Nitro-o-toluidine	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	7,12-Dimethylbenzo(a)anthracene	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	Acenaphthene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Acenaphthylene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Acetophenone	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	alpha, alpha-Dimethylphenethylamine	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	Aniline (Phenylamine, Aminobenzene)	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Anthracene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Aramite (total)	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	Benzo(a)anthracene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Benzo(a)pyrene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Benzo(b)fluoranthene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Benzo(g,h,i)perylene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Benzo(k)fluoranthene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Benzoic acid	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	Benzyl alcohol	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Benzyl butyl phthalate	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	bis(2-Chloroethoxy)methane	mg/kg	0.35 U	NA	0.38 U	0.35 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1901 10 ft 2000-05-12	BHGLAOC1901 10 ft 2000-05-26	BHGLAOC1902 00 ft 2000-05-15	BHGLAOC1902 05 ft 2000-05-15
SW8270C	bis(2-Chloroethyl)ether (2-Chloroethyl ether)	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	bis(2-Ethylhexyl)phthalate	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Chlorobenzilate	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Chrysene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Cresols, m & p	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Diallylate (total of cis and trans isomers)	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Dibenz(a,h)anthracene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Dibenzofuran	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Diethyl phthalate	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Dimethyl phthalate	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Di-n-butyl phthalate	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Di-n-octyl phthalate	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Dinoseb	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	Diphenylamine	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Ethyl methanesulfonate	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Fluoranthene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Fluorene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Hexachlorobenzene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Hexachlorobutadiene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Hexachlorocyclopentadiene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Hexachloroethane	mg/kg	0.35 R	NA	0.38 U	0.35 U
SW8270C	Hexachlorophene	mg/kg	5.3 R	NA	5.7 R	5.3 R
SW8270C	Hexachloropropene	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	Indeno(1,2,3-c,d)pyrene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Isophorone	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Isosafrole	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Methapyrilene	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	Methyl methanesulfonate	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	Naphthalene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Nitrobenzene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	N-Nitrosodiethylamine	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	N-Nitrosodimethylamine	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	N-Nitrosodi-n-butylamine	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	N-Nitrosodi-n-propylamine	mg/kg	0.35 U	NA	0.38 U	0.35 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1901 10 ft 2000-05-12	BHGLAOC1901 10 ft 2000-05-26	BHGLAOC1902 00 ft 2000-05-15	BHGLAOC1902 05 ft 2000-05-15
SW8270C	N-Nitrosodiphenylamine	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	N-Nitrosomethylethylamine	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	N-Nitrosomorpholine	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	N-Nitrosopiperidine	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	N-Nitrosopyrrolidine	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	o-Toluidine	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	p-Dimethylaminoazobenzene	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	Pentachlorobenzene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Pentachloronitrobenzene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Pentachlorophenol	mg/kg	1.8 U	NA	1.9 U	1.8 U
SW8270C	Phenacetin	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	Phenanthrene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Phenol	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	p-Phenylenediamine	mg/kg	1.4 U	NA	1.5 U	1.4 U
SW8270C	Pronamide	mg/kg	0.7 U	NA	0.76 U	0.7 U
SW8270C	Pyrene	mg/kg	0.35 U	NA	0.38 U	0.35 U
SW8270C	Pyridine	mg/kg	0.7 U	NA	0.76 R	0.7 R
SW8270C	Safrole	mg/kg	0.35 U	NA	0.38 U	0.35 U



Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1903 00 ft 2000-05-15	BHGLAOC1903 00 ft 2000-05-15 Dup	BHGLAOC1903 05 ft 2000-05-15	BHGLAOC1904 00 ft 2000-05-15
SW6010B	Arsenic	mg/kg	3 F	4	2.5 F	2.8 F
SW6010B	Barium	mg/kg	66.1 J	70.5 J	45.3 J	81.1 J
SW6010B	Beryllium	mg/kg	0.44 J	0.84	0.38 J	0.6
SW6010B	Cadmium	mg/kg	0.21 F	0.29 F	0.18 F	0.27 F
SW6010B	Chromium, total	mg/kg	12.8 J	14.9 J	10.3 J	13.1 J
SW6010B	Cobalt	mg/kg	3.3 F	4.9	2 F	3 F
SW6010B	Copper	mg/kg	5.4 F	10.2	3.8 F	5.7 F
SW6010B	Nickel	mg/kg	8.1 F	10.7 J	6.7 F	8 J
SW6010B	Tin	mg/kg	8.9 UJ	7.9 UJ	8.4 UJ	6.8 UJ
SW6010B	Vanadium	mg/kg	26.5 F	29.1 J	27 J	25.5 J
SW6010B	Zinc	mg/kg	17.2 F	26.2 J	13.5 F	17.7 F
SW7041	Antimony	mg/kg	0.47 UJ	0.52 UJ	0.43 UJ	0.48 UJ
SW7421	Lead	mg/kg	5.6	8.9	5.9	6.9 J
SW7471A	Mercury	mg/kg	0.04 U	0.04 U	0.04 U	0.04 U
SW7740	Selenium	mg/kg	1.4 UJ	1.6 UJ	1.3 UJ	1.4 UJ
SW7761	Silver	mg/kg	0.19 UJ	0.21 UJ	0.17 UJ	0.19 UJ
SW7841	Thallium	mg/kg	4.7 U	1 UJ	4.3 U	4.8 U
SW8260B	1,1,1,2-Tetrachloroethane	mg/kg	0.003 U	0 U	0.002 U	0.003 U
SW8260B	1,1,1-Trichloroethane	mg/kg	0.004 U	0.004 U	0.003 U	0.004 U
SW8260B	1,1,2,2-Tetrachloroethane	mg/kg	0.002 U	0.002 U	0.002 U	0.002 U
SW8260B	1,1,2-Trichloroethane	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	1,1-Dichloroethane	mg/kg	0.002 U	0.002 U	0.002 U	0.002 U
SW8260B	1,1-Dichloroethene	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	1,2,3-Trichloropropane	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	1,2-Dibromo-3-chloropropane	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	1,2-Dibromoethane (Ethylene dibromide)	mg/kg	0.003 U	0.003 U	0.002 U	0.003 U
SW8260B	1,2-Dichloroethane	mg/kg	0.003 U	0.003 U	0.002 U	0.003 U
SW8260B	1,2-Dichloropropane	mg/kg	0.002 U	0.002 U	0.002 U	0.002 U
SW8260B	2-Chloro-1,3-butadiene	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	2-Hexanone	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Acetone	mg/kg	0.008 U	0.005 U	0.004 U	0.005 U
SW8260B	Acetonitrile	mg/kg	0.036 U	0.04 U	0.034 U	0.04 U
SW8260B	Acrolein	mg/kg	0.089 U	0.1 U	0.084 U	0.1 U
SW8260B	Acrylonitrile	mg/kg	0.036 U	0.04 U	0.034 U	0.04 U

724 220

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1903 00 ft 2000-05-15	BHGLAOC1903 00 ft 2000-05-15 Dup.	BHGLAOC1903 05 ft 2000-05-15	BHGLAOC1904 00 ft 2000-05-15
SW8260B	Allyl chloride (3-Chloropropene)	mg/kg	0.009 U	0.01 U	0.008 U	0.01 U
SW8260B	Benzene	mg/kg	0.002 U	0.002 U	0.002 U	0.002 U
SW8260B	Bromodichloromethane	mg/kg	0.004 U	0.004 U	0.003 U	0.004 U
SW8260B	Bromoform	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Bromomethane	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Carbon disulfide	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Carbon tetrachloride	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Chlorobenzene	mg/kg	0.002 U	0.002 U	0.002 U	0.002 U
SW8260B	Chloroethane	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Chloroform	mg/kg	0.002 U	0.002 U	0.002 U	0.002 U
SW8260B	Chloromethane	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	cis-1,2-Dichloroethene	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	cis-1,3-Dichloropropene	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Dibromochloromethane	mg/kg	0.003 U	0.003 U	0.002 U	0.003 U
SW8260B	Dibromomethane	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Dichlorodifluoromethane	mg/kg	0.004 U	0.005 R	0.004 U	0.005 R
SW8260B	Ethyl methacrylate	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Ethylbenzene	mg/kg	0.003 U	0.003 U	0.002 U	0.003 U
SW8260B	Iodomethane (Methyl iodide)	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Isobutanol	mg/kg	0.18 U	0.2 U	0.17 U	0.2 U
SW8260B	m,p-Xylene (sum of isomers)	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Methyl ethyl ketone (2-Butanone)	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Methyl isobutyl ketone (4-Methyl-2-pentanone)	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Methyl methacrylate	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Methylacrylonitrile	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Methylene chloride	mg/kg	0.002 U	0.009 U	0.002 U	0.002 U
SW8260B	o-Xylene (1,2-Dimethylbenzene)	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Pentachloroethane	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Propane nitrile (Propionitrile)	mg/kg	0.018 U	0.02 U	0.017 U	0.02 U
SW8260B	Styrene	mg/kg	0.002 U	0.002 U	0.002 U	0.002 U
SW8260B	Tert-Butyl Methyl Ether	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Tetrachloroethene (PCE)	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Toluene	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Trans-1,2-Dichloroethene	mg/kg	0.003 U	0.003 U	0.002 U	0.003 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1903 00 ft 2000-05-15	BHGLAOC1903 00 ft 2000-05-15 Dup	BHGLAOC1903 05 ft 2000-05-15	BHGLAOC1904 00 ft 2000-05-15
SW8260B	Trans-1,3-Dichloropropene	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Trans-1,4-Dichloro-2-Butene	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Trichloroethene (TCE)	mg/kg	0.004 U	0.005 U	0.005	0.005 J
SW8260B	Trichlorofluoromethane	mg/kg	0.004 U	0.004 U	0.003 U	0.004 U
SW8260B	Vinyl acetate	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8260B	Vinyl chloride	mg/kg	0.004 U	0.005 U	0.004 U	0.005 U
SW8270C	1,2,4,5-Tetrachlorobenzene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	1,2,4-Trichlorobenzene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	1,2-Dichlorobenzene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	1,3,5-Trinitrobenzene	mg/kg	1.4 U	1.5 U	1.5 U	1.5 U
SW8270C	1,3-Dichlorobenzene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	1,3-Dinitrobenzene	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	1,4-Dichlorobenzene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	1,4-Dioxane (p-Dioxane)	mg/kg	1.4 U	1.5 U	1.5 U	1.5 U
SW8270C	1,4-Naphthoquinone	mg/kg	1.8 R	1.9 R	1.8 R	1.9 R
SW8270C	1-Naphthylamine	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	2,2'-Oxybis(1-chloropropane)	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	2,3,4,6-Tetrachlorophenol	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	2,4,5-Trichlorophenol	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	2,4,6-Trichlorophenol	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	2,4-Dichlorophenol	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	2,4-Dimethylphenol	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	2,4-Dinitrophenol	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	2,4-Dinitrotoluene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	2,6-Dichlorophenol	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	2,6-Dinitrotoluene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	2-Acetylaminofluorene	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	2-Aminonaphthalene (beta-Naphthylamine)	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	2-Chloronaphthalene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	2-Chlorophenol	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	2-Methylnaphthalene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	2-Methylphenol (o-Cresol)	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	2-Nitroaniline	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	2-Nitrophenol	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1903 00 ft 2000-05-15	BHGLAOC1903 00 ft 2000-05-15 Dup	BHGLAOC1903 05 ft 2000-05-15	BHGLAOC1904 00 ft 2000-05-15
SW8270C	2-Picoline (alpha-Picoline)	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	3,3'-Dichlorobenzidine	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	3,3'-Dimethylbenzidine	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	3-Methylcholanthrene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	3-Nitroaniline	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	4,6-Dinitro-2-methylphenol	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	4-Aminobiphenyl (4-Biphenylamine)	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	4-Bromophenyl phenyl ether	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	4-Chloro-3-methylphenol	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	4-Chloroaniline	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	4-Chlorophenyl phenyl ether	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	4-Methylphenol (P-Cresol)	mg/kg	NA	NA	NA	NA
SW8270C	4-Nitroaniline	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	4-Nitrophenol	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	4-Nitroquinoline-1-oxide	mg/kg	1.8 R	1.9 R	1.8 R	1.9 R
SW8270C	5-Nitro-o-toluidine	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	7,12-Dimethylbenzo(a)anthracene	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	Acenaphthene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Acenaphthylene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Acetophenone	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	alpha, alpha-Dimethylphenethylamine	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	Aniline (Phenylamine, Aminobenzene)	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Anthracene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Aramite (total)	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	Benzo(a)anthracene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Benzo(a)pyrene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Benzo(b)fluoranthene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Benzo(g,h,i)perylene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Benzo(k)fluoranthene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Benzoic acid	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	Benzyl alcohol	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Benzyl butyl phthalate	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	bis(2-Chloroethoxy)methane	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1903 00 ft 2000-05-15	BHGLAOC1903 00 ft 2000-05-15 Dup	BHGLAOC1903 05 ft 2000-05-15	BHGLAOC1904 00 ft 2000-05-15
SW8270C	bis(2-Chloroethyl)ether (2-Chloroethyl ether)	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	bis(2-Ethylhexyl)phthalate	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Chlorobenzilate	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Chrysene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Cresols, m & p	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Diallate (total of cis and trans isomers)	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Dibenz(a,h)anthracene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Dibenzofuran	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Diethyl phthalate	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Dimethyl phthalate	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Di-n-butyl phthalate	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Di-n-octyl phthalate	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Dinoseb	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	Diphenylamine	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Ethyl methanesulfonate	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Fluoranthene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Fluorene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Hexachlorobenzene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Hexachlorobutadiene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Hexachlorocyclopentadiene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Hexachloroethane	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Hexachlorophene	mg/kg	5.3 R	5.6 R	5.5 R	5.6 R
SW8270C	Hexachloropropene	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	Indeno(1,2,3-c,d)pyrene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Isophorone	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Isosafrole	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Methapyrene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Methyl methanesulfonate	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	Naphthalene	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	Nitrobenzene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	N-Nitrosodiethylamine	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	N-Nitrosodimethylamine	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	N-Nitrosodimethylamine	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	N-Nitrosodi-n-butylamine	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	N-Nitrosodi-n-propylamine	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U

724 224

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1903 00 ft 2000-05-15	BHGLAOC1903 00 ft 2000-05-15 Dup	BHGLAOC1903 05 ft 2000-05-15	BHGLAOC1904 00 ft 2000-05-15
SW8270C	N-Nitrosodiphenylamine	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	N-Nitrosomethylethylamine	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	N-Nitrosomorpholine	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	N-Nitrosopiperidine	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	N-Nitrosopyrrolidine	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	o-Toluidine	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	p-Dimethylaminoazobenzene	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	Pentachlorobenzene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Pentachloronitrobenzene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Pentachlorophenol	mg/kg	1.8 U	1.9 U	1.8 U	1.9 U
SW8270C	Phenacetin	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	Phenanthrene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Phenol	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	p-Phenylenediamine	mg/kg	1.4 U	1.5 U	1.5 U	1.5 U
SW8270C	Pronamide	mg/kg	0.71 U	0.74 U	0.73 U	0.75 U
SW8270C	Pyrene	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U
SW8270C	Pyridine	mg/kg	0.71 R	0.74 R	0.73 R	0.75 R
SW8270C	Safrole	mg/kg	0.35 U	0.37 U	0.36 U	0.37 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1904 05 ft 2000-05-15	BHGLAOC1905 00 ft 2001-08-20	BHGLAOC1905 05 ft 2001-08-20	BHGLAOC1905 10 ft 2001-08-20
SW6010B	Arsenic	mg/kg	2.4 F	4.9	3.9 F	5.2
SW6010B	Barium	mg/kg	59.1 J	78.1	76.2	47.4
SW6010B	Beryllium	mg/kg	0.45 J	0.92	0.63	0.55
SW6010B	Cadmium	mg/kg	0.23 F	0.088 U	0.085 U	0.075 U
SW6010B	Chromium, total	mg/kg	11.8 J	16.3	12.3	11.8
SW6010B	Cobalt	mg/kg	3 F	5.3 F	2 F	2.9 F
SW6010B	Copper	mg/kg	5.1 F	10.9	5.2 F	5.4 F
SW6010B	Nickel	mg/kg	8.7 J	11.5	7.4 F	7.4 F
SW6010B	Tin	mg/kg	8.6 UJ	1.7 U	1.8 U	1.5 U
SW6010B	Vanadium	mg/kg	29.8 J	31.5	22.9 F	28.2
SW6010B	Zinc	mg/kg	16.2 F	27.3 U	16.3 U	13.9 U
SW7041	Antimony	mg/kg	0.47 UJ	0.23 UJ	0.21 UJ	0.17 UJ
SW7421	Lead	mg/kg	6.4	12.7	7.1	6.6
SW7471A	Mercury	mg/kg	0.03 U	0.0066 U	0.0062 U	0.0061 U
SW7740	Selenium	mg/kg	1.4 UJ	0.19 UJ	0.18 UJ	0.14 UJ
SW7761	Silver	mg/kg	0.19 UJ	0.08 UJ	0.075 UJ	0.059 UJ
SW7841	Thallium	mg/kg	4.7 UJ	0.23 UJ	0.21 UJ	0.17 UJ
SW8260B	1,1,1,2-Tetrachloroethane	mg/kg	0.002 U	0.0008 U	0.0006 U	0.0007 U
SW8260B	1,1,1-Trichloroethane	mg/kg	0.003 U	0.0007 U	0.0005 U	0.0006 U
SW8260B	1,1,2,2-Tetrachloroethane	mg/kg	0.002 U	0.0007 U	0.0006 U	0.0006 U
SW8260B	1,1,2-Trichloroethane	mg/kg	0.004 U	0.0008 U	0.0006 U	0.0007 U
SW8260B	1,1-Dichloroethane	mg/kg	0.002 U	0.001 U	0.0008 U	0.0008 U
SW8260B	1,1-Dichloroethene	mg/kg	0.004 U	0.001 U	0.0009 U	0.001 U
SW8260B	1,2,3-Trichloropropane	mg/kg	0.004 U	0.001 U	0.001 U	0.001 U
SW8260B	1,2-Dibromo-3-chloropropane	mg/kg	0.004 U	0.001 R	0.001 R	0.001 R
SW8260B	1,2-Dibromoethane (Ethylene dibromide)	mg/kg	0.002 U	0.0008 U	0.0007 U	0.0007 U
SW8260B	1,2-Dichloroethane	mg/kg	0.002 U	0.0006 U	0.0005 U	0.0006 U
SW8260B	1,2-Dichloropropane	mg/kg	0.002 U	0.001 U	0.0008 U	0.0009 U
SW8260B	2-Chloro-1,3-butadiene	mg/kg	0.004 U	0.0007 U	0.0006 U	0.0006 U
SW8260B	2-Hexanone	mg/kg	0.004 U	0.002 U	0.001 U	0.002 U
SW8260B	Acetone	mg/kg	0.004 U	0.004 U	0.004 R	0.014 R
SW8260B	Acetonitrile	mg/kg	0.033 U	0.028 U	0.023 U	0.025 U
SW8260B	Acrolein	mg/kg	0.083 U	0.041 U	0.033 U	0.036 U
SW8260B	Acrylonitrile	mg/kg	0.033 U	0.008 U	0.006 U	0.007 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1904 05 ft 2000-05-15	BHGLAOC1905 00 ft 2001-08-20	BHGLAOC1905 05 ft 2001-08-20	BHGLAOC1905 10 ft 2001-08-20
SW8260B	Allyl chloride (3-Chloropropene)	mg/kg	0.008 U	0.002 U	0.002 U	0.002 U
SW8260B	Benzene	mg/kg	0.002 U	0.0007 U	0.0006 U	0.0006 U
SW8260B	Bromodichloromethane	mg/kg	0.003 U	0.0007 U	0.0006 U	0.0006 U
SW8260B	Bromoform	mg/kg	0.004 U	0.001 U	0.0008 U	0.0009 U
SW8260B	Bromomethane	mg/kg	0.004 U	0.003 R	0.003 R	0.003 R
SW8260B	Carbon disulfide	mg/kg	0.004 U	0.002 U	0.002 U	0.002 U
SW8260B	Carbon tetrachloride	mg/kg	0.004 U	0.0009 U	0.0007 U	0.0008 U
SW8260B	Chlorobenzene	mg/kg	0.002 U	0.001 U	0.0008 U	0.0009 U
SW8260B	Chloroethane	mg/kg	0.004 U	0.002 R	0.001 U	0.002 U
SW8260B	Chloroform	mg/kg	0.002 U	0.0007 U	0.0005 U	0.0006 U
SW8260B	Chloromethane	mg/kg	0.004 U	0.001 R	0.0008 U	0.0009 U
SW8260B	cis-1,2-Dichloroethene	mg/kg	0.004 U	0.001 U	0.001 U	0.001 U
SW8260B	cis-1,3-Dichloropropene	mg/kg	0.004 U	0.0009 U	0.0007 U	0.0008 U
SW8260B	Dibromochloromethane	mg/kg	0.002 U	0.0008 U	0.0006 U	0.0007 U
SW8260B	Dibromomethane	mg/kg	0.004 U	0.0008 U	0.0006 U	0.0007 U
SW8260B	Dichlorodifluoromethane	mg/kg	0.004 R	0.0008 U	0.0007 U	0.0007 U
SW8260B	Ethyl methacrylate	mg/kg	0.004 U	0.002 U	0.001 U	0.001 U
SW8260B	Ethylbenzene	mg/kg	0.002 U	0.001 U	0.001 U	0.001 U
SW8260B	Iodomethane (Methyl iodide)	mg/kg	0.004 U	0.004 U	0.003 R	0.003 R
SW8260B	Isobutanol	mg/kg	0.16 U	0.092 U	0.073 U	0.08 U
SW8260B	m,p-Xylene (sum of isomers)	mg/kg	0.004 U	0.002 U	0.002 U	0.002 U
SW8260B	Methyl ethyl ketone (2-Butanone)	mg/kg	0.004 U	0.005 U	0.004 U	0.004 U
SW8260B	Methyl isobutyl ketone (4-Methyl-2-pentanone)	mg/kg	0.004 U	0.003 U	0.003 U	0.003 U
SW8260B	Methyl methacrylate	mg/kg	0.004 U	0.002 U	0.002 U	0.002 U
SW8260B	Methylacrylonitrile	mg/kg	0.004 U	0.005 U	0.004 U	0.004 U
SW8260B	Methylene chloride	mg/kg	0.007 U	0.002 U	0.002 U	0.002 U
SW8260B	o-Xylene (1,2-Dimethylbenzene)	mg/kg	0.004 U	0.001 U	0.0008 U	0.0009 U
SW8260B	Pentachloroethane	mg/kg	0.004 U	0.006 R	0.005 U	0.005 U
SW8260B	Propane nitrile (Propionitrile)	mg/kg	0.016 U	0.021 U	0.017 U	0.018 U
SW8260B	Styrene	mg/kg	0.002 U	0.001 U	0.0009 U	0.001 U
SW8260B	Tert-Butyl Methyl Ether	mg/kg	0.004 U	0.0007 U	0.0006 U	0.0006 U
SW8260B	Tetrachloroethene (PCE)	mg/kg	0.004 U	0.0007 U	0.0006 U	0.0006 U
SW8260B	Toluene	mg/kg	0.004 U	0.001 U	0.0009 U	0.001 U
SW8260B	Trans-1,2-Dichloroethene	mg/kg	0.002 U	0.001 U	0.0008 U	0.0009 U



Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1904 05 ft 2000-05-15	BHGLAOC1905 00 ft 2001-08-20	BHGLAOC1905 05 ft 2001-08-20	BHGLAOC1905 10 ft 2001-08-20
SW8260B	Trans-1,3-Dichloropropene	mg/kg	0.004 U	0.0009 U	0.0007 U	0.0008 U
SW8260B	Trans-1,4-Dichloro-2-Butene	mg/kg	0.004 U	0.002 U	0.002 U	0.002 U
SW8260B	Trichloroethene (TCE)	mg/kg	0.009	0.0006 U	0.006	0.0006 U
SW8260B	Trichlorofluoromethane	mg/kg	0.003 U	0.0008 U	0.0006 U	0.0007 U
SW8260B	Vinyl acetate	mg/kg	0.004 U	0.0006 U	0.0005 U	0.0005 U
SW8260B	Vinyl chloride	mg/kg	0.004 U	0.0008 U	0.0006 U	0.0007 U
SW8270C	1,2,4,5-Tetrachlorobenzene	mg/kg	0.35 U	0.22 U	0.21 U	0.21 U
SW8270C	1,2,4-Trichlorobenzene	mg/kg	0.35 U	0.059 U	0.055 U	0.056 U
SW8270C	1,2-Dichlorobenzene	mg/kg	0.35 U	0.1 U	0.096 U	0.098 U
SW8270C	1,3,5-Trinitrobenzene	mg/kg	1.4 U	0.89 U	0.82 U	0.84 U
SW8270C	1,3-Dichlorobenzene	mg/kg	0.35 U	0.11 U	0.1 U	0.11 U
SW8270C	1,3-Dinitrobenzene	mg/kg	0.7 U	0.41 U	0.38 U	0.38 U
SW8270C	1,4-Dichlorobenzene	mg/kg	0.35 U	0.09 U	0.083 U	0.084 U
SW8270C	1,4-Dioxane (p-Dioxane)	mg/kg	1.4 U	0.98 U	0.9 U	0.92 U
SW8270C	1,4-Naphthoquinone	mg/kg	1.8 R	1.5 U	1.4 U	1.4 U
SW8270C	1-Naphthylamine	mg/kg	0.7 U	0.62 U	0.57 U	0.58 U
SW8270C	2,2'-Oxybis(1-chloropropane)	mg/kg	0.35 U	0.21 U	0.19 U	0.2 U
SW8270C	2,3,4,6-Tetrachlorophenol	mg/kg	0.35 U	0.34 U	0.31 U	0.32 U
SW8270C	2,4,5-Trichlorophenol	mg/kg	1.8 U	0.081 U	0.075 U	0.076 U
SW8270C	2,4,6-Trichlorophenol	mg/kg	0.35 U	0.082 U	0.076 U	0.077 U
SW8270C	2,4-Dichlorophenol	mg/kg	0.35 U	0.069 U	0.064 U	0.065 U
SW8270C	2,4-Dimethylphenol	mg/kg	0.35 U	0.27 U	0.25 U	0.25 U
SW8270C	2,4-Dinitrophenol	mg/kg	1.8 U	0.24 U	0.22 U	0.22 U
SW8270C	2,4-Dinitrotoluene	mg/kg	0.35 U	0.09 U	0.083 U	0.084 U
SW8270C	2,6-Dichlorophenol	mg/kg	0.35 U	0.26 U	0.24 U	0.25 U
SW8270C	2,6-Dinitrotoluene	mg/kg	0.35 U	0.095 U	0.087 U	0.089 U
SW8270C	2-Acetylaminofluorene	mg/kg	0.7 U	0.65 U	0.6 U	0.61 U
SW8270C	2-Aminonaphthalene (beta-Naphthylamine)	mg/kg	0.7 U	0.63 U	0.58 U	0.59 U
SW8270C	2-Chloronaphthalene	mg/kg	0.35 U	0.066 U	0.06 U	0.061 U
SW8270C	2-Chlorophenol	mg/kg	0.35 U	0.084 U	0.077 U	0.078 U
SW8270C	2-Methylnaphthalene	mg/kg	0.35 U	0.29 U	0.27 U	0.27 U
SW8270C	2-Methylphenol (o-Cresol)	mg/kg	0.35 U	0.15 U	0.14 U	0.14 U
SW8270C	2-Nitroaniline	mg/kg	1.8 U	0.13 U	0.12 U	0.12 U
SW8270C	2-Nitrophenol	mg/kg	0.35 U	0.093 U	0.086 U	0.088 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1904 05 ft 2000-05-15	BHGLAOC1905 00 ft 2001-08-20	BHGLAOC1905 05 ft 2001-08-20	BHGLAOC1905 10 ft 2001-08-20
SW8270C	2-Picoline (alpha-Picoline)	mg/kg	0.35 U	0.27 U	0.25 U	0.26 U
SW8270C	3,3'-Dichlorobenzidine	mg/kg	0.7 U	0.14 U	0.13 U	0.13 U
SW8270C	3,3'-Dimethylbenzidine	mg/kg	1.8 U	0.37 U	0.34 U	0.34 U
SW8270C	3-Methylcholanthrene	mg/kg	0.35 U	0.37 U	0.34 U	0.34 U
SW8270C	3-Nitroaniline	mg/kg	1.8 U	0.17 U	0.16 U	0.16 U
SW8270C	4,6-Dinitro-2-methylphenol	mg/kg	1.8 U	0.17 U	0.16 U	0.16 U
SW8270C	4-Aminobiphenyl (4-Biphenylamine)	mg/kg	0.7 U	0.35 U	0.32 U	0.32 U
SW8270C	4-Bromophenyl phenyl ether	mg/kg	0.35 U	0.11 U	0.1 U	0.1 U
SW8270C	4-Chloro-3-methylphenol	mg/kg	0.35 U	0.1 U	0.095 U	0.097 U
SW8270C	4-Chloroaniline	mg/kg	0.35 U	0.15 U	0.14 U	0.14 U
SW8270C	4-Chlorophenyl phenyl ether	mg/kg	0.35 U	0.11 U	0.097 U	0.099 U
SW8270C	4-Methylphenol (P-Cresol)	mg/kg	NA	NA	NA	NA
SW8270C	4-Nitroaniline	mg/kg	1.8 U	0.16 U	0.15 U	0.15 U
SW8270C	4-Nitrophenol	mg/kg	1.8 U	0.44 U	0.41 U	0.42 U
SW8270C	4-Nitroquinoline-1-oxide	mg/kg	1.8 R	1.7 U	1.5 U	1.6 U
SW8270C	5-Nitro-o-toluidine	mg/kg	0.7 U	0.37 U	0.34 U	0.35 U
SW8270C	7,12-Dimethylbenzo(a)anthracene	mg/kg	0.7 U	0.56 U	0.52 U	0.53 U
SW8270C	Acenaphthene	mg/kg	0.35 U	0.064 U	0.059 U	0.06 U
SW8270C	Acenaphthylene	mg/kg	0.35 U	0.067 U	0.061 U	0.063 U
SW8270C	Acetophenone	mg/kg	0.35 U	0.34 U	0.31 U	0.32 U
SW8270C	alpha, alpha-Dimethylphenethylamine	mg/kg	1.8 U	1.8 U	1.6 U	1.7 U
SW8270C	Aniline (Phenylamine, Aminobenzene)	mg/kg	0.35 U	0.13 U	0.12 U	0.12 U
SW8270C	Anthracene	mg/kg	0.35 U	0.089 U	0.081 U	0.083 U
SW8270C	Aramite (total)	mg/kg	0.7 U	0.43 U	0.39 U	0.4 U
SW8270C	Benzo(a)anthracene	mg/kg	0.35 U	0.064 U	0.059 U	0.06 U
SW8270C	Benzo(a)pyrene	mg/kg	0.35 U	0.07 U	0.065 U	0.066 U
SW8270C	Benzo(b)fluoranthene	mg/kg	0.35 U	0.13 U	0.12 U	0.12 U
SW8270C	Benzo(g,h,i)perylene	mg/kg	0.35 U	0.18 U	0.17 U	0.17 U
SW8270C	Benzo(k)fluoranthene	mg/kg	0.35 U	0.14 U	0.13 U	0.13 U
SW8270C	Benzoic acid	mg/kg	1.8 U	0.21 U	0.19 U	0.19 U
SW8270C	Benzyl alcohol	mg/kg	0.35 U	0.12 R	0.11 R	0.12 R
SW8270C	Benzyl butyl phthalate	mg/kg	0.35 U	0.14 U	0.13 U	0.13 U
SW8270C	bis(2-Chloroethoxy)methane	mg/kg	0.35 U	0.072 U	0.066 U	0.067 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1904 05 ft 2000-05-15	BHGLAOC1905 00 ft 2001-08-20	BHGLAOC1905 05 ft 2001-08-20	BHGLAOC1905 10 ft 2001-08-20
SW8270C	bis(2-Chloroethyl)ether (2-Chloroethyl ether)	mg/kg	0.35 U	0.11 U	0.1 U	0.1 U
SW8270C	bis(2-Ethylhexyl)phthalate	mg/kg	0.35 U	0.14 U	0.13 U	0.42
SW8270C	Chlorobenzilate	mg/kg	0.35 U	0.28 U	0.26 U	0.26 U
SW8270C	Chrysene	mg/kg	0.35 U	0.049 U	0.045 U	0.046 U
SW8270C	Cresols, m & p	mg/kg	0.35 U	0.14 U	0.13 U	0.13 U
SW8270C	Diallate (total of cis and trans isomers)	mg/kg	0.35 U	0.35 U	0.33 U	0.33 U
SW8270C	Dibenz(a,h)anthracene	mg/kg	0.35 U	0.14 U	0.13 U	0.13 U
SW8270C	Dibenzofuran	mg/kg	0.35 U	0.067 U	0.061 U	0.063 U
SW8270C	Diethyl phthalate	mg/kg	0.35 U	0.12 U	0.11 U	0.11 U
SW8270C	Dimethyl phthalate	mg/kg	0.35 U	0.091 U	0.084 U	0.085 U
SW8270C	Di-n-butyl phthalate	mg/kg	0.35 U	0.087 U	0.08 U	0.082 U
SW8270C	Di-n-octyl phthalate	mg/kg	0.35 U	0.32 U	0.3 U	0.3 U
SW8270C	Dinoseb	mg/kg	0.7 U	0.55 U	0.51 U	0.52 U
SW8270C	Diphenylamine	mg/kg	0.35 U	0.25 U	0.23 U	0.23 U
SW8270C	Ethyl methanesulfonate	mg/kg	0.35 U	0.4 U	0.37 U	0.37 U
SW8270C	Fluoranthene	mg/kg	0.35 U	0.11 U	0.1 U	0.11 U
SW8270C	Fluorene	mg/kg	0.35 U	0.12 U	0.11 U	0.11 U
SW8270C	Hexachlorobenzene	mg/kg	0.35 U	0.086 U	0.079 U	0.081 U
SW8270C	Hexachlorobutadiene	mg/kg	0.35 U	0.084 U	0.077 U	0.078 U
SW8270C	Hexachlorocyclopentadiene	mg/kg	0.35 U	0.15 U	0.14 U	0.14 U
SW8270C	Hexachloroethane	mg/kg	0.35 U	0.095 U	0.087 U	0.089 U
SW8270C	Hexachlorophene	mg/kg	5.2 R	1.6 U	1.5 U	1.5 U
SW8270C	Hexachloropropene	mg/kg	1.8 U	0.36 U	0.33 U	0.34 U
SW8270C	Indeno(1,2,3-c,d)pyrene	mg/kg	0.35 U	0.14 U	0.13 U	0.13 U
SW8270C	Isophorone	mg/kg	0.35 U	0.061 U	0.056 U	0.057 U
SW8270C	Isosafrole	mg/kg	0.35 U	0.26 U	0.24 U	0.24 U
SW8270C	Methapyrilene	mg/kg	1.8 U	1.8 U	1.7 U	1.7 U
SW8270C	Methyl methanesulfonate	mg/kg	0.7 U	0.4 U	0.37 U	0.38 U
SW8270C	Naphthalene	mg/kg	0.35 U	0.078 U	0.071 U	0.073 U
SW8270C	Nitrobenzene	mg/kg	0.35 U	0.076 U	0.07 U	0.072 U
SW8270C	N-Nitrosodiethylamine	mg/kg	0.7 U	0.41 U	0.38 U	0.38 U
SW8270C	N-Nitrosodimethylamine	mg/kg	0.35 U	0.13 U	0.12 U	0.12 U
SW8270C	N-Nitrosodi-n-butylamine	mg/kg	0.35 U	0.21 U	0.2 U	0.2 U
SW8270C	N-Nitrosodi-n-propylamine	mg/kg	0.35 U	0.12 U	0.11 U	0.11 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1904 05 ft 2000-05-15	BHGLAOC1905 00 ft 2001-08-20	BHGLAOC1905 05 ft 2001-08-20	BHGLAOC1905 10 ft 2001-08-20
SW8270C	N-Nitrosodiphenylamine	mg/kg	0.35 U	0.13 U	0.12 U	0.12 U
SW8270C	N-Nitrosomethylethylamine	mg/kg	0.7 U	0.63 U	0.58 U	0.59 U
SW8270C	N-Nitrosomorpholine	mg/kg	0.7 U	0.48 U	0.44 U	0.45 U
SW8270C	N-Nitrosopiperidine	mg/kg	0.35 U	0.32 U	0.29 U	0.3 U
SW8270C	N-Nitrosopyrrolidine	mg/kg	1.8 U	0.6 U	0.55 U	0.56 U
SW8270C	o-Toluidine	mg/kg	0.35 U	0.29 U	0.26 U	0.27 U
SW8270C	p-Dimethylaminoazobenzene	mg/kg	0.7 U	0.45 U	0.42 U	0.43 U
SW8270C	Pentachlorobenzene	mg/kg	0.35 U	0.21 U	0.19 U	0.19 U
SW8270C	Pentachloronitrobenzene	mg/kg	0.35 U	0.26 U	0.24 U	0.25 U
SW8270C	Pentachlorophenol	mg/kg	1.8 U	0.22 U	0.21 U	0.21 U
SW8270C	Phenacetin	mg/kg	0.7 U	0.47 U	0.43 U	0.44 U
SW8270C	Phenanthrene	mg/kg	0.35 U	0.084 U	0.077 U	0.078 U
SW8270C	Phenol	mg/kg	0.35 U	0.1 U	0.093 U	0.094 U
SW8270C	p-Phenylenediamine	mg/kg	1.4 U	0.98 U	0.9 U	0.92 U
SW8270C	Pronamide	mg/kg	0.7 U	0.5 U	0.46 U	0.46 U
SW8270C	Pyrene	mg/kg	0.35 U	0.17 U	0.16 U	0.16 U
SW8270C	Pyridine	mg/kg	0.7 R	0.12 U	0.11 U	0.12 U
SW8270C	Safrole	mg/kg	0.35 U	0.22 U	0.21 U	0.21 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1906 05 ft 2001-08-20	BHGLAOC1906 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20 Dup
SW6010B	Arsenic	mg/kg	NA	NA	NA	NA
SW6010B	Barium	mg/kg	NA	NA	NA	NA
SW6010B	Beryllium	mg/kg	NA	NA	NA	NA
SW6010B	Cadmium	mg/kg	NA	NA	NA	NA
SW6010B	Chromium, total	mg/kg	NA	NA	NA	NA
SW6010B	Cobalt	mg/kg	NA	NA	NA	NA
SW6010B	Copper	mg/kg	NA	NA	NA	NA
SW6010B	Nickel	mg/kg	NA	NA	NA	NA
SW6010B	Tin	mg/kg	NA	NA	NA	NA
SW6010B	Vanadium	mg/kg	NA	NA	NA	NA
SW6010B	Zinc	mg/kg	NA	NA	NA	NA
SW7041	Antimony	mg/kg	NA	NA	NA	NA
SW7421	Lead	mg/kg	NA	NA	NA	NA
SW7471A	Mercury	mg/kg	NA	NA	NA	NA
SW7740	Selenium	mg/kg	NA	NA	NA	NA
SW7761	Silver	mg/kg	NA	NA	NA	NA
SW7841	Thallium	mg/kg	NA	NA	NA	NA
SW8260B	1,1,1,2-Tetrachloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1,1-Trichloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1,2,2-Tetrachloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1,2-Trichloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1-Dichloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1-Dichloroethene	mg/kg	NA	NA	NA	NA
SW8260B	1,2,3-Trichloropropane	mg/kg	NA	NA	NA	NA
SW8260B	1,2-Dibromo-3-chloropropane	mg/kg	NA	NA	NA	NA
SW8260B	1,2-Dibromoethane (Ethylene dibromide)	mg/kg	NA	NA	NA	NA
SW8260B	1,2-Dichloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,2-Dichloropropane	mg/kg	NA	NA	NA	NA
SW8260B	2-Chloro-1,3-butadiene	mg/kg	NA	NA	NA	NA
SW8260B	2-Hexanone	mg/kg	NA	NA	NA	NA
SW8260B	Acetone	mg/kg	NA	NA	NA	NA
SW8260B	Acetonitrile	mg/kg	NA	NA	NA	NA
SW8260B	Acrolein	mg/kg	NA	NA	NA	NA
SW8260B	Acrylonitrile	mg/kg	NA	NA	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1906 05 ft 2001-08-20	BHGLAOC1906 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20 Dup
SW8260B	Allyl chloride (3-Chloropropene)	mg/kg	NA	NA	NA	NA
SW8260B	Benzene	mg/kg	NA	NA	NA	NA
SW8260B	Bromodichloromethane	mg/kg	NA	NA	NA	NA
SW8260B	Bromoform	mg/kg	NA	NA	NA	NA
SW8260B	Bromomethane	mg/kg	NA	NA	NA	NA
SW8260B	Carbon disulfide	mg/kg	NA	NA	NA	NA
SW8260B	Carbon tetrachloride	mg/kg	NA	NA	NA	NA
SW8260B	Chlorobenzene	mg/kg	NA	NA	NA	NA
SW8260B	Chloroethane	mg/kg	NA	NA	NA	NA
SW8260B	Chloroform	mg/kg	NA	NA	NA	NA
SW8260B	Chloromethane	mg/kg	NA	NA	NA	NA
SW8260B	cis-1,2-Dichloroethene	mg/kg	NA	NA	NA	NA
SW8260B	cis-1,3-Dichloropropene	mg/kg	NA	NA	NA	NA
SW8260B	Dibromochloromethane	mg/kg	NA	NA	NA	NA
SW8260B	Dibromomethane	mg/kg	NA	NA	NA	NA
SW8260B	Dichlorodifluoromethane	mg/kg	NA	NA	NA	NA
SW8260B	Ethyl methacrylate	mg/kg	NA	NA	NA	NA
SW8260B	Ethylbenzene	mg/kg	NA	NA	NA	NA
SW8260B	Iodomethane (Methyl iodide)	mg/kg	NA	NA	NA	NA
SW8260B	Isobutanol	mg/kg	NA	NA	NA	NA
SW8260B	m,p-Xylene (sum of isomers)	mg/kg	NA	NA	NA	NA
SW8260B	Methyl ethyl ketone (2-Butanone)	mg/kg	NA	NA	NA	NA
SW8260B	Methyl isobutyl ketone (4-Methyl-2-pentanone)	mg/kg	NA	NA	NA	NA
SW8260B	Methyl methacrylate	mg/kg	NA	NA	NA	NA
SW8260B	Methylacrylonitrile	mg/kg	NA	NA	NA	NA
SW8260B	Methylene chloride	mg/kg	NA	NA	NA	NA
SW8260B	o-Xylene (1,2-Dimethylbenzene)	mg/kg	NA	NA	NA	NA
SW8260B	Pentachloroethane	mg/kg	NA	NA	NA	NA
SW8260B	Propane nitrile (Propionitrile)	mg/kg	NA	NA	NA	NA
SW8260B	Styrene	mg/kg	NA	NA	NA	NA
SW8260B	Tert-Butyl Methyl Ether	mg/kg	NA	NA	NA	NA
SW8260B	Tetrachloroethene (PCE)	mg/kg	NA	NA	NA	NA
SW8260B	Toluene	mg/kg	NA	NA	NA	NA
SW8260B	Trans-1,2-Dichloroethene	mg/kg	NA	NA	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1906 05 ft 2001-08-20	BHGLAOC1906 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20 Dup
SW8260B	Trans-1,3-Dichloropropene	mg/kg	NA	NA	NA	NA
SW8260B	Trans-1,4-Dichloro-2-Butene	mg/kg	NA	NA	NA	NA
SW8260B	Trichloroethene (TCE)	mg/kg	0.033	0.008 J	0.0006 U	0.0005 U
SW8260B	Trichlorofluoromethane	mg/kg	NA	NA	NA	NA
SW8260B	Vinyl acetate	mg/kg	NA	NA	NA	NA
SW8260B	Vinyl chloride	mg/kg	NA	NA	NA	NA
SW8270C	1,2,4,5-Tetrachlorobenzene	mg/kg	NA	NA	NA	NA
SW8270C	1,2,4-Trichlorobenzene	mg/kg	NA	NA	NA	NA
SW8270C	1,2-Dichlorobenzene	mg/kg	NA	NA	NA	NA
SW8270C	1,3,5-Trinitrobenzene	mg/kg	NA	NA	NA	NA
SW8270C	1,3-Dichlorobenzene	mg/kg	NA	NA	NA	NA
SW8270C	1,3-Dinitrobenzene	mg/kg	NA	NA	NA	NA
SW8270C	1,4-Dichlorobenzene	mg/kg	NA	NA	NA	NA
SW8270C	1,4-Dioxane (p-Dioxane)	mg/kg	NA	NA	NA	NA
SW8270C	1,4-Naphthoquinone	mg/kg	NA	NA	NA	NA
SW8270C	1-Naphthylamine	mg/kg	NA	NA	NA	NA
SW8270C	2,2'-Oxybis(1-chloropropane)	mg/kg	NA	NA	NA	NA
SW8270C	2,3,4,6-Tetrachlorophenol	mg/kg	NA	NA	NA	NA
SW8270C	2,4,5-Trichlorophenol	mg/kg	NA	NA	NA	NA
SW8270C	2,4,6-Trichlorophenol	mg/kg	NA	NA	NA	NA
SW8270C	2,4-Dichlorophenol	mg/kg	NA	NA	NA	NA
SW8270C	2,4-Dimethylphenol	mg/kg	NA	NA	NA	NA
SW8270C	2,4-Dinitrophenol	mg/kg	NA	NA	NA	NA
SW8270C	2,4-Dinitrotoluene	mg/kg	NA	NA	NA	NA
SW8270C	2,6-Dichlorophenol	mg/kg	NA	NA	NA	NA
SW8270C	2,6-Dinitrotoluene	mg/kg	NA	NA	NA	NA
SW8270C	2-Acetylaminofluorene	mg/kg	NA	NA	NA	NA
SW8270C	2-Aminonaphthalene (beta-Naphthylamine)	mg/kg	NA	NA	NA	NA
SW8270C	2-Chloronaphthalene	mg/kg	NA	NA	NA	NA
SW8270C	2-Chlorophenol	mg/kg	NA	NA	NA	NA
SW8270C	2-Methylnaphthalene	mg/kg	NA	NA	NA	NA
SW8270C	2-Methylphenol (o-Cresol)	mg/kg	NA	NA	NA	NA
SW8270C	2-Nitroaniline	mg/kg	NA	NA	NA	NA
SW8270C	2-Nitrophenol	mg/kg	NA	NA	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1906 05 ft 2001-08-20	BHGLAOC1906 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20 Dup
SW8270C	2-Picoline (alpha-Picoline)	mg/kg	NA	NA	NA	NA
SW8270C	3,3'-Dichlorobenzidine	mg/kg	NA	NA	NA	NA
SW8270C	3,3'-Dimethylbenzidine	mg/kg	NA	NA	NA	NA
SW8270C	3-Methylcholanthrene	mg/kg	NA	NA	NA	NA
SW8270C	3-Nitroaniline	mg/kg	NA	NA	NA	NA
SW8270C	4,6-Dinitro-2-methylphenol	mg/kg	NA	NA	NA	NA
SW8270C	4-Aminobiphenyl (4-Biphenylamine)	mg/kg	NA	NA	NA	NA
SW8270C	4-Bromophenyl phenyl ether	mg/kg	NA	NA	NA	NA
SW8270C	4-Chloro-3-methylphenol	mg/kg	NA	NA	NA	NA
SW8270C	4-Chloroaniline	mg/kg	NA	NA	NA	NA
SW8270C	4-Chlorophenyl phenyl ether	mg/kg	NA	NA	NA	NA
SW8270C	4-Methylphenol (P-Cresol)	mg/kg	NA	NA	NA	NA
SW8270C	4-Nitroaniline	mg/kg	NA	NA	NA	NA
SW8270C	4-Nitrophenol	mg/kg	NA	NA	NA	NA
SW8270C	4-Nitroquinoline-1-oxide	mg/kg	NA	NA	NA	NA
SW8270C	5-Nitro-o-toluidine	mg/kg	NA	NA	NA	NA
SW8270C	7,12-Dimethylbenzo(a)anthracene	mg/kg	NA	NA	NA	NA
SW8270C	Acenaphthene	mg/kg	NA	NA	NA	NA
SW8270C	Acenaphthylene	mg/kg	NA	NA	NA	NA
SW8270C	Acetophenone	mg/kg	NA	NA	NA	NA
SW8270C	alpha, alpha-Dimethylphenethylamine	mg/kg	NA	NA	NA	NA
SW8270C	Aniline (Phenylamine, Aminobenzene)	mg/kg	NA	NA	NA	NA
SW8270C	Anthracene	mg/kg	NA	NA	NA	NA
SW8270C	Aramite (total)	mg/kg	NA	NA	NA	NA
SW8270C	Benzo(a)anthracene	mg/kg	NA	NA	NA	NA
SW8270C	Benzo(a)pyrene	mg/kg	NA	NA	NA	NA
SW8270C	Benzo(b)fluoranthene	mg/kg	NA	NA	NA	NA
SW8270C	Benzo(g,h,i)perylene	mg/kg	NA	NA	NA	NA
SW8270C	Benzo(k)fluoranthene	mg/kg	NA	NA	NA	NA
SW8270C	Benzoic acid	mg/kg	NA	NA	NA	NA
SW8270C	Benzyl alcohol	mg/kg	NA	NA	NA	NA
SW8270C	Benzyl butyl phthalate	mg/kg	NA	NA	NA	NA
SW8270C	bis(2-Chloroethoxy)methane	mg/kg	NA	NA	NA	NA



Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1906 05 ft 2001-08-20	BHGLAOC1906 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20 Dup
SW8270C	bis(2-Chloroethyl)ether (2-Chloroethyl ether)	mg/kg	NA	NA	NA	NA
SW8270C	bis(2-Ethylhexyl)phthalate	mg/kg	NA	NA	NA	NA
SW8270C	Chlorobenzilate	mg/kg	NA	NA	NA	NA
SW8270C	Chrysene	mg/kg	NA	NA	NA	NA
SW8270C	Cresols, m & p	mg/kg	NA	NA	NA	NA
SW8270C	Diallate (total of cis and trans isomers)	mg/kg	NA	NA	NA	NA
SW8270C	Dibenz(a,h)anthracene	mg/kg	NA	NA	NA	NA
SW8270C	Dibenzofuran	mg/kg	NA	NA	NA	NA
SW8270C	Diethyl phthalate	mg/kg	NA	NA	NA	NA
SW8270C	Dimethyl phthalate	mg/kg	NA	NA	NA	NA
SW8270C	Di-n-butyl phthalate	mg/kg	NA	NA	NA	NA
SW8270C	Di-n-octyl phthalate	mg/kg	NA	NA	NA	NA
SW8270C	Dinoseb	mg/kg	NA	NA	NA	NA
SW8270C	Diphenylamine	mg/kg	NA	NA	NA	NA
SW8270C	Ethyl methanesulfonate	mg/kg	NA	NA	NA	NA
SW8270C	Fluoranthene	mg/kg	NA	NA	NA	NA
SW8270C	Fluorene	mg/kg	NA	NA	NA	NA
SW8270C	Hexachlorobenzene	mg/kg	NA	NA	NA	NA
SW8270C	Hexachlorobutadiene	mg/kg	NA	NA	NA	NA
SW8270C	Hexachlorocyclopentadiene	mg/kg	NA	NA	NA	NA
SW8270C	Hexachloroethane	mg/kg	NA	NA	NA	NA
SW8270C	Hexachlorophene	mg/kg	NA	NA	NA	NA
SW8270C	Hexachloropropene	mg/kg	NA	NA	NA	NA
SW8270C	Indeno(1,2,3-c,d)pyrene	mg/kg	NA	NA	NA	NA
SW8270C	Isophorone	mg/kg	NA	NA	NA	NA
SW8270C	Isosafrole	mg/kg	NA	NA	NA	NA
SW8270C	Methapyriline	mg/kg	NA	NA	NA	NA
SW8270C	Methyl methanesulfonate	mg/kg	NA	NA	NA	NA
SW8270C	Naphthalene	mg/kg	NA	NA	NA	NA
SW8270C	Nitrobenzene	mg/kg	NA	NA	NA	NA
SW8270C	N-Nitrosodiethylamine	mg/kg	NA	NA	NA	NA
SW8270C	N-Nitrosodimethylamine	mg/kg	NA	NA	NA	NA
SW8270C	N-Nitrosodi-n-butylamine	mg/kg	NA	NA	NA	NA
SW8270C	N-Nitrosodi-n-propylamine	mg/kg	NA	NA	NA	NA

724 236

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1906 05 ft 2001-08-20	BHGLAOC1906 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20	BHGLAOC1907 10 ft 2001-08-20 Dup
SW8270C	N-Nitrosodiphenylamine	mg/kg	NA	NA	NA	NA
SW8270C	N-Nitrosomethylethylamine	mg/kg	NA	NA	NA	NA
SW8270C	N-Nitrosomorpholine	mg/kg	NA	NA	NA	NA
SW8270C	N-Nitrosopiperidine	mg/kg	NA	NA	NA	NA
SW8270C	N-Nitrosopyrrolidine	mg/kg	NA	NA	NA	NA
SW8270C	o-Toluidine	mg/kg	NA	NA	NA	NA
SW8270C	p-Dimethylaminoazobenzene	mg/kg	NA	NA	NA	NA
SW8270C	Pentachlorobenzene	mg/kg	NA	NA	NA	NA
SW8270C	Pentachloronitrobenzene	mg/kg	NA	NA	NA	NA
SW8270C	Pentachlorophenol	mg/kg	NA	NA	NA	NA
SW8270C	Phenacetin	mg/kg	NA	NA	NA	NA
SW8270C	Phenanthrene	mg/kg	NA	NA	NA	NA
SW8270C	Phenol	mg/kg	NA	NA	NA	NA
SW8270C	p-Phenylenediamine	mg/kg	NA	NA	NA	NA
SW8270C	Pronamide	mg/kg	NA	NA	NA	NA
SW8270C	Pyrene	mg/kg	NA	NA	NA	NA
SW8270C	Pyridine	mg/kg	NA	NA	NA	NA
SW8270C	Safrrole	mg/kg	NA	NA	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1908 00 ft 2001-08-21	BHGLAOC1908 05 ft 2001-08-21	BHGLAOC1908 10 ft 2001-08-21	BHGLAOC1909 05 ft 2001-08-22
SW6010B	Arsenic	mg/kg	4.2 F	2.7 F	3.7 F	NA
SW6010B	Barium	mg/kg	80.3	92	53.5	NA
SW6010B	Beryllium	mg/kg	0.79	0.86	0.64	NA
SW6010B	Cadmium	mg/kg	0.093 U	0.11 U	0.11 U	NA
SW6010B	Chromium, total	mg/kg	12.8	17.7	13	NA
SW6010B	Cobalt	mg/kg	5.4 F	3.3 F	2.9 F	NA
SW6010B	Copper	mg/kg	8.6 F	8.9 F	4.4 F	NA
SW6010B	Nickel	mg/kg	10.8	9.4 F	7.6 F	NA
SW6010B	Tin	mg/kg	1.6 U	1.9 U	2.1 U	NA
SW6010B	Vanadium	mg/kg	25.1 F	25 F	25 F	NA
SW6010B	Zinc	mg/kg	20.3 U	25.5 U	16.7 U	NA
SW7041	Antimony	mg/kg	0.43 F	0.23 F	0.24 UJ	NA
SW7421	Lead	mg/kg	11.1	10.1	6.4	NA
SW7471A	Mercury	mg/kg	0.013 F	0.0062 U	0.0065 U	NA
SW7740	Selenium	mg/kg	0.2 UJ	0.18 UJ	0.2 UJ	NA
SW7761	Silver	mg/kg	0.082 UJ	0.075 UJ	0.084 UJ	NA
SW7841	Thallium	mg/kg	0.23 U	0.21 UJ	0.24 UJ	NA
SW8260B	1,1,1,2-Tetrachloroethane	mg/kg	0.0008 U	0.0007 U	0.0007 U	NA
SW8260B	1,1,1-Trichloroethane	mg/kg	0.0007 U	0.0006 U	0.0006 U	NA
SW8260B	1,1,2,2-Tetrachloroethane	mg/kg	0.0007 U	0.0006 U	0.0006 U	NA
SW8260B	1,1,2-Trichloroethane	mg/kg	0.0008 U	0.0007 U	0.0007 U	NA
SW8260B	1,1-Dichloroethane	mg/kg	0.001 U	0.0008 U	0.0008 U	NA
SW8260B	1,1-Dichloroethene	mg/kg	0.001 U	0.0009 U	0.0009 U	NA
SW8260B	1,2,3-Trichloropropane	mg/kg	0.001 U	0.001 U	0.001 U	NA
SW8260B	1,2-Dibromo-3-chloropropane	mg/kg	0.001 U	0.001 U	0.001 U	NA
SW8260B	1,2-Dibromoethane (Ethylene dibromide)	mg/kg	0.0009 U	0.0007 U	0.0007 U	NA
SW8260B	1,2-Dichloroethane	mg/kg	0.0007 U	0.0005 U	0.0005 U	NA
SW8260B	1,2-Dichloropropane	mg/kg	0.001 U	0.0009 U	0.0009 U	NA
SW8260B	2-Chloro-1,3-butadiene	mg/kg	0.0008 U	0.0006 U	0.0006 U	NA
SW8260B	2-Hexanone	mg/kg	0.002 U	0.002 U	0.002 U	NA
SW8260B	Acetone	mg/kg	0.008 U	0.004 U	0.004 U	NA
SW8260B	Acetonitrile	mg/kg	0.029 U	0.024 U	0.024 U	NA
SW8260B	Acrolein	mg/kg	0.043 U	0.035 U	0.035 U	NA
SW8260B	Acrylonitrile	mg/kg	0.008 U	0.007 U	0.007 U	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1908 00 ft 2001-08-21	BHGLAOC1908 05 ft 2001-08-21	BHGLAOC1908 10 ft 2001-08-21	BHGLAOC1909 05 ft 2001-08-22
SW8260B	Allyl chloride (3-Chloropropene)	mg/kg	0.002 U	0.002 U	0.002 U	NA
SW8260B	Benzene	mg/kg	0.0007 U	0.0006 U	0.0006 U	NA
SW8260B	Bromodichloromethane	mg/kg	0.0008 U	0.0006 U	0.0006 U	NA
SW8260B	Bromoform	mg/kg	0.001 U	0.0008 U	0.0008 U	NA
SW8260B	Bromomethane	mg/kg	0.003 R	0.003 R	0.003 R	NA
SW8260B	Carbon disulfide	mg/kg	0.002 U	0.002 U	0.002 U	NA
SW8260B	Carbon tetrachloride	mg/kg	0.0009 U	0.0008 U	0.0008 U	NA
SW8260B	Chlorobenzene	mg/kg	0.001 U	0.0008 U	0.0008 U	NA
SW8260B	Chloroethane	mg/kg	0.002 R	0.001 R	0.001 R	NA
SW8260B	Chloroform	mg/kg	0.0007 U	0.0006 U	0.0006 U	NA
SW8260B	Chloromethane	mg/kg	0.001 R	0.0009 R	0.0009 R	NA
SW8260B	cis-1,2-Dichloroethene	mg/kg	0.001 U	0.001 U	0.001 U	NA
SW8260B	cis-1,3-Dichloropropene	mg/kg	0.0009 U	0.0007 U	0.0007 U	NA
SW8260B	Dibromochloromethane	mg/kg	0.0008 U	0.0006 U	0.0006 U	NA
SW8260B	Dibromomethane	mg/kg	0.0008 U	0.0006 U	0.0006 U	NA
SW8260B	Dichlorodifluoromethane	mg/kg	0.0008 U	0.0007 U	0.0007 U	NA
SW8260B	Ethyl methacrylate	mg/kg	0.002 U	0.001 U	0.001 U	NA
SW8260B	Ethylbenzene	mg/kg	0.001 U	0.001 U	0.001 U	NA
SW8260B	Iodomethane (Methyl iodide)	mg/kg	0.004 U	0.003 U	0.003 U	NA
SW8260B	Isobutanol	mg/kg	0.095 U	0.078 U	0.078 U	NA
SW8260B	m,p-Xylene (sum of isomers)	mg/kg	0.002 U	0.002 U	0.002 U	NA
SW8260B	Methyl ethyl ketone (2-Butanone)	mg/kg	0.005 U	0.004 U	0.004 U	NA
SW8260B	Methyl isobutyl ketone (4-Methyl-2-pentanone)	mg/kg	0.003 U	0.003 U	0.003 U	NA
SW8260B	Methyl methacrylate	mg/kg	0.002 U	0.002 U	0.002 U	NA
SW8260B	Methylacrylonitrile	mg/kg	0.005 U	0.004 U	0.004 U	NA
SW8260B	Methylene chloride	mg/kg	0.002 U	0.002 U	0.002 U	NA
SW8260B	o-Xylene (1,2-Dimethylbenzene)	mg/kg	0.001 U	0.0009 U	0.0009 U	NA
SW8260B	Pentachloroethane	mg/kg	0.006 U	0.005 U	0.005 U	NA
SW8260B	Propane nitrile (Propionitrile)	mg/kg	0.021 U	0.018 U	0.018 U	NA
SW8260B	Styrene	mg/kg	0.001 U	0.0009 U	0.0009 U	NA
SW8260B	Tert-Butyl Methyl Ether	mg/kg	0.0007 U	0.0006 U	0.0006 U	NA
SW8260B	Tetrachloroethene (PCE)	mg/kg	0.0008 U	0.0006 U	0.0006 U	NA
SW8260B	Toluene	mg/kg	0.001 U	0.0009 U	0.0009 U	NA
SW8260B	Trans-1,2-Dichloroethene	mg/kg	0.001 U	0.0009 U	0.0009 U	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1908 00 ft 2001-08-21	BHGLAOC1908 05 ft 2001-08-21	BHGLAOC1908 10 ft 2001-08-21	BHGLAOC1909 05 ft 2001-08-22
SW8260B	Trans-1,3-Dichloropropene	mg/kg	0.0009 U	0.0008 U	0.0008 U	NA
SW8260B	Trans-1,4-Dichloro-2-Butene	mg/kg	0.002 U	0.002 U	0.002 U	NA
SW8260B	Trichloroethene (TCE)	mg/kg	0.0007 U	0.0005 U	0.03	NA
SW8260B	Trichlorofluoromethane	mg/kg	0.0008 U	0.0007 U	0.0007 U	NA
SW8260B	Vinyl acetate	mg/kg	0.0006 U	0.0005 U	0.0005 U	NA
SW8260B	Vinyl chloride	mg/kg	0.0008 U	0.0007 U	0.0007 U	NA
SW8270C	1,2,4,5-Tetrachlorobenzene	mg/kg	0.22 U	0.21 U	0.22 U	0.19 U
SW8270C	1,2,4-Trichlorobenzene	mg/kg	0.058 U	0.055 U	0.058 U	0.051 U
SW8270C	1,2-Dichlorobenzene	mg/kg	0.1 U	0.097 U	0.1 U	0.09 R
SW8270C	1,3,5-Trinitrobenzene	mg/kg	0.88 U	0.83 U	0.88 U	0.77 U
SW8270C	1,3-Dichlorobenzene	mg/kg	0.11 U	0.11 U	0.11 U	0.097 U
SW8270C	1,3-Dinitrobenzene	mg/kg	0.4 U	0.38 U	0.4 U	0.35 U
SW8270C	1,4-Dichlorobenzene	mg/kg	0.088 U	0.084 U	0.088 U	0.077 U
SW8270C	1,4-Dioxane (p-Dioxane)	mg/kg	0.96 U	0.91 U	0.96 U	0.84 U
SW8270C	1,4-Naphthoquinone	mg/kg	1.5 U	1.4 U	1.5 U	1.3 U
SW8270C	1-Naphthylamine	mg/kg	0.61 U	0.58 U	0.61 U	0.53 U
SW8270C	2,2'-Oxybis(1-chloropropane)	mg/kg	0.21 U	0.19 U	0.2 U	0.18 U
SW8270C	2,3,4,6-Tetrachlorophenol	mg/kg	0.33 U	0.32 U	0.33 U	0.29 U
SW8270C	2,4,5-Trichlorophenol	mg/kg	0.08 U	0.076 U	0.08 U	0.07 U
SW8270C	2,4,6-Trichlorophenol	mg/kg	0.081 U	0.077 U	0.081 U	0.071 U
SW8270C	2,4-Dichlorophenol	mg/kg	0.068 U	0.064 U	0.068 U	0.059 U
SW8270C	2,4-Dimethylphenol	mg/kg	0.27 U	0.25 U	0.27 U	0.23 U
SW8270C	2,4-Dinitrophenol	mg/kg	0.23 U	0.22 U	0.23 U	0.21 U
SW8270C	2,4-Dinitrotoluene	mg/kg	0.088 U	0.084 U	0.088 U	0.077 U
SW8270C	2,6-Dichlorophenol	mg/kg	0.26 U	0.25 U	0.26 U	0.23 U
SW8270C	2,6-Dinitrotoluene	mg/kg	0.093 U	0.088 U	0.093 U	0.081 U
SW8270C	2-Acetylaminofluorene	mg/kg	0.64 U	0.61 U	0.64 U	0.56 U
SW8270C	2-Aminonaphthalene (beta-Naphthylamine)	mg/kg	0.62 U	0.58 U	0.61 U	0.54 U
SW8270C	2-Chloronaphthalene	mg/kg	0.064 U	0.061 U	0.064 U	0.056 U
SW8270C	2-Chlorophenol	mg/kg	0.082 U	0.078 U	0.082 U	0.072 U
SW8270C	2-Methylnaphthalene	mg/kg	0.28 U	0.27 U	0.28 U	0.25 U
SW8270C	2-Methylphenol (o-Cresol)	mg/kg	0.15 U	0.14 U	0.15 U	0.13 U
SW8270C	2-Nitroaniline	mg/kg	0.13 U	0.12 U	0.13 U	0.11 U
SW8270C	2-Nitrophenol	mg/kg	0.092 U	0.087 U	0.092 U	0.08 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1908 00 ft 2001-08-21	BHGLAOC1908 05 ft 2001-08-21	BHGLAOC1908 10 ft 2001-08-21	BHGLAOC1909 05 ft 2001-08-22
SW8270C	2-Picoline (alpha-Picoline)	mg/kg	0.27 U	0.25 U	0.27 U	0.23 U
SW8270C	3,3'-Dichlorobenzidine	mg/kg	0.14 U	0.13 U	0.14 U	0.12 U
SW8270C	3,3'-Dimethylbenzidine	mg/kg	0.36 U	0.34 U	0.36 U	0.32 U
SW8270C	3-Methylcholanthrene	mg/kg	0.36 U	0.34 U	0.36 U	0.32 U
SW8270C	3-Nitroaniline	mg/kg	0.17 U	0.16 U	0.17 U	0.15 U
SW8270C	4,6-Dinitro-2-methylphenol	mg/kg	0.17 U	0.16 U	0.17 U	0.15 U
SW8270C	4-Aminobiphenyl (4-Biphenylamine)	mg/kg	0.34 U	0.32 U	0.34 U	0.3 U
SW8270C	4-Bromophenyl phenyl ether	mg/kg	0.11 U	0.1 U	0.11 U	0.096 U
SW8270C	4-Chloro-3-methylphenol	mg/kg	0.1 U	0.096 U	0.1 U	0.089 U
SW8270C	4-Chloroaniline	mg/kg	0.15 U	0.14 U	0.15 U	0.13 U
SW8270C	4-Chlorophenyl phenyl ether	mg/kg	0.1 U	0.098 U	0.1 U	0.091 U
SW8270C	4-Methylphenol (P-Cresol)	mg/kg	NA	NA	NA	NA
SW8270C	4-Nitroaniline	mg/kg	0.16 U	0.15 U	0.16 U	0.14 U
SW8270C	4-Nitrophenol	mg/kg	0.44 U	0.41 U	0.44 U	0.38 U
SW8270C	4-Nitroquinoline-1-oxide	mg/kg	1.6 U	1.5 U	1.6 U	1.4 R
SW8270C	5-Nitro-o-toluidine	mg/kg	0.37 U	0.35 U	0.37 U	0.32 U
SW8270C	7,12-Dimethylbenzo(a)anthracene	mg/kg	0.55 U	0.52 U	0.55 U	0.48 U
SW8270C	Acenaphthene	mg/kg	0.063 U	0.06 U	0.063 U	0.055 U
SW8270C	Acenaphthylene	mg/kg	0.066 U	0.062 U	0.065 U	0.057 U
SW8270C	Acetophenone	mg/kg	0.34 U	0.32 U	0.33 U	0.29 U
SW8270C	alpha, alpha-Dimethylphenethylamine	mg/kg	1.8 U	1.7 U	1.8 U	1.5 U
SW8270C	Aniline (Phenylamine, Aminobenzene)	mg/kg	0.13 U	0.12 U	0.13 U	0.11 U
SW8270C	Anthracene	mg/kg	0.087 U	0.083 U	0.087 U	0.076 U
SW8270C	Aramite (total)	mg/kg	0.42 U	0.4 U	0.42 U	0.37 U
SW8270C	Benzo(a)anthracene	mg/kg	0.063 U	0.06 U	0.063 U	0.055 U
SW8270C	Benzo(a)pyrene	mg/kg	0.069 U	0.066 U	0.069 U	0.061 U
SW8270C	Benzo(b)fluoranthene	mg/kg	0.13 U	0.12 U	0.13 U	0.11 U
SW8270C	Benzo(g,h,i)perylene	mg/kg	0.18 U	0.17 U	0.18 U	0.16 U
SW8270C	Benzo(k)fluoranthene	mg/kg	0.14 U	0.13 U	0.14 U	0.12 R
SW8270C	Benzoic acid	mg/kg	0.2 U	0.19 U	0.2 U	0.18 R
SW8270C	Benzyl alcohol	mg/kg	0.12 R	0.12 R	0.12 R	0.11 U
SW8270C	Benzyl butyl phthalate	mg/kg	0.14 U	0.13 U	0.14 U	0.12 U
SW8270C	bis(2-Chloroethoxy)methane	mg/kg	0.07 U	0.067 U	0.07 U	0.062 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1908 00 ft 2001-08-21	BHGLAOC1908 05 ft 2001-08-21	BHGLAOC1908 10 ft 2001-08-21	BHGLAOC1909 05 ft 2001-08-22
SW8270C	bis(2-Chloroethyl)ether (2-Chloroethyl ether)	mg/kg	0.11 U	0.1 U	0.11 U	0.095 U
SW8270C	bis(2-Ethylhexyl)phthalate	mg/kg	0.13 U	0.13 U	0.13 U	0.12 U
SW8270C	Chlorobenzilate	mg/kg	0.27 U	0.26 U	0.27 U	0.24 U
SW8270C	Chrysene	mg/kg	0.048 U	0.045 U	0.048 U	0.042 U
SW8270C	Cresols, m & p	mg/kg	0.14 U	0.13 U	0.14 U	0.12 U
SW8270C	Diallate (total of cis and trans isomers)	mg/kg	0.35 U	0.33 U	0.35 U	0.3 U
SW8270C	Dibenz(a,h)anthracene	mg/kg	0.13 U	0.13 U	0.13 U	0.12 U
SW8270C	Dibenzofuran	mg/kg	0.066 U	0.062 U	0.065 U	0.057 U
SW8270C	Diethyl phthalate	mg/kg	0.11 U	0.11 U	0.11 U	0.099 U
SW8270C	Dimethyl phthalate	mg/kg	0.089 U	0.085 U	0.089 U	0.078 U
SW8270C	Di-n-butyl phthalate	mg/kg	0.086 U	0.081 U	0.086 U	0.075 U
SW8270C	Di-n-octyl phthalate	mg/kg	0.32 U	0.3 U	0.32 U	0.28 U
SW8270C	Dinoseb	mg/kg	0.54 U	0.51 U	0.54 U	0.47 U
SW8270C	Diphenylamine	mg/kg	0.24 U	0.23 U	0.24 U	0.21 U
SW8270C	Ethyl methanesulfonate	mg/kg	0.39 U	0.37 U	0.39 U	0.34 U
SW8270C	Fluoranthene	mg/kg	0.11 U	0.11 U	0.11 U	0.098 U
SW8270C	Fluorene	mg/kg	0.12 U	0.11 U	0.12 U	0.1 U
SW8270C	Hexachlorobenzene	mg/kg	0.085 U	0.08 U	0.085 U	0.074 U
SW8270C	Hexachlorobutadiene	mg/kg	0.082 U	0.078 U	0.082 U	0.072 U
SW8270C	Hexachlorocyclopentadiene	mg/kg	0.14 U	0.14 U	0.14 U	0.13 U
SW8270C	Hexachloroethane	mg/kg	0.093 U	0.088 U	0.093 U	0.081 U
SW8270C	Hexachlorophene	mg/kg	1.6 U	1.5 U	1.5 U	1.4 U
SW8270C	Hexachloropropene	mg/kg	0.36 U	0.34 U	0.36 U	0.31 U
SW8270C	Indeno(1,2,3-c,d)pyrene	mg/kg	0.13 U	0.13 U	0.13 U	0.12 U
SW8270C	Isophorone	mg/kg	0.06 U	0.057 U	0.06 U	0.052 U
SW8270C	Isosafrole	mg/kg	0.26 U	0.24 U	0.26 U	0.22 U
SW8270C	Methapyrene	mg/kg	1.8 U	1.7 U	1.8 U	1.5 U
SW8270C	Methyl methanesulfonate	mg/kg	0.4 U	0.38 U	0.4 U	0.35 U
SW8270C	Naphthalene	mg/kg	0.076 U	0.072 U	0.076 U	0.067 U
SW8270C	Nitrobenzene	mg/kg	0.075 U	0.071 U	0.075 U	0.066 U
SW8270C	N-Nitrosodiethylamine	mg/kg	0.4 U	0.38 U	0.4 U	0.35 U
SW8270C	N-Nitrosodimethylamine	mg/kg	0.13 U	0.12 U	0.13 U	0.11 U
SW8270C	N-Nitrosodi-n-butylamine	mg/kg	0.21 U	0.2 U	0.21 U	0.18 U
SW8270C	N-Nitrosodi-n-propylamine	mg/kg	0.12 U	0.11 U	0.12 U	0.11 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1908 00 ft 2001-08-21	BHGLAOC1908 05 ft 2001-08-21	BHGLAOC1908 10 ft 2001-08-21	BHGLAOC1909 05 ft 2001-08-22
SW8270C	N-Nitrosodiphenylamine	mg/kg	0.13 U	0.12 U	0.13 U	0.11 U
SW8270C	N-Nitrosomethylethylamine	mg/kg	0.62 U	0.59 U	0.62 U	0.54 U
SW8270C	N-Nitrosomorpholine	mg/kg	0.47 U	0.44 U	0.47 U	0.41 U
SW8270C	N-Nitrosopiperidine	mg/kg	0.31 U	0.3 U	0.31 U	0.27 U
SW8270C	N-Nitrosopyrrolidine	mg/kg	0.59 U	0.56 U	0.59 U	0.52 U
SW8270C	o-Toluidine	mg/kg	0.28 U	0.27 U	0.28 U	0.25 U
SW8270C	p-Dimethylaminoazobenzene	mg/kg	0.45 U	0.42 U	0.45 U	0.39 U
SW8270C	Pentachlorobenzene	mg/kg	0.2 U	0.19 U	0.2 U	0.18 U
SW8270C	Pentachloronitrobenzene	mg/kg	0.26 U	0.24 U	0.26 U	0.23 U
SW8270C	Pentachlorophenol	mg/kg	0.22 U	0.21 U	0.22 U	0.19 U
SW8270C	Phenacetin	mg/kg	0.46 U	0.44 U	0.46 U	0.41 U
SW8270C	Phenanthrene	mg/kg	0.082 U	0.078 U	0.082 U	0.072 U
SW8270C	Phenol	mg/kg	0.099 U	0.094 U	0.099 U	0.087 U
SW8270C	p-Phenylenediamine	mg/kg	0.96 U	0.91 U	0.96 U	0.84 U
SW8270C	Propanide	mg/kg	0.49 U	0.46 U	0.49 U	0.43 U
SW8270C	Pyrene	mg/kg	0.17 U	0.16 U	0.17 U	0.15 U
SW8270C	Pyridine	mg/kg	0.12 U	0.12 U	0.12 U	0.11 U
SW8270C	Safrole	mg/kg	0.22 U	0.21 U	0.22 U	0.19 U



Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1910 00 ft 2001-08-22	BHGLAOC1910 05 ft 2001-08-22	BHGLAOC1910 10 ft 2001-08-22	BHGLAOC1911 05 ft 2001-12-05
SW6010B	Arsenic	mg/kg	NA	NA	NA	NA
SW6010B	Barium	mg/kg	NA	NA	NA	NA
SW6010B	Beryllium	mg/kg	NA	NA	NA	NA
SW6010B	Cadmium	mg/kg	NA	NA	NA	NA
SW6010B	Chromium, total	mg/kg	NA	NA	NA	NA
SW6010B	Cobalt	mg/kg	NA	NA	NA	NA
SW6010B	Copper	mg/kg	NA	NA	NA	NA
SW6010B	Nickel	mg/kg	NA	NA	NA	NA
SW6010B	Tin	mg/kg	NA	NA	NA	NA
SW6010B	Vanadium	mg/kg	NA	NA	NA	NA
SW6010B	Zinc	mg/kg	NA	NA	NA	NA
SW7041	Antimony	mg/kg	NA	NA	NA	NA
SW7421	Lead	mg/kg	NA	NA	NA	NA
SW7471A	Mercury	mg/kg	NA	NA	NA	NA
SW7740	Selenium	mg/kg	NA	NA	NA	NA
SW7761	Silver	mg/kg	NA	NA	NA	NA
SW7841	Thallium	mg/kg	NA	NA	NA	NA
SW8260B	1,1,1,2-Tetrachloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1,1-Trichloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1,2,2-Tetrachloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1,2-Trichloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1-Dichloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1-Dichloroethene	mg/kg	NA	NA	NA	NA
SW8260B	1,2,3-Trichloropropane	mg/kg	NA	NA	NA	NA
SW8260B	1,2-Dibromo-3-chloropropane	mg/kg	NA	NA	NA	NA
SW8260B	1,2-Dibromoethane (Ethylene dibromide)	mg/kg	NA	NA	NA	NA
SW8260B	1,2-Dichloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,2-Dichloropropane	mg/kg	NA	NA	NA	NA
SW8260B	2-Chloro-1,3-butadiene	mg/kg	NA	NA	NA	NA
SW8260B	2-Hexanone	mg/kg	NA	NA	NA	NA
SW8260B	Acetone	mg/kg	NA	NA	NA	NA
SW8260B	Acetonitrile	mg/kg	NA	NA	NA	NA
SW8260B	Acrolein	mg/kg	NA	NA	NA	NA
SW8260B	Acrylonitrile	mg/kg	NA	NA	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1910 00 ft 2001-08-22	BHGLAOC1910 05 ft 2001-08-22	BHGLAOC1910 10 ft 2001-08-22	BHGLAOC1911 05 ft 2001-12-05
SW8260B	Allyl chloride (3-Chloropropene)	mg/kg	NA	NA	NA	NA
SW8260B	Benzene	mg/kg	NA	NA	NA	NA
SW8260B	Bromodichloromethane	mg/kg	NA	NA	NA	NA
SW8260B	Bromoform	mg/kg	NA	NA	NA	NA
SW8260B	Bromomethane	mg/kg	NA	NA	NA	NA
SW8260B	Carbon disulfide	mg/kg	NA	NA	NA	NA
SW8260B	Carbon tetrachloride	mg/kg	NA	NA	NA	NA
SW8260B	Chlorobenzene	mg/kg	NA	NA	NA	NA
SW8260B	Chloroethane	mg/kg	NA	NA	NA	NA
SW8260B	Chloroform	mg/kg	NA	NA	NA	NA
SW8260B	Chloromethane	mg/kg	NA	NA	NA	NA
SW8260B	cis-1,2-Dichloroethene	mg/kg	NA	NA	NA	NA
SW8260B	cis-1,3-Dichloropropene	mg/kg	NA	NA	NA	NA
SW8260B	Dibromochloromethane	mg/kg	NA	NA	NA	NA
SW8260B	Dibromomethane	mg/kg	NA	NA	NA	NA
SW8260B	Dichlorodifluoromethane	mg/kg	NA	NA	NA	NA
SW8260B	Ethyl methacrylate	mg/kg	NA	NA	NA	NA
SW8260B	Ethylbenzene	mg/kg	NA	NA	NA	NA
SW8260B	Iodomethane (Methyl iodide)	mg/kg	NA	NA	NA	NA
SW8260B	Isobutanol	mg/kg	NA	NA	NA	NA
SW8260B	m,p-Xylene (sum of isomers)	mg/kg	NA	NA	NA	NA
SW8260B	Methyl ethyl ketone (2-Butanone)	mg/kg	NA	NA	NA	NA
SW8260B	Methyl isobutyl ketone (4-Methyl-2-pentanone)	mg/kg	NA	NA	NA	NA
SW8260B	Methyl methacrylate	mg/kg	NA	NA	NA	NA
SW8260B	Methylacrylonitrile	mg/kg	NA	NA	NA	NA
SW8260B	Methylene chloride	mg/kg	NA	NA	NA	NA
SW8260B	o-Xylene (1,2-Dimethylbenzene)	mg/kg	NA	NA	NA	NA
SW8260B	Pentachloroethane	mg/kg	NA	NA	NA	NA
SW8260B	Propane nitrile (Propionitrile)	mg/kg	NA	NA	NA	NA
SW8260B	Styrene	mg/kg	NA	NA	NA	NA
SW8260B	Tert-Butyl Methyl Ether	mg/kg	NA	NA	NA	NA
SW8260B	Tetrachloroethene (PCE)	mg/kg	NA	NA	NA	NA
SW8260B	Toluene	mg/kg	NA	NA	NA	NA
SW8260B	Trans-1,2-Dichloroethene	mg/kg	NA	NA	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1910 00 ft 2001-08-22	BHGLAOC1910 05 ft 2001-08-22	BHGLAOC1910 10 ft 2001-08-22	BHGLAOC1911 05 ft 2001-12-05
SW8260B	Trans-1,3-Dichloropropene	mg/kg	NA	NA	NA	NA
SW8260B	Trans-1,4-Dichloro-2-Butene	mg/kg	NA	NA	NA	NA
SW8260B	Trichloroethene (TCE)	mg/kg	NA	NA	NA	NA
SW8260B	Trichlorofluoromethane	mg/kg	NA	NA	NA	NA
SW8260B	Vinyl acetate	mg/kg	NA	NA	NA	NA
SW8260B	Vinyl chloride	mg/kg	NA	NA	NA	NA
SW8270C	1,2,4,5-Tetrachlorobenzene	mg/kg	0.21 U	0.2 U	0.22 U	0.22 U
SW8270C	1,2,4-Trichlorobenzene	mg/kg	0.055 U	0.053 U	0.058 U	0.057 U
SW8270C	1,2-Dichlorobenzene	mg/kg	0.096 R	0.093 R	0.1 R	0.1 U
SW8270C	1,3,5-Trinitrobenzene	mg/kg	0.82 U	0.8 U	0.87 U	0.86 U
SW8270C	1,3-Dichlorobenzene	mg/kg	0.1 U	0.1 U	0.11 U	0.11 U
SW8270C	1,3-Dinitrobenzene	mg/kg	0.37 U	0.36 U	0.4 U	0.39 U
SW8270C	1,4-Dichlorobenzene	mg/kg	0.083 U	0.08 U	0.088 U	0.087 U
SW8270C	1,4-Dioxane (p-Dioxane)	mg/kg	0.9 U	0.87 U	0.95 U	0.94 U
SW8270C	1,4-Naphthoquinone	mg/kg	1.4 U	1.3 U	1.4 U	1.4 U
SW8270C	1-Naphthylamine	mg/kg	0.57 U	0.55 U	0.61 U	0.6 U
SW8270C	2,2'-Oxybis(1-chloropropane)	mg/kg	0.19 U	0.19 U	0.2 U	0.2 U
SW8270C	2,3,4,6-Tetrachlorophenol	mg/kg	0.31 U	0.3 U	0.33 U	0.33 U
SW8270C	2,4,5-Trichlorophenol	mg/kg	0.075 U	0.072 U	0.079 U	0.078 U
SW8270C	2,4,6-Trichlorophenol	mg/kg	0.076 U	0.073 U	0.081 U	0.08 U
SW8270C	2,4-Dichlorophenol	mg/kg	0.064 U	0.062 U	0.068 U	0.067 U
SW8270C	2,4-Dimethylphenol	mg/kg	0.25 U	0.24 U	0.26 U	0.26 U
SW8270C	2,4-Dinitrophenol	mg/kg	0.22 U	0.21 U	0.23 U	0.23 U
SW8270C	2,4-Dinitrotoluene	mg/kg	0.083 U	0.08 U	0.088 U	0.087 U
SW8270C	2,6-Dichlorophenol	mg/kg	0.24 U	0.24 U	0.26 U	0.25 U
SW8270C	2,6-Dinitrotoluene	mg/kg	0.087 U	0.084 U	0.092 U	0.091 U
SW8270C	2-Acetylaminofluorene	mg/kg	0.6 U	0.58 U	0.64 U	0.63 U
SW8270C	2-Aminonaphthalene (beta-Naphthylamine)	mg/kg	0.58 U	0.56 U	0.61 U	0.6 U
SW8270C	2-Chloronaphthalene	mg/kg	0.06 U	0.058 U	0.064 U	0.063 U
SW8270C	2-Chlorophenol	mg/kg	0.077 U	0.075 U	0.082 U	0.081 U
SW8270C	2-Methylnaphthalene	mg/kg	0.27 U	0.26 U	0.28 U	0.28 U
SW8270C	2-Methylphenol (o-Cresol)	mg/kg	0.14 U	0.13 U	0.15 U	0.14 U
SW8270C	2-Nitroaniline	mg/kg	0.12 U	0.12 U	0.13 U	0.13 U
SW8270C	2-Nitrophenol	mg/kg	0.086 U	0.083 U	0.091 U	0.09 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1910 00 ft 2001-08-22	BHGLAOC1910 05 ft 2001-08-22	BHGLAOC1910 10 ft 2001-08-22	BHGLAOC1911 05 ft 2001-12-05
SW8270C	2-Picoline (alpha-Picoline)	mg/kg	0.25 U	0.24 U	0.27 U	0.26 U
SW8270C	3,3'-Dichlorobenzidine	mg/kg	0.13 UJ	0.12 U	0.14 U	0.13 U
SW8270C	3,3'-Dimethylbenzidine	mg/kg	0.34 U	0.33 U	0.36 U	0.35 U
SW8270C	3-Methylcholanthrene	mg/kg	0.34 U	0.33 U	0.36 U	0.35 U
SW8270C	3-Nitroaniline	mg/kg	0.16 U	0.15 U	0.16 U	0.16 U
SW8270C	4,6-Dinitro-2-methylphenol	mg/kg	0.16 U	0.15 U	0.17 U	0.16 U
SW8270C	4-Aminobiphenyl (4-Biphenylamine)	mg/kg	0.32 U	0.31 U	0.34 U	0.33 U
SW8270C	4-Bromophenyl phenyl ether	mg/kg	0.1 U	0.099 U	0.11 U	0.11 U
SW8270C	4-Chloro-3-methylphenol	mg/kg	0.095 U	0.092 U	0.1 U	0.099 U
SW8270C	4-Chloroaniline	mg/kg	0.14 UJ	0.14 U	0.15 U	0.15 U
SW8270C	4-Chlorophenyl phenyl ether	mg/kg	0.097 U	0.094 U	0.1 U	0.1 U
SW8270C	4-Methylphenol (P-Cresol)	mg/kg	NA	NA	NA	0.14 U
SW8270C	4-Nitroaniline	mg/kg	0.15 U	0.15 U	0.16 U	0.16 U
SW8270C	4-Nitrophenol	mg/kg	0.41 UJ	0.4 U	0.43 U	0.43 U
SW8270C	4-Nitroquinoline-1-oxide	mg/kg	1.5 R	1.5 R	1.6 R	1.6 U
SW8270C	5-Nitro-o-toluidine	mg/kg	0.34 U	0.33 U	0.37 U	0.36 U
SW8270C	7,12-Dimethylbenzo(a)anthracene	mg/kg	0.52 U	0.5 U	0.55 U	0.54 U
SW8270C	Acenaphthene	mg/kg	0.059 U	0.057 U	0.063 U	0.13 F
SW8270C	Acenaphthylene	mg/kg	0.061 U	0.059 U	0.065 U	0.064 U
SW8270C	Acetophenone	mg/kg	0.31 U	0.3 U	0.33 U	0.33 U
SW8270C	alpha, alpha-Dimethylphenethylamine	mg/kg	1.6 U	1.6 U	1.7 U	1.7 U
SW8270C	Aniline (Phenylamine, Aminobenzene)	mg/kg	0.12 U	0.11 U	0.13 U	0.12 U
SW8270C	Anthracene	mg/kg	0.081 U	0.079 U	0.086 U	0.23 F
SW8270C	Aramite (total)	mg/kg	0.39 U	0.38 U	0.42 U	0.41 U
SW8270C	Benzo(a)anthracene	mg/kg	0.059 U	0.057 U	0.063 U	0.65
SW8270C	Benzo(a)pyrene	mg/kg	0.065 U	0.077 F	0.069 U	0.58 J
SW8270C	Benzo(b)fluoranthene	mg/kg	0.12 U	0.12 U	0.13 U	0.67
SW8270C	Benzo(g,h,i)perylene	mg/kg	0.17 U	0.16 U	0.18 U	0.3 F
SW8270C	Benzo(k)fluoranthene	mg/kg	0.13 R	0.12 R	0.14 R	0.47
SW8270C	Benzoic acid	mg/kg	0.19 R	0.18 R	0.2 R	0.2 U
SW8270C	Benzyl alcohol	mg/kg	0.11 U	0.11 U	0.12 U	0.12 U
SW8270C	Benzyl butyl phthalate	mg/kg	0.13 U	0.12 U	0.14 U	0.13 U
SW8270C	bis(2-Chloroethoxy)methane	mg/kg	0.066 U	0.064 U	0.07 U	0.069 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1910 00 ft 2001-08-22	BHGLAOC1910 05 ft 2001-08-22	BHGLAOC1910 10 ft 2001-08-22	BHGLAOC1911 05 ft 2001-12-05
SW8270C	bis(2-Chloroethyl)ether (2-Chloroethyl ether)	mg/kg	0.1 U	0.098 U	0.11 U	0.11 U
SW8270C	bis(2-Ethylhexyl)phthalate	mg/kg	0.13 U	0.12 U	0.13 U	0.13 U
SW8270C	Chlorobenzilate	mg/kg	0.26 U	0.25 U	0.27 U	0.27 U
SW8270C	Chrysene	mg/kg	0.045 U	0.043 U	0.047 U	0.74
SW8270C	Cresols, m & p	mg/kg	0.13 U	0.13 U	0.14 U	NA
SW8270C	Diallate (total of cis and trans isomers)	mg/kg	0.33 U	0.32 U	0.35 U	0.34 U
SW8270C	Dibenz(a,h)anthracene	mg/kg	0.12 U	0.12 U	0.13 U	0.13 U
SW8270C	Dibenzofuran	mg/kg	0.061 U	0.059 U	0.065 U	0.064 U
SW8270C	Diethyl phthalate	mg/kg	0.11 U	0.1 U	0.11 U	0.11 U
SW8270C	Dimethyl phthalate	mg/kg	0.084 U	0.081 U	0.089 U	0.088 U
SW8270C	Di-n-butyl phthalate	mg/kg	0.08 U	0.078 U	0.085 U	0.084 U
SW8270C	Di-n-octyl phthalate	mg/kg	0.3 U	0.29 U	0.32 U	0.31 U
SW8270C	Dnoseb	mg/kg	0.51 U	0.49 U	0.54 U	0.53 U
SW8270C	Diphenylamine	mg/kg	0.23 U	0.22 U	0.24 U	0.24 U
SW8270C	Ethyl methanesulfonate	mg/kg	0.37 U	0.35 U	0.39 U	0.38 U
SW8270C	Fluoranthene	mg/kg	0.1 U	0.1 U	0.11 U	2.1 J
SW8270C	Fluorene	mg/kg	0.11 U	0.11 U	0.12 U	0.27 F
SW8270C	Hexachlorobenzene	mg/kg	0.079 U	0.077 U	0.084 U	0.083 U
SW8270C	Hexachlorobutadiene	mg/kg	0.077 U	0.075 U	0.082 U	0.081 U
SW8270C	Hexachlorocyclopentadiene	mg/kg	0.14 U	0.13 U	0.14 U	0.14 U
SW8270C	Hexachloroethane	mg/kg	0.087 U	0.084 U	0.092 U	0.091 U
SW8270C	Hexachlorophene	mg/kg	1.5 U	1.4 U	1.5 U	1.5 U
SW8270C	Hexachloropropene	mg/kg	0.33 U	0.32 U	0.36 U	0.35 U
SW8270C	Indeno(1,2,3-c,d)pyrene	mg/kg	0.12 U	0.12 U	0.13 U	0.31 F
SW8270C	Isophorone	mg/kg	0.056 U	0.054 U	0.059 U	0.058 U
SW8270C	Isosafrole	mg/kg	0.24 U	0.23 U	0.25 U	0.25 U
SW8270C	Methapyrilene	mg/kg	1.7 U	1.6 U	1.8 U	1.7 U
SW8270C	Methyl methanesulfonate	mg/kg	0.37 U	0.36 U	0.39 U	0.39 U
SW8270C	Naphthalene	mg/kg	0.071 U	0.069 U	0.076 U	0.082 F
SW8270C	Nitrobenzene	mg/kg	0.07 U	0.068 U	0.075 U	0.074 U
SW8270C	N-Nitrosodiethylamine	mg/kg	0.38 U	0.36 U	0.4 U	0.39 U
SW8270C	N-Nitrosodimethylamine	mg/kg	0.12 U	0.12 U	0.13 U	0.13 U
SW8270C	N-Nitrosodi-n-butylamine	mg/kg	0.2 U	0.19 U	0.21 U	0.21 U
SW8270C	N-Nitrosodi-n-propylamine	mg/kg	0.11 U	0.11 U	0.12 U	0.12 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1910 00 ft 2001-08-22	BHGLAOC1910 05 ft 2001-08-22	BHGLAOC1910 10 ft 2001-08-22	BHGLAOC1911 05 ft 2001-12-05
SW8270C	N-Nitrosodiphenylamine	mg/kg	0.12 U	0.12 U	0.13 U	0.13 U
SW8270C	N-Nitrosomethylethylamine	mg/kg	0.58 U	0.56 U	0.62 U	0.61 U
SW8270C	N-Nitrosomorpholine	mg/kg	0.44 U	0.42 U	0.46 U	0.46 U
SW8270C	N-Nitrosopiperidine	mg/kg	0.29 U	0.28 U	0.31 U	0.31 U
SW8270C	N-Nitrosopyrrolidine	mg/kg	0.55 U	0.54 U	0.59 U	0.58 U
SW8270C	o-Toluidine	mg/kg	0.26 U	0.26 U	0.28 U	0.28 U
SW8270C	p-Dimethylaminoazobenzene	mg/kg	0.42 U	0.4 U	0.44 U	0.44 U
SW8270C	Pentachlorobenzene	mg/kg	0.19 U	0.18 U	0.2 U	0.2 U
SW8270C	Pentachloronitrobenzene	mg/kg	0.24 U	0.23 U	0.26 U	0.25 U
SW8270C	Pentachlorophenol	mg/kg	0.21 U	0.2 U	0.22 U	0.22 U
SW8270C	Phenacetin	mg/kg	0.43 U	0.42 U	0.46 U	0.45 U
SW8270C	Phenanthrene	mg/kg	0.077 U	0.075 U	0.082 U	1.6 J
SW8270C	Phenol	mg/kg	0.093 U	0.09 U	0.098 U	0.097 U
SW8270C	p-Phenylenediamine	mg/kg	0.9 U	0.87 U	0.95 U	0.94 U
SW8270C	Pronamide	mg/kg	0.46 U	0.44 U	0.48 U	0.48 U
SW8270C	Pyrene	mg/kg	0.16 U	0.15 U	0.17 U	1.3
SW8270C	Pyridine	mg/kg	0.11 U	0.11 U	0.12 U	0.12 U
SW8270C	Safrole	mg/kg	0.21 U	0.2 U	0.22 U	0.22 U

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1911 05 ft 2001-12-05 Dup	BHGLAOC1912 05 ft 2001-12-05	BHGLAOC1912 10 ft 2001-12-05	BHGLAOC1913 05 ft 2001-12-05
SW6010B	Arsenic	mg/kg	NA	NA	NA	NA
SW6010B	Barium	mg/kg	NA	NA	NA	NA
SW6010B	Beryllium	mg/kg	NA	NA	NA	NA
SW6010B	Cadmium	mg/kg	NA	NA	NA	NA
SW6010B	Chromium, total	mg/kg	NA	NA	NA	NA
SW6010B	Cobalt	mg/kg	NA	NA	NA	NA
SW6010B	Copper	mg/kg	NA	NA	NA	NA
SW6010B	Nickel	mg/kg	NA	NA	NA	NA
SW6010B	Tin	mg/kg	NA	NA	NA	NA
SW6010B	Vanadium	mg/kg	NA	NA	NA	NA
SW6010B	Zinc	mg/kg	NA	NA	NA	NA
SW7041	Antimony	mg/kg	NA	NA	NA	NA
SW7421	Lead	mg/kg	NA	NA	NA	NA
SW7471A	Mercury	mg/kg	NA	NA	NA	NA
SW7740	Selenium	mg/kg	NA	NA	NA	NA
SW7761	Silver	mg/kg	NA	NA	NA	NA
SW7841	Thallium	mg/kg	NA	NA	NA	NA
SW8260B	1,1,1,2-Tetrachloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1,1-Trichloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1,2,2-Tetrachloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1,2-Trichloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1-Dichloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,1-Dichloroethene	mg/kg	NA	NA	NA	NA
SW8260B	1,2,3-Trichloropropane	mg/kg	NA	NA	NA	NA
SW8260B	1,2-Dibromo-3-chloropropane	mg/kg	NA	NA	NA	NA
SW8260B	1,2-Dibromoethane (Ethylene dibromide)	mg/kg	NA	NA	NA	NA
SW8260B	1,2-Dichloroethane	mg/kg	NA	NA	NA	NA
SW8260B	1,2-Dichloropropane	mg/kg	NA	NA	NA	NA
SW8260B	2-Chloro-1,3-butadiene	mg/kg	NA	NA	NA	NA
SW8260B	2-Hexanone	mg/kg	NA	NA	NA	NA
SW8260B	Acetone	mg/kg	NA	NA	NA	NA
SW8260B	Acetonitrile	mg/kg	NA	NA	NA	NA
SW8260B	Acrolein	mg/kg	NA	NA	NA	NA
SW8260B	Acrylonitrile	mg/kg	NA	NA	NA	NA

724-250

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1911 05 ft 2001-12-05 Dup	BHGLAOC1912 05 ft 2001-12-05	BHGLAOC1912 10 ft 2001-12-05	BHGLAOC1913 05 ft 2001-12-05
SW8260B	Allyl chloride (3-Chloropropene)	mg/kg	NA	NA	NA	NA
SW8260B	Benzene	mg/kg	NA	NA	NA	NA
SW8260B	Bromodichloromethane	mg/kg	NA	NA	NA	NA
SW8260B	Bromoform	mg/kg	NA	NA	NA	NA
SW8260B	Bromomethane	mg/kg	NA	NA	NA	NA
SW8260B	Carbon disulfide	mg/kg	NA	NA	NA	NA
SW8260B	Carbon tetrachloride	mg/kg	NA	NA	NA	NA
SW8260B	Chlorobenzene	mg/kg	NA	NA	NA	NA
SW8260B	Chloroethane	mg/kg	NA	NA	NA	NA
SW8260B	Chloroform	mg/kg	NA	NA	NA	NA
SW8260B	Chloromethane	mg/kg	NA	NA	NA	NA
SW8260B	cis-1,2-Dichloroethene	mg/kg	NA	NA	NA	NA
SW8260B	cis-1,3-Dichloropropene	mg/kg	NA	NA	NA	NA
SW8260B	Dibromochloromethane	mg/kg	NA	NA	NA	NA
SW8260B	Dibromomethane	mg/kg	NA	NA	NA	NA
SW8260B	Dichlorodifluoromethane	mg/kg	NA	NA	NA	NA
SW8260B	Ethyl methacrylate	mg/kg	NA	NA	NA	NA
SW8260B	Ethylbenzene	mg/kg	NA	NA	NA	NA
SW8260B	Iodomethane (Methyl iodide)	mg/kg	NA	NA	NA	NA
SW8260B	Isobutanol	mg/kg	NA	NA	NA	NA
SW8260B	m,p-Xylene (sum of isomers)	mg/kg	NA	NA	NA	NA
SW8260B	Methyl ethyl ketone (2-Butanone)	mg/kg	NA	NA	NA	NA
SW8260B	Methyl isobutyl ketone (4-Methyl-2-pentanone)	mg/kg	NA	NA	NA	NA
SW8260B	Methyl methacrylate	mg/kg	NA	NA	NA	NA
SW8260B	Methylacrylonitrile	mg/kg	NA	NA	NA	NA
SW8260B	Methylene chloride	mg/kg	NA	NA	NA	NA
SW8260B	o-Xylene (1,2-Dimethylbenzene)	mg/kg	NA	NA	NA	NA
SW8260B	Pentachloroethane	mg/kg	NA	NA	NA	NA
SW8260B	Propane nitrile (Propionitrile)	mg/kg	NA	NA	NA	NA
SW8260B	Styrene	mg/kg	NA	NA	NA	NA
SW8260B	Tert-Butyl Methyl Ether	mg/kg	NA	NA	NA	NA
SW8260B	Tetrachloroethene (PCE)	mg/kg	NA	NA	NA	NA
SW8260B	Toluene	mg/kg	NA	NA	NA	NA
SW8260B	Trans-1,2-Dichloroethene	mg/kg	NA	NA	NA	NA



Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1911 05 ft 2001-12-05 Dup	BHGLAOC1912 05 ft 2001-12-05	BHGLAOC1912 10 ft 2001-12-05	BHGLAOC1913 05 ft 2001-12-05
SW8260B	Trans-1,3-Dichloropropene	mg/kg	NA	NA	NA	NA
SW8260B	Trans-1,4-Dichloro-2-Butene	mg/kg	NA	NA	NA	NA
SW8260B	Trichloroethene (TCE)	mg/kg	NA	NA	NA	0.051 J
SW8260B	Trichlorofluoromethane	mg/kg	NA	NA	NA	NA
SW8260B	Vinyl acetate	mg/kg	NA	NA	NA	NA
SW8260B	Vinyl chloride	mg/kg	NA	NA	NA	NA
SW8270C	1,2,4,5-Tetrachlorobenzene	mg/kg	0.22 U	0.22 U	0.21 U	NA
SW8270C	1,2,4-Trichlorobenzene	mg/kg	0.058 U	0.058 U	0.056 U	NA
SW8270C	1,2-Dichlorobenzene	mg/kg	0.1 U	0.1 U	0.099 U	NA
SW8270C	1,3,5-Trinitrobenzene	mg/kg	0.87 U	0.87 U	0.85 U	NA
SW8270C	1,3-Dichlorobenzene	mg/kg	0.11 U	0.11 U	0.11 U	NA
SW8270C	1,3-Dinitrobenzene	mg/kg	0.4 U	0.4 U	0.39 U	NA
SW8270C	1,4-Dichlorobenzene	mg/kg	0.087 U	0.088 U	0.085 U	NA
SW8270C	1,4-Dioxane (p-Dioxane)	mg/kg	0.95 U	0.96 U	0.92 U	NA
SW8270C	1,4-Naphthoquinone	mg/kg	1.4 U	1.4 U	1.4 U	NA
SW8270C	1-Naphthylamine	mg/kg	0.6 U	0.61 U	0.59 U	NA
SW8270C	2,2'-Oxybis(1-chloropropane)	mg/kg	0.2 U	0.2 U	0.2 U	NA
SW8270C	2,3,4,6-Tetrachlorophenol	mg/kg	0.33 U	0.33 U	0.32 U	NA
SW8270C	2,4,5-Trichlorophenol	mg/kg	0.079 U	0.079 U	0.077 U	NA
SW8270C	2,4,6-Trichlorophenol	mg/kg	0.08 U	0.081 U	0.078 U	NA
SW8270C	2,4-Dichlorophenol	mg/kg	0.067 U	0.068 U	0.065 U	NA
SW8270C	2,4-Dimethylphenol	mg/kg	0.26 U	0.26 U	0.26 U	NA
SW8270C	2,4-Dinitrophenol	mg/kg	0.23 U	0.23 U	0.23 U	NA
SW8270C	2,6-Dinitrophenol	mg/kg	0.087 U	0.088 U	0.085 U	NA
SW8270C	2,6-Dichlorophenol	mg/kg	0.26 U	0.26 U	0.25 U	NA
SW8270C	2,6-Dinitrotoluene	mg/kg	0.092 U	0.093 U	0.089 U	NA
SW8270C	2-Acetylamino-fluorene	mg/kg	0.63 U	0.64 U	0.62 U	NA
SW8270C	2-Aminonaphthalene (beta-Naphthylamine)	mg/kg	0.61 U	0.61 U	0.59 U	NA
SW8270C	2-Chloronaphthalene	mg/kg	0.064 U	0.064 U	0.062 U	NA
SW8270C	2-Chlorophenol	mg/kg	0.081 U	0.082 U	0.079 U	NA
SW8270C	2-Methylnaphthalene	mg/kg	0.28 U	0.28 U	0.27 U	NA
SW8270C	2-Methylphenol (o-Cresol)	mg/kg	0.15 U	0.15 U	0.14 U	NA
SW8270C	2-Nitroaniline	mg/kg	0.13 U	0.13 U	0.12 U	NA
SW8270C	2-Nitrophenol	mg/kg	0.091 U	0.091 U	0.088 U	NA

724 252

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1911 05 ft 2001-12-05 Dup	BHGLAOC1912 05 ft 2001-12-05	BHGLAOC1912 10 ft 2001-12-05	BHGLAOC1913 05 ft 2001-12-05
SW8270C	2-Picoline (alpha-Picoline)	mg/kg	0.26 U	0.27 U	0.26 U	NA
SW8270C	3,3'-Dichlorobenzidine	mg/kg	0.13 U	0.14 U	0.13 U	NA
SW8270C	3,3'-Dimethylbenzidine	mg/kg	0.36 U	0.36 U	0.35 U	NA
SW8270C	3-Methylcholanthrene	mg/kg	0.36 U	0.36 U	0.35 U	NA
SW8270C	3-Nitroaniline	mg/kg	0.16 U	0.16 U	0.16 U	NA
SW8270C	4,6-Dinitro-2-methylphenol	mg/kg	0.17 U	0.17 U	0.16 U	NA
SW8270C	4-Aminobiphenyl (4-Biphenylamine)	mg/kg	0.34 U	0.34 U	0.33 U	NA
SW8270C	4-Bromophenyl phenyl ether	mg/kg	0.11 U	0.11 U	0.11 U	NA
SW8270C	4-Chloro-3-methylphenol	mg/kg	0.1 U	0.1 U	0.097 U	NA
SW8270C	4-Chloroaniline	mg/kg	0.15 U	0.15 U	0.15 U	NA
SW8270C	4-Chlorophenyl phenyl ether	mg/kg	0.1 U	0.1 U	0.1 U	NA
SW8270C	4-Methylphenol (P-Cresol)	mg/kg	0.14 U	0.14 U	0.14 U	NA
SW8270C	4-Nitroaniline	mg/kg	0.16 U	0.16 U	0.15 U	NA
SW8270C	4-Nitrophenol	mg/kg	0.43 U	0.43 U	0.42 U	NA
SW8270C	4-Nitroquinoline-1-oxide	mg/kg	1.6 U	1.6 U	1.6 U	NA
SW8270C	5-Nitro-o-toluidine	mg/kg	0.36 U	0.37 U	0.35 U	NA
SW8270C	7,12-Dimethylbenzo(a)anthracene	mg/kg	0.55 U	0.55 U	0.53 U	NA
SW8270C	Acenaphthene	mg/kg	0.062 U	0.063 U	0.061 U	NA
SW8270C	Acenaphthylene	mg/kg	0.065 U	0.065 U	0.063 U	NA
SW8270C	Acetophenone	mg/kg	0.33 U	0.33 U	0.32 U	NA
SW8270C	alpha, alpha-Dimethylphenethylamine	mg/kg	1.7 U	1.7 U	1.7 U	NA
SW8270C	Aniline (Phenylamine, Aminobenzene)	mg/kg	0.12 U	0.13 U	0.12 U	NA
SW8270C	Anthracene	mg/kg	0.086 U	0.087 U	0.084 U	NA
SW8270C	Aramite (total)	mg/kg	0.41 U	0.42 U	0.4 U	NA
SW8270C	Benzo(a)anthracene	mg/kg	0.64	0.063 U	0.061 U	NA
SW8270C	Benzo(a)pyrene	mg/kg	0.82 J	0.069 U	0.067 U	NA
SW8270C	Benzo(b)fluoranthene	mg/kg	0.91	0.13 U	0.12 U	NA
SW8270C	Benzo(g,h,i)perylene	mg/kg	0.52 J	0.18 U	0.17 U	NA
SW8270C	Benzo(k)fluoranthene	mg/kg	0.62	0.14 U	0.13 U	NA
SW8270C	Benzoic acid	mg/kg	0.2 U	0.2 U	0.2 U	NA
SW8270C	Benzyl alcohol	mg/kg	0.12 U	0.12 U	0.12 U	NA
SW8270C	Benzyl butyl phthalate	mg/kg	0.14 U	0.14 U	0.13 U	NA
SW8270C	bis(2-Chloroethoxy)methane	mg/kg	0.069 U	0.07 U	0.068 U	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1911 05 ft 2001-12-05 Dup	BHGLAOC1912 05 ft 2001-12-05	BHGLAOC1912 10 ft 2001-12-05	BHGLAOC1913 05 ft 2001-12-05
SW8270C	bis(2-Chloroethyl)ether (2-Chloroethyl ether)	mg/kg	0.11 U	0.11 U	0.1 U	NA
SW8270C	bis(2-Ethylhexyl)phthalate	mg/kg	0.16 F	0.13 U	0.13 U	NA
SW8270C	Chlorobenzilate	mg/kg	0.27 U	0.27 U	0.26 U	NA
SW8270C	Chrysene	mg/kg	0.72	0.047 U	0.046 U	NA
SW8270C	Cresols, m & p	mg/kg	NA	NA	NA	NA
SW8270C	Diallate (total of cis and trans isomers)	mg/kg	0.34 U	0.35 U	0.33 U	NA
SW8270C	Dibenz(a,h)anthracene	mg/kg	0.17 F	0.13 U	0.13 U	NA
SW8270C	Dibenzofuran	mg/kg	0.065 U	0.065 U	0.063 U	NA
SW8270C	Diethyl phthalate	mg/kg	0.11 U	0.11 U	0.11 U	NA
SW8270C	Dimethyl phthalate	mg/kg	0.088 U	0.089 U	0.086 U	NA
SW8270C	Di-n-butyl phthalate	mg/kg	0.085 U	0.085 U	0.083 U	NA
SW8270C	Di-n-octyl phthalate	mg/kg	0.31 U	0.32 U	0.31 U	NA
SW8270C	Dinoseb	mg/kg	0.53 U	0.54 U	0.52 U	NA
SW8270C	Diphenylamine	mg/kg	0.24 U	0.24 U	0.23 U	NA
SW8270C	Ethyl methanesulfonate	mg/kg	0.39 U	0.39 U	0.38 U	NA
SW8270C	Fluoranthene	mg/kg	1.1	0.11 U	0.11 U	NA
SW8270C	Fluorene	mg/kg	0.17 F	0.12 U	0.11 U	NA
SW8270C	Hexachlorobenzene	mg/kg	0.084 U	0.084 U	0.081 U	NA
SW8270C	Hexachlorobutadiene	mg/kg	0.081 U	0.082 U	0.079 U	NA
SW8270C	Hexachlorocyclopentadiene	mg/kg	0.14 U	0.14 U	0.14 U	NA
SW8270C	Hexachloroethane	mg/kg	0.092 U	0.093 U	0.089 U	NA
SW8270C	Hexachlorophene	mg/kg	1.5 U	1.5 U	1.5 U	NA
SW8270C	Hexachloropropene	mg/kg	0.35 U	0.36 U	0.34 U	NA
SW8270C	Indeno(1,2,3-c,d)pyrene	mg/kg	0.5 J	0.13 U	0.13 U	NA
SW8270C	Isophorone	mg/kg	0.059 U	0.059 U	0.057 U	NA
SW8270C	Isosafrole	mg/kg	0.25 U	0.26 U	0.25 U	NA
SW8270C	Methapyrene	mg/kg	1.7 U	1.8 U	1.7 U	NA
SW8270C	Methyl methanesulfonate	mg/kg	0.39 U	0.4 U	0.38 U	NA
SW8270C	Naphthalene	mg/kg	0.075 U	0.076 U	0.073 U	NA
SW8270C	Nitrobenzene	mg/kg	0.074 U	0.075 U	0.072 U	NA
SW8270C	N-Nitrosodiethylamine	mg/kg	0.4 U	0.4 U	0.39 U	NA
SW8270C	N-Nitrosodimethylamine	mg/kg	0.13 U	0.13 U	0.13 U	NA
SW8270C	N-Nitrosodi-n-butylamine	mg/kg	0.21 U	0.21 U	0.2 U	NA
SW8270C	N-Nitrosodi-n-propylamine	mg/kg	0.12 U	0.12 U	0.12 U	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1911 05 ft 2001-12-05 Dup	BHGLAOC1912 05 ft 2001-12-05	BHGLAOC1912 10 ft 2001-12-05	BHGLAOC1913 05 ft 2001-12-05
SW8270C	N-Nitrosodiphenylamine	mg/kg	0.13 U	0.13 U	0.12 U	NA
SW8270C	N-Nitrosomethylethylamine	mg/kg	0.61 U	0.62 U	0.6 U	NA
SW8270C	N-Nitrosomorpholine	mg/kg	0.46 U	0.47 U	0.45 U	NA
SW8270C	N-Nitrosopiperidine	mg/kg	0.31 U	0.31 U	0.3 U	NA
SW8270C	N-Nitrosopyrrolidine	mg/kg	0.58 U	0.59 U	0.57 U	NA
SW8270C	o-Toluidine	mg/kg	0.28 U	0.28 U	0.27 U	NA
SW8270C	p-Dimethylaminoazobenzene	mg/kg	0.44 U	0.44 U	0.43 U	NA
SW8270C	Pentachlorobenzene	mg/kg	0.2 U	0.2 U	0.19 U	NA
SW8270C	Pentachloronitrobenzene	mg/kg	0.25 U	0.26 U	0.25 U	NA
SW8270C	Pentachlorophenol	mg/kg	0.22 U	0.22 U	0.21 U	NA
SW8270C	Phenacetin	mg/kg	0.46 U	0.46 U	0.45 U	NA
SW8270C	Phenanthrene	mg/kg	0.55 J	0.082 U	0.079 U	NA
SW8270C	Phenol	mg/kg	0.098 U	0.098 U	0.095 U	NA
SW8270C	p-Phenylenediamine	mg/kg	0.95 U	0.95 U	0.92 U	NA
SW8270C	Pronamide	mg/kg	0.48 U	0.48 U	0.47 U	NA
SW8270C	Pyrene	mg/kg	1.2	0.17 U	0.16 U	NA
SW8270C	Pyridine	mg/kg	0.12 U	0.12 U	0.12 U	NA
SW8270C	Safrole	mg/kg	0.22 U	0.22 U	0.21 U	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1913 10 ft 2001-12-05	THGLAOC1905 03 ft 2001-08-15	WHGLTA050 00 ft 2001-02-07	WHGLTA050 05 ft 2001-02-07
SW6010B	Arsenic	mg/kg	NA	3.5 F	NA	NA
SW6010B	Barium	mg/kg	NA	61.2	NA	NA
SW6010B	Beryllium	mg/kg	NA	0.28	NA	NA
SW6010B	Cadmium	mg/kg	NA	0.28 F	NA	NA
SW6010B	Chromium, total	mg/kg	NA	7.2 F	NA	NA
SW6010B	Cobalt	mg/kg	NA	2.4 F	NA	NA
SW6010B	Copper	mg/kg	NA	3.3 F	NA	NA
SW6010B	Nickel	mg/kg	NA	4.3 F	NA	NA
SW6010B	Tin	mg/kg	NA	1.1 F	NA	NA
SW6010B	Vanadium	mg/kg	NA	15 F	NA	NA
SW6010B	Zinc	mg/kg	NA	17 F	NA	NA
SW7041	Antimony	mg/kg	NA	0.18 U	NA	NA
SW7421	Lead	mg/kg	NA	7.9	NA	NA
SW7471A	Mercury	mg/kg	NA	0.0092 F	NA	NA
SW7740	Selenium	mg/kg	NA	0.76 UJ	NA	NA
SW7761	Silver	mg/kg	NA	0.064 UJ	NA	NA
SW7841	Thallium	mg/kg	NA	0.18 UJ	NA	NA
SW8260B	1,1,1,2-Tetrachloroethane	mg/kg	NA	0.0008 U	NA	NA
SW8260B	1,1,1-Trichloroethane	mg/kg	NA	0.0007 U	NA	NA
SW8260B	1,1,2,2-Tetrachloroethane	mg/kg	NA	0.0007 U	NA	NA
SW8260B	1,1,2-Trichloroethane	mg/kg	NA	0.0008 U	NA	NA
SW8260B	1,1-Dichloroethane	mg/kg	NA	0.001 U	NA	NA
SW8260B	1,1-Dichloroethene	mg/kg	NA	0.001 U	NA	NA
SW8260B	1,2,3-Trichloropropane	mg/kg	NA	0.001 U	NA	NA
SW8260B	1,2-Dibromo-3-chloropropane	mg/kg	NA	0.001 R	NA	NA
SW8260B	1,2-Dibromoethane (Ethylene dibromide)	mg/kg	NA	0.0008 U	NA	NA
SW8260B	1,2-Dichloroethane	mg/kg	NA	0.0006 U	NA	NA
SW8260B	1,2-Dichloropropane	mg/kg	NA	0.001 U	NA	NA
SW8260B	2-Chloro-1,3-butadiene	mg/kg	NA	0.0007 U	NA	NA
SW8260B	2-Hexanone	mg/kg	NA	0.002 U	NA	NA
SW8260B	Acetone	mg/kg	NA	0.004 R	NA	NA
SW8260B	Acetonitrile	mg/kg	NA	0.028 U	NA	NA
SW8260B	Acrolein	mg/kg	NA	0.042 U	NA	NA
SW8260B	Acrylonitrile	mg/kg	NA	0.008 U	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1913 10 ft 2001-12-05	THGLAOC1905 03 ft 2001-08-15	WHGLTA050 00 ft 2001-02-07	WHGLTA050 05 ft 2001-02-07
SW8260B	Allyl chloride (3-Chloropropene)	mg/kg	NA	0.002 U	NA	NA
SW8260B	Benzene	mg/kg	NA	0.0007 U	NA	NA
SW8260B	Bromodichloromethane	mg/kg	NA	0.0007 U	NA	NA
SW8260B	Bromoform	mg/kg	NA	0.001 U	NA	NA
SW8260B	Bromomethane	mg/kg	NA	0.003 R	NA	NA
SW8260B	Carbon disulfide	mg/kg	NA	0.002 U	NA	NA
SW8260B	Carbon tetrachloride	mg/kg	NA	0.0009 U	NA	NA
SW8260B	Chlorobenzene	mg/kg	NA	0.001 U	NA	NA
SW8260B	Chloroethane	mg/kg	NA	0.002 U	NA	NA
SW8260B	Chloroform	mg/kg	NA	0.0007 U	NA	NA
SW8260B	Chloromethane	mg/kg	NA	0.001 U	NA	NA
SW8260B	cis-1,2-Dichloroethene	mg/kg	NA	0.001 U	NA	NA
SW8260B	cis-1,3-Dichloropropene	mg/kg	NA	0.0009 U	NA	NA
SW8260B	Dibromochloromethane	mg/kg	NA	0.0008 U	NA	NA
SW8260B	Dibromomethane	mg/kg	NA	0.0008 U	NA	NA
SW8260B	Dichlorodifluoromethane	mg/kg	NA	0.0008 U	NA	NA
SW8260B	Ethyl methacrylate	mg/kg	NA	0.002 U	NA	NA
SW8260B	Ethylbenzene	mg/kg	NA	0.001 U	NA	NA
SW8260B	Iodomethane (Methyl iodide)	mg/kg	NA	0.004 R	NA	NA
SW8260B	Isobutanol	mg/kg	NA	0.092 U	NA	NA
SW8260B	m,p-Xylene (sum of isomers)	mg/kg	NA	0.002 U	NA	NA
SW8260B	Methyl ethyl ketone (2-Butanone)	mg/kg	NA	0.005 U	NA	NA
SW8260B	Methyl isobutyl ketone (4-Methyl-2-pentanone)	mg/kg	NA	0.003 U	NA	NA
SW8260B	Methyl methacrylate	mg/kg	NA	0.002 U	NA	NA
SW8260B	Methylacrylonitrile	mg/kg	NA	0.005 U	NA	NA
SW8260B	Methylene chloride	mg/kg	NA	0.002 U	NA	NA
SW8260B	o-Xylene (1,2-Dimethylbenzene)	mg/kg	NA	0.001 U	NA	NA
SW8260B	Pentachloroethane	mg/kg	NA	0.006 U	NA	NA
SW8260B	Propane nitrile (Propionitrile)	mg/kg	NA	0.021 U	NA	NA
SW8260B	Styrene	mg/kg	NA	0.001 U	NA	NA
SW8260B	Tert-Butyl Methyl Ether	mg/kg	NA	0.0007 U	NA	NA
SW8260B	Tetrachloroethene (PCE)	mg/kg	NA	0.0007 U	NA	NA
SW8260B	Toluene	mg/kg	NA	0.001 U	NA	NA
SW8260B	Trans-1,2-Dichloroethene	mg/kg	NA	0.001 U	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1913 10 ft 2001-12-05	THGLAOC1905 03 ft 2001-08-15	WHGLTA050 00 ft 2001-02-07	WHGLTA050 05 ft 2001-02-07
SW8260B	Trans-1,3-Dichloropropene	mg/kg	NA	0.0009 U	NA	NA
SW8260B	Trans-1,4-Dichloro-2-Butene	mg/kg	NA	0.002 U	NA	NA
SW8260B	Trichloroethene (TCE)	mg/kg	0.036	0.0006 U	0.006 U	0.002 F
SW8260B	Trichlorofluoromethane	mg/kg	NA	0.0008 U	NA	NA
SW8260B	Vinyl acetate	mg/kg	NA	0.0006 U	NA	NA
SW8260B	Vinyl chloride	mg/kg	NA	0.0008 U	NA	NA
SW8270C	1,2,4,5-Tetrachlorobenzene	mg/kg	NA	0.19 U	NA	NA
SW8270C	1,2,4-Trichlorobenzene	mg/kg	NA	0.051 U	NA	NA
SW8270C	1,2-Dichlorobenzene	mg/kg	NA	0.09 U	NA	NA
SW8270C	1,3,5-Trinitrobenzene	mg/kg	NA	0.77 U	NA	NA
SW8270C	1,3-Dichlorobenzene	mg/kg	NA	0.097 U	NA	NA
SW8270C	1,3-Dinitrobenzene	mg/kg	NA	0.35 U	NA	NA
SW8270C	1,4-Dichlorobenzene	mg/kg	NA	0.077 U	NA	NA
SW8270C	1,4-Dioxane (p-Dioxane)	mg/kg	NA	0.84 U	NA	NA
SW8270C	1,4-Naphthoquinone	mg/kg	NA	1.3 U	NA	NA
SW8270C	1-Naphthylamine	mg/kg	NA	0.53 U	NA	NA
SW8270C	2,2'-Oxybis(1-chloropropane)	mg/kg	NA	0.18 U	NA	NA
SW8270C	2,3,4,6-Tetrachlorophenol	mg/kg	NA	0.29 U	NA	NA
SW8270C	2,4,5-Trichlorophenol	mg/kg	NA	0.07 U	NA	NA
SW8270C	2,4,6-Trichlorophenol	mg/kg	NA	0.071 U	NA	NA
SW8270C	2,4-Dichlorophenol	mg/kg	NA	0.059 U	NA	NA
SW8270C	2,4-Dimethylphenol	mg/kg	NA	0.23 U	NA	NA
SW8270C	2,4-Dinitrophenol	mg/kg	NA	0.21 U	NA	NA
SW8270C	2,4-Dinitrotoluene	mg/kg	NA	0.077 U	NA	NA
SW8270C	2,6-Dichlorophenol	mg/kg	NA	0.23 U	NA	NA
SW8270C	2,6-Dinitrotoluene	mg/kg	NA	0.081 U	NA	NA
SW8270C	2-Acetylaminofluorene	mg/kg	NA	0.56 U	NA	NA
SW8270C	2-Aminonaphthalene (beta-Naphthylamine)	mg/kg	NA	0.54 U	NA	NA
SW8270C	2-Chloronaphthalene	mg/kg	NA	0.056 U	NA	NA
SW8270C	2-Chlorophenol	mg/kg	NA	0.072 U	NA	NA
SW8270C	2-Methylnaphthalene	mg/kg	NA	0.25 U	NA	NA
SW8270C	2-Methylphenol (o-Cresol)	mg/kg	NA	0.13 U	NA	NA
SW8270C	2-Nitroaniline	mg/kg	NA	0.11 U	NA	NA
SW8270C	2-Nitrophenol	mg/kg	NA	0.08 U	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1913 10 ft 2001-12-05	THGLAOC1905 03 ft. 2001-08-15	WHGLTA050 00 ft 2001-02-07	WHGLTA050 05 ft 2001-02-07
SW8270C	2-Picoline (alpha-Picoline)	mg/kg	NA	0.23 U	NA	NA
SW8270C	3,3'-Dichlorobenzidine	mg/kg	NA	0.12 U	NA	NA
SW8270C	3,3'-Dimethylbenzidine	mg/kg	NA	0.32 U	NA	NA
SW8270C	3-Methylcholanthrene	mg/kg	NA	0.32 U	NA	NA
SW8270C	3-Nitroaniline	mg/kg	NA	0.14 U	NA	NA
SW8270C	4,6-Dinitro-2-methylphenol	mg/kg	NA	0.15 U	NA	NA
SW8270C	4-Aminobiphenyl (4-Biphenylamine)	mg/kg	NA	0.3 U	NA	NA
SW8270C	4-Bromophenyl phenyl ether	mg/kg	NA	0.096 U	NA	NA
SW8270C	4-Chloro-3-methylphenol	mg/kg	NA	0.089 U	NA	NA
SW8270C	4-Chloroaniline	mg/kg	NA	0.13 U	NA	NA
SW8270C	4-Chlorophenyl phenyl ether	mg/kg	NA	0.091 U	NA	NA
SW8270C	4-Methylphenol (P-Cresol)	mg/kg	NA	0.12 U	NA	NA
SW8270C	4-Nitroaniline	mg/kg	NA	0.14 U	NA	NA
SW8270C	4-Nitrophenol	mg/kg	NA	0.38 U	NA	NA
SW8270C	4-Nitroquinoline-1-oxide	mg/kg	NA	1.4 U	NA	NA
SW8270C	5-Nitro-o-toluidine	mg/kg	NA	0.32 U	NA	NA
SW8270C	7,12-Dimethylbenzo(a)anthracene	mg/kg	NA	0.48 U	NA	NA
SW8270C	Acenaphthene	mg/kg	NA	0.17 F	NA	NA
SW8270C	Acenaphthylene	mg/kg	NA	0.057 U	NA	NA
SW8270C	Acetophenone	mg/kg	NA	0.29 U	NA	NA
SW8270C	alpha, alpha-Dimethylphenethylamine	mg/kg	NA	1.5 U	NA	NA
SW8270C	Aniline (Phenylamine, Aminobenzene)	mg/kg	NA	0.11 U	NA	NA
SW8270C	Anthracene	mg/kg	NA	0.38	NA	NA
SW8270C	Aramite (total)	mg/kg	NA	0.37 U	NA	NA
SW8270C	Benzo(a)anthracene	mg/kg	NA	2	NA	NA
SW8270C	Benzo(a)pyrene	mg/kg	NA	1.8	NA	NA
SW8270C	Benzo(b)fluoranthene	mg/kg	NA	2.2	NA	NA
SW8270C	Benzo(g,h,i)perylene	mg/kg	NA	1.3	NA	NA
SW8270C	Benzo(k)fluoranthene	mg/kg	NA	1.4	NA	NA
SW8270C	Benzoic acid	mg/kg	NA	0.18 U	NA	NA
SW8270C	Benzyl alcohol	mg/kg	NA	0.11 U	NA	NA
SW8270C	Benzyl butyl phthalate	mg/kg	NA	0.12 U	NA	NA
SW8270C	bis(2-Chloroethoxy)methane	mg/kg	NA	0.061 U	NA	NA



Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1913 10 ft 2001-12-05	THGLAOC1905 03 ft 2001-08-15	WHGLTA050 00 ft 2001-02-07	WHGLTA050 05 ft 2001-02-07
SW8270C	bis(2-Chloroethyl)ether (2-Chloroethyl ether)	mg/kg	NA	0.095 U	NA	NA
SW8270C	bis(2-Ethylhexyl)phthalate	mg/kg	NA	0.66	NA	NA
SW8270C	Chlorobenzilate	mg/kg	NA	0.24 U	NA	NA
SW8270C	Chrysene	mg/kg	NA	2	NA	NA
SW8270C	Cresols, m & p	mg/kg	NA	NA	NA	NA
SW8270C	Diallate (total of cis and trans isomers)	mg/kg	NA	0.3 U	NA	NA
SW8270C	Dibenz(a,h)anthracene	mg/kg	NA	0.43	NA	NA
SW8270C	Dibenzofuran	mg/kg	NA	0.077 F	NA	NA
SW8270C	Diethyl phthalate	mg/kg	NA	0.099 U	NA	NA
SW8270C	Dimethyl phthalate	mg/kg	NA	0.078 U	NA	NA
SW8270C	Di-n-butyl phthalate	mg/kg	NA	0.075 U	NA	NA
SW8270C	Di-n-octyl phthalate	mg/kg	NA	0.28 U	NA	NA
SW8270C	Dinoseb	mg/kg	NA	0.47 U	NA	NA
SW8270C	Diphenylamine	mg/kg	NA	0.21 U	NA	NA
SW8270C	Ethyl methanesulfonate	mg/kg	NA	0.34 U	NA	NA
SW8270C	Fluoranthene	mg/kg	NA	3.5	NA	NA
SW8270C	Fluorene	mg/kg	NA	0.14 F	NA	NA
SW8270C	Hexachlorobenzene	mg/kg	NA	0.074 U	NA	NA
SW8270C	Hexachlorobutadiene	mg/kg	NA	0.072 U	NA	NA
SW8270C	Hexachlorocyclopentadiene	mg/kg	NA	0.13 U	NA	NA
SW8270C	Hexachloroethane	mg/kg	NA	0.081 U	NA	NA
SW8270C	Hexachlorophene	mg/kg	NA	1.4 U	NA	NA
SW8270C	Hexachloropropene	mg/kg	NA	0.31 U	NA	NA
SW8270C	Indeno(1,2,3-c,d)pyrene	mg/kg	NA	1.1	NA	NA
SW8270C	Isophorone	mg/kg	NA	0.052 U	NA	NA
SW8270C	Isosafrole	mg/kg	NA	0.22 U	NA	NA
SW8270C	Methapyrilene	mg/kg	NA	1.5 U	NA	NA
SW8270C	Methyl methanesulfonate	mg/kg	NA	0.35 U	NA	NA
SW8270C	Naphthalene	mg/kg	NA	0.067 U	NA	NA
SW8270C	Nitrobenzene	mg/kg	NA	0.066 U	NA	NA
SW8270C	N-Nitrosodiethylamine	mg/kg	NA	0.35 U	NA	NA
SW8270C	N-Nitrosodimethylamine	mg/kg	NA	0.11 U	NA	NA
SW8270C	N-Nitrosodi-n-butylamine	mg/kg	NA	0.18 U	NA	NA
SW8270C	N-Nitrosodi-n-propylamine	mg/kg	NA	0.11 U	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	BHGLAOC1913 10 ft 2001-12-05	THGLAOC1905 03 ft 2001-08-15	WHGLTA050 00 ft 2001-02-07	WHGLTA050 05 ft 2001-02-07
SW8270C	N-Nitrosodiphenylamine	mg/kg	NA	0.11 U	NA	NA
SW8270C	N-Nitrosomethylethylamine	mg/kg	NA	0.54 U	NA	NA
SW8270C	N-Nitrosomorpholine	mg/kg	NA	0.41 U	NA	NA
SW8270C	N-Nitrosopiperidine	mg/kg	NA	0.27 U	NA	NA
SW8270C	N-Nitrosopyrrolidine	mg/kg	NA	0.52 U	NA	NA
SW8270C	o-Toluidine	mg/kg	NA	0.25 U	NA	NA
SW8270C	p-Dimethylaminoazobenzene	mg/kg	NA	0.39 U	NA	NA
SW8270C	Pentachlorobenzene	mg/kg	NA	0.18 U	NA	NA
SW8270C	Pentachloronitrobenzene	mg/kg	NA	0.23 U	NA	NA
SW8270C	Pentachlorophenol	mg/kg	NA	0.19 U	NA	NA
SW8270C	Phenacetin	mg/kg	NA	0.41 U	NA	NA
SW8270C	Phenanthrene	mg/kg	NA	2.1	NA	NA
SW8270C	Phenol	mg/kg	NA	0.086 U	NA	NA
SW8270C	p-Phenylenediamine	mg/kg	NA	0.84 U	NA	NA
SW8270C	Pronamide	mg/kg	NA	0.43 U	NA	NA
SW8270C	Pyrene	mg/kg	NA	3.6	NA	NA
SW8270C	Pyridine	mg/kg	NA	0.11 U	NA	NA
SW8270C	Safrole	mg/kg	NA	0.19 U	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	WHGLTA051 00 ft 2001-02-07	WHGLTA051 05 ft 2001-02-07	WHGLTA052 05 ft 2001-02-07
SW6010B	Arsenic	mg/kg	NA	NA	NA
SW6010B	Barium	mg/kg	NA	NA	NA
SW6010B	Beryllium	mg/kg	NA	NA	NA
SW6010B	Cadmium	mg/kg	NA	NA	NA
SW6010B	Chromium, total	mg/kg	NA	NA	NA
SW6010B	Cobalt	mg/kg	NA	NA	NA
SW6010B	Copper	mg/kg	NA	NA	NA
SW6010B	Nickel	mg/kg	NA	NA	NA
SW6010B	Tin	mg/kg	NA	NA	NA
SW6010B	Vanadium	mg/kg	NA	NA	NA
SW6010B	Zinc	mg/kg	NA	NA	NA
SW7041	Antimony	mg/kg	NA	NA	NA
SW7421	Lead	mg/kg	NA	NA	NA
SW7471A	Mercury	mg/kg	NA	NA	NA
SW7740	Selenium	mg/kg	NA	NA	NA
SW7761	Silver	mg/kg	NA	NA	NA
SW7841	Thallium	mg/kg	NA	NA	NA
SW8260B	1,1,1,2-Tetrachloroethane	mg/kg	NA	NA	NA
SW8260B	1,1,1-Trichloroethane	mg/kg	NA	NA	NA
SW8260B	1,1,2,2-Tetrachloroethane	mg/kg	NA	NA	NA
SW8260B	1,1,2-Trichloroethane	mg/kg	NA	NA	NA
SW8260B	1,1-Dichloroethane	mg/kg	NA	NA	NA
SW8260B	1,1-Dichloroethene	mg/kg	NA	NA	NA
SW8260B	1,2,3-Trichloropropane	mg/kg	NA	NA	NA
SW8260B	1,2-Dibromo-3-chloropropane	mg/kg	NA	NA	NA
SW8260B	1,2-Dibromoethane (Ethylene dibromide)	mg/kg	NA	NA	NA
SW8260B	1,2-Dichloroethane	mg/kg	NA	NA	NA
SW8260B	1,2-Dichloropropane	mg/kg	NA	NA	NA
SW8260B	2-Chloro-1,3-butadiene	mg/kg	NA	NA	NA
SW8260B	2-Hexanone	mg/kg	NA	NA	NA
SW8260B	Acetone	mg/kg	NA	NA	NA
SW8260B	Acetonitrile	mg/kg	NA	NA	NA
SW8260B	Acrolein	mg/kg	NA	NA	NA
SW8260B	Acrylonitrile	mg/kg	NA	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	WHGLTA051 00 ft 2001-02-07	WHGLTA051 05 ft 2001-02-07	WHGLTA052 05 ft 2001-02-07
SW8260B	Allyl chloride (3-Chloropropene)	mg/kg	NA	NA	NA
SW8260B	Benzene	mg/kg	NA	NA	NA
SW8260B	Bromodichloromethane	mg/kg	NA	NA	NA
SW8260B	Bromoform	mg/kg	NA	NA	NA
SW8260B	Bromomethane	mg/kg	NA	NA	NA
SW8260B	Carbon disulfide	mg/kg	NA	NA	NA
SW8260B	Carbon tetrachloride	mg/kg	NA	NA	NA
SW8260B	Chlorobenzene	mg/kg	NA	NA	NA
SW8260B	Chloroethane	mg/kg	NA	NA	NA
SW8260B	Chloroform	mg/kg	NA	NA	NA
SW8260B	Chloromethane	mg/kg	NA	NA	NA
SW8260B	cis-1,2-Dichloroethene	mg/kg	NA	NA	NA
SW8260B	cis-1,3-Dichloropropene	mg/kg	NA	NA	NA
SW8260B	Dibromochloromethane	mg/kg	NA	NA	NA
SW8260B	Dibromomethane	mg/kg	NA	NA	NA
SW8260B	Dichlorodifluoromethane	mg/kg	NA	NA	NA
SW8260B	Ethyl methacrylate	mg/kg	NA	NA	NA
SW8260B	Ethylbenzene	mg/kg	NA	NA	NA
SW8260B	Iodomethane (Methyl iodide)	mg/kg	NA	NA	NA
SW8260B	Isobutanol	mg/kg	NA	NA	NA
SW8260B	m,p-Xylene (sum of isomers)	mg/kg	NA	NA	NA
SW8260B	Methyl ethyl ketone (2-Butanone)	mg/kg	NA	NA	NA
SW8260B	Methyl isobutyl ketone (4-Methyl-2-pentanone)	mg/kg	NA	NA	NA
SW8260B	Methyl methacrylate	mg/kg	NA	NA	NA
SW8260B	Methylacrylonitrile	mg/kg	NA	NA	NA
SW8260B	Methylene chloride	mg/kg	NA	NA	NA
SW8260B	o-Xylene (1,2-Dimethylbenzene)	mg/kg	NA	NA	NA
SW8260B	Perchloroethane	mg/kg	NA	NA	NA
SW8260B	Propane nitrile (Propionitrile)	mg/kg	NA	NA	NA
SW8260B	Styrene	mg/kg	NA	NA	NA
SW8260B	Tert-Butyl Methyl Ether	mg/kg	NA	NA	NA
SW8260B	Tetrachloroethene (PCE)	mg/kg	NA	NA	NA
SW8260B	Toluene	mg/kg	NA	NA	NA
SW8260B	Trans-1,2-Dichloroethene	mg/kg	NA	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	WHGLTA051 00 ft 2001-02-07	WHGLTA051 05 ft 2001-02-07	WHGLTA052 05 ft 2001-02-07
SW8260B	Trans-1,3-Dichloropropene	mg/kg	NA	NA	NA
SW8260B	Trans-1,4-Dichloro-2-Butene	mg/kg	NA	NA	NA
SW8260B	Trichloroethene (TCE)	mg/kg	0.004 U	0.001 F	0.004 U
SW8260B	Trichlorofluoromethane	mg/kg	NA	NA	NA
SW8260B	Vinyl acetate	mg/kg	NA	NA	NA
SW8260B	Vinyl chloride	mg/kg	NA	NA	NA
SW8270C	1,2,4,5-Tetrachlorobenzene	mg/kg	NA	NA	NA
SW8270C	1,2,4-Trichlorobenzene	mg/kg	NA	NA	NA
SW8270C	1,2-Dichlorobenzene	mg/kg	NA	NA	NA
SW8270C	1,3,5-Trinitrobenzene	mg/kg	NA	NA	NA
SW8270C	1,3-Dichlorobenzene	mg/kg	NA	NA	NA
SW8270C	1,3-Dinitrobenzene	mg/kg	NA	NA	NA
SW8270C	1,4-Dichlorobenzene	mg/kg	NA	NA	NA
SW8270C	1,4-Dioxane (p-Dioxane)	mg/kg	NA	NA	NA
SW8270C	1,4-Naphthoquinone	mg/kg	NA	NA	NA
SW8270C	1-Naphthylamine	mg/kg	NA	NA	NA
SW8270C	2,2'-Oxybis(1-chloropropane)	mg/kg	NA	NA	NA
SW8270C	2,3,4,6-Tetrachlorophenol	mg/kg	NA	NA	NA
SW8270C	2,4,5-Trichlorophenol	mg/kg	NA	NA	NA
SW8270C	2,4,6-Trichlorophenol	mg/kg	NA	NA	NA
SW8270C	2,4-Dichlorophenol	mg/kg	NA	NA	NA
SW8270C	2,4-Dimethylphenol	mg/kg	NA	NA	NA
SW8270C	2,4-Dinitrophenol	mg/kg	NA	NA	NA
SW8270C	2,4-Dinitrotoluene	mg/kg	NA	NA	NA
SW8270C	2,6-Dichlorophenol	mg/kg	NA	NA	NA
SW8270C	2,6-Dinitrotoluene	mg/kg	NA	NA	NA
SW8270C	2-Acetylaminofluorene	mg/kg	NA	NA	NA
SW8270C	2-Aminonaphthalene (beta-Naphthylamine)	mg/kg	NA	NA	NA
SW8270C	2-Chloronaphthalene	mg/kg	NA	NA	NA
SW8270C	2-Chlorophenol	mg/kg	NA	NA	NA
SW8270C	2-Methylnaphthalene	mg/kg	NA	NA	NA
SW8270C	2-Methylphenol (o-Cresol)	mg/kg	NA	NA	NA
SW8270C	2-Nitroaniline	mg/kg	NA	NA	NA
SW8270C	2-Nitrophenol	mg/kg	NA	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	WHGLTA051 00 ft 2001-02-07	WHGLTA051 05 ft 2001-02-07	WHGLTA052 05 ft 2001-02-07
SW8270C	2-Picoline (alpha-Picoline)	mg/kg	NA	NA	NA
SW8270C	3,3'-Dichlorobenzidine	mg/kg	NA	NA	NA
SW8270C	3,3'-Dimethylbenzidine	mg/kg	NA	NA	NA
SW8270C	3-Methylcholanthrene	mg/kg	NA	NA	NA
SW8270C	3-Nitroaniline	mg/kg	NA	NA	NA
SW8270C	4,6-Dinitro-2-methylphenol	mg/kg	NA	NA	NA
SW8270C	4-Aminobiphenyl (4-Biphenylamine)	mg/kg	NA	NA	NA
SW8270C	4-Bromophenyl phenyl ether	mg/kg	NA	NA	NA
SW8270C	4-Chloro-3-methylphenol	mg/kg	NA	NA	NA
SW8270C	4-Chloroaniline	mg/kg	NA	NA	NA
SW8270C	4-Chlorophenyl phenyl ether	mg/kg	NA	NA	NA
SW8270C	4-Methylphenol (P-Cresol)	mg/kg	NA	NA	NA
SW8270C	4-Nitroaniline	mg/kg	NA	NA	NA
SW8270C	4-Nitrophenol	mg/kg	NA	NA	NA
SW8270C	4-Nitroquinoline-1-oxide	mg/kg	NA	NA	NA
SW8270C	5-Nitro-o-toluidine	mg/kg	NA	NA	NA
SW8270C	7,12-Dimethylbenzo(a)anthracene	mg/kg	NA	NA	NA
SW8270C	Acenaphthene	mg/kg	NA	NA	NA
SW8270C	Acenaphthylene	mg/kg	NA	NA	NA
SW8270C	Acetophenone	mg/kg	NA	NA	NA
SW8270C	alpha, alpha-Dimethylphenethylamine	mg/kg	NA	NA	NA
SW8270C	Aniline (Phenylamine, Aminobenzene)	mg/kg	NA	NA	NA
SW8270C	Anthracene	mg/kg	NA	NA	NA
SW8270C	Aramite (total)	mg/kg	NA	NA	NA
SW8270C	Benzo(a)anthracene	mg/kg	NA	NA	NA
SW8270C	Benzo(a)pyrene	mg/kg	NA	NA	NA
SW8270C	Benzo(b)fluoranthene	mg/kg	NA	NA	NA
SW8270C	Benzo(g,h,i)perylene	mg/kg	NA	NA	NA
SW8270C	Benzo(k)fluoranthene	mg/kg	NA	NA	NA
SW8270C	Benzoic acid	mg/kg	NA	NA	NA
SW8270C	Benzyl alcohol	mg/kg	NA	NA	NA
SW8270C	Benzyl butyl phthalate	mg/kg	NA	NA	NA
SW8270C	bis(2-Chloroethoxy)methane	mg/kg	NA	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	WHGLTA051 00 ft 2001-02-07	WHGLTA051 05 ft 2001-02-07	WHGLTA052 05 ft 2001-02-07
SW8270C	bis(2-Chloroethyl)ether (2-Chloroethyl ether)	mg/kg	NA	NA	NA
SW8270C	bis(2-Ethylhexyl)phthalate	mg/kg	NA	NA	NA
SW8270C	Chlorobenzilate	mg/kg	NA	NA	NA
SW8270C	Chrysene	mg/kg	NA	NA	NA
SW8270C	Cresols, m & p	mg/kg	NA	NA	NA
SW8270C	Diallate (total of cis and trans isomers)	mg/kg	NA	NA	NA
SW8270C	Dibenz(a,h)anthracene	mg/kg	NA	NA	NA
SW8270C	Dibenzofuran	mg/kg	NA	NA	NA
SW8270C	Diethyl phthalate	mg/kg	NA	NA	NA
SW8270C	Dimethyl phthalate	mg/kg	NA	NA	NA
SW8270C	Di-n-butyl phthalate	mg/kg	NA	NA	NA
SW8270C	Di-n-octyl phthalate	mg/kg	NA	NA	NA
SW8270C	Dinoseb	mg/kg	NA	NA	NA
SW8270C	Diphenylamine	mg/kg	NA	NA	NA
SW8270C	Ethyl methanesulfonate	mg/kg	NA	NA	NA
SW8270C	Fluoranthene	mg/kg	NA	NA	NA
SW8270C	Fluorene	mg/kg	NA	NA	NA
SW8270C	Hexachlorobenzene	mg/kg	NA	NA	NA
SW8270C	Hexachlorobutadiene	mg/kg	NA	NA	NA
SW8270C	Hexachlorocyclopentadiene	mg/kg	NA	NA	NA
SW8270C	Hexachloroethane	mg/kg	NA	NA	NA
SW8270C	Hexachlorophene	mg/kg	NA	NA	NA
SW8270C	Hexachloropropene	mg/kg	NA	NA	NA
SW8270C	Indeno(1,2,3-c,d)pyrene	mg/kg	NA	NA	NA
SW8270C	Isophorone	mg/kg	NA	NA	NA
SW8270C	Isosafrole	mg/kg	NA	NA	NA
SW8270C	Methapyrene	mg/kg	NA	NA	NA
SW8270C	Methyl methanesulfonate	mg/kg	NA	NA	NA
SW8270C	Naphthalene	mg/kg	NA	NA	NA
SW8270C	Nitrobenzene	mg/kg	NA	NA	NA
SW8270C	N-Nitrosodiethylamine	mg/kg	NA	NA	NA
SW8270C	N-Nitrosodimethylamine	mg/kg	NA	NA	NA
SW8270C	N-Nitrosodi-n-butylamine	mg/kg	NA	NA	NA
SW8270C	N-Nitrosodi-n-propylamine	mg/kg	NA	NA	NA

Table E.1  
Comprehensive Soil Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	WHGLTA051 00 ft 2001-02-07	WHGLTA051 05 ft 2001-02-07	WHGLTA052 05 ft 2001-02-07
SW8270C	N-Nitrosodiphenylamine	mg/kg	NA	NA	NA
SW8270C	N-Nitrosomethylethylamine	mg/kg	NA	NA	NA
SW8270C	N-Nitrosomorpholine	mg/kg	NA	NA	NA
SW8270C	N-Nitrosopiperidine	mg/kg	NA	NA	NA
SW8270C	N-Nitrosopyrrolidine	mg/kg	NA	NA	NA
SW8270C	o-Toluidine	mg/kg	NA	NA	NA
SW8270C	p-Dimethylanilinoazobenzene	mg/kg	NA	NA	NA
SW8270C	Pentachlorobenzene	mg/kg	NA	NA	NA
SW8270C	Pentachloronitrobenzene	mg/kg	NA	NA	NA
SW8270C	Pentachlorophenol	mg/kg	NA	NA	NA
SW8270C	Phenacetin	mg/kg	NA	NA	NA
SW8270C	Phenanthrene	mg/kg	NA	NA	NA
SW8270C	Phenol	mg/kg	NA	NA	NA
SW8270C	p-Phenylenediamine	mg/kg	NA	NA	NA
SW8270C	Protonamide	mg/kg	NA	NA	NA
SW8270C	Pyrene	mg/kg	NA	NA	NA
SW8270C	Pyridine	mg/kg	NA	NA	NA
SW8270C	Safrrole	mg/kg	NA	NA	NA



Table E.2  
Comprehensive Groundwater Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	WHGLTA004 2001-02-22	WHGLTA004 2001-03-26	WHGLTA004 2001-06-15	WHGLTA050 2001-02-21	WHGLTA050 2001-04-06
SW8260B	Trichloroethene (TCE)	mg/L	0.53	0.45	0.66	0.15 J	0.17

Table E.2  
Comprehensive Groundwater Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	WHGLTA050 2001-06-15	WHGLTA051 2001-02-22	WHGLTA051 2001-04-06	WHGLTA051 2001-06-15	WHGLTA052 2001-02-22
SW8260B	Trichloroethene (TCE)	mg/L	0.26	0.19	0.17	0.31	0.3

**Table E.2**  
**Comprehensive Groundwater Results**  
**AOC 19**  
**NAS Fort Worth JRB, Texas**

Method	Analyte	Unit	WHGLTA052 2001-04-06	WHGLTA052 2001-06-26	WHGLTA801 2001-02-22	WHGLTA801 2001-02-22 Dup	WHGLTA801 2001-04-06
SW8260B	Trichloroethene (TCE)	mg/L	0.3	0.57	0.36	0.26	0.15

724 270.

Table E.2  
Comprehensive Groundwater Results  
AOC 19  
NAS Fort Worth JRB, Texas

Method	Analyte	Unit	WHGLTA801 2001-04-06 Dup	WHGLTA801 2001-06-14	WHGLTA801 2001-06-14 Dup
SW8260B	Trichloroethene (TCE)	mg/L	0.17	0.32	0.34

**APPENDIX F**  
**FIELD FORMS**

# TAB

*APPENDIX F*

---

## **BORING LOGS**



Project No: AFC001-26CC

Project: DO26 SI - Phase I

Client: AFCEE

Location: AOC 19 - Suspected FTA-B

Northing:

Borehole ID: BHGLAOC1901

Date: 5/12/00

Geologist: Jorie Wilson

Ground Surface Elevation:

Easting:

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<i>Silty Clay</i> 10YR 3/2 Silty clay, very stiff, with 5% coarse sand, non-plastic.	602	CL	100%	Dry		Wet @ 10.5'
2								
3		<i>Sandy Clayey Silt</i> 10YR 3/2 Clayey silt with 5% coarse sand and pebbles. Stiff. Grading to 10YR 4/2 at 3.5' with increasing sand and pebbles to 20% at 6'.	598	ML	100%	Dry		
4								
5		<i>Sandy Clayey Silt with Gravel</i> 10YR 5/4 Yellowish brown clayey silt, stiff, slightly plastic, with 20% coarse sand and pebbles, angular to subangular gravel from 7-8'.	596	ML	100%	Dry		
6								
7		<i>Sand with Clay</i> 10YR 6/4 Light yellowish brown poorly sorted sand with clay and 10% subrounded to subangular gravel. Increasing clay from 13-14'.	590	SC	100%	Dry		
8								
9					100%	Wet		
10								
11					100%	Wet		
12								
13					100%	Wet		
14								
15								End of boring 14'

Drilled By ESN-South/John Braden

Drill Method DPT

Drilling Equipment SP-4

HydroGeoLogic, Inc  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 2"

Total Depth Drilled: 14

Sheet: 1 of 1



724 275



Project No: AFC001-26CC

Project: DO26 SI - Phase I

Client: AFCEE

Location: AOC 19 - Suspected FTA-B

Northing:

Borehole ID: BHGLAOC1902

Date: 5/15/00

Geologist: Jorie Wilson

Ground Surface Elevation:

Easting:

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<i>Silty Clay</i> 10YR 3/2 Silty clay, very stiff, with 5% coarse sand, non-plastic	599	CL	100%	Dry		Sample collected BHGLAOC1902-01 @ 1'
2								
3		<i>Sandy Clayey Silt with Pebbles</i> 10YR 3/2 Clayey silt with 30% coarse sand and pebbles Subrounded to subangular gravel at 5%	594	GM	100%	Dry		Sample collected BHGLAOC1902-02 @ 5'
4								
5		Coarse sand and pebbles decrease to 10% from 7 to 8'						
6								
7			594		100%	Dry		
8								
9		<i>Silty Sand</i> 2 5Y 7/3 Pale yellow coarse silty sand with subrounded to rounded pebbles and some clay	591	SM		75%	Wet	Wet @ 9 5'
10								
11		<i>Gravel</i> 2 5YR Angular fossiliferous gravel	591	GP				End of boring 11'
12								

Drilled By: ESN-South/John Braden

Drill Method: DPT

Drilling Equipment SP-4

HydroGeoLogic, Inc.  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 2"

Total Depth Drilled: 11

Sheet 1 of 1



Project No: AFC001-26CC

Project: DO26 SI - Phase I

Client: AFCEE

Location: AOC 19 - Suspected FTA-B

Northing:

Borehole ID: BHGLAOC1903

Date: 5/15/00

Geologist: Jorie Wilson

Ground Surface Elevation:

Easting:

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		Clayey Silt with Sand 10YR 3/2 Clayey silt with coarse sand and pebbles (10%), stiff	598	ML				Sample collected BHGLAOC1903-01 @ 1'
2		Silty Clay with Sand 10YR 6/3 Pale brown silty clay Stiff, with coarse sand and pebbles (10%)			80%	Dry		
3		Medium to coarse sand (20%) from 5-6'						Sample collected BHGLAOC1903-02 @ 5'
4				CL	100%	Dry		
5								Wet @ 8'
6		Sandy Pebbly Clay 10YR 7/6 Yellow poorly sorted sandy, pebbly (50%), clay	593					
7				CL	100%	Moist		Refusal @ 9 5'
8		Clayey Sand with Gravel 10YR 7/6 Clayey coarse sand with pebbles and subrounded to subangular gravel (50%)	591					
9			590	SC	60%	Wet		
10		Silty Clay 10YR 6/6 Brownish yellow silty clay Medium stiff Plastic. Bottom 1" is subangular rock fragments	589	CL				

Drilled By: ESN-South/John Braden

Drill Method: DPT

Drilling Equipment SP-4

HydroGeoLogic, Inc  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 2"

Total Depth Drilled 9 5'

Sheet 1 of 1



Project No: AFC001-26CC

Project: DO26 SI - Phase I

Client: AFCEE

Location: AOC 19 - Suspected FTA-B

Northing:

Borehole ID: BHGLAOC1904

Date: 5/15/00

Geologist: Jorie Wilson

Ground Surface Elevation:

Easting:

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<i>Silty Clay With Sand and Pebbles</i> 10YR 4/1 Dk grey silty clay with coarse sand and pebbles	597	CL	100%	Dry		BHGLAOC1904-01 and MS/MSD collected at 1040 at 1'
2								
3								
4		<i>Silty Sand</i> 10YR 5/2 greyish brown stiff silty sand w/10% coarse sand and pebbles, dry Coarse sand and pebbles increase to 30% from 4-5'	595	SM	100%	Dry		BHGLAOC1904-02 @ 5' collected at 1100
5								
6		<i>Silty Clay</i> 2.5Y 6/6 olive yellow silty clay, soft, plastic	594	CL				Wet @ 7'
7								
8		<i>Clay With Sand and Pebbles</i> 10YR 8/1 white clay w/50% medium to coarse sand and pebbles 10YR 6/6 brownish yellow sand mottles at 7'	592	SP	100%	Wet		
9								
10		<i>Sand With Pebbles and Clay</i> 10YR 6/4 light yellowish brown coarse sand with pebbles and clay No clay from 9-10'	590	SP	80%	Wet		Refusal at 10'
11								
12								

Drilled By: ESN-South/John Braden

Drill Method: DPT

Drilling Equipment SP-4

HydroGeoLogic, Inc  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 2"

Total Depth Drilled: 10

Sheet 1 of 1



Project No: AF0001-26CC

Project: Phase II SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6962878 146









Borehole ID: BHGLAOC1905

Date: 8/20/2001

Geologist: M Johnston

Ground Surface Elevation: 601 995

Easting: 2295904 395

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<i>Silty Clay</i> Concrete from 0 - 0.25' 10 YR 2/2 very dark brown silty clay, medium stiff, homogeneous	600	CL	100%	Dry	0 0	Collect BHGLAOC1905-01 from 0.25' - 0.75' at 1530
2		<i>Silty Clay</i> 10 YR 4/3 brown silty clay with 5% small gravel (subangular to round) 0.2- 0.5mm, medium stiff, dry	599	CL				
3		<i>Gravel</i> Limestone gravel	598	GP	60%	Dry	0 0	Collect BHGLAOC1905-02 from 4.75' - 5.25' at 1550
4		<i>Silty Clay</i> 10 YR 5/6 yellowish brown silty clay, stiff, dry	596	CL				
5		<i>Silty Clay</i> 10 YR 5/6 yellowish brown silty clay with 10% gravel (2-10mm), stiff, dry	596	CL	60%	Dry Moist	0 0	Collect BHGLAOC1905-03 from 9.5' - 10' at 1600 Perched water at 10' Refusal at 10.5'
6		<i>Sand and Gravel</i> 10 YR 6/4 light yellowish brown poorly sorted sand (fine to medium grained) with 50% gravel (1-30mm), angular limestone	594	GM				
7		<i>Sandy Silty Clay</i> 10 YR 8/4 yellowish brown silty clay with 30% coarse sand and small gravel (rounded to subrounded), medium stiff, damp to moist	593	CL				
8		<i>Sand</i> 10 YR 7/6 yellow poorly sorted sand (fine to medium grained) with 15% gravel (round to subround), chert	591	SW				
9								
10								
11								
12								

Drilled By: ESN

Drill Method DPT

Drilling Equipment: Strataprobe

HydroGeoLogic, Inc.  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 2"

Total Depth Drilled: 10.5'

Sheet 1 of 1



Project No: AFCOO1-26CC

Project: Phase II SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6962761.843

Borehole ID: BHGLAOC1906

Date: 8/20/2001

Geologist: M Johnston

Ground Surface Elevation: 599.593

Easting: 2295999 029

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		Blind Probe						Southern delineation boring
2								
3			597					
4		Silty Sand 10 YR 7/1 light gray silty sand (fine to medium grained) with 10% gravel (0 25-1mm), dry	595	SM				Collect BHGLAOC1906-02 from 5' - 5 5' at 1435
5		Gravel Limestone gravel	595	LS		Dry	0 0	
6		Silty Clay 10 YR 2/2 dark brown silty clay, mottled with 10 YR 6/4 fine sand and 10% rounded pebbles (0 25-1mm)	594	CL				
7		Blind Probe						Collect BHGLAOC1906-03 from 9.75' - 10 25' at 1450
8								
9			591					
10		Sandy Clay with Gravel 10 YR 4/1 dark gray clay with fine sand and 25% gravel (0 25-1mm) round to subrounded	590	GC				Perched water at 10'
11		Gravel 10 YR 5/8 yellowish brown gravel, poorly sorted, subangular to subround, wet, chert, quartz, feldspar	589	GP		Wet	0 0	
12								Refusal at 10 5'

Drilled By ESN

Drill Method DPT

Drilling Equipment Strataprobe

HydroGeoLogic, Inc  
 1155 Herndon Pkwy, Suite 900  
 Herndon, VA 20170  
 (703) 478-5186 FAX (703) 471-4180

Hole Size 2"

Total Depth Drilled 10 5'

Sheet. 1 of 1



Project No: AF0001-26CC

Project: Phase II SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6963045 976


Borehole ID: BHGLAOC1907

Date: 8/20/2001

Geologist: M Johnston

Ground Surface Elevation: 604 084

Easting: 2296012 436

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		Blind Probe						Confirmation sample of TCE at 10' for BHGLAOC1901
2								
3								
4								
5								
6								
7								
8								
9			595					Collect BHGLAOC1907-03 from 9'75" - 10'25" at 1400
10		Silty Clay with Gravel Mottled 10 YR 4/4 dark yellowish brown, 10 YR 7/4 very pale brown, and 10 YR 8/1 white silty clay with 25% gravel (0.25-10mm), subround to subangular, medium stiff, damp from 9-11', wet at 11'		CL			00	
11								
12								
13			592					

Drilled By: ESN

Drill Method: DPT

Drilling Equipment: Strataprobe

HydroGeoLogic, Inc  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size 2"

Total Depth Drilled: 12'

Sheet: 1 of 1



Project No: AF0001-26CC

Project: Phase II SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6962977.164

Borehole ID: BHGLAOC1908

Date: 8/21/2001

Geologist: M. Johnston

Ground Surface Elevation: 603.08

Easting: 2295949.596

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		Silty Clay Grass, roots, 10 YR 4/4 dark yellowish brown silty clay, damp, medium soft, medium plastic	603	CL			0.0	Collect BHGLAOC1908-01 from 0-1' at 830
			602	SP				
2		Sand 10 YR 7/4 very pale brown sand, fine to medium grained, moderate sorting		CL	100%		Dry	
3		Clay 10 YR 2/2 very dark brown clay, hard, very dry	600					Collect BHGLAOC102 from 4.5' - 5.5' at
4		Silty Clay 10 YR 3/2 very dark grayish brown silty clay, 5% small gravel, subround to subangular, 1-2mm, calcium nodules		CL	100%		Dry	
5		Silty Clay Same as above, with mottled 10 YR 5/2 grayish brown clay, dry stiff	598					
6		2" Limestone layer at bottom	597	CL			Damp	
7		Clay 10 YR 5/6 yellowish brown mottled with 5/2 grayish brown clay with 10% small calcium nodules 1-2mm, subrounded, increasing moisture and plasticity with depth			80%		Moist	
8								Collect BHGLAOC1908-03 from 9.5' - 10.5' at 855 Water table at 11' bgs
9				CL				
10					80%			
11							Wet	
12		Weathered Limestone Weathered limestone with 5% fossils	591					
			591					
13								

Drilled By: ESN

Drill Method: DPT

Drilling Equipment: Strataprobe

HydroGeoLogic, Inc.  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 2"

Total Depth Drilled: 12.5'

Sheet: 1 of 1



Project No: AF0001-26CC

Project: Phase II SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6963052.561

Borehole ID: BHGLAOC1909

Date: 8/22/2001

Geologist: M Johnston

Ground Surface Elevation: 606.541

Easting: 2295993 924

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		Blind Probe						
2								
3			604					
4		Silty Sand and Gravel 10 YR 7/1 light gray silty sand with 50% gravel (1-50mm), subround to angular, dry		GM				
5			602		100%			Collect BHGLAOC1909-02 from 4 5' - 5.5' at 1535
6		Silty Sand and Gravel Mottled 7 5 YR 5/6 strong brown with 10 YR 7/1 light gray silty sand with 50% gravel	601	GM				Fill material
7								End boring at 6' bgs
8								
9								
10								

Drilled By ESN

Drill Method DPT

Drilling Equipment: Strataprobe

HydroGeoLogic, Inc  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 2"

Total Depth Drilled: 6'

Sheet: 1 of 1





Project No: AF0001-26CC

Project: Phase II SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6963080 138

Borehole ID: BHGLAOC1910

Date: 8/22/2001

Geologist: M Johnston

Ground Surface Elevation: 612 536

Easting: 2295977 25

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<b>Sandy Silty Clay</b> 7.5 YR 3/4 dark brown sandy silty clay, poorly sorted with 20% gravel (1-50mm), subangular, brittle, hard	611	CL	75%	Dry		Collect BHGLAOC1910-01 and MS/MSD from 0-1' at 1545
2		<b>Silty Sand with Gravel</b> 10 YR 7/1 light gray silty sand with 50% gravel (1-50mm), fill						
3			606	GM	20%	Dry		Collect BHGLAOC1910-02 from 4 5' - 5 5' at 1545
4								
5			605	CL	50%	Damp		
6		<b>Clay</b> 10 YR 3/4 dark yellowish brown clay, soft, damp, asphalt at 8'						
7		<b>Silty Clay</b> 2" limestone gravel layer, angular 10-50mm, 10 YR 3/2 very dark grayish brown silty clay with gravel (15%) 1-50mm, subround to subangular, hard, dry	604	CL	100%	Dry		Collect BHGLAOC1910-03 from 9 5' - 10 5' at 1605
8		<b>Silty Sand with Gravel</b> 5 Y 5/1 gray silty sand with gravel (50%) angular, 1-40mm, poorly sorted	602	GM				
9		<b>Sandy Silt</b> 10 YR 5/8 yellowish brown mottled with 10 YR 8/1 white sandy silt, dry, brittle, with some well rounded gravel, 10-30mm, hard	601	SM				End boring at 12' bgs
10								
11								
12								
13								
14								

Drilled By: ESN

Drill Method: DPT

Drilling Equipment Strataprobe

HydroGeoLogic, Inc.  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 2"

Total Depth Drilled 12'

Sheet: 1 of 1

724 284



Project No: AF0001-26CC

Project: Phase II SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6963066 961

Borehole ID: BHGLAOC1911

Date: 12/05/2001

Geologist: A Karst

Ground Surface Elevation: 606 637

Easting: 2296003.735

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		Blind Probe						
2								
3								
4				GM				
5								
6				GM				
7								
8								
9		Silty Sand and Clay 10YR 6/6 brownish yellow sandy silty clay, moderate plasticity, damp, medium stiff	598					Collect BHGLAOC1911-03 and DUP04 from 9.5-10 5' at 1140
10					100%	Damp		
11			596					
								End boring at 11' bgs

Drilled By: ESN

Drill Method: DPT

Drilling Equipment: Strataprobe

HydroGeoLogic, Inc.  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 2"

Total Depth Drilled: 11'

Sheet: 1 of 1

724 285



Project No: AF0001-26CC

Project: Phase II SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6963113 194

Borehole ID: BHGLAOC1912

Date: 12/05/2001

Geologist: A Karst

Ground Surface Elevation: 611 104

Easting: 2296037.657

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		Blind Probe						
2								
3								
4			607					Collect BHGLAOC1912-02 and MS/MSD from 4.5-5.5' at 1125
5		Silty Clay with Gravel Top 1' gravel fill 10YR 2/2 very dark brown silty clay, soft, high plasticity, 8% sub-angular pebbles (1-4mm)		CL	70%	Dry		
6			605					
7		Blind Probe						
8								
9			602					
10		Silty Clay with Gravel 10YR 6/6 brownish yellow silty clay with gravel, friable, low plasticity		CL	100%	Dry	0 0	Collect BHGLAOC1912-03 from 9.5-10.5' at 1130
11			600					End boring at 11' bgs

Drilled By ESN

Drill Method: DPT

Drilling Equipment Strataprobe

HydroGeoLogic, Inc.  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 2"

Total Depth Drilled 11'

Sheet 1 of 1



Project No: AF0001-26CC

Project: Phase II SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6962755 909

Borehole ID: BHGLAOC1913

Date: 12/05/2001

Geologist: A. Karst

Ground Surface Elevation: 599 538

Easting: 2295995 226

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		Blind Probe						Collect BHGLAOC1913-02 from 4 5-5 5' at 1215
2								
3								
4			596					Collect BHGLAOC1913-03 from 9 5-10' at 1225
5		Silty Clay with Gravel 10YR 2/2 very dark brown silty clay with 4-6mm sub-angular pebbles, high plasticity, slightly damp, medium stiff		CL	100%	Damp	0.0	
6			594					
7		Blind Probe						Collect BHGLAOC1913-03 from 9 5-10' at 1225
8								
9			591					
10		Sand and Gravel 10YR 6/8 brownish yellow fine to coarse sand and gravel, loose, poorly sorted, moist, gravel is sub-angular to sub-rounded Wet at 10' with well sorted fine sand from 10 to 11'		SP	100%	Moist Wet	0.0	Wet at 10'
11			589					
								End boring at 11' bgs

Drilled By: ESN

Drill Method DPT

Drilling Equipment: Strataprobe

HydroGeoLogic, Inc  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 2"

Total Depth Drilled: 11'

Sheet 1 of 1

724.287



Project No: AFC001-26CC  
 Project: Phase II SI  
 Client: AFCEE  
 Location: NAS FW JRB, Texas  
 Northing: 6963013 359

Borehole ID: WHGLTA050

Date: 2/9/2001

Geologist: M Johnston

Ground Surface Elevation: 599 19

Easting: 2296420.086

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<b>Silty Clay</b> Top 2" grass and roots, 10YR 2/2 v dk brown silty clay, damp, medium stiff, roots	597	CL				
2		<b>Silty Clay with Gravel</b> At 2' 10YR 3/4 dk yellowish brown silty clay with 10% small gravel, medium stiff. Gravel is subround and 2-5 mm	595	CL	100%	Moist	0 0	
3								
4		<b>Clayey Fine Sand</b> Mottled 10YR 5/6 yellowish brown, 5/2 grayish brown, and 8/1 white poorly sorted clayey fine sand with 5% small gravel abd calcium nodules (2-5mm) Moist in the bottom foot	594	SC				
5								
6								
7		<b>Clayey Fine Sand</b> 10YR 5/4 yellowish brown clayey fine sand, saturated, with 5% calcium nodules	592	SC	20%	Wet	0 0	
8								
9								
10								
11								
12								
13								
14								
15								
16								

Drilled By: Dixie Drilling

Drill Method: HSA

Drilling Equipment:

HydroGeoLogic, Inc.  
 1155 Herndon Pkwy, Suite 900  
 Herndon, VA 20170  
 (703) 478-5186 FAX (703) 471-4180

Hole Size:

Total Depth Drilled 7'

Sheet: 1 of 1



**Project No:** AFC001-26CC  
**Project:** Phase II SI  
**Client:** AFCEE  
**Location:** NAS FW JRB, Texas  
**Northing:** 6962894 901

**Borehole ID:** WHGLTA051  
**Date:** 2/9/2001  
**Geologist:** M Johnston  
**Ground Surface Elevation:** 598.37  
**Easting:** 2296247 122

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<b>Silty Clay</b> Grass top 2"; 10YR 3/2 v dk grayish brown silty clay, damp, medium stiff, with 5% roots	596	CL				Collect WHGLTA051-01 at 1310 from 0-6" No odor
2		<b>Clayey Sand</b> 10YR 5/4 yellowish brown clayey fine-coarse sand with 3% calcium nodules, damp, medium stiff	594	SC	50%	Damp	0 0	
3								Collect WHGLTA051-02 at 1315 from 4.5-5' No odor
4								
5		<b>Saprolite</b> Weathered limestone, moist, 10YR 8/1 mottled with 10YR 6/3 pale brown clay with gravel. Gravel is 10%, subrounded-subangular, less than 2" increasing water content - saturated from 5.5' to 7'	591	LS/SC	20%	Moist Wet	0 0	Use the auger flights to drill through the saprolite from 5-7' End boring at 7' (bedrock)
6								
7								Set well WHGLTA051 screen from 2-7', filter pack from 1.5-2', seal from 0.5-1.5', grout 0-0.5'
8								
9								
10								
11								
12								
13								
14								
15								
16								

Drilled By: Dixie Drilling  
 Drill Method: HSA  
 Drilling Equipment

HydroGeoLogic, Inc  
 1155 Herndon Pkwy, Suite 900  
 Herndon, VA 20170  
 (703) 478-5186 FAX (703) 471-4180

Hole Size.  
 Total Depth Drilled: 7'  
 Sheet 1 of 1



**Project No:** AFC001-26CC  
**Project:** Phase II SI  
**Client:** AFCEE  
**Location:** NAS FW JRB, Texas  
**Northing:** 6962769 451

**Borehole ID:** WHGLTA052

**Date:** 2/9/2001

**Geologist:** M Johnston

**Ground Surface Elevation:** 597.12

**Easting:** 2296098.067

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<b>Silty Clay</b> Grass top 2", 10YR 3/2 v dk grayish brown silty clay, damp, medium stiff, with 10% roots	595	CL	30%	Damp	0 0	Collect WHGLTA052-02 at 1420 from 4.5-5' Water table at 5 5', no odor  Use the auger flights drill through the saprolite from 5-7' End boring at 7' (bedrock)  Set well WHGLTA052, screen from 2-7', filter pack from 1.5-2', seal from 0.5-1 5', grout 0-0 5'
2								
3		<b>Clayey Sand</b> 10YR 5/4 yellowish brown and 10YR 5/2 grayish brown clayey fine-coarse sand, damp	593	SC				
4								
5		<b>Saprolite</b> Weathered limestone, 10YR 8/1 mottled with 10YR 6/3 pale brown clay with gravel Gravel is 15%, subrounded-subangular, wet from 5 5' to 7'	590	LS/SC	15%	Moist Wet	0 0	
6								
7								
8								
9								
10								
11								
12								
13								
14								
15								
16								

Drilled By. Dixie Drilling

Drill Method. HSA

Drilling Equipment

HydroGeoLogic, Inc  
 1155 Herndon Pkwy, Suite 900  
 Herndon, VA 20170  
 (703) 478-5186 FAX (703) 471-4180

Hole Size

Total Depth Drilled. 7'

Sheet: 1 of 1



Project No: AFC001-26CC

Project: Excavation SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6962827.984

Borehole ID: THGLAOC1901

Date: 8/14/2001

Geologist: M Johnston

Ground Surface Elevation: 599.157

Easting: 2296060 224

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		Silty Clay Grass, roots in 10YR 4/3 brown silty clay with 30% gravel fill (0 25-50mm), subangular to sub round, hard dry	598	CL			0 0	The anomaly is a steel plate, 2'x2 5'x 25". No odor, no stain, the plate was about 0.5' down. Once removed used magnetic locator to see if anything else was there - no more anomalies. Dry 6" down - nothing else, Backfill
		End of Trench						
2								
3								
4								
5								
6								
7								
8								
9								
10								

Drilled By: Sunbelt

Drill Method: Excavation

Drilling Equipment: Trackhoe

HydroGeoLogic, Inc.  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 6"x5"x1'

Total Depth Drilled: 1'

Sheet 1 of 1



724 291



Project No: AFC001-26CC

Project: Excavation SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6962804 601

Borehole ID: THGLAOC1902

Date: 8/15/2001

Geologist: M Johnston

Ground Surface Elevation: 600.356

Easting: 2296060 224

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<i>Silty Clay</i> Grass, roots, with 10 YR 4/3 brown silty clay, dry, hard, with 15% gravel, subround to subangular, 0 25mm-35mm, calcium streaks	599	CL			0 0	2'x15' rusty scrap piece of metal and 20' of 2" pipe. No stain, odor, or PID detection - backfill after removing pipe and scrap metal Trench location about 20' of A-13 - started there because magnetic locator detected stronger anomaly in that location
2		<i>Silty Clay</i> Mottled 10 YR 7/3 very pale brown with 3/2 very dark grayish brown silty clay with 10% gravel fill, subangular to subround, 0 2mm - 40mm	597	CL			0 0	
3		End of Trench					0 0	
4								
5								
6								
7								
8								
9								
10								

Drilled By: Sunbelt

Drill Method Excavation

Drilling Equipment Trackhoe

HydroGeoLogic, Inc  
 1155 Herndon Pkwy, Suite 900  
 Herndon, VA 20170  
 (703) 478-5186 FAX (703) 471-4180

Hole Size: 9'x15'x3'

Total Depth Drilled: 3'

Sheet 1 of 1



Project No: AFC001-26CC

Project: Excavation SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6962801 471

Borehole ID: THGLAOC1903

Date: 8/15/2001

Geologist: M Johnston

Ground Surface Elevation: 600.846

Easting: 2295927 572

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<b>Silty Clay</b> Grass and roots with 10 YR 5/2 grayish brown silty clay, hard, dry, with 25% gravel fill, subround to subangular, .3mm-45mm	599	CL				Only concrete, barbed wire, and a couple of pieces of wire cable.
2		<b>Silty Clay</b> 10 YR 3/2 very dark grayish brown and 5/3 brown silty clay with 10% gravel fill (1-30mm), subround to subangular	598	CL				No odor, stains, or PID detections (all 0 0 ppm)
3		<b>End of Trench</b>						Trench location is about 30' East of W801, where A-13 should be
4								
5								
6								
7								
8								
9								
10								

Drilled By: Sunbelt

Drill Method: Excavation

Drilling Equipment: Trackhoe

HydroGeoLogic, Inc  
 1155 Herndon Pkwy, Suite 900  
 Herndon, VA 20170  
 (703) 478-5186 FAX (703) 471-4180

Hole Size: 10"x7"x2.5'

Total Depth Drilled: 2.5'

Sheet: 1 of 1



Project No: AFC001-26CC

Project: Excavation SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6963002 676

Borehole ID: THGLAOC1904

Date: 8/15/2001

Geologist: M Johnston

Ground Surface Elevation: 603 789

Easting: 2295961 437

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<i>Silty Clay</i> Grass, roots with 10 YR 7/2 light gray silty clay with 20% gravel (1mm-25mm), subround to subangular, dry, hard	603	CL				Piece of scrap metal and wire cable (took pictures of both)  No odor, stains, or PID detections Backfill
2		<i>Silty Clay</i> 10 YR 3/2 very dark grayish brown silty clay, 5% gravel (1mm-15mm), subround to subangular, dry, stiff/hard Damp at bottom						
3				CL				
4			599					
5		End of Trench						
6								
7								
8								
9								
10								

Drilled By: Sunbelt

Drill Method: Excavation

Drilling Equipment: Trackhoe

 HydroGeoLogic, Inc.  
 1155 Herndon Pkwy, Suite 900  
 Herndon, VA 20170  
 (703) 478-5186 FAX (703) 471-4180

Hole Size: 15'x9'x4 5'

Total Depth Drilled: 4.5'

Sheet: 1 of 1



Project No: AFC001-26CC

Project: Excavation SI

Client: AFCEE

Location: NAS FW JRB

Northing: 6963048.419

Borehole ID: THGLAOC1905

Date: 8/15/2001

Geologist: M Johnston

Ground Surface Elevation: 604.2

Easting: 2296001.747

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		Silty Sandy Clay Grass, roots in 10 YR 5/3 silty sandy clay, dry, hard, with 25% gravel (1mm-35mm), subangular to subrounded	603	CL				In part of anomaly a-4 (NE lobe)
2		Silty Sandy Clay 10 YR 7/2 light gray and 10 YR 5/3 brown silty sandy clay with construction debris (see remarks), dry, hard	601	CL				Found landfill debris (bottles, 3 crushed 55 gallon drums, PID = 0.0 ppm in drums, no lids, rusty and empty, 2 5gallon buckets, concrete, wire, glass, nails, roofing tar).
3		Silty Clay 10 YR 3/2 very dark grayish brown silty clay, dry, hard End of Trench	601	CL				Collected THGLAOC1905-02 from 3' at 1225
4								IDW sample from stockpile collected at 1235.
5								
6								
7								
8								
9								
10								

Drilled By: Sunbelt

Drill Method: Excavation

Drilling Equipment: Trackhoe

HydroGeoLogic, Inc.  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 13'x21'x3'

Total Depth Drilled: 3'

Sheet 1 of 1



Project No: AFC001-023E

Borehole ID: BHGLTA812

Project: NAS FTW Landfill RFI

Date: 6/2/98

Client: AFCEE

Geologist: Brad Nielsen

Location: LF-8

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PI/D (ppm)	
1		<b>Gravelly Silty Clay</b> 7.5Y 6/6 reddish yellow gravelly silty clay, moderate plasticity, poorly sorted	611 87	GL	100%	dry		Asphalt and concrete debris
2		<b>No Recovery</b> Blind probe Rock at 2' bgs Drilled through to 6'						
3								
4					0%	dry		Landfill material
5								
6			607 87					
7		<b>Debris</b> Asphalt and concrete debris with some clay and sand		GC	30%	dry		Offset boring 10' to north
8			605 87					
9		<b>No Recovery</b>	604 87		0%			
10		<b>Gravelly Sandy Clay</b> 7 5YR 3/2 dark brown gravelly sandy clay, moderate to low plasticity, firm to stiff, poorly sorted	602 87	GL		dry		Asphalt and concrete landfill material
11		<b>Silty Clay</b> 7 5YR 2 5/1 black silty clay, high plasticity, stiff, well sorted						
12				CH		damp		
13			600 87					Out of landfill
14		<b>Gravelly Clay</b> 7.5YR 4/2 brown gravelly clay with silt, high plasticity, stiff, moderately to poorly sorted		MH		damp		
15			598 87					
16		<b>Gravelly Clay</b> 7 5YR 5/3 brown gravelly clay with silt, high plasticity, stiff, moderately to poorly		MH				

Drilled By: EDI

Drill Method: DPT

Drilling Equipment XD-2

HydroGeoLogic, Inc.  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 4"

Total Depth Drilled 23'

Sheet: 1 of 2

724 296



Project No: AFC001-023E

Borehole ID: BHGLTA812

Project: NAS FTW Landfill RFI

Date: 6/2/98

Client: AFCEE

Geologist: Brad Nielsen

Location: LF-8

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
17			596 87			moist		Some gravel from 17 to 18'
18		<b>Silty Sandy Clay</b> 7 5YR 5/4 yellowish brown silty sandy clay, high plasticity, stiff, moderately sorted		GM		damp		
19			594 87					Increase in gravel
20		<b>Sandy Clay</b> 10YR 5/4 yellowish brown sandy clay with some gravel, high plasticity, stiff, poorly sorted		MH				
21			592 87					Water at 21 0' bgs
22		<b>Silty Gravel</b> 10YR 6/8 brownish yellow silty gravel with some clay, loose to firm, very poorly sorted		GM		wet		End of boring 23' bgs
23			590 87					
24								
25								
26								
27								
28								
29								
30								
31								
32								

Drilled By: EDI

Drill Method: DPT

Drilling Equipment: XD-2

HydroGeoLogic, Inc.  
 1155 Herndon Pkwy, Suite 900  
 Herndon, VA 20170  
 (703) 478-5186 FAX (703) 471-4180

Hole Size 4"

Total Depth Drilled 23'

Sheet. 2 of 2

724 297



Project No: AFC001-023E

Borehole ID: BHGLTA814

Project: NAS FTW Landfill RFI

Date: 5/18/98

Client: AFCEE

Geologist: Brad Nielsen

Location: LF-8

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<b>Silty Clay</b> 10YR 2/1 black silty clay, stiff	600.85	CL		dry		
2		<b>Silty Clay</b> 10YR 4/2 dark grayish brown silty clay with 15 - 20% gravel and coarse sand (1/2" dia), stiff		CL		dry		
3								
4			597.35					
5		<b>Silty Clay</b> Mottled 10YR 4/1 dark gray and 10YR 4/4 dark yellowish brown silty clay with 15% gravel (up to 1/4" dia) Some gravel up to 1/2" dia near bottom of section		MH		damp		Collected VOC sample from 5.0 - 5.5' depth
6								
7			594.35					
8		<b>Silty Clay</b> Mottled 2.5Y 7/6 yellow and 6/1 gray silty clay with some coarse sand and gravel (up to 1/4" dia), high plasticity. Increasing moisture with depth		MH		damp		Collected VOC sample from 9.0 - 9.5' depth
9								
10			591.35					
11		<b>Gravelly Clay</b> Mottled 2.5Y 7/6 yellow and 6/1 gray gravelly clay, high plasticity, firm. Bottom 4" of section is weathered limestone bedrock	590.35	GC		moist		Refusal at 11.0' bgs
12								
13								
14								
15								
16								

Drilled By: PSI

Drill Method: DPT

Drilling Equipment: XD-2

HydroGeologic, Inc.  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 2"

Total Depth Drilled: 11'

Sheet: 1 of 1



Project No: AFC001-024C

Borehole ID: WHGLTA801

Project: NAS Fort Worth JRB

Date: 10/28/99

Client: AFCEE

Geologist: Nielsen/ Webster

Location: LF-8/ SWMU 25

SUBSURFACE PROFILE					SAMPLE			Remarks
Depth	Symbol	Description	Elevation	ASTM	Recovery	Moisture	PID (ppm)	
1		<b>Clayey Gravel</b> Clayey gravel, poorly sorted, medium to low plasticity, stiff to loose, dry, 10YR 3/3 dark brown	598 83		80%			Gravelly and grassy surface 30-40% gravel
2								
3								
4		<b>Silty Clay</b> Silty clay, moderate sorting, high plasticity, firm, damp, 10YR 3/2 very dark grayish brown	594 83		100%	Damp		Some small calcareous nodules  Collected WHGLTA801-02 from 5 - 7' at 1150
5								
6								
7		<b>Clayey Gravel with Silt</b> Clayey gravel with silt, poorly sorted, moderate to low plasticity, moist, 10YR 5/8 yellowish brown	592 83			Moist		Collected WHGLTA801-03 from 10 - 11' at 1210
8								
9								
10		<b>Silty Gravel</b> Silty gravel, poorly sorted, low plasticity, hard, 10YR 6/5 brownish yellow	590 83		50%			
11								
12								
13		<b>Gravelly Sandy Clay</b> Gravelly sandy clay, very poorly sorted, moderate plasticity, firm to loose, saturated, 10YR 5/4 yellowish brown	589 83		50%	Sat		
14								
15								
16		<b>Clay Shale</b> Clay shale, very hard, dry, gley1 4/1 dark gray	587 33		75%	Sat		Bedrock at 14 5' Total depth at 14 5 bgs DTW at 11' Well installed
17								
18								

Drilled By: TSS

Drill Method: HSA

Drilling Equipment: B-59

HydroGeoLogic, Inc.  
1155 Herndon Pkwy, Suite 900  
Herndon, VA 20170  
(703) 478-5186 FAX (703) 471-4180

Hole Size: 8"

Total Depth Drilled 14 5'

Sheet: 1 of 1



## **MONITORING WELL CONSTRUCTION DETAILS**



# WELL CONSTRUCTION DETAILS AND ABANDONMENT FORM

FIELD REPRESENTATIVE Margaret JohnstonTYPE OF FILTER PACK 20/40DRILLING CONTRACTOR: Dixie DrillingGRADATION medium-coarse

AMOUNT OF FILTER PACK USED \_\_\_\_\_

DRILLING TECHNIQUE DPT/HSATYPE OF BENTONITE 3/8" Envirocore MediumAUGER SIZE AND TYPE: 5' split spoon

AMOUNT BENTONITE USED \_\_\_\_\_

BOREHOLE IDENTIFICATION WHGLTA050TYPE OF CEMENT QuickreteBOREHOLE DIAMETER 5"

AMOUNT CEMENT USED \_\_\_\_\_

WELL IDENTIFICATION WHGLTA050

GROUT MATERIALS USED \_\_\_\_\_


WELL CONSTRUCTION START DATE 2/7/2001

WELL CONSTRUCTION COMPLETE DATE \_\_\_\_\_

DIMENSIONS OF SECURITY BOX: \_\_\_\_\_

SCREEN MATERIAL PVCTYPE OF WELL CAP Pressure capSCREEN DIAMETER 2"TYPE OF END CAP 4" pointSTRATUM-SCREENED INTERVAL (FT): 2-7'

COMMENTS

CASING MATERIAL PVCCASING DIAMETER 2"SPECIAL CONDITIONS  
(describe and draw)

NOT TO SCALE


INSTALLED BY Chuck DelisiINSTALLATION OBSERVED BY: Margaret Johnston

DISCREPANCIES: \_\_\_\_\_

724 301



# WELL CONSTRUCTION DETAILS AND ABANDONMENT FORM

FIELD REPRESENTATIVE Margaret JohnstonTYPE OF FILTER PACK 20/40DRILLING CONTRACTOR Dixie DrillingGRADATION Med-coarseAMOUNT OF FILTER PACK USED                     DRILLING TECHNIQUE DPT/HSATYPE OF BENTONITE 3/8" Envirocore MediumAUGER SIZE AND TYPE 5' split spoonAMOUNT BENTONITE USED                     BOREHOLE IDENTIFICATION WHGLTA051TYPE OF CEMENT QuickreteBOREHOLE DIAMETER 5"AMOUNT CEMENT USED                     WELL IDENTIFICATION WHGLTA051GROUT MATERIALS USED                     WELL CONSTRUCTION START DATE 2/7/2001DIMENSIONS OF SECURITY BOX                     WELL CONSTRUCTION COMPLETE DATE                     SCREEN MATERIAL Schedule 40 PVCTYPE OF WELL CAP Pressure capSCREEN DIAMETER 2"TYPE OF END CAP 4" pointSTRATUM-SCREENED INTERVAL (FT) 2-7'COMMENTS                     CASING MATERIAL Schedule 40 PVCCASING DIAMETER 2"SPECIAL CONDITIONS  
(describe and draw)

NOT TO SCALE

INSTALLED BY: Chuck DelisiINSTALLATION OBSERVED BY: Margaret JohnstonDISCREPANCIES



# WELL CONSTRUCTION DETAILS AND ABANDONMENT FORM

FIELD REPRESENTATIVE: Margaret JohnstonTYPE OF FILTER PACK: 20/40DRILLING CONTRACTOR: Dixie DrillingGRADATION: Med-coarse

AMOUNT OF FILTER PACK USED: \_\_\_\_\_

DRILLING TECHNIQUE: DPT/HSATYPE OF BENTONITE: 3/8" Envirocure MediumAUGER SIZE AND TYPE: 5' split spoon

AMOUNT BENTONITE USED: \_\_\_\_\_

BOREHOLE IDENTIFICATION: WHGLTA052TYPE OF CEMENT: QuickreteBOREHOLE DIAMETER: 5"

AMOUNT CEMENT USED: \_\_\_\_\_

WELL IDENTIFICATION: WHGLTA052

GROUT MATERIALS USED: \_\_\_\_\_


WELL CONSTRUCTION START DATE: 2/7/2001

WELL CONSTRUCTION COMPLETE DATE: \_\_\_\_\_

DIMENSIONS OF SECURITY BOX: \_\_\_\_\_

SCREEN MATERIAL: Schedule 40 PVCTYPE OF WELL CAP: Pressure capSCREEN DIAMETER: 2"TYPE OF END CAP: 4" pointSTRATUM-SCREENED INTERVAL (FT): 2-7'

COMMENTS

CASING MATERIAL: Schedule 40 PVCCASING DIAMETER: 2"SPECIAL CONDITIONS  
(describe and draw)

NOT TO SCALE

INSTALLED BY: Chuck DelisiINSTALLATION OBSERVED BY: Margaret Johnston

DISCREPANCIES: \_\_\_\_\_

**MONITORING WELL DEVELOPMENT FORMS**



724 304

## WELL DEVELOPMENT RECORD

WELL/BIOMETER ID WAC17AC01  
SHEET 1 of 1

PROJECT NAME Phase II SE PROJECT ID AFCEE-26 CD DATE 2/17/01  
 LOCATION AFCE DATE INSTALLED 2/7/01  
 TOTAL DEPTH (FTOC) 1.22 CASING DIAMETER 2

## METHODS OF DEVELOPMENT

☒ Swabbing ☐ Bailing ☒ Pumping ☐ Describe Swabbed on 2/14/01, pumped again on 2/17  
 Equipment decontaminated prior to development ☐ Yes ☒ NO  
 Describe \_\_\_\_\_

## EQUIPMENT NUMBERS

pH Meter \_\_\_\_\_ EC Meter \_\_\_\_\_ Turbidity Meter \_\_\_\_\_ Thermometer \_\_\_\_\_

## CASING VOLUME INFORMATION


Casing ID (ft)	0	1	2	3	4	5	6	7	8	9	10
Casing Volume (gal)	0.04	0.09	0.14	0.19	0.24	0.29	0.34	0.39	0.44	0.49	0.54

## PURGING INFORMATION

Measured Well Depth (B) 6.22 ft  
 Measured Water Level Depth (C) 3.37 ft  
 Length of Static Water Column (D) =  $\frac{(B) - (C)}{(C)}$  = 3.45 ft

Casing Water Volume (E) =  $\frac{(A) \times (D)}{(C)}$  = 0.55 gal

Total Purge Volume = \_\_\_\_\_ (gal)



Date	Time	Water Level (FTOC)	Volume Removed (gal)	pH	EC	Temperature (F or C)	Turbidity/Sand (ppm)	Comments
2/17/01	1305	3.37	3 gal	7.49	3720	14.02	118.3	Swabbed & pumped 3 gal on 2/14/2001
2/17/01	1315	x	4	7.24	326	14.30	33.7	Cloudy, no odor
	1320		4.5	7.21	331	14.43	17.5	cleared up quickly
	1325		5.0	7.15	339	14.45	11.7	
	1330		5.5	7.12	341	14.46	9.5	
	1335		6.0	7.11	346	14.53	6.73	
	1340		6.5	7.09	349	14.56	5.91	Stop pumping - development finished - parameters stable
	1345	✓	7.0					

AFCEE FORM WDU

Flow 0.1 gal/min  
 21 rows < top of pump

724 305

LTD  
GEOLOGIC

## WELL DEVELOPMENT RECORD

WELL PNEUMETER ID 00462 7705.2  
SHEET 1 OF 1PROJECT NAME AW-1151 PROJECT NO AF0041-26 (D) DATE 2/17/2001LOCATION AOC 19 DATE INSTALLED 2/7/01TOTAL DEPTH (FTOC) 7.10 CASING DIAMETER \_\_\_\_\_DTW = 4.30

## METHODS OF DEVELOPMENT

☒ Swabbing    ☐ Gauging    ☒ Pumping    ☐ Deschone  
 Equipment decontaminated prior to development    ☐ Yes    ☒ NO  
 Deschone \_\_\_\_\_

## EQUIPMENT NUMBERS

pH Meter \_\_\_\_\_ EC Meter \_\_\_\_\_ Turbidity Meter \_\_\_\_\_ Thermometer \_\_\_\_\_


## CASING VOLUME INFORMATION

Casing Diameter	1.0	1.5	2.0	2.5	3.0	4.0	5.0	6.0	8.0	10.0	12.0	14.0	16.0	18.0	20.0
Casing Volume (cu ft)	0.04	0.09	0.16	0.25	0.37	0.53	0.75	1.1	1.5	2.0	2.5	3.0	3.5	4.0	4.5

## PURGING INFORMATION

Measured Well Depth (B) 7.10Measured Water Level Depth (C) 4.30Length of Static Water Column (D)  $\frac{7.10}{(B)} - \frac{4.30}{(C)} = \underline{2.80}$ Casing Water Volume (E) =  $\frac{0.16}{(A)} \times \frac{2.80}{(D)} = \underline{\hspace{1cm}}$  gal

Total Purge Volume = \_\_\_\_\_ (gal)



Date	Time	Water Level (FTOC)	Volume Removed (gal)	pH	EC	Temperature (F or C)	Turbidity/ Sand (ppm)	Comments
2/17/01	1340	4.30	28	Start pump				Swabbed & purged 2-3 gal on 2/14/01
2/17/01	1355	3.50	29	708	601.0	14.51	100.2	
2/17/01	1400			699	601	14.47	60.2	
2/17/01	1405			693	602	14.50	39.3	
2/17/01	1410			694	601	14.46	39.0	
2/17/01	1415		20	691	604	14.60	26.5	
2/17/01	1420			692	599	14.39	22.3	
2/17/01	1425			690	598	14.32	8.67	
2/17/01	1430			691	601	14.52	19.7	
2/17/01	1435			691	599	14.35	10.2	

\* TOP OF PUMP ABOVE  
WATER LEVEL

-FC FORM WDJ

PROJECT Phase II SI

DATE 2/17/01

LOCATION. ACC 19

EXPLOSIMETER BOREHOLE READING \_\_\_\_\_

WELL ID: WHGLTA052

PURGE VOLUME  
(3 WELLBORE VOLUMES): \_\_\_\_\_ (L)

WELL DEPTH 710

[illegible]

Note: Condition of the well:

pH - Calibrate at start and before last reading

Sampler M. NAWAL

Observer J RINS



**FIELD SAMPLING FORMS**



## FIELD SAMPLING REPORT

LOCATION. NAS Fort Worth JRB		PROJECT NAME DO 26 Site Investigation	
SITE. <u>AOC19</u>		PROJECT NAME AFC-001-26CC	
<b>SAMPLE INFORMATION</b>			
SAMPLE ID BHGLAOC1901-01		DATE <u>5/12/00</u> TIME <u>1510</u>	
MATRIX TYPE SO		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE	
SAMPLING METHOD: <u>Split Spoon / Bore</u>			
LOT CONTROL # _____			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #: _____			
SAMPLE BEG DPETH (FT) <u>0'</u>		MATRIX SPIKE (MS) _____	
SAMPLE END DPETH (FT) <u>3'</u>		MATRIX SPIKE DUP (SD) _____	
GRAB <input checked="" type="checkbox"/> COMPOSITE ( )		FIELD DUP (FD) _____	
		AMBIENT BLANK (AB) _____	
		EQUIPMENT BLANK (EB) <u>EB 051200</u>	
		TRIP BLANK (TB) <u>TB 051200</u>	

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
4 oz Jar	1	Cool to 4C	SW6010B/SW7471A	Metals + Mercury
5g Encore	3	Cool to 4C	SW8260B	VOCs
4 oz Jar	1	Cool to 4C	SW8270C	SVOCs

NOTABLE OBSERVATIONS			
PID READINGS		SAMPLE CHARACTERISTICS	
1st <u>0.0 ppm</u>	COLOR	MISCELLANEOUS	
2nd	ODOR		
OTHER			
<p>pH _____ Temperature _____ (C) Dissolved Oxygen _____ (mg/L) Specific Conductivity _____ (umhos/cm)</p> <p>Iron _____ (mg/L) Oxidation/Reduction Potential _____ (mv) Turbidity _____ (NTU)</p>			
GENERAL INFORMATION			
WEATHER SUN/CLEAR <u>X</u> OVERCAST/RAIN _____ WIND DIRECTION <u>From W</u> AMBIENT TEMPERATURE <u>90°F</u>			
SHIPMENT VIA FEDEX <u>x</u> HAND DELIVER _____ COURIER _____ OTHER _____			
SHIPPED TO <u>STL - Chicago</u>			
COMMENTS _____			
SAMPLER <u>J. Wilson</u>		OBSERVER <u>E. Dambach</u>	

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

# FIELD SAMPLING REPORT

LOCATION	NAS Fort Worth JRB	PROJECT NAME	DO 26 Site Investigation
SITE	<u>AOC19</u>	PROJECT NAME	AFC-001-26CC

## SAMPLE INFORMATION

SAMPLE ID	BHGLAOC1901-02	DATE	<u>5/12/00</u>	TIME	<u>1515</u>
MATRIX TYPE	SO	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>EB 051200</u> TRIP BLANK (TB) <u>TB 051200</u>			
SAMPLING METHOD	<u>SPLIT SPOON/ENCORE</u>				
LOT CONTROL #	_____				
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)					
CHAIN-OF-CUSTODY #	_____				
SAMPLE BEG DPETH (FT)	<u>3'</u>				
SAMPLE END DPETH (FT)	<u>6'</u>				
GRAB <input checked="" type="checkbox"/> COMPOSITE ( )					
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS		
SIZE/TYPE	#				
4 oz Jar	1	Cool to 4C	Metals + Mercury		
5g Encore	3	Cool to 4C	VOCs		
4 oz Jar	1	Cool to 4C	SVOCs		

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <u>0 ppm</u>	COLOR	
2nd	ODOR	
	OTHER	
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Specific Conductivity _____ (umhos/cm)
	Turbidity _____ (NTU)	

## GENERAL INFORMATION

WEATHER	SUN/CLEAR <u>X</u>	OVERCAST/RAIN _____	WIND DIRECTION	<u>From W</u>	AMBIENT TEMPERATURE	<u>90°F</u>
SHIPMENT VIA	FEDEX <u>x</u>	HAND DELIVER _____	COURIER _____	OTHER _____		
SHIPPED TO	<u>STL - Chicago</u>					
COMMENTS	_____					
SAMPLER	<u>J. WILSON</u>		OBSERVER	<u>E. DANGAUBH</u>		

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



## FIELD SAMPLING REPORT

BEST AVAILABLE  
COPY

724 310

LOCATION: NAS Ft Worth JRB	PROJECT NAME
SITE	PROJECT NAME

## SAMPLE INFORMATION

SAMPLE ID	DATE	TIME
MATRIX TYPE SO	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE	
SAMPLING METHOD	MATRIX SPIKE (MS)	
LOT CONTROL #	MATRIX SPIKE DLP (SD)	
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)	FIELD DUP (FD)	
CHAIN-OF-CUSTODY #	AMBIENT BLANK (AB)	
SAMPLE BEG DPETH (FT)	EQUIPMENT BLANK (EB)	
SAMPLE END DPETH (FT)	TRIP BLANK (TB)	
GRAB ( ) COMPOSITE ( )		

CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
<del>402 PAK</del> 1	<del>Cool to 4C</del>	<del></del>	<del>METALS ANALYSIS</del>
<del>50 PAK</del> 1	<del>Cool to 4C</del>	<del>SWAB/DOE</del>	<del>VOL</del>
<del>402 PAK</del> 1	<del>Cool to 4C</del>	<del></del>	<del>SWAB</del>

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
st	COLOR	
nd	ODOR	
OTHER		
pH	Temperature (C)	Dissolved Oxygen (mg/L)
Iron	Oxidation/Reduction Potential (mv)	Specific Conductivity (umhos/cm)
	Turbidity (NTU)	

## GENERAL INFORMATION

WEATHER	SUN/CLEAR	OVERCAST/RAIN	WIND DIRECTION	AMBIENT TEMPERATURE
SHIPMENT VIA	FEDEX x	HAND DELIVER	COURIER	OTHER
SHIPPED TO	STL - Chicago			
COMMENTS				
SAMPLER	OBSERVER			

MATRIX TYPE CODES	SAMPLING METHOD CODES
C=DRILL CUTTINGS	B=BAILER
G=GROUND WATER	BP=BLADDER PUMP
I=HAZARDOUS LIQUID WASTE	BR=BRASS RING
I=HAZARDOUS SOLID WASTE	CS=COMPOSITE SAMPLE
=SEDIMENT	C=CONTINUOUS FLIGHT AUGER
	DT=DRIVEN TUBE
	G=GRAB
	HA=HAND AUGER
	H=HOLLOW STEM AUGER
	HP=HYDRO PUNCH
	SS=SPLIT SPOON
	SP=SUBMERSIBLE PUMP

724 311



## FIELD SAMPLING REPORT

LOCATION NAS Fort Worth JRB PROJECT NAME DO 26 Site Investigation  
 SITE: AOC 19 PROJECT NAME AFC-001-26CC

## SAMPLE INFORMATION

SAMPLE ID BHGLAOC1901-03		DATE: <u>5/12/00</u> TIME: <u>1545</u>	
MATRIX TYPE: SO		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE.  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>EB 05/200</u> TRIP BLANK (TB) <u>TB 05/200</u>	
SAMPLING METHOD: <u>SPLIT SPOON/ENCORE</u>			
LOT CONTROL # _____			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY # _____			
SAMPLE BEG DPETH (FT) <u>9'</u>			
SAMPLE END DPETH (FT) <u>11'</u>			
GRAB <input checked="" type="checkbox"/> COMPOSITE ( )			

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
4 oz Jar	1	Cool to 4C	SW6010B/SW7471A	Metals + Mercury
5g Encore	3	Cool to 4C	SW8260B	VOCs
4 oz Jar	1	Cool to 4C	SW8270C	SVOCs

## NOTABLE OBSERVATIONS

PID READINGS		SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st	<u>0 ppm</u>	COLOR		
2nd		ODOR		
OTHER				
pH	Temperature	(C)	Dissolved Oxygen	(mg/L) Specific Conductivity
Iron	(mg/L)	Oxidation/Reduction Potential	(mv)	Turbidity (NTU)

## GENERAL INFORMATION

WEATHER SUN/CLEAR ☒ OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION from W AMBIENT TEMPERATURE 90°F

SHIPMENT VIA FEDEX ☒ HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

SHIPPED TO STL - Chicago

COMMENTS \_\_\_\_\_

SAMPLER J. Wilson OBSERVER E. Damaugh

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

LOCATION NAS Ft Worth JRB

PROJECT NAME 1st 100' to 200' depth

SITE 100 19

PROJECT NAME 1st 100' to 200' depth

### SAMPLE INFORMATION

SAMPLE ID <u>1st 100' to 200' depth</u>	DATE <u>5/20/02</u> TIME: <u>08:30</u>
MATRIX TYPE: SO	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>1 100 100</u> TRIP BLANK (TB) <u>1 100 100</u>
SAMPLING METHOD <u>1st 100' to 200' depth</u>	
LOT CONTROL #. _____	
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)	
CHAIN-OF-CUSTODY # _____	
SAMPLE BEG DPETH (FT) <u>3</u>	
SAMPLE END DPETH (FT) <u>6</u>	
GRAB <input checked="" type="checkbox"/> COMPOSITE ( )	

CONTAINER SIZE/TYPE	#	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
	1	Cool to 4C		
<u>500 mL</u>	1	Cool to 4C	<u>SW 8210 B</u>	<u>VOCS</u>
	1	Cool to 4C		

### NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
SI <u>100 19</u>	COLOR	
Ind <u>11</u>	ODOR	
	OTHER	

pH \_\_\_\_\_ Temperature \_\_\_\_\_ (C) Dissolved Oxygen \_\_\_\_\_ (mg/L) Specific Conductivity \_\_\_\_\_ (umhos/cm)  
 Iron \_\_\_\_\_ (mg/L) Oxidation/Reduction Potential \_\_\_\_\_ (mv) Turbidity \_\_\_\_\_ (NTU)

### GENERAL INFORMATION

VEATHER SUN/CLEAR \_\_\_\_\_ OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION SE AMBIENT TEMPERATURE 78

HIPMENT VIA FEDEX ☒ HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

HIPPED TO STL - Chicago

OMMENTS \_\_\_\_\_

AMPLER 1st 100' to 200' depth OBSERVER 1st 100' to 200' depth

#### MATRIX TYPE CODES

C=DRILL CUTTINGS SL=SLUDGE  
 G=GROUND WATER SO=SOIL  
 H=HAZARDOUS LIQUID WASTE GS=SOIL GAS  
 I=HAZRDOLUS SOLID WASTE WS=SURFACE WATER  
 S=SEDIMENT SW=SWAB/WIPE

#### SAMPLING METHOD CODES

B=BAILER G=GRAB  
 BP=BLADDER PUMP HA=HAND AUGER  
 BR=BRASS RING H=HOLLOW STEM AUGER  
 CS=COMPOSITE SAMPLE HP=HYDRO PUNCH  
 C=CONTINUOUS FLIGHT AUGER SS=SPLIT SPOON  
 DT=DRIVEN TUBE SP=SUBMERSIBLE PLMP

LOCATION: NAS Ft Worth JRB

PROJECT NAME

SITE: 1

PROJECT NAME 143

SAMPLE INFORMATION

SAMPLE ID	DATE	TIME
MATRIX TYPE: SO	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE	
SAMPLING METHOD:	MATRIX SPIKE (MS)	
LOT CONTROL #:	MATRIX SPIKE DUP (SD)	
Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #	FIELD DUP (FD)	
CHAIN-OF-CUSTODY #	AMBIENT BLANK (AB)	
SAMPLE BEG DPETH (FT) 9	EQUIPMENT BLANK (EB)	
SAMPLE END DPETH (FT) 11	TRIP BLANK (TB)	
SAB (.) COMPOSITE ( )		

CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#		
	1	Cool to 4C	
Swabs	1	Cool to 4C	SWABS
	1	Cool to 4C	VCKS

NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
0.072	COLOR	
	ODOR	
	OTHER	
H Temperature (C) Dissolved Oxygen (mg/L) Specific Conductivity (umhos/cm) on (mg/L) Oxidation/Reduction Potential (mv) Turbidity (NTU)		

GENERAL INFORMATION

WEATHER: SUN/CLEAR OVERCAST/RAIN WIND DIRECTION 143 AMBIENT TEMPERATURE  
 SHIPMENT VIA: FEDEX x HAND DELIVER COURIER OTHER  
 SHIPPED TO STL - Chicago  
 COMMENTS  
 SAMPLER OBSERVER

MATRIX TYPE CODES		SAMPLING METHOD CODES	
= DRILL CUTTINGS	SL = SLUDGE	B = BAILER	G = GRAB
= GROUND WATER	SO = SOIL	BP = BLADDER PUMP	HA = HAND AUGER
= HAZARDOUS LIQUID WASTE	GS = SOIL GAS	BR = BRASS RING	H = HOLLOW STEM AUGER
HAZARDOUS SOLID WASTE	WS = SURFACE WATER	CS = COMPOSITE SAMPLE	HP = HYDRO PUNCH
SEDIMENT	SW = SWAB/WIPE	C = CONTINUOUS FLIGHT AUGER	SS = SPLIT SPOON
		DT = DRIVEN TUBE	SP = SUBMERSIBLE PUMP



## FIELD SAMPLING REPORT

724 314

LOCATION: NAS Fort Worth JRB		PROJECT NAME DO 26 Site Investigation																							
SITE: <u>AFC-19</u>		PROJECT NAME AFC-001-26CC																							
<b>SAMPLE INFORMATION</b>																									
SAMPLE ID BHGLAOC1902-01		DATE <u>5/5/00</u> TIME <u>0850</u>																							
MATRIX TYPE SO		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>EB 05/500</u> TRIP BLANK (TB) <u>TB 05/500</u>																							
SAMPLING METHOD <u>SPLIT SPOON/EXTRACT</u>																									
LOT CONTROL # _____ (Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)																									
CHAIN-OF-CUSTODY # _____																									
SAMPLE BEG DPETH (FT) <u>0 FT</u> SAMPLE END DPETH (FT) <u>3 FT</u> GRAB <input checked="" type="checkbox"/> COMPOSITE ( )																									
<table border="1" style="width:100%"><thead><tr><th colspan="2">CONTAINER</th><th rowspan="2">PRESERVATIVE/ PREPARATION</th><th rowspan="2">ANALYTICAL METHOD</th><th rowspan="2">ANALYSIS</th></tr><tr><th>SIZE/TYPE</th><th>#</th></tr></thead><tbody><tr><td>4 oz Jar</td><td>1</td><td>Cool to 4C</td><td>SW6010B/SW7471A</td><td>Metals + Mercury</td></tr><tr><td>5g Encore</td><td>3</td><td>Cool to 4C</td><td>SW8260B</td><td>VOCs</td></tr><tr><td>4 oz Jar</td><td>1</td><td>Cool to 4C</td><td>SW8270C</td><td>SVOCs</td></tr></tbody></table>		CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS	SIZE/TYPE	#	4 oz Jar	1	Cool to 4C	SW6010B/SW7471A	Metals + Mercury	5g Encore	3	Cool to 4C	SW8260B	VOCs	4 oz Jar	1	Cool to 4C	SW8270C	SVOCs		
CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD				ANALYSIS																		
SIZE/TYPE	#																								
4 oz Jar	1	Cool to 4C	SW6010B/SW7471A	Metals + Mercury																					
5g Encore	3	Cool to 4C	SW8260B	VOCs																					
4 oz Jar	1	Cool to 4C	SW8270C	SVOCs																					

<b>NOTABLE OBSERVATIONS</b>					
PID READINGS		SAMPLE CHARACTERISTICS		MISCELLANEOUS	
1st	<u>0.0 ppm</u>	COLOR			
2nd		ODOR			
		OTHER			
pH _____		Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)	Specific Conductivity _____ (umhos/cm)	
Iron _____ (mg/L)		Oxidation/Reduction Potential _____ (mv)	Turbidity _____ (NTU)		
<b>GENERAL INFORMATION</b>					
WEATHER SUN/CLEAR <u>X</u>		OVERCAST/RAIN _____	WIND DIRECTION <u>From S</u>	AMBIENT TEMPERATURE <u>75°F</u>	
SHIPMENT VIA FEDEX <u>x</u>		HAND DELIVER _____	COURIER _____	OTHER _____	
SHIPPED TO <u>STL - Chicago</u>					
COMMENTS _____					
SAMPLER <u>J. Wilson</u>			OBSERVER <u>E. Jambalga</u>		
<b>MATRIX TYPE CODES</b>			<b>SAMPLING METHOD CODES</b>		
DC=DRILL CUTTINGS SL=SLUDGE			B=BAILER G=GRAB		
WG=GROUND WATER SO=SOIL			BP=BLADDER PUMP HA=HAND AUGER		
LH=HAZARDOUS LIQUID WASTE GS=SOIL GAS			BR=BRASS RING H=HOLLOW STEM AUGER		
SH=HAZARDOUS SOLID WASTE WS=SURFACE WATER			CS=COMPOSITE SAMPLE HP=HYDRO PUNCH		
SE=SEDIMENT SW=SWAB/WIPE			C=CONTINUOUS FLIGHT AUGER SS=SPLIT SPOON		
			DT=DRIVEN TUBE SP=SUBMERSIBLE PUMP		



LOCATION: NAS Fort Worth JRB

PROJECT NAME

DO 26 Site Investigation

SITE AFC-19

PROJECT NAME

AFC-001-26CC

## SAMPLE INFORMATION

SAMPLE ID BHGLAOC1902-02

DATE 5/15/00 TIME 0855

MATRIX TYPE: SO

SAMPLING METHOD. SPLIT SPOON / EXTRACTENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:

LOT CONTROL #: \_\_\_\_\_

MATRIX SPIKE (MS) \_\_\_\_\_

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

MATRIX SPIKE DUP (SD) \_\_\_\_\_

CHAIN-OF-CUSTODY #: \_\_\_\_\_

FIELD DUP (FD) \_\_\_\_\_

SAMPLE BEG DPETH (FT) 3

AMBIENT BLANK (AB) \_\_\_\_\_

SAMPLE END DPETH (FT) 6EQUIPMENT BLANK (EB) EB 05/15/00GRAB ☒ COMPOSITE ( )TRIP BLANK (TB) TB 05/15/00

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
4 oz Jar	1	Cool to 4C	SW6010B/SW7471A	Metals + Mercury
5g Encore	3	Cool to 4C	SW8260B	VOCs
4 oz Jar	1	Cool to 4C	SW8270C	SvOCs

## NOTABLE OBSERVATIONS

PID READINGS		SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st <u>0.0 ppm</u>	COLOR			
2nd	ODOR			
	OTHER			
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)	Specific Conductivity _____ (umhos/cm)	
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Turbidity _____ (NTU)		

## GENERAL INFORMATION

WEATHER SUN/CLEAR ☒ OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION from S AMBIENT TEMPERATURE 75°FSHIPMENT VIA FEDEX ☒ HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_SHIPPED TO STL - Chicago

COMMENTS \_\_\_\_\_

AMPLER J. W. WilsonOBSERVER ES. L. M. R. G. H.

MATRIX TYPE CODES		SAMPLING METHOD CODES	
C=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
G=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
H=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
I=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
S=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



## FIELD SAMPLING REPORT

724 316

LOCATION	NAS Fort Worth JRB	PROJECT NAME	DO 26 Site Investigation
SITE	<u>ACC 19</u>	PROJECT NAME	AFC-001-26CC

## SAMPLE INFORMATION

SAMPLE ID	BHGLAOC1903-01	DATE	<u>5/15/00</u>	TIME	<u>0935</u>
MATRIX TYPE	SO	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE			
SAMPLING METHOD	<u>SPLIT SPOON / MAX</u>				
LOT CONTROL #:					
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cocler #)					
CHAIN-OF-CUSTODY #		MATRIX SPIKE (MS)		MATRIX SPIKE DUP (SD)	
SAMPLE BEG DPETH (FT)	<u>0</u>	FIELD DUP (FD)	<u>DRUG</u>	AMBIENT BLANK (AB)	
SAMPLE END DPETH (FT)	<u>3</u>	EQUIPMENT BLANK (EB)	<u>EB CST 500</u>	TRIP BLANK (TB)	<u>TB CST 500</u>
GRAB (X) COMPOSITE ( )					

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
4 oz Jar	1	Cool to 4C	SW6010B/SW7471A	Metals + Mercury
5g Encore	3	Cool to 4C	SW8260B	VOCs
4 oz Jar	1	Cool to 4C	SW8270C	SVOCs

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <u>0.0 ppm</u>	COLOR	
2nd	ODOR	
	OTHER	
pH	Temperature (C)	Dissolved Oxygen (mg/L)
Iron (mg/L)	Oxidation/Reduction Potential (mv)	Specific Conductivity (umhos/cm)
	Turbidity (NTU)	

## GENERAL INFORMATION

WEATHER	SUN/CLEAR <u>X</u>	OVERCAST/RAIN	WIND DIRECTION <u>E 15 S</u>	AMBIENT TEMPERATURE <u>75.9</u>
SHIPMENT VIA	FEDEX <u>x</u>	HAND DELIVER	COURIER	OTHER
SHIPPED TO	<u>STL - Chicago</u>			
COMMENTS				
SAMPLER	<u>J. Wilson</u>	OBSERVER	<u>E. J. Ambrose</u>	

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

724 317



## FIELD SAMPLING REPORT

ATION. NAS Ft Worth JRB		PROJECT NAME DO26/29 RFI/SI	
SITE <u>ACC-19</u>		PROJECT NAME AFC001-26CC/29BBBA	
<b>SAMPLE INFORMATION</b>			
SAMPLE ID <u>DUP06</u>		DATE <u>5/15/00</u> TIME <u>0835 (collected 0435)</u>	
MATRIX TYPE. <u>SO</u>		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>TB 05/1500</u> TRIP BLANK (TB) <u>TB 05/1500</u>	
SAMPLING METHOD <u>SPLIT SPOON/EDMONT</u>			
LOT CONTROL #: _____			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY # _____			
SAMPLE BEG DPETH (FT) <u>0</u>			
SAMPLE END DPETH (FT) <u>3</u>			
GRAB <input checked="" type="checkbox"/> COMPOSITE ( )			
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
4 oz Jar 1	Cool to 4C	SW6010B/SW7471A	Metals + Mercury
4 oz Jar 1	Cool to 4C	SW8270C	SVOCs
<u>5g EDmunt</u> 3	<u>Cool to 4C</u>	<u>SW8260B</u>	<u>VOCs</u>
<b>NOTABLE OBSERVATIONS</b>			
PID READINGS		SAMPLE CHARACTERISTICS	
1st <u>0.0 PPM</u> COLOR			
2nd _____ ODOR			
OTHER			
pH _____ Temperature _____ (C) Dissolved Oxygen _____ (mg/L) Specific Conductivity _____ (umhos/cm) Iron _____ (mg/L) Oxidation/Reduction Potential _____ (mv) Turbidity _____ (NTU)			
<b>GENERAL INFORMATION</b>			
WEATHER SUN/CLEAR <input checked="" type="checkbox"/> OVERCAST/RAIN _____ WIND DIRECTION <u>E-SE</u> AMBIENT TEMPERATURE <u>75°F</u>			
SHIPMENT VIA FEDEX <input checked="" type="checkbox"/> HAND DELIVER _____ COURIER _____ OTHER _____			
SHIPPED TO <u>STL - Chicago</u>			
COMMENTS _____			
SAMPLER <u>J. Wilson</u>		OBSERVER <u>G. Dambach</u>	
MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



## FIELD SAMPLING REPORT

724 318

STATION		NAS Fort Worth JRB		PROJECT NAME		DO 26 Site Investigation					
SITE		ACC19		PROJECT NAME		AFC-001-26CC					
<b>SAMPLE INFORMATION</b>											
SAMPLE ID				BHGLAOC1903-02		DATE		5/15/00		TIME: 0950	
MATRIX TYPE:				SO				ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>EB 05/1500</u> TRIP BLANK (TB) <u>TB 05/1500</u>			
SAMPLING METHOD:				<u>SPUT SPOON / 1/2 CUP</u>							
LOT CONTROL #				_____							
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)				_____							
CHAIN-OF-CUSTODY #				_____							
SAMPLE BEG DPETH (FT)				3							
SAMPLE END DPETH (FT)				6							
GRAB (X) COMPOSITE ( )											
CONTAINER		PRESERVATIVE/ PREPARATION		ANALYTICAL METHOD		ANALYSIS					
SIZE/TYPE	#										
4 oz Jar	1	Cool to 4C		SW6010B/SW7471A		Metals + Mercury					
5g Encore	3	Cool to 4C		SW 8260B		VOCs					
4 oz Jar	1	Cool to 4C		SW8270C		SVOCs					

<b>NOTABLE OBSERVATIONS</b>																											
PID READINGS		SAMPLE CHARACTERISTICS				MISCELLANEOUS																					
1st	<u>0.0 ppm</u>	COLOR																									
2nd		ODOR																									
		OTHER																									
pH		Temperature		(C)		Dissolved Oxygen		(mg/L)		Specific Conductivity		(umhos/cm)															
Iron		(mg/L)		Oxidation/Reduction Potential		(mv)		Turbidity		(NTU)																	
<b>GENERAL INFORMATION</b>																											
WEATHER		SUN/CLEAR		X		OVERCAST/RAIN				WIND DIRECTION		<u>EWS</u>		AMBIENT TEMPERATURE		<u>75°F</u>											
SHIPMENT VIA		FEDEX		x		HAND DELIVER				COURIER				OTHER													
SHIPPED TO		STL - Chicago																									
COMMENTS																											
SAMPLER		<u>J. Wilson</u>				OBSERVER		<u>E. J. Dambach</u>																			
MATRIX TYPE CODES							SAMPLING METHOD CODES																				
DC=DRILL CUTTINGS							SL=SLUDGE							B=BAILER							G=GRAB						
WG=GROUND WATER							SO=SOIL							BP=BLADDER PUMP							HA=HAND AUGER						
LH=HAZARDOUS LIQUID WASTE							GS=SOIL GAS							BR=BRASS RING							H=HOLLOW STEM AUGER						
SH=HAZARDOUS SOLID WASTE							WS=SURFACE WATER							CS=COMPOSITE SAMPLE							HP=HYDRO PUNCH						
SE=SEDIMENT							SW=SWAB/WIPE							C=CONTINUOUS FLIGHT AUGER							SS=SPLIT SPOON						
														DT=DRIVEN TUBE							SP=SUBMERSIBLE PUMP						

## FIELD SAMPLING REPORT

LOCATION	NAS Ft Worth JRB	PROJECT NAME	DO26/29 RFI/SI
SITE	<u>AOC 19</u>	PROJECT NAME	AFC001-26CC/29BBBA

## SAMPLE INFORMATION

SAMPLE ID	BHGLAOC1904MS	DATE	<u>5/15/00</u>	TIME	<u>1040</u>
MATRIX TYPE	SO	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE			
SAMPLING METHOD	<u>SPLIT SPOON/ENCORE</u>				
LOT CONTROL #	_____				
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)	_____				
CHAIN-OF-CUSTODY #	_____	MATRIX SPIKE (MS)	_____	MATRIX SPIKE DUP (SD)	_____
SAMPLE BEG DPETH (FT)	<u>0</u>	FIELD DUP (FD)	_____	AMBIENT BLANK (AB)	_____
SAMPLE END DPETH (FT)	<u>3</u>	EQUIPMENT BLANK (EB)	<u>EB 657500</u>	TRIP BLANK (TB)	<u>TB 657500</u>
GRAB <input checked="" type="checkbox"/> COMPOSITE <input type="checkbox"/>					

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
4 oz Jar	1	Cool to 4C	SW6010B/SW7471A	Metals + Mercury
5g Encore	3	Cool to 4C	SW8260B	VOCs
4 oz Jar	1	Cool to 4C	SW8270C	SVOCs

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <u>0.0 PPM</u>	COLOR	
2nd	ODOR	
	OTHER	
pH	Temperature	(C) Dissolved Oxygen
Iron	(mg/L) Oxidation/Reduction Potential	(mv) Turbidity
		(NTU) Specific Conductivity
		(umhos/cm)

## GENERAL INFORMATION

WEATHER	SUN/CLEAR <input checked="" type="checkbox"/>	OVERCAST/RAIN	WIND DIRECTION	<u>From S</u>	AMBIENT TEMPERATURE	<u>75°F</u>
SHIPMENT VIA	FEDEX <input checked="" type="checkbox"/>	HAND DELIVER	COURIER		OTHER	
SHIPPED TO	STL - Chicago					
COMMENTS						
SAMPLER	<u>J. Wilson</u>		OBSERVER	<u>B. D. M. B. M. L. H.</u>		

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



## FIELD SAMPLING REPORT

724' 320'

LOCATION: NAS Fort Worth JRB	PROJECT NAME DO 26 Site Investigation
SITE: <u>AOC 19</u>	PROJECT NAME AFC-001-26CC

## SAMPLE INFORMATION

SAMPLE ID BHGLAOC1904-01	DATE <u>5/15/00</u> TIME <u>1040</u>
MATRIX TYPE SO	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE  MATRIX SPIKE (MS) <u>BHGLAOC1904MS</u> MATRIX SPIKE DUP (SD) <u>BHGLAOC1904MSD</u> FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>EB 09500</u> TRIP BLANK (TB) <u>TB 054500</u>
SAMPLING METHOD <u>SPLIT SPOON</u>	
LOT CONTROL #. _____ (Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)	
CHAIN-OF-CUSTODY # _____	
SAMPLE BEG DPETH (FT) <u>0</u> SAMPLE END DPETH (FT) <u>3</u> GRAB <input checked="" type="checkbox"/> COMPOSITE ( )	

CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
4 oz Jar 1	Cool to 4C	SW6010B/SW7471A	Metals + Mercury
5g Encore 3	Cool to 4C	SW8260B	VOCs
4 oz Jar 1	Cool to 4C	SW8270C	SVOCs

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <u>0.0 ppm</u>	COLOR	
2nd	ODOR	
OTHER		
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Specific Conductivity _____ (umhos/cm)
Turbidity _____ (NTU)		

## GENERAL INFORMATION

WEATHER: SUN/CLEAR <u>X</u>	OVERCAST/RAIN _____	WIND DIRECTION <u>From S</u>	AMBIENT TEMPERATURE <u>75.9</u>
SHIPMENT VIA FEDEX <u>x</u>	HAND DELIVER _____	COURIER _____	OTHER _____
SHIPPED TO <u>STL - Chicago</u>			
COMMENTS _____			
SAMPLER <u>J. Wilson</u>		OBSERVER <u>E. Darnault</u>	

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

## FIELD SAMPLING REPORT

LOCATION NAS Ft Worth JRB		PROJECT NAME DO26/29 RFI/SI																							
SITE <u>AOC19</u>		PROJECT NAME AFC001-26CC/29BBBA																							
<b>SAMPLE INFORMATION</b>																									
SAMPLE ID BHGLAOC1904MSD		DATE <u>5/5/00</u> TIME <u>1040</u>																							
MATRIX TYPE SO		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE.  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>EB C57520</u> TRIP BLANK (TB) <u>TB C57500</u>																							
SAMPLING METHOD <u>SPLIT SPOON</u>																									
LOT CONTROL #. _____ (Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)																									
CHAIN-OF-CUSTODY # _____																									
SAMPLE BEG DPETH (FT) <u>0</u> SAMPLE END DPETH (FT) <u>3</u> GRAB (X) COMPOSITE ( )																									
<table border="1" style="width:100%"><thead><tr><th colspan="2">CONTAINER</th><th rowspan="2">PRESERVATIVE/ PREPARATION</th><th rowspan="2">ANALYTICAL METHOD</th><th rowspan="2">ANALYSIS</th></tr><tr><th>SIZE/TYPE</th><th>#</th></tr></thead><tbody><tr><td>4 oz Jar</td><td>1</td><td>Cool to 4C</td><td>SW6010B/SW7471A</td><td>Metals + Mercury</td></tr><tr><td>5g Encore</td><td>3</td><td>Cool to 4C</td><td>SW8260B</td><td>VOCs</td></tr><tr><td>4 oz Jar</td><td>1</td><td>Cool to 4C</td><td>SW8270C</td><td>SVOCs</td></tr></tbody></table>		CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS	SIZE/TYPE	#	4 oz Jar	1	Cool to 4C	SW6010B/SW7471A	Metals + Mercury	5g Encore	3	Cool to 4C	SW8260B	VOCs	4 oz Jar	1	Cool to 4C	SW8270C	SVOCs		
CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD				ANALYSIS																		
SIZE/TYPE	#																								
4 oz Jar	1	Cool to 4C	SW6010B/SW7471A	Metals + Mercury																					
5g Encore	3	Cool to 4C	SW8260B	VOCs																					
4 oz Jar	1	Cool to 4C	SW8270C	SVOCs																					
<b>NOTABLE OBSERVATIONS</b>																									
PID READINGS		SAMPLE CHARACTERISTICS																							
1st <u>0.0 ppm</u> COLOR _____		MISCELLANEOUS																							
2nd _____ ODOR _____																									
OTHER _____																									
pH _____ Temperature _____ (C) Dissolved Oxygen _____ (mg/L) Specific Conductivity _____ (umhos/cm)																									
Iron _____ (mg/L) Oxidation/Reduction Potential _____ (mv) Turbidity _____ (NTU)																									
<b>GENERAL INFORMATION</b>																									
WEATHER SUN/CLEAR <u>X</u> OVERCAST/RAIN _____ WIND DIRECTION <u>EWS</u> AMBIENT TEMPERATURE <u>75 F</u>																									
SHIPMENT VIA. FEDEX <u>x</u> HAND DELIVER _____ COURIER _____ OTHER _____																									
SHIPPED TO <u>STL - Chicago</u>																									
COMMENTS _____																									
SAMPLER <u>J. Wilson</u>		OBSERVER <u>E. DAMBAUGH</u>																							
<b>MATRIX TYPE CODES</b>		<b>SAMPLING METHOD CODES</b>																							
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB																						
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER																						
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER																						
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH																						
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON																						
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP																						



## FIELD SAMPLING REPORT

724 322

LOCATION. NAS Fort Worth JRB	PROJECT NAME DO 26 Site Investigation
S. - <u>AOC19</u>	PROJECT NAME AFC-001-26CC

## SAMPLE INFORMATION

SAMPLE ID BHGLAOC1904-02	DATE <u>5/15/00</u> TIME <u>1100</u>
MATRIX TYPE: SO	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE.  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>EB C57500</u> TRIP BLANK (TB) <u>TB C57500</u>
SAMPLING METHOD <u>SPLIT SPOON</u>	
LOT CONTROL # _____ (Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)	
CHAIN-OF-CUSTODY #. _____	
SAMPLE BEG DPETH (FT) <u>3</u> SAMPLE END DPETH (FT) <u>6</u> GRAB ( <input checked="" type="checkbox"/> ) COMPOSITE ( )	

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
4 oz Jar	1	Cool to 4C	SW6010B/SW7471A	Metals + Mercury
5g Encore	3	Cool to 4C	SW8260B	VOCs
4 oz Jar	1	Cool to 4C	SW8270C	SVOCs

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st <u>0.0 ppm</u>	COLOR		
2nd	ODOR		
	OTHER		
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)	Specific Conductivity _____ (umhos/cm)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Turbidity _____ (NTU)	

## GENERAL INFORMATION

WEATHER SUN/CLEAR <input checked="" type="checkbox"/>	OVERCAST/RAIN _____	WIND DIRECTION <u>from S</u>	AMBIENT TEMPERATURE <u>75°F</u>
SHIPMENT VIA FEDEX <input checked="" type="checkbox"/>	HAND DELIVER _____	COURIER _____	OTHER _____
SHIPPED TO <u>STL - Chicago</u>			
COMMENTS _____			
SAMPLER <u>J. Wilson</u>		OBSERVER <u>E. Dambach</u>	

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



724 323



## FIELD SAMPLING REPORT

LOCATION NAS Fort Worth JRB, TX  
SITE AOC 19

PROJECT NAME: Phase II RFI FT-001  
PROJECT NO. AFC001-26CC

## SAMPLE INFORMATION

SAMPLE ID	BHGLAOC1905-01	DATE	8-20-01	TIME	1530
MATRIX TYPE	SO	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) <u>121A</u> EQUIPMENT BLANK (EB) <u>98622CC1</u> TRIP BLANK (TB) <u>76522CC1</u>			
SAMPLING METHOD	SS				
LOT CONTROL #:	<u>C-111H</u>				
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)					
CHAIN-OF-CUSTODY #:					
SAMPLE BEG DPETH (FT)	<u>0.25</u>				
SAMPLE END DPETH (FT)	<u>0.75</u>				
GRAB (X) COMPOSITE ( )					

CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
5g Encore 3	Cool to 4C	SW8260B	USE (Apply) and include in the
4g jar 12	Cool to 4C	SW8260B / SW8260B	USE (Apply) and include in the

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <u>0.000m</u>	COLOR	
2nd	ODOR <u>None</u>	
	OTHER	

pH \_\_\_\_\_ Temperature \_\_\_\_\_ (C) Dissolved Oxygen \_\_\_\_\_ (mg/L) Specific Conductivity \_\_\_\_\_ (umhos/cm)  
 Iron \_\_\_\_\_ (mg/L) Oxidation/Reduction Potential \_\_\_\_\_ (mv) Turbidity \_\_\_\_\_ (NTU)

## GENERAL INFORMATION

WEATHER SUN/CLEAR X OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION \_\_\_\_\_ AMBIENT TEMPERATURE 100F  
 SHIPMENT VIA FEDEX X HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_  
 SHIPPED TO STL - Chicago  
 COMMENTS \_\_\_\_\_  
 SAMPLER M. Johnston OBSERVER T. L. L.

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=\$WAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



## FIELD SAMPLING REPORT

BEST AVAILABLE  
COPY

724 224

LOCATION: NAS Fort Worth JRB, TX		PROJECT NAME: Phase II RFI FT-001	
SITE: AOC 19		PROJECT NO: AFC001-26CC	
<b>SAMPLE INFORMATION</b>			
SAMPLE ID: BHGLAOC1906-037 TRC2001		DATE: 8-20-01 TIME: 900	
MATRIX TYPE: 50m we		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) <u>N/A</u> EQUIPMENT BLANK (EB) <u>FCR 2001</u> TRIP BLANK (TB) _____	
SAMPLING METHOD: SS, G			
LOT CONTROL # <u>C-1-1-1</u> (Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #: _____			
SAMPLE BEG DPETH (FT) <u>N/A</u> SAMPLE END DPETH (FT) _____ GRAB <input checked="" type="checkbox"/> COMPOSITE ( )			
CONTAINER SIZE/TYPE #	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
5g Encore <u>2</u>	Cool to 4C, HCL	SW8260B	VOCs (Hyg IV) 1, 2, 4, 5, 6, 7

<b>NOTABLE OBSERVATIONS</b>			
FID READINGS		SAMPLE CHARACTERISTICS	
1st		COLOR	
2nd		ODOR	
		OTHER	
pH _____ Temperature _____ (C) Dissolved Oxygen _____ (mg/L) Specific Conductivity _____ (umhos/cm)			
Iron _____ (mg/L) Oxidation/Reduction Potential _____ (mv) Turbidity _____ (NTU)			
<b>GENERAL INFORMATION</b>			
WEATHER SUN/CLEAR <u>X</u> OVERCAST/RAIN _____ WIND DIRECTION _____ AMBIENT TEMPERATURE <u>100 F</u>			
SHIPMENT VIA: FEDEX <u>X</u> HAND DELIVER _____ COURIER _____ OTHER _____			
SHIPPED TO <u>STL - Chicago</u>			
COMMENTS _____			
SAMPLER <u>M. Johnston</u>		OBSERVER <u>T. L. L.</u>	
<b>MATRIX TYPE CODES</b>		<b>SAMPLING METHOD CODES</b>	
UC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

724 025

E16AJIYAT238

1903

HYDRO  
Geologic<sup>INC.</sup>

## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME Phase II RFI FT 001

SITE: acc 19

PROJECT NO: AFG001-26C

## SAMPLE INFORMATION

SAMPLE ID HYDRO-1903-1903-01DATE 8-21-01 TIME 830MATRIX TYPE: W-60SAMPLING METHOD DTLOT CONTROL #. 011A

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY # \_\_\_\_\_

SAMPLE BEG DPETH (FT) 0SAMPLE END DPETH (FT) 1GRAB ☒ COMPOSITE ☒ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE

MATRIX SPIKE (MS) \_\_\_\_\_

MATRIX SPIKE DUP (SD) \_\_\_\_\_

FIELD DUP (FD) \_\_\_\_\_

AMBIENT BLANK (AB) N/AEQUIPMENT BLANK (EB) EB082101TRIP BLANK (TB) TB082101

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
agm 2.0L HDPE	3	Cool to 4C HCl to pH < 2	SW8260B	VOCs (App IX) + <u>CIS 12 DCE</u>
4oz 2.0L HDPE	1	Cool to 4C	SW8270C	SVOCs (App IX)
4oz 2.0L HDPE	1	Cool to 4C NaOH pH > 12	SW 6010B / 7000	Total Metals (App IX) + <u>Hg</u>

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <u>0.0 ppm</u>	COLOR	
2nd	ODOR	
	OTHER	
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Specific Conductivity _____ (umhos/cm)
	Turbidity _____ (NTU)	

## GENERAL INFORMATION

WEATHER SUN/CLEAR ☒ OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION SE AMBIENT TEMPERATURE 90°FSHIPMENT VIA FEDX ☒ HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_SHIPPED TO STL - Chicago

COMMENTS \_\_\_\_\_

SAMPLER M JohnstonOBSERVER J Rihls

MATRIX TYPE CODES		SAMPLING METHOD CODES	
HC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LJI=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	IL=HOLD LOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DI=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



**FIELD SAMPLING REPORT**

LOCATION: <u>NAS FLD J23</u>		PROJECT NAME: <u>Phase II RFI FT-001</u>	
SITE: <u>AOC 19</u>		PROJECT NO: <u>AFC001-26CC</u>	
<b>SAMPLE INFORMATION</b>			
SAMPLE ID: <u>DUP005</u>		DATE: <u>7 20 01</u> TIME: <u>1700</u>	
MATRIX TYPE: <u>SO</u>		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD): <u>BLK ACC FIC 7-03</u> AMBIENT BLANK (AB) <u>N/A</u> EQUIPMENT BLANK (EB) <u>EBL 2001</u> TRIP BLANK (TB) <u>TB 22001</u>	
SAMPLING METHOD: <u>SS</u>			
LOT CONTROL # <u>011A</u>			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #: _____			
SAMPLE BEG DPETH (FT) <u>9.75</u>			
SAMPLE END DPETH (FT) <u>10.25</u>			
GRAB (X) COMPOSITE ( )			
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
5g Encore 3	Cool to 4C	SW8260B	TCE

<b>NOTABLE OBSERVATIONS</b>			
PID READINGS		SAMPLE CHARACTERISTICS	
1st <u>C.C. ppm</u>	COLOR <u>Y</u>		
2nd	ODOR <u>none</u>		
OTHER _____			
pH _____ Temperature _____ (C) Dissolved Oxygen _____ (mg/L) Specific Conductivity _____ (umhos/cm) Iron _____ (mg/L) Oxidation/Reduction Potential _____ (mv) Turbidity _____ (NTU)			
<b>GENERAL INFORMATION</b>			
WEATHER <u>SUN/CLEAR</u> <input checked="" type="checkbox"/> <u>OVERCAST/RAIN</u> <input type="checkbox"/> WIND DIRECTION _____ AMBIENT TEMPERATURE <u>100 F</u>			
SHIPMENT VIA <u>FEDEX</u> <input checked="" type="checkbox"/> <u>HAND DELIVER</u> <input type="checkbox"/> <u>COURIER</u> <input type="checkbox"/> <u>OTHER</u> _____			
SHIPPED TO <u>STL - Chicago</u>			
COMMENTS _____			
SAMPLER <u>G. K. H.</u>		OBSERVER <u>M. Johnston</u>	
MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

724 327

315A.NW.7229

7/2/03



## FIELD SAMPLING REPORT

CATION: NAS Fort Worth JRB, TX		PROJECT NAME: Phase II RFI FT-001	
SITE: AOC 19		PROJECT NO: AFC001-26CC	
<b>SAMPLE INFORMATION</b>			
SAMPLE ID: BHGLAOC1907-03		DATE: <u>8-20-01</u> TIME: <u>1400</u>	
MATRIX TYPE: SO		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) <u>Duplicate</u> AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB): <u>EB0000001</u> TRIP BLANK (TB): <u>TB0000001</u>	
SAMPLING METHOD: SS			
LOT CONTROL # <u>C 1 1 A</u>			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #: _____			
SAMPLE BEG DPETH (FT) <u>9.75</u>			
SAMPLE END DPETH (FT) <u>10.25</u>			
GRAB ( ) COMPOSITE ( )			
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
5g Encore 3	Cool to 4C	SW8260B	TCE

NOTABLE OBSERVATIONS			
PID READINGS		SAMPLE CHARACTERISTICS	
1st	<u>2.30m</u>	COLOR	
2nd	<u>2.30m</u>	ODOR: <u>None</u>	
		OTHER	
pH _____ Temperature _____ (C) Dissolved Oxygen _____ (mg/L) Specific Conductivity _____ (umhos/cm)			
Iron _____ (mg/L) Oxidation/Reduction Potential _____ (mv) Turbidity _____ (NTU)			
GENERAL INFORMATION			
WEATHER: SUN/CLEAR <u>✓</u> OVERCAST/RAIN _____		WIND DIRECTION <u>5</u> AMBIENT TEMPERATURE <u>100°F</u>	
SHIPMENT VIA: FEDEX <u>x</u> HAND DELIVER _____		COURIER _____ OTHER _____	
SHIPPED TO: <u>STL - Chicago</u>			
COMMENTS _____			
SAMPLER: <u>M. Johnston</u>		OBSERVER: <u>J. R. R.</u>	
<b>MATRIX TYPE CODES</b> DC=DRILL CUTTINGS SL=SLUDGE WG=GROUND WATER SO=SOIL LH=HAZARDOUS LIQUID WASTE GS=SOIL GAS SH=HAZARDOUS SOLID WASTE WS=SURFACE WATER SE=SEDIMENT SW=SWAB/WIPE		<b>SAMPLING METHOD CODES</b> B=BAILER G=GRAB BP=BLADDER PUMP HA=HAND AUGER BR=BRASS RING H=HOLLOW STEM AUGER CS=COMPOSITE SAMPLE HP=HYDRO PUNCH C=CONTINUOUS FLIGHT AUGER SS=SPLIT SPOON DT=DRIVEN TUBE SP=SUBMERSIBLE PUMP	



**BEST AVAILABLE COPY**  
**FIELD SAMPLING REPORT**

724 328

CATION	NAS Fort Worth JRB, TX	PROJECT NAME	Phase II RFI FT-001																
SITE:	AOC 19	PROJECT NO:	AFC001-26CC																
<b>SAMPLE INFORMATION</b>																			
SAMPLE ID BHGLAOC1906-02		DATE: <u>8-20-01</u> TIME: <u>1435</u>																	
MATRIX TYPE: SO		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE																	
SAMPLING METHOD: SS																			
LOT CONTROL # <u>0 1 1 A</u>																			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)																			
CHAIN-OF-CUSTODY #. _____																			
SAMPLE BEG DPETH (FT) <u>4.75</u>		MATRIX SPIKE (MS) _____																	
SAMPLE END DPETH (FT) <u>5.25</u>		MATRIX SPIKE DUP (SD) _____																	
GRAB ( <input checked="" type="checkbox"/> ) COMPOSITE ( )		FIELD DUP (FD) _____																	
		AMBIENT BLANK (AB) <u>N/A</u>																	
		EQUIPMENT BLANK (EB) <u>CB082001</u>																	
		TRIP BLANK (TB) <u>7B082001</u>																	
<table border="1" style="width: 100%; border-collapse: collapse;"><tr><td style="width: 15%;">CONTAINER</td><td style="width: 15%;">PRESERVATIVE/ PREPARATION</td><td style="width: 25%;">ANALYTICAL METHOD</td><td style="width: 45%;">ANALYSIS</td></tr><tr><td>SIZE/TYPE</td><td>#</td><td></td><td></td></tr><tr><td>5g Encore</td><td>3</td><td>Cool to 4C</td><td>SW8260B</td></tr><tr><td></td><td></td><td></td><td>TCE</td></tr></table>				CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS	SIZE/TYPE	#			5g Encore	3	Cool to 4C	SW8260B				TCE
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS																
SIZE/TYPE	#																		
5g Encore	3	Cool to 4C	SW8260B																
			TCE																

**NOTABLE OBSERVATIONS**

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <u>0.00ppm</u>	COLOR _____	
2nd _____	ODOR <u>None</u>	
	OTHER _____	
pH _____ Temperature _____ (C) Dissolved Oxygen _____ (mg/L) Specific Conductivity _____ (umhos/cm)		
Iron _____ (mg/L) Oxidation/Reduction Potential _____ (mv) Turbidity _____ (NTU)		

**GENERAL INFORMATION**

WEATHER	SUN/CLEAR <input checked="" type="checkbox"/>	OVERCAST/RAIN _____	WIND DIRECTION _____	AMBIENT TEMPERATURE <u>10.0</u>
SHIPMENT VIA	FEDEX <input checked="" type="checkbox"/>	HAND DELIVER _____	COURIER _____	OTHER _____
SHIPPED TO <u>STL - Chicago</u>				
COMMENTS _____				
SAMPLER <u>MT Johnston</u>		OBSERVER <u>J L L</u>		

MATRIX TYPE CODES	SAMPLING METHOD CODES
DC=DRILL CUTTINGS	B=BAILER
WG=GROUND WATER	BP=BLADDER PUMP
LH=HAZARDOUS LIQUID WASTE	BR=BRASS RING
SH=HAZARDOUS SOLID WASTE	CS=COMPOSITE SAMPLE
SE=SEDIMENT	C=CONTINUOUS FLIGHT AUGER
	DT=DRIVEN TUBE
SL=SLUDGE	G=GRAB
SO=SOIL	HA=HAND AUGER
GS=SOIL GAS	H=HOLLOW STEM AUGER
WS=SURFACE WATER	HP=HYDRO PUNCH
SW=SWAB/WIPE	SS=SPLIT SPOON
	SP=SUBMERSIBLE PUMP

724 329



**BEST-AVAILABLE COPY**  
**FIELD SAMPLING REPORT**

LOCATION	NAS Fort Worth JRB, TX	PROJECT NAME	Phase II RFI FT-001
SITE:	AOC 19	PROJECT NO.	AFC001-26CC
<b>SAMPLE INFORMATION</b>			
SAMPLE ID    BHGLAOC1906-03		DATE: <u>8-20-01</u> TIME: <u>1457</u>	
MATRIX TYPE: SO		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) <u>1314</u> EQUIPMENT BLANK (EB) <u>EP 2201</u> TRIP BLANK (TB) <u>TR 52001</u>	
SAMPLING METHOD: SS			
LOT CONTROL # <u>C 1 1 A</u>			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #. _____			
SAMPLE BEG DPETH (FT) <u>9.75</u>			
SAMPLE END DPETH (FT) <u>10.25</u>			
GRAB (X) COMPOSITE ( )			
CONTAINER		PRESERVATIVE/	ANALYTICAL
SIZE/TYPE	#	PREPARATION	METHOD
5g Encore	3	Cool to 4C	SW8260B
			ANALYSIS
			TCE

**NOTABLE OBSERVATIONS**

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <u>0.0ppm</u>	COLOR _____	
2nd _____	ODOR <u>None</u>	
	OTHER _____	
pH _____ Temperature _____ (C)    Dissolved Oxygen _____ (mg/L)    Specific Conductivity _____ (umhos/cm)		
Iron _____ (mg/L)    Oxidation/Reduction Potential _____ (mv)    Turbidity _____ (NTU)		

**GENERAL INFORMATION**

WEATHER: SUN/CLEAR X    OVERCAST/RAIN \_\_\_\_\_    WIND DIRECTION \_\_\_\_\_    AMBIENT TEMPERATURE 99 f  
 SHIPMENT VIA: FEDEX x    HAND DELIVER \_\_\_\_\_    COURIER \_\_\_\_\_    OTHER \_\_\_\_\_  
 SHIPPED TO STL - Chicago  
 COMMENTS \_\_\_\_\_  
 SAMPLER M. Johnson    OBSERVER T. Libs

MATRIX TYPE CODES	SAMPLING METHOD CODES
DC=DRILL CUTTINGS    SL=SLUDGE	B=BAILER    G=GRAB
WG=GROUND WATER    SO=SOIL	BP=BLADDER PUMP    HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE    GS=SOIL GAS	BR=BRASS RING    H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE    WS=SURFACE WATER	CS=COMPOSITE SAMPLE    HP=HYDRO PUNCH
SE=SEDIMENT    SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER    SS=SPLIT SPOON
	DT=DRIVEN TUBE    SP=SUBMERSIBLE PUMP



**BEST AVAILABLE  
COPY**  
**FIELD SAMPLING REPORT**

724 330

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME Phase II RFI FT-001

SITE: AOC 19

PROJECT NO: AFC001-26CC

**SAMPLE INFORMATION**

SAMPLE ID BHGLAOC1905-03

DATE: 8-20-01 TIME: 1600

MATRIX TYPE: SO

SAMPLING METHOD: SS

LOT CONTROL #: C 1 1 E

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #: \_\_\_\_\_

SAMPLE BEG DPETH (FT) 9.5

SAMPLE END DPETH (FT) 10

GRAB (X) COMPOSITE ( )

ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE

MATRIX SPIKE (MS) \_\_\_\_\_

MATRIX SPIKE DUP (SD). \_\_\_\_\_

FIELD DUP (FD) \_\_\_\_\_

AMBIENT BLANK (AB) N/A

EQUIPMENT BLANK (EB) E3C22CC1

TRIP BLANK (TB) T3C22CC1

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
5g Encore	3	Cool to 4C	SW8260B	VOL (H <sub>2</sub> O, H <sub>2</sub> SO <sub>4</sub> )
4oz Jar	2	Cool to 4C	SW8260B and GC/MS	VOL (H <sub>2</sub> O, H <sub>2</sub> SO <sub>4</sub> ) and Hg

**NOTABLE OBSERVATIONS**

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st 0.6 ppm	COLOR	
2nd	ODOR None	
	OTHER	
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Specific Conductivity _____ (umhos/cm)
	Turbidity _____ (NTU)	

**GENERAL INFORMATION**

WEATHER SUN/CLEAR X OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION \_\_\_\_\_ AMBIENT TEMPERATURE 122 F

SHIPMENT VIA FEDEX X HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

SHIPPED TO: STL - Chicago

COMMENTS: \_\_\_\_\_

SAMPLER: Rich

OBSERVER: M Johnston

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



724,331

BEST AVAILABLE  
COPY

## FIELD SAMPLING REPORT

LOCATION: NAS Fw JCB		PROJECT NAME: Phase II RFI FT-001	
SITE: AOC 19		PROJECT NO.: AFC001-26CC	
<b>SAMPLE INFORMATION</b>			
SAMPLE ID: BHGLAOC1905-02		DATE: 8-20-01 TIME: 1552	
MATRIX TYPE: SO		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) <u>WHA</u> EQUIPMENT BLANK (EB) <u>EB072001</u> TRIP BLANK (TB) <u>TB072001</u>	
SAMPLING METHOD: SS			
LOT CONTROL #: <u>C 1 1 A</u>			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #: _____			
SAMPLE BEG DPETH (FT) <u>4.75</u>			
SAMPLE END DPETH (FT) <u>5.25</u>			
GRAB (X) COMPOSITE ( )			
CONTAINER		PRESERVATIVE/	ANALYTICAL
SIZE/TYPE	#	PREPARATION	METHOD
5g Encore	3	Cool to 4C	SW8260B
4oz jar	2	cool to 4C	SW8260C / SW8260B
			ANALYSIS
			AC (Apply) + 0.5% FCB
			ENVS (Apply) and Analyst Hg
<b>NOTABLE OBSERVATIONS</b>			
PID READINGS		SAMPLE CHARACTERISTICS	
1st <u>1.0 ppm</u>		COLOR	
2nd		ODOR <u>None</u>	
		OTHER	
pH _____ Temperature _____ (C) Dissolved Oxygen _____ (mg/L) Specific Conductivity _____ (umhos/cm)			
Iron _____ (mg/L) Oxidation/Reduction Potential _____ (mv) Turbidity _____ (NTU)			
<b>GENERAL INFORMATION</b>			
WEATHER SUN/CLEAR <u>X</u> OVERCAST/RAIN _____ WIND DIRECTION _____ AMBIENT TEMPERATURE <u>80F</u>			
SHIPMENT VIA. FEDEX <u>x</u> HAND DELIVER _____ COURIER _____ OTHER _____			
SHIPPED TO <u>STL - Chicago</u>			
COMMENTS: _____			
SAMPLER: <u>D. R. H.</u>		OBSERVER: <u>W. J. H.</u>	
MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



## FIELD SAMPLING REPORT

CATION	NAS Fort Worth JRB, TX	PROJECT NAME	Phase II RFI FT-001
SITE	<del>hac</del> 19	PROJECT NO.	AFC001-260C
<b>SAMPLE INFORMATION</b>			
SAMPLE ID		DATE	TIME
<del>FT09-12A-WG01</del> <b>BK61AOC1908-02</b>		<b>8-21-01</b>	<b>845</b>
MATRIX TYPE: <b>WG SO</b>		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <b>2B082101</b> TRIP BLANK (TB) <b>TB082101</b>	
SAMPLING METHOD: <b>DT</b>			
LOT CONTROL #: <b>011A</b>			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY # _____			
SAMPLE BEG DPETH (FT) <b>4.5</b>			
SAMPLE END DPETH (FT) <b>5.5</b>			
GRAB <input checked="" type="checkbox"/> COMPOSITE <input checked="" type="checkbox"/>			
CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD
SIZE/TYPE	#		
<del>SW</del> <b>CHL-VOM</b>	3	Cool to 4C <del>HCl to pH=2</del> <b>NaOH pH=9</b>	SW8260B
<del>br</del> <b>1-L Amber</b>	3	Cool to 4C	SW8270C
<del>for</del> <b>1-L Poly</b>	1	Cool to 4C <del>NaOH pH=9</del>	SW6010B / 7000
			ANALYSIS
			VOCs (App IX) + <b>cis 1,2 DCE</b>
			SVOCs (App IX)
			<del>Trace</del> Metals (App IX) + <b>Hg</b>
<b>NOTABLE OBSERVATIONS</b>			
PID READINGS		SAMPLE CHARACTERISTICS	
1st		COLOR	
2nd		ODOR	
		OTHER	
pH _____ Temperature _____ (C) Dissolved Oxygen _____ (mg/L) Specific Conductivity _____ (umhos/cm)			
Iron _____ (mg/L) Oxidation/Reduction Potential _____ (mv) Turbidity _____ (NTU)			
<b>GENERAL INFORMATION</b>			
WEATHER: SUN/CLEAR <input checked="" type="checkbox"/> OVERCAST/RAIN _____ WIND DIRECTION <b>SE</b> AMBIENT TEMPERATURE <b>90°F</b>			
SHIPMENT VIA FEDEX <input checked="" type="checkbox"/> HAND DELIVER _____ COURIER _____ OTHER _____			
SHIPPED TO: <b>STL - Chicago</b>			
COMMENTS _____			
SAMPLER: <b>M Johnston</b>		OBSERVER: <b>J Ellis</b>	
MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

# FIELD SAMPLING REPORT

LOCATION	NAS Fort Worth JRB, TX	PROJECT NAME	Phase II RFI FT-001																									
SITE	AOC my 19	PROJECT NO	AFC001-260C																									
<b>SAMPLE INFORMATION</b>																												
SAMPLE ID <del>EL00-1244500</del> BH6LAOC1908-03		DATE: 8-21-01 TIME 855																										
MATRIX TYPE. <del>NO</del> SD		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) EB082101 TRIP BLANK (TB) _____																										
SAMPLING METHOD: <del>BT</del> DT																												
LOT CONTROL # 0 1 1 A																												
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)																												
CHAIN OF-CUSTODY # _____																												
SAMPLE BEG DPETH (FT) 9.5																												
SAMPLE END DPETH (FT) 10.5																												
GRAB (X) COMPOSITE (X)																												
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th colspan="2">CONTAINER</th> <th>PRESERVATIVE/ PREPARATION</th> <th>ANALYTICAL METHOD</th> <th>ANALYSIS</th> </tr> <tr> <th>SIZE/TYPE</th> <th>#</th> <td></td> <td></td> <td></td> </tr> <tr> <td>5 gal. metal drum</td> <td>3</td> <td>Cool to 4C <del>NO</del></td> <td>SW8260B</td> <td>VOCs (App IX) + cis 1,2 DCE</td> </tr> <tr> <td>1 gal. metal drum</td> <td>2</td> <td>Cool to 4C</td> <td>SW8270C</td> <td>SVOCs (App IX)</td> </tr> <tr> <td>4 oz. metal can</td> <td>1</td> <td>Cool to 4C <del>NO</del></td> <td>SW6010B / 7000</td> <td>Total Metals (App IX) + Hg</td> </tr> </table>				CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS	SIZE/TYPE	#				5 gal. metal drum	3	Cool to 4C <del>NO</del>	SW8260B	VOCs (App IX) + cis 1,2 DCE	1 gal. metal drum	2	Cool to 4C	SW8270C	SVOCs (App IX)	4 oz. metal can	1	Cool to 4C <del>NO</del>	SW6010B / 7000	Total Metals (App IX) + Hg
CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS																								
SIZE/TYPE	#																											
5 gal. metal drum	3	Cool to 4C <del>NO</del>	SW8260B	VOCs (App IX) + cis 1,2 DCE																								
1 gal. metal drum	2	Cool to 4C	SW8270C	SVOCs (App IX)																								
4 oz. metal can	1	Cool to 4C <del>NO</del>	SW6010B / 7000	Total Metals (App IX) + Hg																								

NOTABLE OBSERVATIONS			
PID READINGS		SAMPLE CHARACTERISTICS	
1st 0.0 ppm	COLOR		
2nd	ODOR		
OTHER			
pH _____ Temperature _____ (C) Dissolved Oxygen _____ (mg/L) Specific Conductivity _____ (umhos/cm)			
Iron _____ (mg/L) Oxidation/Reduction Potential _____ (mv) Turbidity _____ (NTU)			
GENERAL INFORMATION			
WEATHER SUN/CLEAR X OVERCAST/RAIN _____		WIND DIRECTION SE AMBIENT TEMPERATURE 90 F	
SHIPMENT VIA FEDEX X HAND DELIVER _____		COURIER _____ OTHER _____	
SHIPPED TO STL - Chicago			
COMMENTS _____			
SAMPLER J Rihs		OBSERVER m Johnston	
<b>MATRIX TYPE CODES</b> DC=DRILL CUTTINGS SL=SLUDGE WG=GROUND WATER SO=SOIL LH=HAZARDOUS LIQUID WASTE GS=SOIL GAS SH=HAZARDOUS SOLID WASTE WS=SURFACE WATER SE=SEDIMENT SW=SWAB WIPE		<b>SAMPLING METHOD CODES</b> B=BAILER G=GRAB BP=BLADDER PUMP HA=HAND AUGER BR=BRASS RING H=HOLLOW STEM AUGER CS=COMPOSITE SAMPLE HP=HYDRO PUNCH C=CONTINUOUS FLIGHT AUGER SS=SPLIT SPOON DT=DRIVEN TUBE SP=SUBMERSIBLE PUMP	

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: Phase II RFI FT-001

SITE: ~~AOC~~ ~~SWMU 19~~

PROJECT NO AFC001-26C6

## SAMPLE INFORMATION

SAMPLE ID <del>FE001247001</del> <b>BA6LA0C190A-02</b>		DATE: <b>8-22-01</b>	TIME: <b>1535</b>
MATRIX TYPE <b>WCH SU</b>		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (ID) _____ AMBIENT BLANK (AB) <b>N/A</b> EQUIPMENT BLANK (EB) <b>58082201</b> TRIP BLANK (TB) <b>N/A</b>	
SAMPLING METHOD <b>BP DT</b>			
LOT CONTROL # <b>0 1 1 A</b>			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY # _____			
SAMPLE BEG DEPTH (FT) <b>4.5</b>			
SAMPLE END DEPTH (FT) <b>5.5</b>			
GRAB ( ) COMPOSITE (X)			
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
TIME FOR			
<del>4.2 L Amber</del>	<del>Cool to 4C</del>	<del>SW8270C</del>	<del>SVOCs (App IX)</del>
<del>1.2 L Poly</del>	<del>Cool to 4C NaOH, 1% D</del>	<del>SW6010B</del>	<del>Total Metals (App IX)</del>

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <b>0.0 ppm</b>	COLOR	
2nd	ODOR <b>None</b>	
	OTHER	
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Specific Conductivity _____ (umhos/cm)
	Turbidity _____ (NTU)	

## GENERAL INFORMATION

WTA HLR	SUN/CLEAR <b>X</b>	OVERCAST/RAIN _____	WIND DIRECTION <b>SE</b>	AMBIENT TEMPERATURE <b>75 F</b>
SHIPMENT VIA	FEDEX <b>X</b>	HAND DELIVER _____	COURIER _____	OTHER _____
SHIPPED TO <b>SFL - Chicago</b>				
COMMENTS _____				
SAMPLER <b>J Kuba</b>		OBSERVER <b>M Johnston</b>		

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC = DRIED CUTTINGS	SI = SLUDGE	B = BAILER	G = GRAB
WG = GROUND WATER	SO = SOIL	BP = BLADDER PUMP	HA = HAND AUGER
LH = HAZARDOUS LIQUID WASTE	GS = SOIL GAS	BR = BRASS RING	HI = HOLLOW STEM AUGER
SH = HAZARDOUS SOLID WASTE	WS = SURFACE WATER	CS = COMPOSITE SAMPLE	HP = HYDRO PUNCH
ST = SEDIMENT	SW = SWAB/WIPE	C = CONTINUOUS FLIGHT AUGER	SS = SPIIT SPOON
		DT = DRIVEN TUBE	SP = SUBMERSIBLE PUMP

## FIELD SAMPLING REPORT

LOCATION NAS Fort Worth JRB, TX

PROJECT NAME: Phase II RFI FT-001

SITE ~~W-3 WING~~ 19 <sup>AOC</sup>

PROJECT NO: AFC001-26CC

## SAMPLE INFORMATION

SAMPLE ID ~~109-12AW007~~ <sup>BNGLAOC1910-01</sup>

DATE: 8-22-01 TIME: 1545

MATRIX TYPE: ~~MS~~ SOENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:SAMPLING METHOD ~~DT~~ DTMATRIX SPIKE (MS) ✓

LOT CONTROL # 0 1 1 A

MATRIX SPIKE DUP (SD) ✓

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

FIELD DUP (FD) \_\_\_\_\_

CHAIN-OF-CUSTODY # \_\_\_\_\_

AMBIENT BLANK (AB) N/A

SAMPLE BEG DPETH (FT)

EQUIPMENT BLANK (EB) 28032201

SAMPLE END DPETH (FT)

TRIP BLANK (TB) \_\_\_\_\_

GRAB ( ) COMPOSITE ( )

CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA 3	Cool to 4C HCl to pH 2	SW8260A	PCBs (App IX)
102 mL Amber 3	Cool to 4C	SW8270C	SVOCs (App IX)
1 L 100 7	Cool to 4C N <sub>2</sub> to pH 2	SW8270C	Total Metals (App IX)

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st 0.0 ppm	COLOR	
2nd	ODOR <u>None</u>	
	OTHER	
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mV)	Specific Conductivity _____ (umhos/cm)
	Turbidity _____ (NTU)	

## GENERAL INFORMATION

WEATHER SUN/CLEAR X OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION SE AMBIENT TEMPERATURE 95 FSHIPMENT VIA: FEDEX x HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_SHIPPED TO SIL - Chicago

COMMENTS: \_\_\_\_\_

SAMPLER J RihsOBSERVER M Johnston

MATRIX TYPE CODES	SAMPLING METHOD CODES
DC=DRI LL CUTTINGS	B=BAILER
WG=GROUND WATER	BP=BLADDER PUMP
LH=HAZARDOUS LIQUID WASTE	BR=BRASS RING
SH=HAZARDOUS SOLID WASTE	CS=COMPOSITE SAMPLE
SF=SEDIMENT	C=CONTINUOUS FLIGHT AUGER
SL=SLUDGE	DT=DRIVEN TUBE
SO=SOIL	G=GRAB
GS=SOIL GAS	HA=HAND AUGER
WS=SURFACE WATER	HA=HOLLOW STEM AUGER
SW=SWAB/WIPE	HP=HYDRO PUNCH
	SS=SPLIT SPOON
	SP=SUBMERSIBLE PUMP

LOCATION NAS Fort Worth JRB, TX PROJECT NAME Phase II RFI F1-001  
 DATE 8-22-01 PROJECT NO. AFC001-2600

### SAMPLE INFORMATION

SAMPLE ID <u>109-12A-001</u> <u>BHGLAOC1910-01MS</u>	DATE: <u>8-22-01</u> TIME <u>1545</u>
MATRIX TYPE <u>SO</u>	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) <u>✓</u> MATRIX SPIKE DUP (SD) <u>✓</u> FIELD DUP (FD) _____ AMBIENT BLANK (AB) <u>N/A</u> EQUIPMENT BLANK (EB) <u>28032201</u> TRIP BLANK (TB) _____
SAMPLING METHOD <u>DT</u>	
LOT CONTROL # <u>0 1 1 A</u>	
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)	
CHAIN OF CUSTODY # _____	
SAMPLE BEG DPETH (FT) _____	
SAMPLE END DPETH (FT) _____	
GRAB ( ) COMPOSITE ( )	

CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
10 mL VOA	Cool to 4C HCL to pH 2	SW8260A	SVOCs (App IX)
1/2 L Amber	Cool to 4C	SW8270C	SVOCs (App IX)
1 L Poly	Cool to 4C HCL to pH 2	SW8260A	Total Metals (App IX)

### NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <u>0.0ppm</u>	COLOR _____	
2nd _____	ODOR <u>None</u>	
	OTHER _____	
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Specific Conductivity _____ (umhos/cm)
	Turbidity _____ (NTU)	

### GENERAL INFORMATION

WEATHER SUN/CLAR ☒ OVERCAST/RAIN ☐ WIND DIRECTION SE AMBIENT TEMPERATURE 95 F  
 SHIPMENT VIA FEDX ☒ HAND DELIVER ☐ COURIER ☐ OTHER ☐  
 SHIPPED TO SIL - Chicago  
 COMMENTS \_\_\_\_\_  
 SAMPLER J Rihs OBSERVER M Johnston

MATRIX TYPE CODES	SAMPLING METHOD CODES
DC - DRILL CUTTINGS	B - BAILER
WG - GROUND WATER	BP - BLADDER PUMP
LH - HAZARDOUS LIQUID WASTE	BR - BRASS RING
SH - HAZARDOUS SOLID WASTE	CS - COMPOSITE SAMPLE
SE - SEDIMENT	C - CONTINUOUS FLIGHT AUGER
SI - SLUDGE	DT - DRIVEN TUBE
SO - SOIL	G - GRAB
GS - SOIL GAS	HA - HAND AUGER
WS - SURFACE WATER	HS - HOLLOW STEM AUGER
SW - SWAB/WIFE	HP - HYDRO PUNCH
	SS - SPIRIT SPOON
	SP - SUMMERSIDE PUMP

## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: Phase II RFI FF-001

SITE: ~~WJ-011110~~ <sup>AOC</sup> 19

PROJECT NO: AF-C001-260C

## SAMPLE INFORMATION

SAMPLE ID: <del>WJ-011110-01ND</del> <sup>BH6LAOC1910-01ND</sup>	DATE: <u>8-22-01</u> TIME: <u>1545</u>
MATRIX TYPE: <del>WJ</del> <u>SO</u>	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE.  MATRIX SPIKE (MS) <u>✓</u> MATRIX SPIKE DUP (SD) <u>✓</u> FIELD DUP (FD) _____ AMBIENT BLANK (AB) <u>N/A</u> EQUIPMENT BLANK (EB) <u>28032201</u> TRIP BLANK (TB) _____
SAMPLING METHOD: <del>WJ</del> <u>DT</u>	
LOT CONTROL # <u>011A</u>	
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)	
CHAIN OF CUSTODY # _____	
SAMPLE BEG DPETH (FT)	
SAMPLE END DPETH (FT)	
GRAB ( ) COMPOSITE ( )	

CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE			
100 mL VOA	Cool to 4C HCl to pH 2	SW8260A	VOCs (App IX)
1 L Amber	Cool to 4C	SW8270C	SVOCs (App IX)
1 L Poly	Cool to 4C HCl to pH 2	SW8260A	Total Metals (App IX)

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <u>0.0 ppm</u>	COLOR	
2nd	ODOR <u>None</u>	
	OTHER	
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Specific Conductivity _____ (umhos/cm)
	Turbidity _____ (NTU)	

## GENERAL INFORMATION

WEATHER	SUN/CLAR <u>X</u>	OVERCAST/RAIN _____	WIND DIRECTION <u>SE</u>	AMBIENT TEMPERATURE <u>95 F</u>
SHIPMENT VIA	FEDEX <u>X</u>	HAND DELIVER _____	COURIER _____	OTHER _____
SHIPPED TO	<u>SIL - Chicago</u>			
COMMENTS	_____			
SAMPLER	<u>J Rihs</u>		OBSERVER	<u>M Johnston</u>

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC - DEEP CUTTINGS	SI - SLUDGE	B - BAILER	G - GRAB
WG - GROUND WATER	SO - SOIL	BP - BLADDER PUMP	HA - HAND AUGER
LH - HAZARDOUS LIQUID WASTE	GS - SOIL GAS	BR - BRASS RING	H - HOLLOW STEM AUGER
SH - HAZARDOUS SOLID WASTE	WS - SURFACE WATER	CS - COMPOSITE SAMPLE	HP - HYDRO PUNCH
SE - SEDIMENT	SW - SWAB/WIPE	C - CONTINUOUS FLIGHT AUGER	SS - SPIRIT SPOON
		DT - DRIVEN TUBE	SP - SUBMERSIBLE PUMP

LOCATION SITE	NAS Fort Worth JRB, TX AOC RWMD 19	PROJECT NAME	Phase II RFI FT-001
		PROJECT NO	AFC001-26CG
SAMPLE INFORMATION			
SAMPLE ID	<del>BH61AOC1910-02</del> AFC001-26CG-02	DATE	8-22-01
MATRIX TYPE	WH SU	TIME	1535 1555
SAMPLING METHOD	HH DT	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE	
LOT CONTROL #	0 L L A	MATRIX SPIKE (MS) _____	
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)		MATRIX SPIKE DUP (SD) _____	
CHAIN-OF-CUSTODY #		FIELD DUP (FD) _____	
SAMPLE BEGIN DEPTH (FT)	4.5	AMBIENT BLANK (AB) N/A	
SAMPLE END DEPTH (FT)	5.5	EQUIPMENT BLANK (EB) EB072201	
GRAB ( ) COMPOSITE (X)		TRIP BLANK (TB) N/A	
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#		
WATER	1	SW8260A	Metals (App IX)
1/2 L Amber	1	SW8270C	SVOCs (App IX)
1 L Poly	1	SW6010B	Total Metals (App IX)

## NOTABLE OBSERVATIONS

FID READINGS		SAMPLE CHARACTERISTICS		MISCELLANEOUS	
1st	0.01ppm	COLOR			
2nd		ODOR	NONE		
		OTHER			
pH		Temperature	(C)	Dissolved Oxygen	(mg/L)
Iron		Oxidation/Reduction Potential	(mv)	Specific Conductivity	(umhos/cm)
		Turbidity	(NTU)		

## GENERAL INFORMATION

WEATHER	SUN/CLAR	X	OVERCAST/RAIN		WIND DIRECTION	SE	AMBIENT TEMPERATURE	75 F
SHIPMENT VIA	FEDEX	X	HAND DELIVER		COURIER		OTHER	
SHIPPED TO	SIL - Chicago							
COMMENTS								
SAMPLER	J. Kuba			SERVER	M. Johnston			

MATRIX TYPE CODES		SAMPLING METHOD CODES	
OC=DRILL CUTTINGS	SL=SLUDGE	B=BAH LER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	HL=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SUPERFICIAL WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
ST=SEDIMENT	SW=SWAB/WIPE	CC=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



724 339



## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: Phase II RFI FT-001

SITE: ~~CHURCH~~ 19

PROJECT NO AFC001-26CE

## SAMPLE INFORMATION

SAMPLE ID	<del>10-11-001</del> 6H6L90C1910-03	DATE: 8-22-01	TIME: 1605
MATRIX TYPE	SO	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:	
SAMPLING METHOD	DT		
LOT CONTROL #	011A		
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #		MATRIX SPIKE (MS) _____	
SAMPLE BEG DPETH (FT) 9.5		MATRIX SPIKE DUP (SD) _____	
SAMPLE END DPETH (FT) 10.5		FIELD DUP (FD) _____	
GRAB ( ) COMPOSITE (X)		AMBIENT BLANK (AB) _____	
		EQUIPMENT BLANK (EB) <u>EB082201</u>	
		TRIP BLANK (TB) _____	

CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA	Cool to 4C	SW8260A	SVOCs (App IX)
1021-6 Amber	Cool to 4C	SW8270C	SVOCs (App IX)
1 L Poly	Cool to 4C	SW8260B	SVOCs (App IX)

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st 2.0 ppm	COLOR	
2nd	ODOR NONE	
	OTHER	
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Specific Conductivity _____ (umhos/cm)
	Turbidity _____ (NTU)	

## GENERAL INFORMATION

WEATHER: SUN/CLEAR X OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION SE AMBIENT TEMPERATURE 98 F

SHIPMENT VIA FEDEX X HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

SHIPPED TO: STL - Chicago

COMMENTS: \_\_\_\_\_

SAMPLER J. Ribs OBSERVER M. Johnston

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HIA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	HS=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



## FIELD SAMPLING REPORT

724 340

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: Phase III SI

SITE: AOC 19

PROJECT NO: AFC001-26CC

## SAMPLE INFORMATION

SAMPLE ID BHGLAOC1911-03

DATE: 12/65/01 TIME: 1140

MATRIX TYPE: SO

SAMPLING METHOD: DT

LOT CONTROL #: \_\_\_\_\_

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #: \_\_\_\_\_

SAMPLE BEG DPETH (FT) 9.5

SAMPLE END DPETH (FT) 10.5

GRAB (X) COMPOSITE ( )

ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:

MATRIX SPIKE (MS) \_\_\_\_\_

MATRIX SPIKE DUP (SD) \_\_\_\_\_

FIELD DUP (FD) DUP04

AMBIENT BLANK (AB) \_\_\_\_\_

EQUIPMENT BLANK (EB) EB120501

TRIP BLANK (TB) TB120501

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
4 oz jar	1	Cool to 4C	SW8270	SVOCs (App IX)

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
0.0	COLOR 10120/6 BROWNISH YELLOW	
	ODOR NONE	
	OTHER	

pH \_\_\_\_\_ Temperature \_\_\_\_\_ (C) Dissolved Oxygen \_\_\_\_\_ (mg/L) Specific Conductivity \_\_\_\_\_ (umhos/cm)

Iron \_\_\_\_\_ (mg/L) Oxidation/Reduction Potential \_\_\_\_\_ (mv) Turbidity \_\_\_\_\_ (NTU)

## GENERAL INFORMATION

WEATHER SUN/CLEAR \_\_\_\_\_ OVERCAST/RAIN X WIND DIRECTION S AMBIENT TEMPERATURE 70°SHIPMENT VIA FEDEX x HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_SHIPPED TO STL - Chicago

COMMENTS. \_\_\_\_\_

SAMPLER ADAM KARSTOBSERVER JONATHAN RINS

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

## FIELD SAMPLING REPORT

LOCATION:	NAS Fort Worth JRB, TX	PROJECT NAME:	Phase III SI
SITE:	AOC 19	PROJECT NO:	AFC001-26CC
<b>SAMPLE INFORMATION</b>			
SAMPLE ID BHGLAOC1912-02		DATE: <u>12/05/01</u> TIME: <u>1125</u>	
MATRIX TYPE: SO		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) <input checked="" type="checkbox"/> <u>BHGLAOC19-02 MS</u> MATRIX SPIKE DUP (SD) <input checked="" type="checkbox"/> <u>BHGLAOC19-02 MS</u> FIELD DUP (FD): _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>EB120501</u> TRIP BLANK (TB) <u>TB120501</u>	
SAMPLING METHOD: DT			
LOT CONTROL #. _____			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #: _____			
SAMPLE BEG DPETH (FT) <u>4.5</u>			
SAMPLE END DPETH (FT) <u>5.5</u>			
GRAB <input checked="" type="checkbox"/> COMPOSITE ( )			
CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD
SIZE/TYPE	#		
4 oz jar	1	Cool to 4C	SW8270
			ANALYSIS
			SVOCs (App IX)

NOTABLE OBSERVATIONS			
PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS	
1st <u>0.0</u>	COLOR <u>10422/2 v. DARK BROWN</u>		
2nd	ODOR <u>None</u>		
OTHER _____			
pH _____ Temperature _____ (C) Dissolved Oxygen _____ (mg/L) Specific Conductivity _____ (umhos/cm) Iron _____ (mg/L) Oxidation/Reduction Potential _____ (mv) Turbidity _____ (NTU)			
GENERAL INFORMATION			
WEATHER. SUN/CLEAR _____ OVERCAST/RAIN <input checked="" type="checkbox"/> WIND DIRECTION <u>S</u> AMBIENT TEMPERATURE <u>70°</u>			
SHIPMENT VIA FEDEX <input checked="" type="checkbox"/> HAND DELIVER _____ COURIER _____ OTHER _____			
SHIPPED TO <u>STL - Chicago</u>			
COMMENTS _____			
SAMPLER <u>ADAM KRIST</u>		OBSERVER <u>JONATHAN EHS</u>	
MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

LOCATION <u>NAS FUEL WORTH JRB</u>		PROJECT: <u>PHASE III SI</u>			
SITE <u>AOC 19</u>		<u>AF001-26CC</u>			
SAMPLE INFORMATION					
MATRIX <u>SOIL</u>		SAMPLE ID. <u>BHGLAOC1912-03</u>			
SAMPLING METHOD <u>DT</u>		DUP/REP. OF: _____			
BEGINNING DEPTH <u>9.5</u>		MATRIX SPIKE/MATRIX SPIKE DUPLICATE YES ( ) NO ( )			
END DEPTH <u>10.5</u>					
GRAB <input checked="" type="checkbox"/> COMPOSITE ( )		DATE: <u>12/05/01</u> TIME: <u>1130</u>			
CONTAINER		PRESERVATIVE/ PREPARATION	EXTRACTION METHOD	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#				
<u>1/2 GZAL</u>	<u>1</u>	<u>NONE 4C</u>		<u>8270C</u>	<u>APP 1X 560LS</u>
NOTABLE OBSERVATIONS					
PID READINGS		SAMPLE CHARACTERISTICS		MISCELLANEOUS	
1st	<u>0.0</u>	COLOR <u>10YR 6/6 BROWNISH YELLOW</u>			
2nd		ODOR <u>NONE</u>			
		OTHER			
pH _____ Temperature _____ Dissolved oxygen _____ Specific Conductivity _____					
GENERAL INFORMATION					
WEATHER		SUN/CLEAR _____	OVERCAST/RAIN <input checked="" type="checkbox"/>	WIND DIRECTION <u>S</u>	AMBIENT TEMP <u>70°</u>
SHIPMENT VIA		FED-X <input checked="" type="checkbox"/>	HAND DELIVER _____	COURIER _____	OTHER _____
SHIPPED TO. <u>DTL-CHICAGO</u>					
COMMENTS: _____					
SAMPLER <u>ADAM KARST</u>			OBSERVER: <u>JONATHAN</u>		
MATRIX TYPE CODES			SAMPLING METHOD CODES		
DC=DRILL CUTTINGS WG=GROUND WATER LH=HAZARDOUS LIQUID WASTE SH=HAZARDOUS SOLID WASTE SE=SEDIMENT			SL=SLUDGE SO=SOIL GS=SOIL GAS WS=SURFACE WATER SW=SWABWIPE		
			B=BAILER BR=BRASS RING CS=COMPOSITE SAMPLE C=CONTINUOUS FLIGHT AUGER DT=DRIVEN TUBE W=SWABWIPE		
			G=GRAB HA=HAND AUGER H=HOLLOW STEM AUGER HP=HYDRO PUNCH SS=SPLIT SPOON SP=SUBMERSIBLE PUMP		

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: Phase III RFI ~~FT-001~~SITE: ~~SWMU~~ 19

PROJECT NO: AFC001-26CC

## SAMPLE INFORMATION

SAMPLE ID BHGLSWMU1938-04 AOC 1913-02		DATE: 12/05/01		TIME: 1215	
MATRIX TYPE: SO		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) EB120501 TRIP BLANK (TB) TB120501			
SAMPLING METHOD: DT					
LOT CONTROL #: _____ (Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)					
CHAIN-OF-CUSTODY #: _____					
SAMPLE BEG DPETH (FT) 5'					
SAMPLE END DPETH (FT): 5'					
GRAB (X) COMPOSITE ( )					
CONTAINER		PRESERVATIVE/ PREPARATION		ANALYTICAL METHOD	
SIZE/TYPE #					
5g Encore 3		Cool to 4C		SW8260B	
				TCE <del>Asbestos</del>	

## NOTABLE OBSERVATIONS

PID READINGS		SAMPLE CHARACTERISTICS		MISCELLANEOUS	
1st	0.0	COLOR	10402/2 VERY DARK BROWN		
2nd		ODOR	NONE		
		OTHER			
pH _____		Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)	Specific Conductivity _____ (umhos/cm)	
Iron _____ (mg/L)		Oxidation/Reduction Potential _____ (mv)	Turbidity _____ (NTU)		

## GENERAL INFORMATION

WEATHER. SUN/CLEAR _____		OVERCAST/RAIN <u>X</u>		WIND DIRECTION <u>S</u>		AMBIENT TEMPERATURE <u>70</u> °	
SHIPMENT VIA FEDEX <u>x</u>		HAND DELIVER _____		COURIER _____		OTHER _____	
SHIPPED TO: STL - Chicago							
COMMENTS _____							
SAMPLER. ADAM KIRST		OBSERVER JONATHAN RUS					

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: Phase III RFI-~~TT-001~~SITE: SWMU-19  
AOC

PROJECT NO: AFC001-26CC

## SAMPLE INFORMATION

SAMPLE ID BHGLSWMU-1938-01-5  
AOC1913-03

DATE: 12/05/01 TIME: 1225

MATRIX TYPE: SO

SAMPLING METHOD: DT

LOT CONTROL #: \_\_\_\_\_

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #: \_\_\_\_\_

SAMPLE BEG DPETH (FT): 10'

SAMPLE END DPETH (FT): 10'

GRAB ☒ COMPOSITE ( )ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:

MATRIX SPIKE (MS): \_\_\_\_\_

MATRIX SPIKE DUP (SD): \_\_\_\_\_

FIELD DUP (FD): \_\_\_\_\_

AMBIENT BLANK (AB): \_\_\_\_\_

EQUIPMENT BLANK (EB): EB120501

TRIP BLANK (TB): TB120501

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
4 oz jar	1	Cool to 4C	SW6010, SW7000	Ba, Cd, Cr, Pb, Zn
4 oz jar	1	Cool to 4C	SW8270	2 methnaph/B2EHP/Naphthalene
5g Encore	3	Cool to 4C	SW8260B	Acetone/BTEX/PCB/TCE

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st 0.0	COLOR	10412 6/8 BROWNISH YELLOW	
2nd	ODOR	NONE	
OTHER			
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)	Specific Conductivity _____ (umhos/cm)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Turbidity _____ (NTU)	

## GENERAL INFORMATION

WEATHER SUN/CLEAR \_\_\_\_\_ OVERCAST/RAIN ☒ WIND DIRECTION S AMBIENT TEMPERATURE 70°SHIPMENT VIA. FEDEX ☒ HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

SHIPPED TO STL - Chicago

COMMENTS \_\_\_\_\_

SAMPLER. ADMIN KRIST

OBSERVER. SONATHAN RUS

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

724 345



## FIELD SAMPLING REPORT

BEST AVAILABLE  
COPY
 LOCATION: NAS Fort Worth JRB, TX  
 SITE: ~~HCC~~ SWMU 19

PROJECT NAME: Phase II RFI FT-001

PROJECT NO: AFC001-26CE

## SAMPLE INFORMATION

SAMPLE ID: FT09-12AWG01 ~~THGL40C1905-01~~

DATE: 8-15-01 TIME: 1225

MATRIX TYPE: WG SC

SAMPLING METHOD: BP GC

LOT CONTROL #: 011A

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #: \_\_\_\_\_

SAMPLE BEG OPETH (FT) 2.5'

SAMPLE END DPETH (FT) 3

GRAB (✓) COMPOSITE (✓)

ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:

MATRIX SPIKE (MS) \_\_\_\_\_

MATRIX SPIKE DUP (SD) \_\_\_\_\_

FIELD DUP (FD) \_\_\_\_\_

AMBIENT BLANK (AB): 211A

EQUIPMENT BLANK (EB) 211A

TRIP BLANK (TB) 211A

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
40 mL VOA	3	Cool to 4C HCl to pH < 2	SW8260A	VOCs (App IX) + 12 Dec
1-L Amber	25	Cool to 4C	SW8270C	SVOCs (App IX)
1-L Poly	1	Cool to 4C NaOH pH > 9	SW6010B/7000	Total Metals (App IX) + Hg

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st 0.000	COLOR	light brown	
2nd 0.000	ODOR	none	
OTHER			
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)	Specific Conductivity _____ (umhos/cm)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Turbidity _____ (NTU)	

## GENERAL INFORMATION

WEATHER: SUN/CLEAR ☒ OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION \_\_\_\_\_ AMBIENT TEMPERATURE 100°FSHIPMENT VIA FEDEX ☒ HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

SHIPPED TO STL - Chicago

COMMENTS \_\_\_\_\_

SAMPLER: M Johnston

OBSERVER: J Kungu

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: Phase II RFI FT-001

SITE: <sup>ACC</sup> SWMU 19

PROJECT NO: AF001-26CE

## SAMPLE INFORMATION

SAMPLE ID FT09-12AWG01 (ID008)501

DATE: 7-15-01 TIME: 1235

MATRIX TYPE: WG SO

SAMPLING METHOD BP<sub>6</sub>

LOT CONTROL # 011A

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #

SAMPLE BEG DPETH (FT) 0

SAMPLE END DPETH (FT) 3

GRAB ( ) COMPOSITE (x)

ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:

MATRIX SPIKE (MS) \_\_\_\_\_

MATRIX SPIKE DUP (SD) \_\_\_\_\_

FIELD DUP (FD) \_\_\_\_\_

AMBIENT BLANK (AB) N/A

EQUIPMENT BLANK (EB) EBC815C1

TRIP BLANK (TB) TBC815C1

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
4.40 mL-VOA	13	Cool to 4C HCl to pH < 2	SW8260A	VOCs (App IX)
1-L Amber	12	Cool to 4C	SW8270C3 TX1005	SVOCs (App IX) TPH
1-L Poly	1	Cool to 4C NaOH-pH > 9	SW6010B 7555	Total Metals (App IX) - Hg
4-L	2	Cool to 4C	SW-826, SW-110, SW-12-CA	Lead, Cu, Cobalt, Mn, Fe, Zn, Pb, Hg

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st 0.000	COLOR	brown	
2nd 0.000	ODOR	none	
	OTHER		

pH \_\_\_\_\_ Temperature \_\_\_\_\_ (C) Dissolved Oxygen \_\_\_\_\_ (mg/L) Specific Conductivity \_\_\_\_\_ (umhos/cm)  
Iron \_\_\_\_\_ (mg/L) Oxidation/Reduction Potential \_\_\_\_\_ (mv) Turbidity \_\_\_\_\_ (NTU)

## GENERAL INFORMATION

WEATHER SUN/CLEAR ☒ OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION \_\_\_\_\_ AMBIENT TEMPERATURE 100°FSHIPMENT VIA FEDEX ☒ HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

SHIPPED TO STL - Chicago

COMMENTS \_\_\_\_\_

SAMPLER M Johnston

OBSERVER J Kringer

MATRIX TYPE CODES

DC=DRILL CUTTINGS  
WG=GROUND WATER  
LH=HAZARDOUS LIQUID WASTE  
SH=HAZARDOUS SOLID WASTE  
SE=SEDIMENT

SL=SLUDGE  
SO=SOIL  
GS=SOIL GAS  
WS=SURFACE WATER  
SW=SWAB/WIPE

SAMPLING METHOD CODES

B=BAILER  
BP=BLADDER PUMP  
BR=BRASS RING  
CS=COMPOSITE SAMPLE  
C=CONTINUOUS FLIGHT AUGER  
DT=DRIVEN TUBE

G=GRAB  
HA=HAND AUGER  
H=HOLLOW STEM AUGER  
HP=HYDRO PUNCH  
SS=SPILLIT SPOON  
SP=SUBMERSIBLE PUMP



724 347



## FIELD SAMPLING REPORT

BEST AVAILABLE  
COPY
 LOCATION. NAS Fort Worth JRB, TX  
 SITE <sup>AFC</sup> SWMU 19

 PROJECT NAME Phase II RFI FT-001  
 PROJECT NO. AFC001-26CE

## SAMPLE INFORMATION

SAMPLE ID FT09-12AWG013 ZBC &amp; ISO 1

DATE 2-15-01 TIME: 11:30

MATRIX TYPE: WG

SAMPLING METHOD: BP <sup>g</sup> E

LOT CONTROL #: 011A

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #: \_\_\_\_\_

SAMPLE BEG DPETH (FT) N/A

SAMPLE END DPETH (FT)

GRAB (X) COMPOSITE ( )

ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:

MATRIX SPIKE (MS) \_\_\_\_\_

MATRIX SPIKE DUP (SD) \_\_\_\_\_

FIELD DUP (FD) \_\_\_\_\_

AMBIENT BLANK (AB) N/A

EQUIPMENT BLANK (EB) \_\_\_\_\_

TRIP BLANK (TB) RSC 81401

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
40 mL VOA	3	Cool to 4C HCl to pH < 2	SW8260A	VOCs (App IX)
1 L Amber	2	Cool to 4C	SW8270C	SVOCs (App IX)
1 L Poly	1	Cool to 4C NaOH pH > 9	SW6010B / HCCU	Total Metals (App IX) - 14 g

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st	COLOR		
2nd	ODOR		
	OTHER		
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)	Specific Conductivity _____ (umhos/cm)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Turbidity _____ (NTU)	

## GENERAL INFORMATION

WEATHER: SUN/CLEAR X OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION \_\_\_\_\_ AMBIENT TEMPERATURE 100 FSHIPMENT VIA: FEDEX x HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

SHIPPED TO: STL - Chicago

COMMENTS: \_\_\_\_\_

SAMPLER: J Heringer

OBSERVER: M Johnston

## MATRIX TYPE CODES

 DC=DRILL CUTTINGS SL=SLUDGE  
 WG=GROUND WATER SO=SOIL  
 LH=HAZARDOUS LIQUID WASTE GS=SOIL GAS  
 SH=HAZARDOUS SOLID WASTE WS=SURFACE WATER  
 SE=SEDIMENT SW=SWAB/WIPE

## SAMPLING METHOD CODES

 B=BAILER G=GRAB  
 BP=BLADDER PUMP HA=HAND AUGER  
 BR=BRASS RING H=HOLLOW STEM AUGER  
 CS=COMPOSITE SAMPLE HP=HYDRO PUNCH  
 C=CONTINUOUS FLIGHT AUGER SS=SPLIT SPOON  
 DT=DRIVEN TUBE SP=SUBMERSIBLE PUMP





## FIELD SAMPLING REPORT

LOCATION	NAS Fort Worth JRB, TX	PROJECT NAME	Phase II RFI FT-001
SITE	AOC 19	PROJECT NO	AFC001-26CEA
<b>SAMPLE INFORMATION</b>			
SAMPLE ID	WHGLTA19EWG01 050	DATE	2/21/01 TIME 1815
MATRIX TYPE	WG	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) _____ TRIP BLANK (TB) _____	
SAMPLING METHOD	BP		
LOT CONTROL #	_____		
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #:	_____		
Pump SAMPLE BEG DPETH (FT) 5.7 well SAMPLE END DPETH (FT) 7.03 GRAB (X) COMPOSITE ( )			
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA 3	Cool to 4C HCl pH<2	SW8260B	TCE

NOTABLE OBSERVATIONS			
PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS	
1st .00 ppm	COLOR		
2nd	ODOR None		
	OTHER		
pH 7.25	Temperature 15.29(C)	Dissolved Oxygen 6.13 (mg/L)	Specific Conductivity 137 (umhos/cm)
Iron _____ (mg/L)	Oxidation/Reduction Potential 243.5 (mv)	Turbidity 4.01 (NTU)	
GENERAL INFORMATION			
WEATHER	SUN/CLEAR _____	OVERCAST/RAIN X	WIND DIRECTION NW AMBIENT TEMPERATURE 46 F
SHIPMENT VIA	FEDEX x	HAND DELIVER _____	COURIER _____ OTHER _____
SHIPPED TO: STL - Chicago			
COMMENTS _____			
SAMPLER M Mahal		OBSERVER M Johnston	
<b>MATRIX TYPE CODES</b> DC=DRILL CUTTINGS      SL=SLUDGE WG=GROUND WATER      SO=SOIL LH=HAZARDOUS LIQUID WASTE      GS=SOIL GAS SH=HAZARDOUS SOLID WASTE      WS=SURFACE WATER SE=SEDIMENT      SW=SWAB/WIPE		<b>SAMPLING METHOD CODES</b> B=BAILER      G=GRAB BP=BLADDER PUMP      HA=HAND AUGER BR=BRASS RING      H=HOLLOW STEM AUGER CS=COMPOSITE SAMPLE      HP=HYDRO PUNCH C=CONTINUOUS FLIGHT AUGER      SS=SPLIT SPOON DT=DRIVEN TUBE      SP=SUBMERSIBLE PUMP	

## GROUNDWATER FIELD SAMPLING DATA SHEET

Well No - WHGLTA19C50	Location	AOC 19
Sampler(s). m manual / m Johnston	Project Name:	Phase II RFI FT-001
Well Depth 7.03 ft	Project #.	AFC001-26CEA Date: 2/21/01 Time 1710
DTW (ft). 4.4 DTP (ft).	Courier	X FedEx UPS Hand Other
MP Ht Above/Below Ground Surface n/a	Sampling Method .	BP
Condition of Bottom of Well. good	Type of Pump:	Bladder
Screen Interval (ft): 7 ( - ) 2	Weather (sun/clear, overcast/rain, wind direction, ambient temperature).	
Well Diameter (in) 2	Overcast, windy (NW), 46°F	
Placement of Pump (ft) 5.7'		

## Field Parameters

\* Water level below top of pump

[illegible]

## Observations

Color: <u>Clear</u> Other (describe):
Odor: <u>None</u> Low Medium High Very Strong H2S Fuel-like
Notes:
Signed/Sampler(s): <u>Mh</u>

LOCATION		NAS Fort Worth JRB, TX		PROJECT NAME		Phase II RFI FT-001	
SITE		AOC 19		PROJECT NO		AFC001-26CE	
SAMPLE INFORMATION							
SAMPLE ID				WHGLTA19FWG01 051		DATE: 2-22-01	
MATRIX TYPE				WG		TIME: 1530	
SAMPLING METHOD				BP		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) <u>N/A</u> EQUIPMENT BLANK (EB) <u>EB022201</u> TRIP BLANK (TB) <u>TB022201</u>	
LOT CONTROL #.				_____			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)				_____			
CHAIN-OF-CUSTODY #.				_____			
SAMPLE BEG DPETH (FT)				5.5			
SAMPLE END DPETH (FT)				6.92			
GRAB <input checked="" type="checkbox"/> COMPOSITE ( )							
CONTAINER		PRESERVATIVE/ PREPARATION		ANALYTICAL METHOD		ANALYSIS	
SIZE/TYPE		#					
40 mL VOA		3		Cool to 4C HCl pH < 2		SW8260B	
						TCE	

NOTABLE OBSERVATIONS					
PID READINGS		SAMPLE CHARACTERISTICS		MISCELLANEOUS	
0.0 ppm		COLOR <u>clear</u>			
2nd		ODOR <u>none</u>			
		OTHER			
pH <u>6.93</u>		Temperature <u>15.45</u> (C)		Dissolved Oxygen <u>6.68</u> (mg/L)	
Iron _____ (mg/L)		Oxidation/Reduction Potential <u>249.6</u> (mv)		Specific Conductivity <u>365</u> (umhos/cm)	
		Turbidity <u>6.99</u> (NTU)			
GENERAL INFORMATION					
WEATHER: SUN/CLEAR <input checked="" type="checkbox"/>		OVERCAST/RAIN _____		WIND DIRECTION <u>NW</u>	
SHIPMENT VIA FEDEX <input checked="" type="checkbox"/>		HAND DELIVER _____		AMBIENT TEMPERATURE <u>43°F</u>	
SHIPPED TO <u>STL - Chicago</u>		COURIER _____		OTHER _____	
COMMENTS _____					
SAMPLER <u>m mahal</u>		OBSERVER <u>m Johnston</u>			
MATRIX TYPE CODES			SAMPLING METHOD CODES		
DC = DRILL CUTTINGS			B = BAILER		
WG = GROUND WATER			G = GRAB		
LH = HAZARDOUS LIQUID WASTE			BP = BLADDER PUMP		
SH = HAZARDOUS SOLID WASTE			BR = BRASS RING		
SE = SEDIMENT			CS = COMPOSITE SAMPLE		
SL = SLUDGE			C = CONTINUOUS FLIGHT AUGER		
SO = SOIL			DT = DRIVEN TUBE		
GS = SOIL GAS			HA = HAND AUGER		
WS = SURFACE WATER			H = HOLLOW STEM AUGER		
SW = SWAB/WIPE			HP = HYDRO PUNCH		
			SS = SPLIT SPOON		
			SP = SUBMERSIBLE PUMP		

724 552

## GROUNDWATER FIELD SAMPLING DATA SHEET

Well No.. WHGLTA051	Location. AOC 19		
Sampler(s) mmahal, M Johnston	Project Name Phase II RFI FT-001		
Well Depth 6.92	Project #. AFC001-26CBA	Date: 2-22-01 Time: 1410	
DTW (ft) 4.15	DTP (ft):	Courier: <input checked="" type="checkbox"/> FedEx <input type="checkbox"/> UPS <input type="checkbox"/> Hand <input type="checkbox"/> Other	
MP Ht Above/Below Ground Surface: N/A	Sampling Method : BP		
Condition of Bottom of Well: good	Type of Pump Bladder		
Screen Interval (ft) 6.9 - 1.9	Weather (sun/clear, overcast/rain, wind direction, ambient temperature). Sunny, NW wind, 43°F		
Well Diameter (in) 2			
Placement of Pump (ft) 5.5			

## Field Parameters

Time	Depth to Water (ft)	Flow Rate (L/m)	Total Volume (L)	pH	Temp. (C)	Cond. (umhos/cm)	ORP (mv)	DO (mg/L)	Turb. (NTU)	Type, Size, and Amount of Sediment Discharged
1425	4	0.1	Start pumping							Cloudy, no odor
1435		0.15	1.25	7.10	15.35	356	239.6	5.55	115	
1440		0.15	2.0	7.02	15.29	355	241.4	5.36	94.1	
1445		0.15	2.75	6.91	14.88	352	245.8	6.05	65.0	
1450		0.15	3.5	6.92	15.08	355	245.9	5.99	51.5	
1455		0.15	4.25	6.93	15.17	358	246.1	4.89	34.2	
1500		0.15	5	6.93	15.19	359	246.5	6.58	24.6	
1505		0.15	5.75	6.92	15.24	361	247.9	7.54	17.7	
1510		0.15	6.5	6.92	15.35	364	249.1	6.84	10.6	
1515		0.15	7.25	6.91	15.34	364	249.6	6.76	7.9	
1520		0.15	8	6.92	15.42	365	249.8	6.69	6.65	
1525	✓	0.15	8.75	6.93	15.45	365	249.6	6.68	6.99	
1530	Collect sample WHGLTA051W601									

\* DTW below top of pump.

## Observations

Color: <u>Clear</u> Other (describe):
Odor: <u>None</u> Low Medium High Very Strong H2S Fuel-like
Notes:
Signed/Sampler(s): <u>M Johnston</u>



## FIELD SAMPLING REPORT

724 353

LOCATION: NAS Fort Worth JRB, TX		PROJECT NAME: Phase II RFI FT-001		
SITE: AOC 19		PROJECT NO. AFC001-26CE		
<b>SAMPLE INFORMATION</b>				
SAMPLE ID WHGLTA19GWG01mg 0522201		DATE 02-22-01 TIME: 1600		
MATRIX TYPE: WG		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE.  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) 022201 TRIP BLANK (TB) TB022201		
SAMPLING METHOD: BP				
LOT CONTROL #: _____				
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)				
CHAIN-OF-CUSTODY #: _____				
SAMPLE BEG DPETH (FT)				
SAMPLE END DPETH (FT)				
GRAB <input checked="" type="checkbox"/> COMPOSITE ( )				
CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
40 mL VOA	3	Cool to 4C HCl pH < 2	SW8260B	TCE

<b>NOTABLE OBSERVATIONS</b>				
PID READINGS		SAMPLE CHARACTERISTICS		MISCELLANEOUS
0.0 ppm		COLOR clear no odor		
2nd 0.0 ppm		ODOR " " "		
OTHER				
pH 7.25	Temperature 15.48 (C)	Dissolved Oxygen 4.76 (mg/L)	Specific Conductivity 320 (umhos/cm)	
Iron _____ (mg/L)	Oxidation/Reduction Potential 1473 (mv)	Turbidity 50 (NTU)		
<b>GENERAL INFORMATION</b>				
WEATHER SUN/CLEAR _____		OVERCAST/RAIN _____		WIND DIRECTION NE 15 mph
SHIPMENT VIA FEDEX <input checked="" type="checkbox"/>		HAND DELIVER _____		COURIER _____
SHIPPED TO STL - Chicago				
COMMENTS _____				
SAMPLER R. Wallace		OBSERVER J. R. Rhs		
MATRIX TYPE CODES		SAMPLING METHOD CODES		
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB	
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER	
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER	
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH	
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON	
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP	

## GROUNDWATER FIELD SAMPLING DATA SHEET

Well No. WHGLTA190052	Location AOC 19
Sampler(s) R. Wallace, J. R. hs	Project Name Phase II RFI FT-001
Well Depth 6.99'	Project #. AFC001-26CE 02-22-01 Date 1455 Time.
DTW (ft) 4.46' DTP (ft) -	Courier FedEx UPS Hand Other
MP Ht Above/Below Ground Surface: 0.4'	Sampling Method: BP
Condition of Bottom of Well: clean	Type of Pump QED Bladder pump
Screen Interval (ft) (-) 2'-7'	Weather (sun/clear) overcast/rain, wind direction, ambient temperature). NE 10 mph 54°
Well Diameter (in) 2"	
Placement of Pump (ft). 5.73'	

4.46  
+ 1.53  
5.99  
DTW  
Screen

## Field Parameters

Time	Depth to Water (ft)	Flow Rate (L/min)	Total Volume (L)	pH	Temp (C)	Cond. (umhos/cm)	ORP (mv)	DO (mg/L)	Turb. (NTU)	Type, Size, and Amount of Sediment Discharged
1505	Ground	0.05	0.25	7.56	15.41	320.0	117.3	5.53	57.2	slightly cloudy
1510	water	0.05	0.5	7.49	15.53	327.0	119.3	5.58	45.2	"
1515	below	0.05	0.75	7.43	15.51	327.0	123.3	4.94	37.7	"
1520	top of	0.05	1.0	7.37	15.78	328.0	120.0	4.84	31.9	"
1525	pump	0.05	1.25	7.34	16.02	331.0	127.4	4.71	25.1	clear
1530		0.05	1.5	7.30	16.12	336.0	132.9	4.72	19.7	"
1535		0.05	1.75	7.27	15.80	330.0	137.3	4.76	14.2	"
1540		0.05	2.0	7.20	15.44	327.0	141.3	4.60	12.0	"
1545		0.05	2.25	7.27	15.36	325.0	143.5	4.5-1	8.7	"
1550		0.05	2.5	7.20	15.43	325.0	144.3	4.71	7.0	"
1555		0.05	2.75	7.25	15.45	326.0	147.3	4.70	5.0	"
collect sample										

## Observations

Color: Clear Other (describe).
Odor: None Low Medium High Very Strong H2S Fuel-like
Notes.
Signed/Sampler(s) <i>R. Wallace</i>

BEST AVAILABLE  
COPY





## FIELD SAMPLING REPORT

724 355

LOCATION	NAS Fort Worth JRB, TX	PROJECT NAME	Phase II RFI FT-001
SITE	AOC 19	PROJECT NO	AFC001-26CE
SAMPLE INFORMATION			
SAMPLE ID	WHGLTA004WG01	DATE	8/22/01
MATRIX TYPE	WG	TIME	1040
SAMPLING METHOD	BP	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE	
LOT CONTROL #:		MATRIX SPIKE (MS) _____	
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)		MATRIX SPIKE DUP (SD) _____	
CHAIN-OF-CUSTODY #.		FIELD DUP (FD) _____	
SAMPLE BEG DPETH (FT)		AMBIENT BLANK (AB) _____	
SAMPLE END DPETH (FT)		EQUIPMENT BLANK (EB) <u>8/1A dedicated pump</u>	
GRAB (X) COMPOSITE ( )		TRIP BLANK (TB) <u>TB022201</u>	
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA 3	Cool to 4C HCl pH < 2	SW8260B	TCE

NOTABLE OBSERVATIONS			
PID READINGS	SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st	COLOR <u>clear</u>		
2nd	ODOR <u>none</u>		
	OTHER		
pH	Temperature (C)	Dissolved Oxygen (mg/L)	Specific Conductivity (umhos/cm)
Iron (mg/L)	Oxidation/Reduction Potential (mv)	Turbidity (NTU)	
GENERAL INFORMATION			
WEATHER	SUN/CLEAR <u>✓</u>	OVERCAST/RAIN	WIND DIRECTION <u>NW</u>
			AMBIENT TEMPERATURE <u>43°F</u>
SHIPMENT VIA	FEDEX <u>x</u>	HAND DELIVER	COURIER
			OTHER
SHIPPED TO.	STL - Chicago		
COMMENTS			
SAMPLER	<u>M Mahal</u>	OBSERVER	<u>M Mahal</u>
MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

724 356

## GROUNDWATER FIELD SAMPLING DATA SHEET

Well No	WHGLTA004	Location	AOC 19
Sampler(s):	mmahal, M Johnston		
Well Depth	233'	Project #:	AFC001-26CEA
DTW (ft)	17.01	DTP (ft)	N/A
MP Ht. Above/Below Ground Surface	-0.2	Courier	X FedEx ___ UPS ___ Hand ___ Other
Condition of Bottom of Well:	good	Sampling Method	BP
Screen Interval (ft)	(13.3 - 23.3)	Type of Pump	Dedicated bladder
Well Diameter (in)	2	Weather (sun/clear, overcast/rain, wind direction, ambient temperature)	Sunny, winds from NW, 35°F
Placement of Pump (ft):	Dedicated		

## Field Parameters

Time	Depth to Water (ft)	Flow Rate (L/m)	Total Volume (L)	pH	Temp (C)	Cond. (umhos/cm)	ORP (mv)	DO (mg/L)	Turb. (NTU)	Type, Size, and Amount of Sediment Discharged
1000	17.01	0.2	Start pump						8.1	Clear
1003	17.02	0.2	1	7.31	18.54	450	180.4	2.14	8.1	
1010	17.02	0.2	2	7.28	18.59	439	182.8	2.05	7.7	
1015	17.02	0.2	3	7.03	18.84	400	192.1	1.87	6.6	
1020	17.02	0.2	4	6.87	19.23	383	200.1	2.11	5.3	
1025	17.02	0.2	5	6.81	19.34	380	201.3	1.73	5.21	
1030	17.02	0.2	6	6.78	19.31	380	202.4	1.88	4.77	
1035	17.02	0.2	7	6.78	19.30	379	203.3	1.98	4.29	
1040	<del>17.02</del>	<del>0.2</del>	8	Collect sample WHGLTA004W601						

## Observations

Color	Clear	Other (describe).
Odor	None	Low Medium High Very Strong H2S Fuel-like
Notes		
Signed/Sampler(s).	mmahal, m Johnston	



## FIELD SAMPLING REPORT

724 357

LOCATION SITE	NAS Fort Worth JRB, TX AOC 19	PROJECT NAME	Phase II RFI FT-001
		PROJECT NO:	AFC001-26CE <u>9</u>
SAMPLE INFORMATION			
SAMPLE ID	WHGLTA80IWG01	DATE	<u>2/22/01</u> TIME <u>1230</u>
MATRIX TYPE:	WG	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE.  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) <u>DUP04</u> AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>EB022201</u> TRIP BLANK (TB) <u>TB022201</u>	
SAMPLING METHOD:	BP		
LOT CONTROL #	_____		
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #:	_____		
Pump SAMPLE BEG DPETH (FT) <u>10.8'</u> well SAMPLE END DPETH (FT) <u>13.95'</u> GRAB (X) COMPOSITE ( )			
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#		
40 mL VOA	3	Cool to 4C HCl pH < 2	SW8260B TCE

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
<u>0.0 ppm</u>	COLOR	
<u>2nd</u>	ODOR <u>none</u>	
	OTHER	
pH <u>6.68</u>	Temperature <u>18.26</u> (C)	Dissolved Oxygen <u>2.34</u> (mg/L)
Iron _____ (mg/L)	Oxidation/Reduction Potential <u>203.2</u> (mv)	Specific Conductivity <u>356</u> <del>203.2</del> (umhos/cm)
	Turbidity <u>6.93</u> (NTU)	

## GENERAL INFORMATION

WEATHER	<u>(SUN) CLEAR</u> <u>x</u>	OVERCAST/RAIN	_____	WIND DIRECTION	_____	AMBIENT TEMPERATURE	<u>43°F</u>
SHIPMENT VIA	FEDEX <u>x</u>	HAND DELIVER	_____	COURIER	_____	OTHER	_____
SHIPPED TO	<u>STL - Chicago</u>						
COMMENTS	_____						
SAMPLER	<u>M Mahal</u>			OBSERVER	<u>M Johnston</u>		

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

724 358

## GROUNDWATER FIELD SAMPLING DATA SHEET

Well No. WHGLTA801	Location: AOC 19		
Sampler(s) M. Mahal, M. Johnston	Project Name Phase II RFI FT-001		
Well Depth. 13.95	Project # AFC001-26CE/A	Date. 2/22/01	Time 11:00
DTW (ft). 7.84	DTP (ft).	Courier: <input checked="" type="checkbox"/> FedEx <input type="checkbox"/> UPS <input type="checkbox"/> Hand <input type="checkbox"/> Other	
MP Ht. Above/Below Ground Surface:	Sampling Method . BP		
Condition of Bottom of Well good	Type of Pump Bladder		
Screen Interval (ft): 14 (-) 4	Weather (sun/clear, overcast/rain, wind direction, ambient temperature):		
Well Diameter (in) 2	Sun, 43°F, No winds		
Placement of Pump (ft): 10.8			

## Field Parameters

Time	Depth to Water (ft)	Flow Rate (L/m)	Total Volume (L)	pH	Temp. (C)	Cond. (umhos/cm)	ORP (mv)	DO (mg/L)	Turb. (NTU)	Type, Size, and Amount of Sediment Discharged
1125	7.90	0.25	Start pump							
1135	7.89	0.25	2.5	6.87	16.94	360	235.1	5.88	55	
1140	7.89	0.25	3.75	6.79	17.58	354	230.9	5.04	32.5	
1145	7.89	0.25	5.0	6.74	17.49	352	229.7	4.57	19.43	
1150	7.89	0.25	6.25	6.72	17.67	353	226.5	2.06	14.26	
1155	7.89	0.25	7.5	6.71	17.97	354	222.6	4.10	8.55	
1200	7.90	0.25	8.75	6.71	18.21	357	215.6	4.07	10.65	
1205	7.90	0.25	10	6.68	18.40	358	212.7	4.00	8.59	
1210	7.90	0.25	11.25	6.68	18.35	359	208.9	4.10	9.45	
1215	7.90	0.25	12.5	6.68	18.41	362	204.1	2.03	5.05	
1220	7.90	0.25	13.75	6.69	18.23	360	203.2	2.29	5.28	
1225	7.90	0.25	15	6.68	18.26	356	203.2	2.34	6.93	
1230	Collect WHGLTA801 WGO1									

## Observations

Color: Clear	Other (describe):
Odor: None	Low Medium High Very Strong H2S Fuel-like
Notes:	
Signed/Sampler(s).	

LOCATION:	NAS Fort Worth JRB, TX	PROJECT NAME:	Phase II RFI FT-001
SITE:	AOC 19	PROJECT NO	AFC001-26CE- <u>Ang</u>
SAMPLE INFORMATION			
SAMPLE ID	WHOLTA801W601 <u>DUP04</u>	DATE:	<u>2/22/01</u> TIME: <u>1230p 1200</u>
MATRIX TYPE:	WG	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) <u>DUP04 - WHOLTA801W601</u> AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>EB022201</u> TRIP BLANK (TB) <u>TB022201</u>	
SAMPLING METHOD:	BP		
LOT CONTROL #:	_____		
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #:	_____		
<u>Pump</u> SAMPLE BEG DPETH (FT) <u>10.8'</u> <u>well</u> SAMPLE END DPETH (FT) <u>13.95'</u> GRAB (X) COMPOSITE ( )			
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#		
40 mL VOA	3	SW8260B	TCE

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
<u>0.0ppm</u>	COLOR _____ ODOR <u>none</u> OTHER _____	
pH <u>6.68</u>	Temperature <u>18.26</u> (C)	Dissolved Oxygen <u>2.34</u> (mg/L)
Iron _____ (mg/L)	Oxidation/Reduction Potential <u>203.2</u> (mv)	Specific Conductivity <u>356</u> <del>203.2</del> (umhos/cm)
	Turbidity <u>6.93</u> (NTU)	

## GENERAL INFORMATION

WEATHER.	<u>(SUN) CLEAR</u> <u>x</u>	OVERCAST/RAIN _____	WIND DIRECTION _____	AMBIENT TEMPERATURE <u>43F</u>
SHIPMENT VIA	FEDEX <u>x</u>	HAND DELIVER _____	COURIER _____	OTHER _____
SHIPPED TO	<u>STL - Chicago</u>			
COMMENTS	_____			
SAMPLER	<u>M Mahal</u>		OBSERVER	<u>M Johnston</u>

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

724 360



## FIELD SAMPLING REPORT

LOCATION. NAS Fort Worth JRB PROJECT NAME ~~AFC001-16888~~ Phase II RFI/ISI  
 SITE 90C19 + SWMU 19 PROJECT NAME AFC001-16888 26CEA

## SAMPLE INFORMATION

SAMPLE ID <del>EB04-007</del> <u>EB022201</u>	DATE: <u>2/22/01</u> TIME: <u>1430</u>
MATRIX TYPE: WG	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE
SAMPLING METHOD: <u>G</u>	
LOT CONTROL # <u>      </u>	
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)	
CHAIN-OF-CUSTODY # <u>      </u>	
SAMPLE BEG DEPTH (FT) <u>N/A</u>	MATRIX SPIKE (MS) <u>      </u>
SAMPLE END DEPTH (FT) <u>N/A</u>	MATRIX SPIKE DUP (SD) <u>      </u>
GRAB <u>X</u> COMPOSITE ( )	FIELD DUP (FD) <u>      </u>
	AMBIENT BLANK (AB) <u>      </u>
	EQUIPMENT BLANK (EB) <u>      </u>
	TRIP BLANK (TB) <u>      </u>

CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA 3	Cool to 4C/HCl to pH < 2	SW3260B	VOCs

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st	COLOR	
2nd	ODOR	
	OTHER	
pH	Temperature (C)	Dissolved Oxygen (mg/L)
Iron	Oxidation/Reduction Potential (mv)	Specific Conductivity (umhos/cm)
	Turbidity (NTU)	

## GENERAL INFORMATION

WEATHER SUN/CLEAR X OVERCAST/RAIN        WIND DIRECTION NW AMBIENT TEMPERATURE 43°F  
 SHIPMENT VIA FEDEX x HAND DELIVER        COURIER        OTHER         
 SHIPPED TO STL -  
 COMMENTS         
 SAMPLER M Johnston OBSERVER M Mahal

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC = DRILL CUTTINGS	SL = SLUDGE	B = BAILER	G = GRAB
WG = GROUND WATER	SO = SOIL	BP = BLADDER PUMP	HA = HAND AUGER
LH = HAZARDOUS LIQUID WASTE	GS = SOIL GAS	BR = BRASS RING	H = HOLLOW STEM AUGER
SH = HAZARDOUS SOLID WASTE	WS = SURFACE WATER	CS = COMPOSITE SAMPLE	HP = HYDRO PUNCH
SE = SEDIMENT	SW = SWAB/WIPE	C = CONTINUOUS FLIGHT AUGER	SS = SPLIT SPOON
		DT = DRIVEN TUBE	SP = SUBMERSIBLE PUMP



## FIELD SAMPLING REPORT

724 361

LOCATION: NAS Fort Worth JRB, TX  
SITE: AOC 19PROJECT NAME: Phase II RFI FT-001, Round 2 Groundwater  
PROJECT NO. AFC001-26CE

## SAMPLE INFORMATION

SAMPLE ID WHGLTA050WG02

DATE: 4/6/01 TIME: 1430

MATRIX TYPE: WG

SAMPLING METHOD: BP

LOT CONTROL #: 091A

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #:

SAMPLE BEG DPETH (IT) —

SAMPLE END DPETH (FT) —

GRAB (✓) COMPOSITE ( )

ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:

MATRIX SPIKE (MS): —

MATRIX SPIKE DUP (SD): —

FIELD DUP (FD): —

AMBIENT BLANK (AB): —

EQUIPMENT BLANK (EB): EB-040601

TRIP BLANK (TB): TB-040601

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
40 mL VOA	3	Cool to 4C HCl pH < 2	SW8260B	TCE

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st 4.0 ppm	COLOR	clear	
2nd 4.0 ppm	ODOR	none	
	OTHER:		
pH 6.62	Temperature 20.0 (C)	Dissolved Oxygen 3.64 (mg/L)	Specific Conductivity 410 (umhos/cm)
Iron — (mg/L)	Oxidation/Reduction Potential 230.4 (mv)	Turbidity 2.8 (NTU)	

## GENERAL INFORMATION

WEATHER: partly SUN/CLAR OVERCAST/RAIN WIND DIRECTION south AMBIENT TEMPERATURE

SHIPMENT VIA FEDEX \* HAND DELIVER COURIER OTHER

SHIPPED TO: STL - Chicago

COMMENTS:

SAMPLER: Christopher Donohue

OBSERVER: Kent Duren

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

AFCEE FORM SR.11

## GROUNDWATER FIELD SAMPLING DATA SHEET

Well No.: WHGLTA050	Location: AOC 19
Sampler(s): C. Donohue, K. Owen	Project Name: Phase II RFI FT-001, Round 2 Groundwater
Well Depth: 7.00'	Project #: AFC001-26CE Date: 4/6/01 Time: 1352
DTW (ft): 4.87 DTP (ft): —	Courier: <input checked="" type="checkbox"/> FedEx <input type="checkbox"/> UPS <input type="checkbox"/> Hand <input type="checkbox"/> Other
MP Ht. Above/Below Ground Surface: -0.112	Sampling Method: <del>SR</del> Low Flow
Condition of Bottom of Well: Hard	Type of Pump: Bladder Pump
Screen Interval (ft): (2.03 - 7.03)	Weather (sun/clear, overcast/rain, wind direction, ambient temperature):
Well Diameter (in): 2	partly sunny, south wind, 70's °F
Placement of Pump (ft): 5.94'	

## Field Parameters

Time	Depth (ft)	DTW (ft)	DTP (ft)	Temp (°F)	Temp (°C)	pH	DO (mg/L)	DO (%)	ORP (mV)	Specific Conductance (µmhos/cm)	Salinity (ppt)
1352	—*	0.140	0	6.86	21.68	429	181.3	4.83	28.2		
1357	—	0.14	0.7	6.69	21.96	432	179.6	4.02	24.1		
1402	—	0.14	1.4	6.66	22.17	434	209.3	3.98	16.6		
1407	—	0.10	1.9	6.71	21.69	428	179.6	4.47	12.3		
1412	—	0.10	2.4	6.63	21.93	424	212.4	3.84	7.0		
1417	—	0.10	2.9	6.60	20.02	412	221.4	3.73	4.7		
1422	—	0.10	3.4	6.60	19.82	409	226.9	3.67	4.3		
1427	—	0.10	3.9	6.62	20.01	410	230.4	3.64	2.8		
N30	Sampler taken										

## Observations

Color: <u>Clear</u> Other (describe): <u>clear</u>
Odor: <u>None</u> Low Medium High Very Strong H <sub>2</sub> S Fuel-like <u>none</u>
Notes: * Note = can't take depth to water - pump sticks up above water level -
Signed/Sampler(s): <u>2/2/01 K. Owen</u> <u>K. Owen</u>

BEST AVAILABLE  
COPY



**GROUNDWATER FIELD SAMPLING DATA SHEET**

Well No: WHGLTA051	Location: NAS Fort Worth JRB, Texas
Sampler(s): C. Dwyer, K. Duran	Project Name: April 2001 Semi-Annual Sampling
Well Depth: 6.93'	Project #: AFC001-330AA Date: 4/6/01 Time: 1017
DTW (ft): 4.25' DTP (ft): —	Courier: <input checked="" type="checkbox"/> FedEx <input type="checkbox"/> UPS <input type="checkbox"/> Hand <input type="checkbox"/> Other
MP Ht. Above/Below GS: 0.071	Sampling Method: Low Flow
Condition of Bottom of Well	Type of Pump: Bladder
Screen Interval (ft): 1.92' 2-7	Weather (sun/clear, overcast/rain, wind direction, ambient temperature):  partly sunny, humid, south wind, 20's
Well Diameter (in): 2	
Placement of Pump Inlet (ft): 5.59'	

**Field Parameters**

Time	Depth to Water (ft)	Flow Rate (L/min)	Total Volume (L)	pH	Temp. (C)	Cond. (umhos/cm)	ORP (mv)	DO (mg/L)	Turb. (NTU)	Type, Size, and Amount of Sediment Discharged
1021	—	0.110	0	7.20	19.65	446	177.6	6.52	112	
1026	—	0.110	0.55	7.18	19.01	351	170.8	5.32	138	
1031	—	0.110	1.1	6.99	18.96	329	185.9	4.45	108	
1036	—	0.110	1.65	6.87	19.33	364	170.8	3.56	69	
1041	—	0.110	2.2	6.78	19.94	399	172.6	2.83	49	
1046	—	0.110	2.75	6.73	20.29	424	173.7	2.46	32	
1051	—	0.110	3.3	6.70	20.44	440	174.9	2.12	21.9	
1056	—	0.110	3.85	6.67	20.37	447	176.2	1.84	18.1	
1101	—	0.110	4.4	6.63	20.34	508	202.3	1.69	15.5	
1106	—	0.110	4.95	6.65	19.42	447	178.3	1.35	10.6	
1111	—	0.110	5.5	6.64	19.56	441	177.1	1.21	9.8	
1116	—	0.110	6.05	6.64	20.10	455	177.0	1.22	6.7	
1121	—	0.110	6.6	6.64	20.41	458	177.2	1.24	6.0	
1125	samples taken									

**Observations**

Color:	<input checked="" type="radio"/> Clear <input type="radio"/> Other (describe):
Odor:	<input checked="" type="radio"/> None <input type="radio"/> Low <input type="radio"/> Medium <input type="radio"/> High <input type="radio"/> Very Strong <input type="radio"/> H2S <input type="radio"/> Fuel-like
Notes:	* can't measure depth to water - pump sticks up above waterline.
Signed/Sampler(s):	<i>C. Dwyer</i> <i>K. Duran</i>

724 364



## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, Texas		PROJECT NAME: April 2001 Semi-Annual Sampling	
SITE: _____		PROJECT NAME: AFC001-33DAA	
<b>SAMPLE INFORMATION</b>			
SAMPLE ID: WHGLTA051WG14		DATE: 4/6/01 TIME: 1125	
MATRIX TYPE: WG		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD): _____ FIELD DUP (FD): _____ AMBIENT BLANK (AB): _____ EQUIPMENT BLANK (EB) ● EB 040601 TRIP BLANK (TB) ● TB 040601	
SAMPLING METHOD: Low Flow			
LOT CONTROL #: 0 4 1 A			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler			
CHAIN-OF-CUSTODY #:			
SAMPLE BEG DEPTH (FT): N/A			
SAMPLE END DEPTH (FT): N/A			
GRAB (X) COMPOSITE ( )			
CONTAINER		PRESERVATIVE/	ANALYTICAL
SIZE/TYPE	#	PREPARATION	METHOD
40 mL VOA	3	Cool to 4C/HCl to pH<2	SW8260B
		ANALYSIS	
		VOCs	

NOTABLE OBSERVATIONS			
PID READINGS	SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st 0	COLOR: Clear		
2nd 0	ODOR: None		
OTHER: 4/6/01			
pH 6.64	Temperature 11.65 (C)	Dissolved Oxygen 0.52 (mg/L)	Conductivity 476 (umhos/cm)
Iron — (mg/L)	Oxidation/Reduction Potential 197.2	Turbidity 6.0 (NTU)	
GENERAL INFORMATION			
WEATHER: SUN/CLEAR	OVERCAST/RAIN	WIND DIRECTION: South	AMBIENT TEMPERATURE
SHIPMENT VIA FEDEX	HAND DELIVER	COURIER	OTHER: 70.5 °F
SHIPPED TO: STL Chicago			
COMMENTS: C. - Denohue			
SAMPLER: _____		OBSERVER: K. Duran	
MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDG	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WAST	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WAST	WS=SURFACE WATE	CS=COMPOSITE SAMPLE	HP=HYDRO PUNC
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

AFCEE FORM SR 11

Well No : WHCILTA052	Location: AOC 19		
Sampler(s): K. Doran, C. Doran	Project Name: Phase II RFI FT-001, Round 2 Groundwater		
Well Depth: 694	Project #: AFC001-26CE	Date: 9/6/01	Time: 1215
DTW (ft) 452	DTP (ft): na	Courier: <input checked="" type="checkbox"/> FedEx <input type="checkbox"/> UPS <input type="checkbox"/> Hand <input type="checkbox"/> Other	
MP Ht. Above/Below Ground Surface: -0.122	Sampling Method: BPT Low Flow		
Condition of Bottom of Well: S. 44	Type of Pump: Bladder Pump		
Screen Interval (ft): (1.99 - 6.99)	Weather (sun/clear, overcast/rain, wind direction, ambient temperature): S/SW 87°F		
Well Diameter (in): 2			
Placement of Pump (ft): 5.73			

[illegible]

Color: Clear Other (describe): clear  
Odor: None Low Medium High Very Strong H<sub>2</sub>S Fuel-like None  
Notes: Depth of top of pipe above water table level.  
  
  
  
  
  
  
Signed/Sampler(s) Kat Dunn RECEIVED

724 386



## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: Phase II RFI FT-001, Round 2 Groundwat

SITE: AOC 19

PROJECT NO: AFC001-26CE

## SAMPLE INFORMATION

SAMPLE ID: WF-GLTA052WG02

DATE: 4/6/01 TIME: 1259

MATRIX TYPE: WG

SAMPLING METHOD: BP

LOT CONTROL #: C 1 A

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #: \_\_\_\_\_

SAMPLE BEG. DPETH (FT): NA

SAMPLE END DPETH (FT): NA

GRAB ☒ COMPOSITE ( )ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:

MATRIX SPIKE (MS): \_\_\_\_\_

MATRIX SPIKE DUP (SD): \_\_\_\_\_

FIELD DUP (FD): \_\_\_\_\_

AMBIENT BLANK (AB): \_\_\_\_\_

EQUIPMENT BLANK (EB): EB040601

TRIP BLANK (TB): TB040601

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
40 mL VOA	3	Cool to 4C HCl pH < 2	SW8260B	TCE

## NOTABLE OBSERVATIONS

PID READINGS		SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st	5.8	COLOR	clear	
2nd		ODOR	none	
		OTHER		
pH	6.6	Temperature	19.9 (C)	Dissolved Oxygen 4.08 (mg/L)
				Specific Conductivity 419 (umhos/cm)
Iron	— (mg/L)	Oxidation/Reduction Potential	290 (mv)	Turbidity 4.4 (NTU)

## GENERAL INFORMATION

WEATHER: SUN/CLEAR ☒ OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION S/SE AMBIENT TEMPERATURE 80°FSHIPMENT VIA: FEDEX ☒ HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

SHIPPED TO: STL - Chicago

COMMENTS: \_\_\_\_\_

SAMPLER: C. Donahue

OBSERVER: K. D. Donahue

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

AFCEE FORM SR 11



## FIELD SAMPLING REPORT

LOCATION: N/A Fort Worth JRB, Texas	PROJECT NAME: April 2001 Semi-Annual Sampling		
SITE: _____	PROJECT NAME: AFC001-33DAA		
<b>SAMPLE INFORMATION</b>			
SAMPLE ID: WHGLTA004WG14	DATE: <u>3/16/01</u>	TIME: <u>1450</u>	
MATRIX TYPE: WG	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS): _____ MATRIX SPIKE DUP (SD): _____ FIELD DUP (FD): _____ AMBIENT BLANK (AB): _____ EQUIPMENT BLANK (EB): _____ TRIP BLANK (TB): <u>TR032601</u>		
SAMPLING METHOD: Low Flow			
LOT CONTROL #: <u>001A</u>			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler)			
CHAIN-OF-CUSTODY #:			
SAMPLE BEG DEPTH (FT): <u>N/A</u>			
SAMPLE END DEPTH (FT): <u>N/A</u>			
GRAB (X) COMPOSITE ( )			
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA 3	Cool to 4C/HCl to pH<2	SW8260B	VOCs

## NOTABLE OBSERVATIONS

PID READINGS:	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <u>51</u>	COLOR: <u>clear</u>	
2nd	ODOR: <u>none</u>	
	OTHER:	
pH <u>6.9</u>	Temperature <u>19.7</u> (C)	Dissolved Oxygen <u>2.0</u> (mg/L)
		Conductivity <u>512</u> (umhos/cm)
Iron <u>NA</u> (mg/L)	Oxidation/Reduction Potential <u>265</u> (mv)	Turbidity <u>3.4</u> (NTU)

## GENERAL INFORMATION

WEATHER: SUN/CLEAR _____ OVERCAST/RAIN <u>✓</u>	WIND DIRECTION: <u>N/E</u>	AMBIENT TEMPERATURE: <u>58F</u>
SHIPMENT VIA: FEDEX <u>x</u>	HAND DELIVER _____	COURIER _____
OTHER: _____		
SHIPPED TO: STL - Chicago		
COMMENTS: <u>A Karst</u>	OBSERVER: <u>K. Duran</u>	

MATRIX TYPE CODES	SAMPLING METHOD CODES
DC=DRILL CUTTINGS	B=BAILER
WG=GROUND WATER	BP=BLADDER PUMP
LH=HAZARDOUS LIQUID WASTE	BR=BRASS RING
SH=HAZARDOUS SOLID WASTE	CS=COMPOSITE SAMPLE
SE=SEDIMENT	C=CONTINUOUS FLIGHT AUGER
SL=SLUDG	DT=DRIVEN TUBE
SO=SOIL	G=GRAB
GS=SOIL GAS	HA=HAND AUGER
WS=SURFACE WATER	H=HOLLOW STEM AUGER
SW=SWAB/WIPE	HP=HYDRO PUMP
	SS=SPLIT SPOON
	SP=SUBMERSIBLE PUMP

AFCEE FORM SR.11

# GROUNDWATER FIELD SAMPLING DATA SHEET

Well No.: WH01TA004	Location: NAS Fort Worth JRB, Texas
Sampler(s) E. Dura, A. Fast	Project Name: April 2001 Semi-Annual Sampling
Well Depth: NA	Project #: AFC001-33DAA Date: 3/24/01 Time: 1408
DTW (ft): 17.0 DTP (ft): 18.20	Courier: <input checked="" type="checkbox"/> FedEx <input type="checkbox"/> UPS <input type="checkbox"/> Hand <input type="checkbox"/> Other
MP Hr. Above/Below GS: 0.2	Sampling Method: Low Flow
Condition of Bottom of Well NA	Type of Pump: Bladder
Screen Interval (ft): 13.3 - 23.3	Weather (Sun/clear, overcast/rain, wind direction, ambient temperature): B/NO 54°
Well Diameter (in): 2	
Placement of Pump Inlet (ft): 21	

### Field Parameters

[illegible]

## Observations

Color: Clear (Other (describe): clear)  
Odor: None Low Medium High Very Strong H<sub>2</sub>S Fuel-like none  
Notes:  
  
  
  
  
  
  
Signed/Sampler(s): Adam Kaut Kat Dur

**BEST AVAILABLE  
COPY**



## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: Phase II RFI FT-001

SITE: AOC 19

PROJECT NO: AFC001-26CE

## SAMPLE INFORMATION

SAMPLE ID: W1GLTA801WG01

DATE: 4/6/01 TIME: 1000

MATRIX TYPE: WG

ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:

SAMPLING METHOD: BP

LOT CONTROL #: 12 1 1 A

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #:

SAMPLE BEG DPETH (FT): N/A

SAMPLE END DPETH (FT): N/A

GRAB (X) COMPOSITE ( )

MATRIX SPIKE (MS):

MATRIX SPIKE DUP (SD):

FIELD DUP (FD): DUP06WG02

AMBIENT BLANK (AB):

EQUIPMENT BLANK (EB): EB040601

TRIP BLANK (TB): TB040601

CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA 3	Cool to 4C HCl pH < 2	SW8260B	TCE

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st 100 ppm	COLOR clear	
2nd 0 ppm	ODOR none	
	OTHER:	
pH 6.51	Temperature 20.26 (C)	Dissolved Oxygen 0.88 (mg/L)
Iron N/A (mg/L)	Oxidation/Reduction Potential 257.1 (mv)	Specific Conductivity 424 (unhos/cm)
	Turbidity 3.62 (NTU)	

## GENERAL INFORMATION

WEATHER: SUN/CLEAR OVERCAST/RAIN X WIND DIRECTION S AMBIENT TEMPERATURE 75°

SHIPMENT VIA FEDEX X HAND DELIVER COURIER OTHER

SHIPPED TO: STL - Chicago

COMMENTS:

SAMPLER: A. Kerst

OBSERVER: J. Wallau

MATRIX TYPE CODES	SAMPLING METHOD CODES
DC=DRILL CUTTINGS	B=BAILER
WG=GROUND WATER	BF=BLADDER PUMP
LH=HAZARDOUS LIQUID WASTE	BR=BRASS RING
SH=HAZARDOUS SOLID WASTE	CS=COMPOSITE SAMPLE
SE=SEDIMENT	C=CONTINUOUS FLIGHT AUGER
	DT=DRIVEN TUBE
SL=SLUDGE	O=GRAB
SO=SOIL	HA=HAND AUGER
GS=SOIL GAS	H=HOLLOW STEM AUGER
WS=SURFACE WATER	HP=HYDRO PUNCH
SW=SWAB/WIPE	SS=SPLIT SPOON
	SP=SUBMERSIBLE PUMP

AFCEE FORM SR 11

724 370



## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, TX		PROJECT NAME: Phase II RFI QC	
SITE:		PROJECT NO: AFC001-26008 26CE	
<b>SAMPLE INFORMATION</b>			
SAMPLE ID TH <u>DUPO6</u>		DATE: <u>4/6/01</u>	TIME: <u>1200</u> <span style="border: 1px solid black; padding: 2px;">Actual time 1000</span>
MATRIX TYPE: <u>GW</u>		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS): _____ MATRIX SPIKE DUP (SD): _____ FIELD DUP (FD): <u>WHGLTA001WGOZ</u> AMBIENT BLANK (AB): _____ EQUIPMENT BLANK (EB): <u>EB040601</u> TRIP BLANK (TB): <u>TB040601</u>	
SAMPLING METHOD <u>LW Flow</u>			
LOT CONTROL #: <u>011A</u> (Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #: _____			
SAMPLE BEG DPETH (FT): <u>N/A</u> SAMPLE END DPETH (FT): <u>N/A</u> GRAB <input checked="" type="checkbox"/> COMPOSITE ( )			
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA 3	Cons to 4C HCl pH < 2	SW8260B	<u>TCE</u>

NOTABLE OBSERVATIONS			
PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS	
1st <u>100 ppm</u>	COLOR: <u>clear</u>		
2nd <u>0 ppm</u>	ODOR: <u>none</u>		
	OTHER		
pH <u>6.51</u> Temperature <u>20.26</u> (C) Dissolved Oxygen <u>0.88</u> (mg/L) Specific Conductivity <u>429</u> (umhos/cm) Iron <u>N/A</u> (mg/L) Oxidation/Reduction Potential <u>257.1</u> (mv) Turbidity <u>3.62</u> (NTU)			
GENERAL INFORMATION			
WEATHER SUN/CLEAR _____ OVERCAST/RAIN <u>X</u>		WIND DIRECTION <u>S</u> AMBIENT TEMPERATURE <u>75°</u>	
SHIPMENT VIA FEDEX _____ HAND DELIVER _____ COURIER _____ OTHER _____			
SHIPPED TO: <u>STL - Chicago</u>			
COMMENTS _____			
SAMPLER <u>A. Karst</u>		OBSERVER <u>J. Wallace</u>	
<b>MATRIX TYPE CODES</b> DC=DRILL CUTTINGS      SL=SLUDGE WG=GROUND WATER      SO=SOIL LH=HAZARDOUS LIQUID WASTE      GS=SOIL GAS SH=HAZARDOUS SOLID WASTE      WS=SURFACE WATER SE=SEDIMENT      SW=SWAB/WIPE		<b>SAMPLING METHOD CODES</b> B=BAILER      O=GRAB BP=BLADDER PUMP      HA=HAND AUGER BR=BRASS RING      H=HOLLOW STEM AUGER CS=COMPOSITE SAMPLE      HP=HYDRO PUNCH C=CONTINUOUS FLIGHT AUGER      SS=SPLIT SPOON DT=DRIVEN TUBE      SP=SUBMERSIBLE PUMP	

AFCEE FORM SR.11



## GROUNDWATER FIELD SAMPLING DATA SHEET

Well No.: WHGLTA801	Location: AOC 19	
Sampler(s): A. Karst J. Wallace	Project Name: Phase II RFI FT-001	
Well Depth: 13.90	Project #: AFC001-25CE	Date: 4/6/01 Time: 0924
DTW (ft): 9.08 DTP (ft): —	Courier: <input checked="" type="checkbox"/> FedEx <input type="checkbox"/> UPS <input type="checkbox"/> Hand <input type="checkbox"/> Other	
MP Ht. Above/Below Ground Surface:	Sampling Method: <del>DP</del> LOW FLOW	
Condition of Bottom of Well: firm	Type of Pump: Bladder	
Screen Interval (ft): (-) 4-14	Weather (sun/clear, overcast/rain, wind direction, ambient temperature): overcast, S, 75°	
Well Diameter (in): 2"		
Placement of Pump (ft): 11		

## Field Parameters

[illegible]

## Observations

Color: Clear Other (describe): Clear  
Odor: None Low Medium High Very Strong H<sub>2</sub>S Fuel-like none  
Notes: \* DTW below top of pump  
Difficult to maintain flow rate less than 0.2 L/min.  
  
Signed/Sampler(s): Wallace William East

**BEST AVAILABLE  
COPY**

724 372



## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, Texas		PROJECT NAME: April 2001 Semi-Annual Sampling													
SITE: _____		PROJECT NAME: AFC001-33DAA													
<b>SAMPLE INFORMATION</b>															
SAMPLE ID: TB040601		DATE: 4/6/01 TIME: 0705													
MATRIX TYPE: WG		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB) _____ EQUIPMENT BLANK (EB) <u>EB040601</u> TRIP BLANK (TB) <u>TB040601</u>													
SAMPLING METHOD: Low Flow															
LOT CONTROL #: <u>0 1 1 A</u> (Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler)															
CHAIN-OF-CUSTODY #:															
SAMPLE BEG. DEPTH (FT): <u>N/A</u> SAMPLE END DEPTH (FT): <u>N/A</u> GRAB (X) COMPOSITE ( )															
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th>CONTAINER</th> <th>PRESERVATIVE/ PREPARATION</th> <th>ANALYTICAL METHOD</th> <th>ANALYSIS</th> </tr> <tr> <td>SIZE/TYPE #</td> <td></td> <td></td> <td></td> </tr> <tr> <td>40 mL VOA 3</td> <td>Cool to 4C/HCl to pH&lt;2</td> <td>SW8260B</td> <td>VOCs</td> </tr> </table>		CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS	SIZE/TYPE #				40 mL VOA 3	Cool to 4C/HCl to pH<2	SW8260B	VOCs		
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS												
SIZE/TYPE #															
40 mL VOA 3	Cool to 4C/HCl to pH<2	SW8260B	VOCs												

NOTABLE OBSERVATIONS			
PID READINGS		SAMPLE CHARACTERISTICS	
1st _____	COLOR: _____	MISCELLANEOUS	
2nd _____	ODOR: _____		
OTHER: _____			
pH _____ Temperature _____ (C) Dissolved Oxygen _____ (mg/L) Conductivity _____ (umhos/cm) Iron _____ (mg/L) Oxidation/Reduction Potential _____ (mv) Turbidity _____ (NTU)			
GENERAL INFORMATION			
WEATHER: SUN/CLEAR _____ OVERCAST/RAIN <u>*</u> WIND DIRECTION <u>S</u> AMBIENT TEMPERATURE <u>80°</u> SHIPMENT VIA: FEDEX <u>x</u> HAND DELIVER _____ COURIER _____ OTHER _____ SHIPPED TO: STL -Chicago COMMENTS: _____ SAMPLER: <u>J. Wallace</u> OBSERVER: <u>A. Karst</u>			
MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WAST	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WAST	WS=SURFACE WATE	CS=COMPOSITE SAMPLE	HP=HYDRO PUNC
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

AFCEE FORM SR 11



## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: Phase II RFI QC

SITE:

PROJECT NO: AFC001-26CE

## SAMPLE INFORMATION

SAMPLE ID EB 040601

DATE: 4/6/01 TIME: 1540

MATRIX TYPE: WATER

SAMPLING METHOD: GRAB

LOT CONTROL #: 0 1 1 A

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #:

SAMPLE BEG DPETH (FT): N/A

SAMPLE END DPETH (FT): N/A

GRAB ☒ COMPOSITE ( )ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:

MATRIX SPIKE (MS):

MATRIX SPIKE DUP (SD):

FIELD DUP (FD):

AMBIENT BLANK (AB):

EQUIPMENT BLANK (EB): EB040601

TRIP BLANK (TB): TB040601

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
40 mL VOA	3	Cool to 4C HCl pH < 2	SW8260B	VOCs (App IX)
1 L Poly	1	Cool to 4C NaOH pH > 9	SW6010B	Total Metals (App IX)
1 L Amber	2	Cool to 4C	SW8270C	SVOCs (App IX)

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st =	COLOR: —		
2nd =	ODOR: —		
	OTHER:		
pH —	Temperature — (C)	Dissolved Oxygen — (mg/L)	Specific Conductivity — (umhos/cm)
Iron — (mg/L)	Oxidation/Reduction Potential — (mv)	Turbidity — (NTU)	

## GENERAL INFORMATION

WEATHER: SUN/CLEAR \_\_\_\_\_ OVERCAST/RAIN ☒ WIND DIRECTION S AMBIENT TEMPERATURE 80°SHIPMENT VIA FEDEX ☒ HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

SHIPPED TO: STL - Chicago

COMMENTS

SAMPLER: J. Waller

OBSERVER: A. Karst

**MATRIX TYPE CODES**

DC=DRILL CUTTINGS SL=SLUDGE  
 WG=GROUND WATER SO=SOIL  
 LH=HAZARDOUS LIQUID WASTE GS=SOIL GAS  
 SH=HAZARDOUS SOLID WASTE WS=SURFACE WATER  
 SE=SEDIMENT SW=SWAB/WIPE

**SAMPLING METHOD CODES**

B=BAILER G=GRAB  
 BP=BLADDER PUMP HA=HAND AUGER  
 BR=BRASS RING H=HOLLOW STEM AUGER  
 CS=COMPOSITE SAMPLE HP=HYDRO PUNCH  
 C=CONTINUOUS FLIGHT AUGER SS=SPLIT SPOON  
 DT=DRIVEN TUBE SP=SUBMERSIBLE PUMP

AFCEE FORM SR.11

724 374



## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, TX		PROJECT NAME: Phase II SI, Round 3	
SITE: AOC 19		PROJECT NO: AFC001-26CE	
<b>SAMPLE INFORMATION</b>			
SAMPLE ID WHGLTA050-WG03		DATE: <u>6/15/2001</u> TIME: <u>1000</u>	
MATRIX TYPE: WG		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS): <u>WHGLTA055-W603</u> MATRIX SPIKE DUP (SD) <u>WHGLTA055-W603</u> FIELD DUP (FD) <u>DUP07</u> AMBIENT BLANK (AB): <u>N/A</u> EQUIPMENT BLANK (EB) <u>EB061501</u> TRIP BLANK (TB) <u>TB061501</u>	
SAMPLING METHOD: BP			
LOT CONTROL #: <u>Q 1 1 A</u>			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #: _____			
SAMPLE BEG DPETH (FT) <u>6.57</u> SAMPLE END DPETH (FT) _____ GRAB ( <input checked="" type="checkbox"/> ) COMPOSITE ( )			
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA 3	Cool to 4C	SW8260B	TCE

NOTABLE OBSERVATIONS			
PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS	
1st <u>0.0 ppm</u>	COLOR		
2nd	ODOR		
	OTHER		
pH <u>6.29</u> Temperature <u>22.05</u> (C) Dissolved Oxygen <u>4.71</u> (mg/L) Specific Conductivity <u>289</u> (umhos/cm) Iron _____ (mg/L) Oxidation/Reduction Potential <u>334.1</u> (mv) Turbidity <u>2.7</u> (NTU)			
GENERAL INFORMATION			
WEATHER SUN/CLEAR <input checked="" type="checkbox"/> OVERCAST/RAIN _____ WIND DIRECTION <u>N/A</u> AMBIENT TEMPERATURE <u>88 F</u>			
SHIPMENT VIA. FEDEX <input checked="" type="checkbox"/> HAND DELIVER _____ COURIER _____ OTHER _____			
SHIPPED TO. <u>STL - Chicago</u>			
COMMENTS _____			
SAMPLER <u>K Duran</u>		OBSERVER <u>M Johnston</u>	
MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

## GROUNDWATER FIELD SAMPLING DATA SHEET

Well No..	WHGLTA050	Location:	AOC 19					
Sampler(s).	K. Duran, M. Johnston	Project Name:	Phase II St, Round 3					
Well Depth:	7.12	Project #:	AFC001-26CE	Date:	6/15/01	Time:	9:10	
DTW (ft).	6.02	DTP (ft):	N/A	Courier	X FedEx	UPS	Hand	Other
MP Ht. Above/Below Ground Surface:	-0.112	Sampling Method :	BP					
Condition of Bottom of Well:		Type of Pump	Bladder					
Screen Interval (ft):	(2.03 - 7.03)	Weather (sun/clear, overcast/rain, wind direction, ambient temperature):	Sunny, humid, little to no wind, 80°					
Well Diameter (in):	2							
Placement of Pump (ft):	6.57							

## Field Parameters

[illegible]

## Observations

Color: Clear Other (describe):

Odor: None Low Medium High Very Strong H<sub>2</sub>S Fuel-like

Notes:

Signed/Sampler(s): MAH 1

724 376



## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: Phase II SI, Round 3

SITE: AOC 19

PROJECT NO: AFC001-26CE

## SAMPLE INFORMATION

SAMPLE ID WHGLTA051-WG03

DATE: 6/15/01 TIME: 1105

MATRIX TYPE: WG

SAMPLING METHOD: BP

LOT CONTROL #: 0 1 1 A

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #:

SAMPLE SEG DPETH (FT) 6.03'

SAMPLE END DPETH (FT)

GRAB (X) COMPOSITE ( )

ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:

MATRIX SPIKE (MS) WHGLTA055-WG03MS

MATRIX SPIKE DUP (SD) WHGLTA055-WG03MD

FIELD DUP (FD) DUP07

AMBIENT BLANK (AB) N/A

EQUIPMENT BLANK (EB) EB061501

TRIP BLANK (TB) TB061501

CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA 3	Cool to 4C	SW8260B	TCE

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st 7.7	COLOR	
2nd 0.0	ODOR	
	OTHER	
pH 6.44	Temperature 23.67 (C)	Dissolved Oxygen 2.13 (mg/L)
Iron — (mg/L)	Oxidation/Reduction Potential 307.2 (mv)	Specific Conductivity 313 (umhos/cm)
	Turbidity 5.4 (NTU)	

## GENERAL INFORMATION

WEATHER SUN/CLEAR X OVERCAST/RAIN WIND DIRECTION N/A AMBIENT TEMPERATURE 88 F

SHIPMENT VIA FEDEX x HAND DELIVER COURIER OTHER

SHIPPED TO STL - Chicago

COMMENTS

SAMPLER: K Duran

OBSERVER: M Johnston

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

## GROUNDWATER FIELD SAMPLING DATA SHEET

Well No. WHGLTA051	Location: AOC 19	
Sampler(s): K Duan, M Johnston	Project Name Phase II SI, Round 3	
Well Depth: 6.80	Project #: AFC001-26CE	Date: 6/15/01 Time: 1015
DTW (ft): 5.26 DTP (ft): N/A	Courier: <input checked="" type="checkbox"/> FedEx <input type="checkbox"/> UPS <input type="checkbox"/> Hand <input type="checkbox"/> Other	
MP Ht. Above/Below Ground Surface: -0.071	Sampling Method: BP	
Condition of Bottom of Well: Silty	Type of Pump: Bladder	
Screen Interval (ft): (1.92 - 6.92)	Weather (sun/clear, overcast/rain, wind direction, ambient temperature): Sunny, very little breeze, humid, high 80's	
Well Diameter (in) 2		
Placement of Pump (ft) 6.03'		

## Field Parameters

Time	Depth to Water (ft)	Flow Rate (L/m)	Total Volume (L)	pH	Temp. (C)	Cond. (umhos/cm)	ORP (mv)	DO (mg/L)	Turb. (NTU)	Type, Size, and Amount of Sediment Discharged
1020	5.10	Start pump								Cloudy, no odor
1025	5.35	0.175	0.875	6.67	24.51	141	321.3	6.45	104	Cloudy
1030	5.37	0.175	1.75	6.67	23.18	159	325.4	3.06	139	Cloudy
1035	5.29	0.175	2.62	6.48	22.94	228	329.8	2.11	88	Cloudy
1040	5.35	0.175	3.40	6.42	23.12	287	323.7	2.07	29	Clearing up
1045	5.32	0.175	4.28	6.42	23.13	299	318.7	2.21	16.4	
1050	5.29	0.175	5.16	6.41	23.15	305	316.1	2.15	9.3	Clear
1055	5.28	0.175	6.04	6.43	23.30	310	310.3	2.14	6.6	Clear
1100	5.28	0.175	6.92	6.44	23.67	313	307.2	2.13	5.4	Clear
1105	Collect sample									

## Observations

Color: (Clear) Other (describe):
Odor: (None Low Medium High Very Strong H2S Fuel-like)
Notes:
Signed/Sampler(s): M Johnston

724 378



## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, TX  
SITE AOC 19

PROJECT NAME: Phase II SI, Round 3  
PROJECT NO: AFC001-26CE

## SAMPLE INFORMATION

SAMPLE ID WHGLTA052-WG03

DATE: 6/26/01 TIME: 1346

MATRIX TYPE WG

SAMPLING METHOD: BP

LOT CONTROL #: 011A

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #: \_\_\_\_\_

SAMPLE BEG DPETH (FT) N/ASAMPLE END DPETH (FT) N/A

GRAB (X) COMPOSITE ( )

ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE

MATRIX SPIKE (MS): \_\_\_\_\_

MATRIX SPIKE DUP (SD) \_\_\_\_\_

FIELD DUP (FD) \_\_\_\_\_

AMBIENT BLANK (AB) \_\_\_\_\_

EQUIPMENT BLANK (EB) EB062601TRIP BLANK (TB) TB062601

CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA 3	Cool to 4C	SW8260B	TCE

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS
1st <u>NA</u>	COLOR <u>clear</u>	
2nd <u>NA</u>	ODOR <u>none</u>	
	OTHER	

pH 6.55 Temperature 25.73 (C) Dissolved Oxygen 9.11 (mg/L) Specific Conductivity 142 (umhos/cm)  
Iron N/A (mg/L) Oxidation/Reduction Potential 288 (mv) Turbidity 4.7 (NTU)

## GENERAL INFORMATION

WEATHER: SUN/CLEAR X OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION E AMBIENT TEMPERATURE 90°

SHIPMENT VIA. FEDEX x HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

SHIPPED TO. STL - Chicago

COMMENTS: \_\_\_\_\_

SAMPLER K. Duran

OBSERVER J. Wallace

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



## GROUNDWATER FIELD SAMPLING DATA SHEET

Well No. WHGLTA052	Location AOC 19	
Sampler(s): K. Duran, J. Wallace	Project Name: Phase II SI, Round 3	
Well Depth: 6.88	Project #: AFC001-26CE	Date: 6/26/01 Time 1300
DTW (ft): 95.25 95.25 <sub>10</sub>	DTP (ft): —	Courier: ___ FedEx ___ UPS ___ Hand ___ Other
MP Ht. Above/Below Ground Surface: -0.122	Sampling Method: BP LOW FLOW	
Condition of Bottom of Well: firm	Type of Pump: BLADDER PUMP	
Screen Interval (ft): (1.99 - 6.99)	Weather (sun/clear, overcast/rain, wind direction, ambient temperature): Sunny, 90°, E	
Well Diameter (in): 2		
Placement of Pump (ft): TOP 3.07		

## Field Parameters

[illegible]

## Observations

Color: Clear Other (describe): clear  
Odor: None Low Medium High Very Strong H<sub>2</sub>S Fuel-like none  
Notes: initial DOV prior to lowering pump = 5.26  
  
  
Signed/Sampler(s): A. Bell

## FIELD SAMPLING REPORT

LOCATION:	NAS Fort Worth JRB, TX	PROJECT NAME:	Phase II SI, Round 3
SITE:	AOC 19	PROJECT NO:	AFC001-26CE
<b>SAMPLE INFORMATION</b>			
SAMPLE ID WHGLTA004-WG03		DATE: <u>6/15/2001</u> TIME: <u>1340</u>	
MATRIX TYPE: WG		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) <u>WHGLTA055-WG03MS</u> MATRIX SPIKE DUP (SD) <u>WHGLTA055-WG03MS</u> FIELD DUP (FD) <u>DUP07</u> AMBIENT BLANK (AB) <u>N/A</u> EQUIPMENT BLANK (EB) <u>EB N/A</u> TRIP BLANK (TB) <u>TBCK1501</u>	
SAMPLING METHOD: BP			
LOT CONTROL #: <u>011A</u>			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY #: _____			
SAMPLE BEG DPETH (FT) <u>Dedicated</u>			
SAMPLE END DPETH (FT)			
GRAB <input checked="" type="checkbox"/> COMPOSITE <input type="checkbox"/>			
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA 3	Cool to 4C	SW8260B	TCE

NOTABLE OBSERVATIONS			
PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS	
1st <u>49.8 ppm</u>	COLOR: <u>Clear</u>		
2nd <u>5.1 ppm</u>	ODOR: <u>none</u>		
	OTHER		
pH <u>6.39</u> Temperature <u>23.38</u> (C) Dissolved Oxygen <u>2.50</u> (mg/L) Specific Conductivity <u>296</u> (umhos/cm)			
Iron _____ (mg/L) Oxidation/Reduction Potential <u>296.9</u> (mv) Turbidity <u>2.8</u> (NTU)			
GENERAL INFORMATION			
WEATHER: <u>SUN/CLEAR</u> <input checked="" type="checkbox"/> OVERCAST/RAIN _____ WIND DIRECTION _____ AMBIENT TEMPERATURE <u>90 F</u>			
SHIPMENT VIA: FEDEX <input checked="" type="checkbox"/> HAND DELIVER _____ COURIER _____ OTHER _____			
SHIPPED TO <u>STL - Chicago</u>			
COMMENTS: _____			
SAMPLER: <u>Eduran</u>		OBSERVER: <u>M. Johnston</u>	
MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

Well No.: WHGLTA004	Location: AOC 19	
Sampler(s): K Duran, M Johnston	Project Name: Phase II SI, Round 3	
Well Depth: *	Project #: AFC001-26CE	Date: 6/15/01 Time: 1245
DTW (ft): * DTP (ft): N/A	Courier: <input checked="" type="checkbox"/> FedEx <input type="checkbox"/> UPS <input type="checkbox"/> Hand <input type="checkbox"/> Other	
MP Ht. Above/Below Ground Surface: -0.2	Sampling Method: BP	
Condition of Bottom of Well: unknown	Type of Pump: Dedicated bladder	
Screen Interval (ft): (13.3 - 23.3)	Weather (sun/clear, overcast/rain, wind direction, ambient temperature):	
Well Diameter (in): 2	Sun, very little breeze,	
Placement of Pump (ft): Dedicated		

## Field Parameters

[illegible]

## Observations

Color: Clear Other (describe):  
Odor: None Low Medium High Very Strong H<sub>2</sub>S Fuel-like  
Notes: \* 18.25' top of pump. Couldn't gauge dtw or td  
Signed/Sampler(s): M. Hunt

724 382



## FIELD SAMPLING REPORT

LOCATION: NAS Fort Worth JRB, TX	PROJECT NAME: Phase II SI, Round 3		
SITE: AOC 19	PROJECT NO: AFC001-26CE		
<b>SAMPLE INFORMATION</b>			
SAMPLE ID WHGLTA801-WG03	DATE: <u>6/14/01</u> TIME: <u>1610</u>		
MATRIX TYPE: WG	ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE.  MATRIX SPIKE (MS) <u>WHGLTA055-WG03MS</u> MATRIX SPIKE DUP (SD) <u>WHGLTA055-WG03MD</u> FIELD DUP (FD) <u>DUP02</u> AMBIENT BLANK (AB) <u>N/A</u> EQUIPMENT BLANK (EB) <u>EB061401</u> TRIP BLANK (TB) <u>TB061401</u>		
SAMPLING METHOD: BP			
LOT CONTROL #: <u>0 1 1 A</u>			
(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)			
CHAIN-OF-CUSTODY # _____			
SAMPLE <sup>PUMP</sup> BEG DPETH (FT) <u>8.54</u>			
SAMPLE END DPETH (FT)			
GRAB (X) COMPOSITE ( )			
CONTAINER	PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE #			
40 mL VOA 3	Cool to 4C	SW8260B	TCE

NOTABLE OBSERVATIONS			
PID READINGS	SAMPLE CHARACTERISTICS	MISCELLANEOUS	
1st <u>3.7 ppm</u>	COLOR <u>clear</u>		
2nd <u>0.0 ppm</u>	ODOR <u>none</u>		
	OTHER		
pH <u>10.40</u>	Temperature <u>24.59</u> (C)	Dissolved Oxygen <u>2.10</u> (mg/L)	Specific Conductivity <u>301</u> (umhos/cm)
Iron <u>—</u> (mg/L)	Oxidation/Reduction Potential <u>190.1</u> (mv)	Turbidity <u>5.7</u> (NTU)	
GENERAL INFORMATION			
WEATHER <u>SUN/CLEAR</u> <input checked="" type="checkbox"/>	OVERCAST/RAIN _____	WIND DIRECTION <u>S/SE</u>	AMBIENT TEMPERATURE <u>95 F</u>
SHIPMENT VIA FEDEX <u>x</u>	HAND DELIVER _____	COURIER _____	OTHER _____
SHIPPED TO: <u>STL - Chicago</u>			
COMMENTS _____			
SAMPLER <u>K Duxan</u>		OBSERVER <u>M Johnston</u>	
MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP



## FIELD SAMPLING REPORT

724 383

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: Phase II SI, Round 3

SITE: AOC 19

PROJECT NO: AFC001-26CE

## SAMPLE INFORMATION

SAMPLE ID ~~WH6LTA01~~ WH6LTA055DATE: 6/14/01 TIME 1200

MATRIX TYPE: WG

SAMPLING METHOD: BP

LOT CONTROL #: 0 1 1 4

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #. \_\_\_\_\_

SAMPLE BEG DPETH (FT) STAY 8.54

SAMPLE END DPETH (FT)

GRAB ☒ COMPOSITE ( )ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:MATRIX SPIKE (MS): WH6LTA055-W603MSMATRIX SPIKE DUP (SD) WH6LTA055-W603MDFIELD DUP (FD): WH6LTA055-W603MSAMBIENT BLANK (AB) N/AEQUIPMENT BLANK (EB) EB061401TRIP BLANK (TB) EB061401

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
40 mL VOA	3	Cool to 4C	SW8260B	TCE

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS		MISCELLANEOUS
1st <u>3.7</u>	COLOR	<u>clear</u>	
2nd <u>0.0</u>	ODOR	<u>none</u>	
	OTHER		
pH <u>6.41</u>	Temperature <u>24.57</u> (C)	Dissolved Oxygen <u>2.10</u> (mg/L)	Specific Conductivity <u>301</u> (umhos/cm)
Iron <u>—</u> (mg/L)	Oxidation/Reduction Potential <u>190.1</u> (mv)	Turbidity <u>5.7</u> (NTU)	

## GENERAL INFORMATION

WEATHER SUN/CLEAR OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION S/SE AMBIENT TEMPERATURE 95°FSHIPMENT VIA: FEDEX x HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_SHIPPED TO: STL - Chicago

COMMENTS: \_\_\_\_\_

SAMPLER K DuranOBSERVER M Johnston

MATRIX TYPE CODES		SAMPLING METHOD CODES	
DC=DRILL CUTTINGS	SL=SLUDGE	B=BAILER	G=GRAB
WG=GROUND WATER	SO=SOIL	BP=BLADDER PUMP	HA=HAND AUGER
LH=HAZARDOUS LIQUID WASTE	GS=SOIL GAS	BR=BRASS RING	H=HOLLOW STEM AUGER
SH=HAZARDOUS SOLID WASTE	WS=SURFACE WATER	CS=COMPOSITE SAMPLE	HP=HYDRO PUNCH
SE=SEDIMENT	SW=SWAB/WIPE	C=CONTINUOUS FLIGHT AUGER	SS=SPLIT SPOON
		DT=DRIVEN TUBE	SP=SUBMERSIBLE PUMP

724 384

## GROUNDWATER FIELD SAMPLING DATA SHEET

Well No.: WHGLTA801	Location: AOC 19
Sampler(s): <i>K. Duran M. Johnston</i>	Project Name: Phase II SI, Round 3
Well Depth: <i>13.94</i>	Project #: AFC001-26CE Date: <i>6/14/01</i> Time: <i>1500</i>
DTW (ft): <i>9.13</i> DTP (ft): <i>N/A</i>	Courier: <input checked="" type="checkbox"/> FedEx <input type="checkbox"/> UPS <input type="checkbox"/> Hand <input type="checkbox"/> Other
MP Ht. Above/Below Ground Surface:	Sampling Method: BP
Condition of Bottom of Well: <i>Good</i>	Type of Pump: <i>Bladder</i>
Screen Interval (ft): (-)	Weather (sun/clear, overcast/rain, wind direction, ambient temperature):
Well Diameter (in): <i>2</i>	<i>Sun, windy (S/SE), 90°F</i>
Placement of Pump (ft): <i>8.54</i>	

## Field Parameters

Time	Depth to Water (ft)	Flow Rate (L/m)	Total Volume (L)	pH	Temp. (C)	Cond. (umhos/cm)	ORP (mv)	DO (mg/L)	Turb. (NTU)	Type, Size, and Amount of Sediment Discharged
1520	8.90	Start pump								
1525	8.86	0.24	1.2	6.56	25.61	310	163.7	5.44	<i>240</i> <i>234</i>	
1530	8.85	0.175	2.08	6.36	25.17	305	190.7	3.74	180	
1535	8.86	0.175	2.96	6.38	25.28	305	189.9	2.85	68	
1540	8.87	0.175	3.84	6.40	25.28	306	190.8	2.34	29	
1545	8.87	0.175	4.72	6.41	25.62	307	189.6	2.16	17.2	
1550	8.87	0.175	5.60	6.42	25.91	309	187.1	2.15	10.4	
1555	8.86	0.2	6.60	6.49	24.62	314	187.8	2.32	7.8	Compressor overheated Stop pump change compressor
1600	8.86	0.2	7.60	6.40	24.44	300	192.2	2.22	5.9	
1605	8.86	0.2	8.60	6.40	24.59	301	190.1	2.10	5.7	
1610	Collect sample (WHGLTA801-W603 and DUP07)									

## Observations

Color: <i>Clear</i> Other (describe):
Odor: <i>None</i> Low Medium High Very Strong H <sub>2</sub> S Fuel-like
Notes: <i>There was 4" standing water in</i>
Signed/Sampler(s): <i>M. Johnston</i>



## FIELD SAMPLING REPORT

724 385

LOCATION: NAS Fort Worth JRB, TX

PROJECT NAME: RFI Landfills Investigation

SITE: SWMU 17 / Acc 19

PROJECT NO: AFC001-33CBC / 2666

## SAMPLE INFORMATION

SAMPLE ID TB061501

DATE: 6/15/01 TIME: 730

MATRIX TYPE: W

SAMPLING METHOD: G

LOT CONTROL #: C L L A

(Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)

CHAIN-OF-CUSTODY #:

SAMPLE BEG DPETH (FT) N/A

SAMPLE END DPETH (FT)

GRAB (X) COMPOSITE ( )

ENTER SAMPLE NUMBERS FOR QC SAMPLES/  
BLANKS ASSOCIATED WITH THIS SAMPLE:

MATRIX SPIKE (MS) \_\_\_\_\_

MATRIX SPIKE DUP (SD) \_\_\_\_\_

FIELD DUP (FD) \_\_\_\_\_

AMBIENT BLANK (AB) N/A

EQUIPMENT BLANK (EB) TB061501

TRIP BLANK (TB) \_\_\_\_\_

CONTAINER		PRESERVATIVE/ PREPARATION	ANALYTICAL METHOD	ANALYSIS
SIZE/TYPE	#			
1 L Amber	10	Cool to 4C HCL	5682603	BTEX + TOC

## NOTABLE OBSERVATIONS

PID READINGS	SAMPLE CHARACTERISTICS		MISCELLANEOUS
N/A	COLOR		
2nd	ODOR		
	OTHER		
pH _____	Temperature _____ (C)	Dissolved Oxygen _____ (mg/L)	Specific Conductivity _____ (umhos/cm)
Iron _____ (mg/L)	Oxidation/Reduction Potential _____ (mv)	Turbidity _____ (NTU)	

## GENERAL INFORMATION

WEATHER SUN/CLEAR X OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION N/A AMBIENT TEMPERATURE 73°F

SHIPMENT VIA FEDEX x HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

SHIPPED TO: STL - Chicago

COMMENTS:

SAMPLER: K. Duval

OBSERVER: M. Johnson

MATRIX TYPE CODES

DC=DRILL CUTTINGS SL=SLUDGE  
WG=GROUND WATER SO=SOIL  
LH=HAZARDOUS LIQUID WASTE GS=SOIL GAS  
SH=HAZARDOUS SOLID WASTE WS=SURFACE WATER  
SE=SEDIMENT SW=SWAB/WIPE

SAMPLING METHOD CODES

B=BAILER G=GRAB  
BP=BLADDER PUMP HA=HAND AUGER  
BR=BRASS RING H=HOLLOW STEM AUGER  
CS=COMPOSITE SAMPLE HP=HYDRO PUNCH  
C=CONTINUOUS FLIGHT AUGER SS=SPLIT SPOON  
DT=DRIVEN TUBE SP=SUBMERSIBLE PUMP

## FIELD SAMPLING REPORT

LOCATION NAS Fort Worth JRB, TX  
SITE SWMU 17 / Acc 19

PROJECT NAME: RFI Landfills Investigation  
PROJECT NO: AFC001-33CBC / 2000

## SAMPLE INFORMATION

SAMPLE ID EB061501		DATE: 6/15/01		TIME: 1415	
MATRIX TYPE: W		ENTER SAMPLE NUMBERS FOR QC SAMPLES/ BLANKS ASSOCIATED WITH THIS SAMPLE:  MATRIX SPIKE (MS) _____ MATRIX SPIKE DUP (SD) _____ FIELD DUP (FD) _____ AMBIENT BLANK (AB): 151A EQUIPMENT BLANK (EB) _____ TRIP BLANK (TB) 9306-1501			
SAMPLING METHOD: E					
LOT CONTROL # C 1 1 1A (Ambient Blank # - Equipment Blank # - Trip Blank # - Cooler #)					
CHAIN-OF-CUSTODY #: _____					
SAMPLE BEG DPETH (FT) N/A					
SAMPLE END DPETH (FT)					
GRAB (X) COMPOSITE ( )					
CONTAINER		PRESERVATIVE/ PREPARATION		ANALYTICAL METHOD	
SIZE/TYPE	#				
1 L Amber	10	Cool to 4C HCL		SWEETGUB	
				BTEX + TCE	

## NOTABLE OBSERVATIONS

PID READINGS		SAMPLE CHARACTERISTICS		MISCELLANEOUS	
1st	151A	COLOR			
2nd		ODOR			
OTHER					
pH _____		Temperature _____ (C)		Dissolved Oxygen _____ (mg/L)	
Iron _____ (mg/L)		Oxidation/Reduction Potential _____ (mv)		Specific Conductivity _____ (umhos/cm)	
		Turbidity _____ (NTU)			

## GENERAL INFORMATION

WEATHER SUN/CLEAR \_\_\_\_\_ OVERCAST/RAIN \_\_\_\_\_ WIND DIRECTION \_\_\_\_\_ AMBIENT TEMPERATURE \_\_\_\_\_

SHIPMENT VIA FEDEX x HAND DELIVER \_\_\_\_\_ COURIER \_\_\_\_\_ OTHER \_\_\_\_\_

SHIPPED TO STL - Chicago

COMMENTS: \_\_\_\_\_

SAMPLER: \_\_\_\_\_ OBSERVER: \_\_\_\_\_

## MATRIX TYPE CODES

DC=DRILL CUTTINGS SL=SLUDGE  
 WG=GROUND WATER SO=SOIL  
 LH=HAZARDOUS LIQUID WASTE GS=SOIL GAS  
 SH=HAZARDOUS SOLID WASTE WS=SURFACE WATER  
 SE=SEDIMENT SW=SWAB/WIPE

## SAMPLING METHOD CODES

B=BAILER G=GRAB  
 BP=BLADDER PUMP HA=HAND AUGER  
 BR=BRASS RING H=HOLLOW STEM AUGER  
 CS=COMPOSITE SAMPLE HP=HYDRO PUNCH  
 C=CONTINUOUS FLIGHT AUGER SS=SPLIT SPOON  
 DT=DRIVEN TUBE SP=SUBMERSIBLE PUMP



**CHAINS OF CUSTODY**





**Chicago Laboratory**  
2417 Bond Street  
University Park, IL 60466  
Phone 708-534-5200  
Fax 708-534-5211

Report To:

Contact: Chris Camp  
Company: Hydro Laboratories  
Address: 1155 Herndon Pkwy  
Herndon VA 20170  
Phone: (703) 478-5186  
Fax: \_\_\_\_\_  
E-Mail: CCamp@HGL.com

Bill To:

Contact: - Same -  
Company: \_\_\_\_\_  
Address: \_\_\_\_\_  
Phone: \_\_\_\_\_  
Fax: \_\_\_\_\_  
PO#: \_\_\_\_\_

724 389  
Shaded Areas For Internal Use Only 1 of 2

Lab Lot #

Package Sealed Yes No  
Samples Sealed Yes No  
Received on Ice Yes No  
Samples Intact Yes No  
Temperature °C of Cooler

Within Hold Time Yes No  
Preserv. indicated Yes No NA  
pH Check ok Yes No NA  
Res. Cl<sub>2</sub> Check ok Yes No NA  
Sample Labels and COC Agree Yes No  
COC not present

Additional Analyses / Remarks

Laboratory ID	MS/SD	Client Sample ID	Sampling Date	Matrix			Refrig #	# Cont.	Volume	Preserv	Quote
				Comp/Grab	Matrix	Matrix					
BHGLAOC1801-01			5/15/13	5							
BHGLAOC1801-02			1315	1							
BHGLAOC1801-03			1330	1							
BHGLAOC1802-01			1405	1							
BHGLAOC1802-02			1416	1							
BHGLAOC1802-03			1436	1							
DUP04			1515	1							
BHGLAOC1803-01			1505	1							
BHGLAOC1803-02			1510	1							
BHGLAOC1803-03			1530	1							
DUP05			1630	1							

RELINQUISHED BY: J. Wilson COMPANY: Hydro Laboratories DATE: 5/15/13 TIME: 1830  
RELINQUISHED BY: \_\_\_\_\_ COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_ TIME: \_\_\_\_\_

<b>Matrix Key</b> WW = Wastewater W = Water S = Soil SL = Sludge MS = Miscellaneous OL = Oil A = Air	<b>Container Key</b> 1 Plastic 2 VOA Vial 3 Sterile Plastic 4 Amber Glass 5 Widemouth Glass 6 Other	<b>Preservative Key</b> 1 HCl, Cool to 4° 2 H2SO4, Cool to 4° 3 HNO3, Cool to 4° 4 NaOH, Cool to 4° 5 NaOH/Zn Acetate, Cool to 4° 6 Cool to 4° 7 None	<b>Comments</b> Please hold extra volume for SPL analyses * use Appendix IX Lists	<b>Date Received</b> _____ <b>Courier</b> _____ <b>Hand Delivered</b> <input type="checkbox"/> <b>Bill of Lading</b> _____
---	---	--	---	---



**Chicago Laboratory**  
2417 Bond Street  
University Park, IL 60466  
Phone 708-534-5200  
Fax 708-534-5211

Report To:

Contact Chris Camd  
Company HydroGed Labs  
Address 1155 Herndon Pkwy  
Herndon VA 20170  
Phone (703) 478-5186  
Fax  
E-Mail

Bill To:

Contact Same  
Company  
Address  
Phone  
Fax  
PO#

Shaded Areas For Internal Only 1 of 2

Lab Lot #

Package Sealed  
Yes No  
Samples Sealed  
Yes No

Received on Ice  
Yes No  
Samples Intact  
Yes No

Temperature °C of Cooler

Quote

Within Hold Time  
Yes No  
Preserv. Indicated  
Yes No NA  
pH Check ok  
Yes No NA  
Res. Cl<sub>2</sub> Check ok  
Yes No NA  
Sample Labels and COC Agree  
Yes No COC not present

Additional Analyses / Remarks

Laboratory ID	MS/SD	Client Sample ID	Sampling Date Time	Matrix	Comp/Grab	Refr #	Signature				Ref #	Project Name				#/Cont.	Volume	Preserv	Date Required				Hard Copy	Fax
							Signature	Project Number	Project Location	Lab PM		Signature	Project Number	Project Location	Lab PM									
		BHG-LAOC1902-01	5/15/08 0850	S	G	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1
		BHG-LAOC1902-02	0855			1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1
		BHG-LAOC1903-01	0935			1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1
		BHG-LAOC1903-02	0950			1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1
		BHG-LAOC1904-01	1040			1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1
		BHG-LAOC1904-02	1100			1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1
		DUPOL	0835			1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1
		BHG-LAOC1904-01MS	1040			1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1
		BHG-LAOC1904-01MSD	1040			1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1
		EB051500	1730			1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1
		TB051500	800			1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1	3	1

RELINQUISHED BY

COMPANY

DATE

TIME

DATE

RECEIVED BY

COMPANY

DATE

TIME

RELINQUISHED BY

COMPANY

DATE

TIME

DATE

RECEIVED BY

COMPANY

DATE

TIME

Matrix Key

WW = Wastewater  
W = Water  
S = Soil  
SL = Sludge  
MS = Miscellaneous  
OL = Oil  
A = Air  
SE = Sediment  
SO = Solid  
DS = Drum Solid  
DL = Drum Liquid  
L = Leachate  
WI = Wipe  
O =

Container Key

1 Plastic  
2 VOA Vial  
3 Sterile Plastic  
4 Amber Glass  
5 Wide-mouth Glass  
6 Other

Preservative Key

1 HCl, Cool to 4°  
2 H<sub>2</sub>SO<sub>4</sub>, Cool to 4°  
3 HNO<sub>3</sub>, Cool to 4°  
4 NaOH, Cool to 4°  
5 NaOH/Zn Acetate, Cool to 4°  
6 Cool to 4°  
7 None

COMMENTS: Please hold extra volume for SPI analyses. These appendices 1x1515

Date Received

Courier

Hand Delivered

Bill of Lading





## Report To:

## Bill To:

Contact Kim Evers  
 Company Hydrogeologic, Inc.  
 Address 1155 Herndon Hwy, STE 500  
Herndon VA 20170  
 Phone 703-478-5186  
 Fax 703-471-4180  
 E-Mail KimEvers@hgl.com

Contact Kim Evers  
 Company (same)  
 Address \_\_\_\_\_  
 Phone \_\_\_\_\_  
 Fax \_\_\_\_\_  
 PO# \_\_\_\_\_  
 Quote \_\_\_\_\_

# SEVERN

# TRENT

# SERVICES

STL Chicago  
 2417 Bond Street  
 University Park, IL 60466  
 Phone 708-534-5200  
 Fax 708-534-5211

Sampler Name: <u>M Johnston</u>		Signature: <u>[Signature]</u>		Ref #		3		2		1		3		Within Hold Time		Preserv. Indicated	
Project Name: <u>Phase II RFI/ST</u>		Project Number: <u>AF001-26CE</u>		# / Cont.		40ml		12		1L		40ml		Yes		No NA	
Project Location: <u>NAS FW JRS</u>		Date Required: <u>1/1/11</u>		Volume		40ml		7		3		1		pH Check OK		Res Cl <sub>2</sub> Check OK	
Lab PM: <u>Donna Ingersoll</u>		Hard Copy: <u>1/1/11</u>		Preserv		1		7		3		1		Yes		No NA	
Laboratory ID		Client Sample ID		Matrix		Comp/Grab		SW2608		SW2706		SW2808		SW2808		SW2808	
MS-MSD		Sampling Date		Time		Date		Date		Date		Date		Date		Date	
W66LTA055W601		2/2/01		1620		W		G		X		X		X		X	
W66LTA053W601		2/2/01		1350		W		G		X		X		X		X	
W66LTA056W601		2/11/01		1155		W		G		X		X		X		X	
DWP03		2/11/01		1200		W		G		X		X		X		X	
W66LTA050W601		2/11/01		1815		W		G		X		X		X		X	
E8022101		2/11/01		1830		W		G		X		X		X		X	
E80222001		2/12/01		1800		W		G		X		X		X		X	
FT09-12BW601		2/12/01		1700		W		G		X		X		X		X	
X FT09-12BP45X		2/11/01		1700		W		G		X		X		X		X	
X FT09-12BP45X		2/11/01		1700		W		G		X		X		X		X	
TB022001		2/10/01		0730		W		G		X		X		X		X	

RELINQUISHED BY: <u>[Signature]</u>	COMPANY: <u>Hydrogeologic</u>	DATE: <u>2/11/01</u>	TIME: <u>1840</u>
RELINQUISHED BY:	COMPANY:	DATE:	TIME:

Matrix Key		Container Key		Preservative Key	
WW = Wastewater	SE = Sediment	1 Plastic	1 HCl Cool to 4	1 HCl Cool to 4	1 HCl Cool to 4
W = Water	SO = Solid	2 VOA Vial	2 H2SO4 Cool to 4	2 H2SO4 Cool to 4	2 H2SO4 Cool to 4
S = Soil	DS = Drum Solid	3 Sterile Plastic	3 HNO3 Cool to 4	3 HNO3 Cool to 4	3 HNO3 Cool to 4
SL = Sludge	DL = Drum Liquid	4 Amber Glass	4 NaOH Cool to 4	4 NaOH Cool to 4	4 NaOH Cool to 4
MS = Miscellaneous	L = Leachate	5 Widenmouth Glass	5 NaOH/Zn Cool to 4	5 NaOH/Zn Cool to 4	5 NaOH/Zn Cool to 4
OL = Oil	WI = Wipe	6 Other	6 Cool to 4	6 Cool to 4	6 Cool to 4
A = Air	O =				

Date Received	Hand Delivered
Courier	Bill of Lading

**SEVER  
TRENT  
SERVICES**

STL Chicago

2417 Bond Street  
University Park, IL 60466  
Phone 708 534-5200  
Fax 708 534-5211

Report To:

Contact Kim Evers  
Company Hydrobiologic, Inc.  
Address 1155 Herndon Pkwy STE 900  
Herndon VA 20170  
Phone 703-478-5186  
Fax 703-471-4180  
E Mail keverschgl.com

To:

Contact Kim Evers  
Company (Same)  
Address \_\_\_\_\_  
Phone \_\_\_\_\_  
Fax \_\_\_\_\_  
PO# \_\_\_\_\_

Shaded Areas For Internal Use Only

Lab L t# 902672720

Package Sealed	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	Samples Sealed	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Received on Ice	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	Samples Intact	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Temperature °C of Cooler <u>2.7</u>			

Within Hold Time	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	Preserv. Indicated	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> NA
PH Check OK	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> NA	Res Cl <sub>2</sub> Check OK	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> NA
Sample Labels and COC Agree			
Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> COC not present			

Additional Analyses / Remarks

Sampler Name:		Signature:		Refrg #																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
---------------	--	------------	--	---------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

only 240ml vials

RELINQUISHED BY	RELINQUISHED BY	DATE	TIME	DATE	TIME
<u>M Johnston</u>	<u>Kim Evers</u>	<u>2/22/01</u>	<u>1450</u>	<u>2/23/01</u>	<u>1345</u>
COMPANY	COMPANY				
<u>Hydrobiologic</u>	<u>Hydrobiologic</u>				

Matrix Key	Container Key	Preservative Key
WW = Wastewater W = Water S = Soil SL = Sludge MS = Miscellaneous OL = Oil A = Air	1 Plastic 2 VOA Vial 3 Sterile Plastic 4 Another Glass 5 Wide-mouth Glass 6 Other	1 HCl, Cool to 4 2 H2SO4, Cool to 4 3 HNO3, Cool to 4 4 NaOH, Cool to 4 5 NaOH/7h, Cool to 4 6 Cool to 4 7 None

Date Received	2/23/01
Courier	FX
Hand Delivered	
Bill of Lading	See Attached

724 304







**BEST AVAILABLE COPY**

**STL Chicago**  
2417 Bond Street  
University Park, IL 60466  
Phone 708-534-5200  
Fax 708-534-5211

[illegible]

RELINQUISHED BY <i>[Signature]</i>	COMPANY Vicki's Geology	DATE 6/15/01	TIME 17:00
RELINQUISHED BY	COMPANY	DATE	TIME

RECEIVED BY	COMPANY	DATE	TIME
RECEIVED BY	COMPANY	DATE	TIME

<b>Matrix Key</b> WW = Wastewater W = Water S = Soil SL = Sludge MS = Miscellaneous OL = Oil A = Air  SE = Sediment SO = Solid DS = Drum Solid DL = Drum Liquid L = Leachate WI = Wipe O =	<b>Container Key</b> 1 Plastic 2 VOA Vial 3 Sterile Plastic 4 Amber Glass 5 Widemouth Glass 6 Other	<b>Preservative Key</b> 1 HCl, Cool to 4° 2 H2SO4, Cool to 4° 3 HNO3, Cool to 4° 4 NaOH, Cool to 4° 5 NaOH/Zn, Cool to 4° 6 Cool to 4° 7 None	<b>Comments</b>  	<b>Date Received</b> / /	<input type="checkbox"/>
			<b>Courier:</b>	<b>Hand Delivered</b>	
			<b>Bill of Lading</b>		

STL Chicago is a part of Southern Toxic Laboratories, Inc.





**Chicago Laboratory**  
2417 Bond Street  
University Park, IL 60466  
Phone 708-534-5200  
Fax 708-534-5211

724 399

Shaded Areas For Internal Use Only

Contact Kim Evers  
Company HydroGenetic, Inc  
Address 1155 Herndon Pkwy Ste 900  
Herndon VA 20176  
Phone 703-478-5126  
Fax 703-471-4180  
E-Mail kevers@hgi.com

Lab Lot #  
Package Sealed Yes No  
Samples Seated Yes No  
Received on Ice Yes No  
Samples Intact Yes No  
Temperature °C of Cooler

Sampler Name	Signature	Ref #	Matrix	Comp/Grab	Matrix	Volume	Preserv	Within Hold Time	Preserv. indicated
MS-MSD								Yes No	Yes No NA
Project Name	Project/Number							pH Check ok	Res Cl <sub>2</sub> Check ok
Phase II SI	AF001-2600							Yes No NA	Yes No NA
Project Location	Date Required							Sample Labels and COC Agree	
NAS FCU JRB	Hard Copy							Yes No	COC not present
Lab PM	Fax							Additional Analyses / Remarks	
Danna Ingersoll									
Laboratory ID	Client Sample ID							Additional Analyses / Remarks	
	BHGLAOC1905-01	8-10-01	1530	S	G				
	BHGLAOC1905-02		1550	S	G				
	BHGLAOC1905-03		1600	S	G				
	BHGLAOC1906-02		1435	S	G				
	BHGLAOC1906-03		1450	S	G				
	BHGLAOC1907-03		1400	S	G				
	DW052001		1200	S	G				
	FB032001		1640	W	G				
	TB032001		900	W	G				

REQUISITIONED BY Danna Ingersoll COMPANY HydroGenetic DATE 7-20-01 TIME 1740

RECEIVED BY \_\_\_\_\_ DATE \_\_\_\_\_ TIME \_\_\_\_\_

RECEIVED BY \_\_\_\_\_ DATE \_\_\_\_\_ TIME \_\_\_\_\_

**Matrix Key**  
WW = Wastewater  
W = Water  
S = Soil  
SL = Sludge  
MS = Miscellaneous  
CL = Oil  
A = Air

**Container Key**  
1 Plastic  
2 VOA Vial  
3 Sterile Plastic  
4 Amber Glass  
5 Widemouth Glass  
6 Other

**Preservative Key**  
1 HCl, Cool to 4°  
2 H2SO4, Cool to 4°  
3 HNO3, Cool to 4°  
4 NaOH, Cool to 4°  
5 NaOH/Zn Acetate, Cool to 4°  
6 Cool to 4°  
7 None

**Comments**  
App IV lot vcs also included  
w 1,2-DCE  
TB and TB also submitted w/  
BAGB SWIN 5004-24 on AF001-298823 CC

Date Received \_\_\_\_\_  
Counter \_\_\_\_\_  
Hand Delivered ☐  
Bill of Lading \_\_\_\_\_



Committed to your success

### Chicago Laboratory

2417 Bond Street  
University Park, IL 60466  
Phone 708-534-5200  
Fax 708-534-5211

Sample Name

M Johnston

Project Name

Phase II RFI ISI

Project Location

WAS FW JRB

Lab PM

Bonna Ingersoll

Laboratory ID

MS-MSD

Client Sample ID

BH6LACC1908-01

BH6LACC1908-02

BH6LACC1908-03

BH6LSWMM1919-02

BH6LSWMM1919-03

BH6LSWMM1919-04

X BH6LSWMM1919-01MS

X BH6LSWMM1919-04MD

BH6LSWMM1924-01

BH6LSWMM1924-02

X BH6LSWMM1924-02MS

X BH6LSWMM1924-02MD

RELINQUISHED BY

M Johnston

RELINQUISHED BY

HydroGeoLogic

DATE

8-21-01

DATE

12/1

TIME

COMPANY

HydroGeoLogic

COMPANY

DATE

DATE

TIME

COMPANY

COMPANY

DATE

DATE

TIME

COMPANY

COMPANY

DATE

DATE

Contact Kim Evers

Company HydroGeoLogic, Inc.

Address 1155 Herndon Pkwy Ste 500

Herndon, VA 20170

Phone 703-478-5136

Fax 703-471-4120

E Mail kevers@hgl.com

Signature M Johnston

Project Number AFC001-20CC

Date Required

Hard Copy

Fax

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

1/1

Contact Kim Evers

Company (Same)

Address

Phone

Fax

PO#

Quote

Lab Lot #

Package Sealed

Yes No

Samples Sealed

Yes No

Received on Ice

Yes No

Samples Intact

Yes No

Temperature °C of Cooler

Within Hold Time

Yes No

Preserv. indicated

Yes No

NA

pH Check ok

Yes No

Res. Cl<sub>2</sub> Check ok

Yes No

NA

Sample Labels and COC Agree

Yes No

COC not present

Additional Analyses / Remarks

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

As (Swabbed), Heaters (Swabbed)

**Chicago Laboratory**

2417 Bond Street  
University Park, IL 60466  
Phone 708-534-5200  
Fax 708-534-5211

124401

**TO: 1115**

**Shaded Areas For Internal Use Only**

Contact Kim Evers  
Company HydroGeologic, Inc.  
Address 1155 Harnden Pkwy Ste 900  
Harnden VA 20170  
Phone 703-473-5126  
Fax 703-471-4180  
E Mail Revers@hgi.com

Contact Kim Ennis  
 Company (Same)  
 Address \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 Phone \_\_\_\_\_  
 Fax \_\_\_\_\_  
 PO# \_\_\_\_\_ Quote \_\_\_\_\_

**Shaded Areas For**

Package Sealed Yes No	Samples Sealed Yes No

Received on Ice	Samples Intact	
	Yes	No
Yes		
No		

Temperature °C of Cooler

Within Hold Time	Preserv. indicated
Yes No	Yes No NA

pH Check ok	Res. Cl <sub>2</sub> Check ok
Yes No	Yes No NA

**Sample Labels and COC Agree**

	Yes	No	COC not present
--	-----	----	-----------------

Additional Analyses / Remarks

$C_0$  (wt %): BTEX, acetone, MEK, methyl isobutyl ketone

Co. Cu

Ac Ch. C. V

Franklin, Minnesota, extract

Defining 41312, and von der Benzene  
Acrylonitrile - 41312, and von der Benzene

"1712, 2 run for availability

Eintrag 1312 - von für 2004 270

Benzene, run 30.1 for benzene, extract  
Benzene, run 31.2 + run for benzene

\_\_\_\_\_

---

\_\_\_\_\_

---

---

100

DATE	TIME
------	------

DATE	TIME
------	------

[illegible]

--	--

Date Received 1/1

Courier	Hand Delivered

Bill of Lading

Guided by the	
---------------	--

SIL Chicago Chain of Custody CHL 22-09 231/A-5/99

1







# TAB

*APPENDIX G*

---

**APPENDIX G**  
**DATA VALIDATION REPORTS**

**ENVIRONMENTAL**  
Data Services, Inc.

### METALS

USEPA SW846 Methods 6010B/7000 - Level III Review

Site: Naval Air Station Fort Worth - D026CC SDG # 9A05G259

Client HydroGeoLogic, Inc. Date June 28, 2000

Laboratory Severn Trent Laboratories, Chicago, IL Reviewer Cathy Shelby

Client Sample ID	Laboratory Sample ID	Matrix
BHGLAOC1901-02	9A05G259-001	Soil
BHGLAOC1901-03	9A05G259-002	Soil
BHGLAOC1901-01	9A05G259-003	Soil

Holding Times - All samples were extracted and analyzed within 28 days for mercury and 180 days for all other metals as specified in the NAS Fort Worth JRB Basewide Quality Assurance Project Plan (QAPP), March 2000. No qualifications were required

Calibration - All initial and continuing calibration verifications exhibited acceptable %R values. No qualifications were required.

Method Blanks - The water preparation blank PBW, initial and continuing calibration blanks exhibited beryllium and vanadium contamination at 1.5 ug/L and 2.2 ug/L, respectively. Beryllium has been qualified (U) in samples BHGLAOC1901-02 and BHGLAOC1901-03. All other associated results are greater than 5X the blank concentration and no further qualifications were required.

The water preparation blank PBW, initial and continuing calibration blanks exhibited negative blank contamination for several compounds. Antimony and silver have been qualified (U) in samples BHGLAOC1901-01, BHGLAOC1901-02 and BHGLAOC1901-03. All other associated results are greater than 5X the blank concentration or less than the PQL and no further qualifications were required.

Field and equipment blank - Equipment blank EB051200 (from SDG 9A05G263) exhibited zinc contamination at 11.9 ug/L, however, all associated results are greater than 5X the blank concentration and no qualifications were required.

ICP Interference Check Sample - All % recovery values met the QC acceptance criteria. No qualifications were required.

LCS - The LCS sample exhibited acceptable %R values. No qualifications were required.

ICP Serial Dilutions - An ICP serial dilution was not analyzed with this data package.

Matrix Spike/Duplicate - A matrix spike/duplicate sample was not analyzed with this data package.

Field Duplicates - Field duplicate samples were not analyzed with this data package.

Graphite Furnace Atomic Absorption (GFAA) Analysis - Samples BHGLAOC1901-02 and BHGLAOC1901-03 exhibited a postdigestion spike for the silver and thallium analyses out of control limits (85-115%) and sample absorbance is less than 50% of spike absorbance. The laboratory flagged these results (W) and the reviewer further qualified these results (J/UJ) unless already qualified due to other problems.

Sample BHGLAOC1901-01 exhibited a postdigestion spike for the selenium and silver analyses out of control limits (85-115%) and sample absorbance is less than 50% of spike absorbance. The laboratory flagged these results (W) and the reviewer further qualified these results (J/UJ) unless already qualified due to other problems.

Compound Quantitation - All results between the MDL and the PQL have been qualified (F).

Comments - The analyses of environmental samples and quality control samples are valid within the constraints identified with the data quality flags as presented in the method blank, GFAA and compound quantitation sections of this report. The NAS Fort Worth JRB 2000 Basewide Quality Assurance Project Plan, March 2000, data validation criteria were used in evaluating the data in this summary report.

Data Validation Summary Table - The following table summarizes all qualifications as described in this data validation summary report.

Qualification Summary Table - Metals SDG 9A05G259					
Sample No	Compound(s)	Reported		Validated	
		Conc	Qualifier	Conc	Qualifier
BHGLA0C1901-02	Antimony	0.29	U	0.29	UJ
	Arsenic	4.4	B	4.4	F
	Beryllium	0.60	-	0.60	U
	Cadmium	0.07	B	0.07	F
	Cobalt	5.2	B	5.2	F
	Copper	5.3	B	5.3	F
	Silver	0.01	UW	0.01	UJ
	Thallium	0.20	UW	0.20	UJ
	Tin	1.6	B	1.6	F
	Vanadium	29.5	B	29.5	F
	Zinc	21.0	B	21.0	F
BHGLA0C1901-03	Antimony	0.24	U	0.24	UJ
	Barium	33.3	B	33.3	F
	Beryllium	0.26	B	0.26	U
	Cadmium	0.13	B	0.13	F
	Chromium	7.4	B	7.4	F
	Cobalt	2.9	B	2.9	F
	Copper	4.2	B	4.2	F
	Nickel	7.6	B	7.6	F
	Silver	0.01	UW	0.01	UJ
	Thallium	0.17	UW	0.17	UJ
	Tin	1.0	B	1.0	F
	Vanadium	22.6	B	22.6	F
	Zinc	9.8	B	9.8	F
BHGLA0C1901-01	Antimony	0.31	U	0.31	UJ
	Arsenic	4.9	B	4.9	F
	Cobalt	4.6	B	4.6	F
	Copper	7.4	B	7.4	F
	Lead	14.9	B	14.9	F
	Nickel	10.0	B	10.0	F
	Selenium	0.22	UW	0.22	UJ
	Silver	0.01	UW	0.01	UJ
	Tin	1.2	B	1.2	F
	Vanadium	31.1	B	31.1	F
	Zinc	22.7	B	22.7	F

724 409

ENVIRONMENTAL

Data Services, Inc.

## APPENDIX IX SEMIVOLATILE ORGANIC COMPOUNDS

USEPA SW846 Method 8270C - Level III Review

Site Naval Air Station Fort Worth - DO26CC SDG #: 9A05G259Client: HydroGeoLogic, Inc. Date: June 28, 2000Laboratory: Severn Trent Laboratories, Chicago, IL Reviewer Cathy Shelby

Client Sample ID	Laboratory Sample ID	Matrix
BHCLAOC1901-02	9A05G259-001	Soil
BHCLAOC1901-03	9A05G259-002	Soil
BHCLAOC1901-01	9A05G259-003	Soil

Holding Times - All samples were extracted within 14 days for soil samples and analyzed within 40 days as specified in the NAS Fort Worth JRB 2000 Basewide Quality Assurance Project Plan (QAPP), March 2000. No qualifications were required.

GC/MS Tuning - All of the DFTPP tunes in the initial and continuing calibrations met the percent relative abundance criteria. No qualifications were required.

Initial Calibration - The initial calibrations analyzed on 03/02/00-05/16/00 exhibited acceptable %RSD and/or correlation coefficients and mean RRF values. No qualifications were required.

The initial calibration analyzed on 03/02/00 exhibited high %RSD values for 1,4-naphthoquinone, 4-nitroquinoline-1-oxide and hexachlorophene of 56.3%, 46.7% and 39.3%, respectively. All three compounds have been rejected (R) in samples BHCLAOC1901-01, BHCLAOC1901-02, and BHCLAOC1901-03.

Continuing Calibration - The continuing calibration analyzed on 05/30/00 exhibited high %D values for hexachloroethane and 2,4-dinitrophenol of 29.03% and 28.39%, respectively. Both compounds have been rejected (R) in samples BHCLAOC1901-01, BHCLAOC1901-02, and BHCLAOC1901-03.

Surrogates - All samples exhibited acceptable surrogate %R values. No qualifications were required.

Laboratory Control Samples - LCS sample SBLKRS exhibited acceptable %R values. No qualifications were required.

MS/MSD - A MS/MSD sample was not analyzed with this data package.

Internal Standard (IS) Area Performance - All internal standards met response and retention time (RT) criteria. No qualifications were required.

Method Blank - Method blank SBLKRS (05/22/00) was free of contamination. No qualifications were required.

Field, equipment blank - Equipment blank EB051200 (from SDG 9A05G263) exhibited bis(2-ethylhexyl)phthalate contamination at 14 ug/L, however, all associated results are non-detect and no qualifications were required.

Field Duplicates - Field duplicate samples were not analyzed with this data package.

Tentatively Identified Compounds (TICs) - TICs were not identified in any of the samples.

Compound Quantitation - All results between the MDL and PQF have been qualified (F)

Comments - The analyses of environmental samples and quality control samples are valid within the constraints identified with the data quality flags as presented in the compound quantitation section of this report with the exception of five compounds which were rejected in all samples due to the initial and continuing calibrations. The NAS Fort Worth JRB 2000 Basewide Quality Assurance Project Plan, March 2000, data validation criteria were used in evaluating the data in this summary report.



Data Validation Summary Table - The following table summarizes all qualifications as described in this data validation summary report.

Qualification Summary Table - Semivolatiles SDG 9A05G259					
Sample No	Compound(s)	Reported		Validated	
		Conc	Qualifier	Conc	Qualifier
BHCLA0C1901-02	Hexachloroethane	380	U	380	R
	2,4-Dinitrophenol	1900	U	1900	R
	1,4-Naphthoquinone	1900	U	1900	R
	4-Nitroquinoline-1-Oxide	1900	U	1900	R
	Hexachlorophene	5700	U	5700	R
BHCLA0C1901-03	Hexachloroethane	350	U	350	R
	2,4-Dinitrophenol	1800	U	1800	R
	1,4-Naphthoquinone	1800	U	1800	R
	4-Nitroquinoline-1-Oxide	1800	U	1800	R
	Hexachlorophene	5300	U	5300	R
BHCLA0C1901-01	Hexachloroethane	390	U	390	R
	2,4-Dinitrophenol	2000	U	2000	R
	Butylbenzylphthalate	280	J	280	F
	1,4-Naphthoquinone	2000	U	2000	R
	4-Nitroquinoline-1-Oxide	2000	U	2000	R
	Hexachlorophene	5900	U	5900	R

**ENVIRONMENTAL**  
Data Services, Inc.

# APPENDIX IX VOLATILE ORGANIC COMPOUNDS

USEPA SW846 Method 8260B - Level III Review

Site: Naval Air Station Fort Worth - DO26CC SDG #: 9A05G507

Client: HydroGeoLogic, Inc. Date: July 25, 2000

Laboratory: Severn Trent Laboratories, Chicago, IL Reviewer: Cathy Shelby

Client Sample ID	Laboratory Sample ID	Matrix
BHGLAOC1901-01	9A05G507-001	Soil
BHGLAOC1901-02	9A05G507-002	Soil
BHGLAOC1901-03	9A05G507-003	Soil
TB052600	9A05G507-004	Water
EB052600	9A05G507-005	Water

Holding Times - All soil samples were extracted within 48 hours for encore samples and analyzed within 14 days for preserved water and soil samples as specified in the NAS Fort Worth JRB 2000 Basewide Quality Assurance Project Plan (QAPP), March 2000. No qualifications were required.

GC/MS Tuning - All of the BFB tunes in the initial and continuing calibrations met the percent relative abundance criteria. No qualifications were required.

Initial Calibration - The initial calibrations analyzed on 01/12/00-03/27/00, 01/12/00-05/31/00 and 01/14/00-06/04/00 exhibited acceptable %RSD values and/or correlation coefficients. No qualifications were required.

Continuing Calibration - The continuing calibration analyzed on 06/07/00 exhibited high %D values for trichlorofluoromethane of 30.34%. Trichlorofluoromethane has been rejected (R) in samples TB052600 and EB062600.

The continuing calibrations analyzed on 06/06/00 and 06/08/00 exhibited acceptable %D value. No qualifications were required.

Surrogates - All samples exhibited acceptable surrogate %R values. No qualifications were required.

Laboratory Control Samples - LCS samples VBLKYX and VBLKZB exhibited acceptable %R values. No qualifications were required.

LCS sample VBLKYZ exhibited a high %R value for tetrachloroethane of 109%. All associated results are non-detect and no qualifications were required.

MS/MSD - MS/MSD sample was not analyzed with this data package

Internal Standard (IS) Area Performance - Sample BHGLAOC1901-01 exhibited low area counts for internal standard 1,4-dichlorobenzene-d4 (IS4). All associated compounds have been qualified (J/UJ) in this sample.

Method Blank - Method blanks VBLKZB (06/06/00), VBLKYX (06/07/00), and VBLKYZ (06/08/00) were free of contamination. No qualifications were required

Trip, field, equipment blank - Trip blank TB052600 was free of contamination. No qualifications were required.

Equipment blank EB052600 exhibited methylene chloride contamination at 2 ug/L. Sample results were non-detect and no qualifications were required.

Field Duplicates - Field duplicate samples were not analyzed with this data package.

Tentatively Identified Compounds - TIC results have been qualified (T)

Compound Quantitation - All results between the MDL and the PQL have been qualified (F)

Comments - The analyses of environmental samples and quality control samples are valid within the constraints identified with the data quality flags as presented in the continuing calibration, internal standards, TICs and compound quantitation sections of this report with the exception of several rejections due to the continuing calibration. The NAS Fort Worth JRB 2000 Basewide Quality Assurance Project Plan, March 2000, data validation criteria were used in evaluating the data in this summary report.

**Data Validation Summary Table** - The following table summarizes all qualifications as described in this data validation summary report.

Qualification Summary Table - Volatiles SDG # 9A05G507					
Sample No	Compound(s)	Reported		Validated	
		Conc	Qualifier	Conc	Qualifier
BHGLAOC1901-01	1,1,2,2-Tetrachloroethane	2	U	2	UJ -
	1,2,3-Trichloropropane	4	U	4	UJ -
	Pentachloroethane	4	U	4	UJ -
	1,2-Dibromo-3-Chloropropane	4	U	4	UJ -
BHGLAOC1901-02	Trichloroethene	4	J	4	F
TB052600	Trichlorofluoromethane	0.5	U	0.5	R -
EB052600	Trichlorofluoromethane	0.5	U	0.5	R -

724 415

**ENVIRONMENTAL**  
Data Services, Inc.

4/25/01

**VOLATILE ORGANIC COMPOUNDS**  
USEPA SW846 Method 8260B - Level III ReviewSite: Naval Air Station Fort Worth - DO26CEA SDG #: 9B02G272Client: HydroGeoLogic, Inc Date: April 13, 2001Laboratory: Severn Trent Laboratories, Chicago, IL Reviewer: Nancy Weaver

Client Sample ID	Laboratory Sample ID	Matrix
FT09-12CWG01	9B02G272-001	Water
WHGLTA004WG01	9B02G272-002	Water
WHGLTA801WG01	9B02G272-003	Water
WHGLTA051WG01	9B02G272-004	Water
WHGLTA052WG01	9B02G272-005	Water
DUP04	9B02G272-006	Water
EB022201	9B02G272-007	Water
TB022201	9B02G272-008	Water

Holding Times - All samples were analyzed within 14 days for preserved water samples as specified in the NAS Fort Worth JRB 2000 Basewide Quality Assurance Project Plan (QAPP), March 2000. No qualifications were required

GC/MS Tuning - All of the BFB tunes in the initial and continuing calibrations met the percent relative abundance criteria. No qualifications were required.

Initial Calibration - The initial calibrations analyzed on 12/28/00-02/24/01 exhibited acceptable %RSD values and/or correlation coefficients and mean RRF values. No qualifications were required

Continuing Calibration - The continuing calibrations analyzed on 02/28/01, 03/01/01 and 03/04/01 exhibited acceptable %D values. No qualifications were required

Surrogates - All samples exhibited acceptable surrogate %R values. No qualifications were required

Laboratory Control Samples - LCS samples VBLKHQ and VBLKHU exhibited acceptable %R values. No qualifications were required.

LCS sample VBLKHO exhibited a low %R value for methylene chloride of 74%. Methylene chloride has been rejected (R) in associated sample FT09-12CWG01.

MS/MSD - A MS/MSD sample was not analyzed with this data package.

Internal Standard (IS) Area Performance - All internal standards met response and retention time (RT) criteria. No qualifications were required.

Method Blank - Method blanks VBLKHQ (03/01/01) and VBLKHU (03/04/01) were free of contamination. No qualifications were required.

Method blank VBLKHO (02/28/01) exhibited 2-hexanone contamination at 2 ug/L, however, the associated results are non-detect and no qualifications were required.

Trip, field, equipment blank - Equipment blank EB022201 was free of contamination. No qualifications were required.

Trip blank TB022201 was free of contamination. No qualifications were required.

Field Duplicates - Field duplicate results are summarized in the table below. No qualifications were required.

Compound	WHGLTA801WG01 ug/L	DUP04 ug/L	RPD
Trichloroethene	360	260	32%

Tentatively Identified Compounds - All TICs were qualified (T).

Compound Quantitation - All results between the MDL and the PQL have been qualified (F).

724-417.

Comments - The analyses of environmental samples and quality control samples are valid within the constraints identified with the data quality flags as presented in the TICs and compound quantitation sections of this report with the exception of one compound rejected due to the low LCS recovery. The NAS Basewide Quality Assurance Project Plan, March 2000, data validation criteria were used in evaluating the data in this summary report.

Data Validation Summary Table - The following table summarizes all qualifications as described in this data validation summary report

Qualification Summary Table - Volatiles SDG 9B02G272					
Sample No	Compound(s)	Reported		Validated	
		Conc	Qualifier	Conc	Qualifier
FT09-12CWG01	Methylene Chloride	0.5	U	0.5	R
	Benzene	0.3	J	0.3	F
	Chlorobenzene	0.3	J	0.3	F

**APPENDIX IX VOLATILE ORGANIC COMPOUNDS**

USEPA SW846 Method 8260B - Level III Review

 Site: Naval Air Station Fort Worth - DO26CE SDG #: 202786

 Client: HydroGeoLogic, Inc. Date: June 5, 2001

 Laboratory: Severn Trent Laboratories, Chicago, IL Reviewer: Nancy Weaver

Client Sample ID	Laboratory Sample ID	Matrix
EB040601	202786-1	Water
EB040601MS	202786-1MS	Water
EB040601MSD	202786-1MSD	Water
WHGLTA801WG02	202786-2	Water
WHGLTA056WG02	202786-3	Water
DUP05WG02	202786-4	Water
DUP06WG02	202786-5	Water
WHGLTA055WG02	202786-6	Water
WHGLTA054WG02	202786-7	Water
WHGLTA050WG02	202786-8	Water
WHGLTA052WG02	202786-9	Water
WHGLTA053WG02	202786-10	Water

Holding Times - All samples were analyzed within 14 days for preserved water samples as specified in the NAS Fort Worth JRB 2000 Basewide Quality Assurance Project Plan (QAPP). March 2000. No qualifications were required.

GC/MS Tuning - All of the BFB tunes in the initial and continuing calibrations met the percent relative abundance criteria. No qualifications were required.

Initial Calibration - The initial calibrations analyzed on 03/14/01-04/02/01 exhibited acceptable %RSD values and/or correlation coefficients and mean RRF values. No qualifications were required.

Continuing Calibration - The continuing calibrations analyzed on 04/11/01 and 04/12/01 exhibited high %D values for dichlorodifluoromethane of 27.2% and 28.2%, respectively. Dichlorodifluoromethane has been rejected (R) in all samples.



Surrogates - All samples exhibited acceptable surrogate %R values. No qualifications were required.

Laboratory Control Samples - LCS samples 15826 and 17551 exhibited low %R values for dichlorodifluoromethane, however, this compound has already been qualified due to the continuing calibration and no further qualifications were required.

MS/MSD - MS/MSD sample EB040601 exhibited low MS/MSD %R values for dichlorodifluoromethane of 41%/41% and a high RPD value for styrene of 21%. However, dichlorodifluoromethane is already qualified and styrene is non-detect in this sample and no qualifications were required.

Internal Standard (IS) Area Performance - All internal standards met response and retention time (RT) criteria. No qualifications were required.

Method Blank - Method blanks 15826 (04/12/01), 15998 (04/16/01) and 17551 (04/11/01) were free of contamination. No qualifications were required.

Trip, field, equipment blank - Equipment blank EB040601 exhibited methylene chloride contamination at 3 ug/L, however, all associated results are non-detect and no qualifications were required.

Field Duplicates - Field duplicate results are summarized in the tables below. No qualifications were required.

Compound	WHGLTA056WG02 ug/L	DUP05WG02 ug/L	RPD
Dichlorodifluoromethane	1	1	0%
Trans-1,2-Dichloroethene	1	1	0%
Cis-1,2-Dichloroethene	27	25	8%
Trichloroethene	68	67	1%

Compound	WHGLTA801WG02 ug/L	DUP06WG02 ug/L	RPD
Vinyl Chloride	5	6	18%
1,1-Dichloroethene	1	1	0%
Trans-1,2-Dichloroethene	29	29	0%
Cis-1,2-Dichloroethene	200	210	5%
Trichloroethene	150	170	13%

Tentatively Identified Compounds - TICs were not reported with the samples in this data package

Compound Quantitation - All results between the MDL and the PQL have been qualified (F).

Several samples exhibited compounds which exceeded the linear range of the instrument. The samples were diluted and reanalyzed and the laboratory replaced the original results for these compounds with the dilution results on the Form Is

Comments - The analyses of environmental samples and quality control samples are valid within the constraints identified with the data quality flags as presented in the compound quantitation section of this report with the exception of one compound rejected due to the continuing calibration. The NAS Basewide Quality Assurance Project Plan, March 2000, data validation criteria were used in evaluating the data in this summary report

Data Validation Summary Table - The following table summarizes all qualifications as described in this data validation summary report.

Qualification Summary Table - Volatiles SDG 202786					
Sample No	Compound(s)	Reported		Validated	
		Conc	Qualifier	Conc	Qualifier
EB040601	Dichlorodifluoromethane	0.4	U*	0.4	R
WHGLTA801WG02	Dichlorodifluoromethane	0.4	U*	0.4	R
WHGLTA056WG02	Dichlorodifluoromethane	1	*	1	R
DUP05WG02	Dichlorodifluoromethane	1	*	1	R
DUP06WG02	Dichlorodifluoromethane	0.4	U*	0.4	R
WHGLTA055WG02	Dichlorodifluoromethane	0.4	U*	0.4	R
	Trichloroethene	0.5	FA	0.5	F
	Tetrachloroethene	0.5	FA	0.5	F
WHGLTA054WG02	Dichlorodifluoromethane	0.4	U*	0.4	R
WHGLTA050WG02	Dichlorodifluoromethane	0.4	U*	0.4	R
	1,1-Dichloroethene	0.5	FA	0.5	F
	Tetrachloroethene	0.4	FA	0.4	F
WHGLTA052WG02	Dichlorodifluoromethane	0.4	U*	0.4	R
WHGLTA053WG02	Dichlorodifluoromethane	0.4	U*	0.4	R

**Volatile Organic Compounds**  
 SW-846 Method 8260B  
 USEPA Level III Review

Site NAS Fort Worth JRB

SDG #: 202564

Laboratory: STL-Chicago

Date 06/13/01

HydroGeoLogic, Inc. Reviewer: Kimberly Evers

Project: AFC001-33DAA

Client Sample ID	Laboratory Sample ID	Matrix
WHGLTA004WG14	202564-1	Water
MW-53WG14	202564-2	Water
LF04-02WG14	202564-3	Water
DUP02WG14	202564-4	Water
WHGLTA025WG14	202564-5	Water
LF05-19WG14	202564-6	Water
TB032601	202564-7	Water

Note The only compounds that are being considered are the target compounds reported in this SDG and those relevant compounds used for data validation

Sample Delivery and Condition - The samples arrived at the laboratory in acceptable condition and temperature, and properly preserved. Proper custody was documented. No qualification required

Holding Times - All samples were analyzed within the required holding times for preserved water samples. No qualification required

GC/MS Tuning [Form 5] - The initial calibration and sample analytical sequences were all performed within 12 hours of an acceptable MS tune. No qualification required

Initial Calibration [Form 6] - Two initial calibrations are associated with these samples. Both initial calibrations had acceptable average RRFs for all SPCCs. The mean %RSD for all analytes was below 15%; all compound %RSDs were <30%. No Qualification required.

Continuing Calibration [Form 7] - Four continuing calibration verifications (CCVs) are associated with this SDG, a CCV run on 03.30.01 (on instrument GCL6), a CCV run on 03/30/01 (on instrument GCL3), a CCV run on 03/31/01 (on instrument GCL3) and one run on 04/02/01 (on instrument GCL3). All SPCCs had CCRFs in control. All CCC %Ds were <20%, all other compound %Ds were in control with the following exceptions:

03/30/01 (on instrument GCL6): Dichlorodifluoromethane had a %D of -41.8%. All associated results should be R-qualified.

03/30/01 (on instrument GCL6): Chloromethane had a %D of -37.4%. All associated results should be R-qualified.

03 30 01(on instrument GCL6) Methylene chloride had a %D of 31.4% All associated results should be R-qualified.

03 30 01(on instrument GCL6) 1,2-dibromo-3-chloropropane had a %D of 28.1%. All associated results should be R-qualified

04 02 01(on instrument GCL3). Bromomethane had a %D of 25.9% All associated results should be R-qualified

Surrogates [Form 2] -All surrogate recoveries were within established control limits No data required qualification

Laboratory Control Samples [Form 3] - All %R results for LSC VBLK14720 met established control limits and no qualification is required All %R results for LSC VBLK14810 met established control limits except for a high %R value for chloromethane of 130% and a low %R for methylene chloride of 67% All associated results for chloromethane are non-detect and no qualifications are required. All associated results for methylene chloride have already been R qualified due to failure to meet acceptance criteria in the CCV All %R results for LSC VBLK14702 met established control limits and no qualifications are required All %R results for LSC VBLK14845 met established control limits and no qualifications are required.

MS/MSD [Form 3] - Sample WHGLTA025WG14 was used for the MS/MSD All %Rs were in control except for high %R for dichlorodifluoromethane, chloromethane and chloroethane in the MS and MSD There were no detections of the affected compounds and no qualification necessary A low %R was reported for methylene chloride, styrene and 1,2,4-trimethylbenzene in the MS and methylene chloride in the MSD. All associated results are non-detect and should be UJ qualified All RPDs were in control with the exception of bromomethane, styrene and 1,2,4-trimethylbenzene Styrene and 1,2,4-trimethylbenzene results in the parent sample have already been UJ qualified due to a low %R in the MS There were no detections of bromomethane reported and no qualification is necessary

Internal Standard Performance [Form 8] - All internal standards met area and retention time criteria No qualification necessary

Method Blanks [Form 1] - All method blanks were free from contamination No qualification necessary

Equipment and Trip Blanks [Form 1] - Trip blank TB032601 was free from contamination. No qualification necessary.

Field Duplicates [Form 1] - Field duplicate DUP02WG14 is associated with sample LF04-02WG14 Analyte RPDs meet the acceptance criteria and no qualification is required

Compound Quantitation - Sample WHGLTA004WG14 was analyzed at a 25 fold dilution due to high levels of cis-1,2-dichloroethene and trichloroethene. Sample LF04-02WG14 was analyzed at a 50 fold dilution due to high levels of trans-1,2-dichloroethene and cis-1,2-dichloroethene and a 100 fold dilution due to high levels of trichloroethene. Sample DUP02WG14 was analyzed at a 50 fold dilution due to high levels of trans-1,2-dichloroethene and cis-1,2-dichloroethene and a 100 fold dilution due to high levels of trichloroethene. Sample LF05-19WG14 was analyzed at a 100 fold dilution due to high levels of trichloroethene

724 423

## Qualification Summary Table

Note - The laboratory provides informational codes in a column in the report page called flags. Those codes are removed and replaced with the appropriate qualifier.

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
WHGLTA004WG14	Dichlorodifluoromethane	0.4	U	0.4	R
	Chloromethane	0.4	U	0.4	R
	Methylene chloride	0.3	U	0.3	R
	1,2-dibromo-3-chloropropane	0.5	U	0.5	R
MW-53WG14	No flag changes necessary				
LF04-02WG14	Dichlorodifluoromethane	0.4	U	0.4	R
	Chloromethane	0.4	U	0.4	R
	Methylene chloride	0.3	U	0.3	R
	1,2-dibromo-3-chloropropane	0.5	U	0.5	R
DUP02WG14	Dichlorodifluoromethane	0.4	U	0.4	R
	Chloromethane	0.4	U	0.4	R
	Methylene chloride	0.3	U	0.3	R
	1,2-dibromo-3-chloropropane	0.5	U	0.5	R
WHGLTA025WG14	Methylene chloride	0.3	U	0.3	UJ
	Styrene	0.2	U	0.2	UJ
	1,2,4-trimethylbenzene	0.4	U	0.4	UJ
LF05-19WG14	No flag changes necessary				

**Volatile Organic Compounds**  
SW-846 Method 8260B  
USEPA Level III Review

Site NAS Fort Worth JRB

SDG # 202789

Laboratory STL-Chicago

Date 06/19/01

HydroGeoLogic, Inc. Reviewer: Kimberly Evers

Project: AFC001-33DAA

Client Sample ID	Laboratory Sample ID	Lab Batch	Matrix
TB040601	202789-1	18248	Water
WHGLTA603WG14	202789-2	18248	Water
WHGLPU001WG14	202789-3	18248	Water
DUP05WG14	202789-4	18248	Water
WHGLTA051WG14	202789-5	18248	Water
WHGLTA029WG14	202789-6	18248	Water

Note: The only compounds that are being considered are the target compounds reported in this SDG and those relevant compounds used for data validation

Sample Delivery and Condition - The samples arrived at the laboratory in acceptable condition and temperature, and properly preserved. Proper custody was documented. No qualification required.

Holding Times - All samples were analyzed within the required holding times for preserved water samples. No qualification required.

GC/MS Tuning [Form 5] - The initial calibration and sample analytical sequences were all performed within 12 hours of an acceptable MS tune. No qualification required.

Initial Calibration [Form 6] - The initial calibration had acceptable average RRFs for all SPCCs. The mean %RSD for all analytes was below 15%, all compound %RSDs were <30%. Compounds with a %RSD <15% are quantified using relative standard deviation. Those with %RSD >15% are quantified using the calibration curve. All calibration curves were evaluated and found to have  $r^2 > 0.995$  and no qualification is necessary.

Continuing Calibration [Form 7] - One continuing calibration verification (CCV), run on 04/16/01, is associated with this SDG. All SPCCs had CCRFs in control. All CCC %Ds were <20%, all other compound %Ds were in control with the following exceptions:

04/16/01: Bromomethane had a %D of 42.51%. All associated results should be R qualified.

04/16/01: Methylene chloride had a %D of 34.13%. All associated results should be R qualified.

Surrogates [Form 2] - All surrogate recoveries were within established control limits. No data required qualification.

724 425

Laboratory Control Samples [Form 3] - All %R results for LSC VBLK15998BS met established control limits with the exception of a low %R for methylene chloride. All methylene chloride results have already been R qualified due to a failure to meet method specific control limits in the CCV.

MS/MSD [Form 3] - Matrix Spike/Matrix Spike Duplicate analyses were not performed in this sample batch. No qualification required.

Internal Standard Performance [Form 8] - All internal standards met area and retention time criteria. No qualification necessary.

Method Blanks [Form 1] - The method blank was free from contamination. No qualification necessary.

Trip Blanks [Form 1] - Trip blank TB040601 was free from contamination and no qualification is necessary. No equipment blank was submitted with this SDG.

Field Duplicates [Form 1] - Field duplicate DUP05WG14 is associated with sample WHGLTA603WG14. The RPD meets the acceptance criteria and no qualification is required.

Compound Quantitation - Sample WHGLTA051WG14 was analyzed at a 10 fold dilution due to high levels of TCE.

#### Qualification Summary Table

Note - The laboratory provides informational codes in a column in the report page called flags. Those codes are removed and replaced with the appropriate qualifier.

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
WHGLTA603WG14	Bromomethane	0.4	U	0.4	R
	Methylene chloride	0.3	U	0.3	R
WHGLPU001WG14	Bromomethane	0.4	U	0.4	R
	Methylene chloride	0.3	U	0.3	R
DUP05WG14	Bromomethane	0.4	U	0.4	R
	Methylene chloride	0.3	U	0.3	R
WHGLTA051WG14	Bromomethane	0.4	U	0.4	R
	Methylene chloride	0.3	U	0.3	R
	Trichloroethene	Dilution result used			
WHGLTA051WG14DL	Trichloroethene	170	--	170	No flag
WHGLTA029WG14	Bromomethane	0.4	U	0.4	R
	Methylene chloride	0.3	U	0.3	R

**Volatile Organic Compounds**  
**SW-846 Method 8260B**  
**USEPA Level III Review**

Site: NAS Fort Worth JRB

SDG #: 203945

Laboratory: STL-Chicago

Date: 07/30/01

HydroGeoLogic, Inc. Reviewer: Kimberly Evers

Project: AFC001-26CE

Client Sample ID	Laboratory Sample ID	Lab Batch	Matrix
WHGLTA801-WG03	203945-1	25604	Water
DUP07	203945-2	25604	Water

Note The only compounds that are being considered are the target compounds reported in this SDG and those relevant compounds used for data validation

Sample Delivery and Condition - The samples arrived at the laboratory in acceptable condition and temperature, and properly preserved. Proper custody was documented. No qualification required.

Holding Times - All samples were analyzed within the required holding times for preserved water samples. No qualification required.

GC/MS Tuning [Form 5] - The initial calibration and sample analytical sequences were all performed within 12 hours of an acceptable MS tune. No qualification required

Initial Calibration [Form 6] - The initial calibration had acceptable average RRFs for all SPCCs. The mean %RSD for all analytes was below 15%; all compound %RSDs were <30%. Compounds with a %RSD <15% are quantified using relative standard deviation. Those with %RSD >15% are quantified using the calibration curve. All calibration curves were evaluated and found to have  $r^2 > 0.995$  and no qualification is necessary.

Continuing Calibration [Form 7] - One continuing calibration verification (CCV), run on 06/26/01, is associated with this SDG. All SPCCs had CCRFs in control. All CCC %Ds were <20%; all other compound %Ds were in control and no qualification is necessary.

Surrogates [Form 2] - All surrogate recoveries were within established control limits. No data required qualification.

Laboratory Control Samples [Form 3] - All %R results for LSC VBLK25604BS met established control limits and no qualification is necessary.

MS/MSD [Form 3] - Matrix Spike/Matrix Spike Duplicate analyses were not performed in this sample batch. No qualification required.

Internal Standard Performance [Form 8] - All internal standards met area and retention time criteria. No qualification necessary.



724. 427.

Method Blanks [Form 1] - The method blank was free from contamination. No qualification necessary

Trip Blanks [Form 1] - Trip blank TB06140101 and equipment blank EB061401 from SDG #203944 are associated with these samples. They were free from contamination and no qualification is necessary.

Field Duplicates [Form 1] - Field duplicate DUP07 is associated with sample WHGLTA801-WG03. The RPD meets the acceptance criteria and no qualification is required.

Compound Quantitation - Samples WHGLTA801-WG03 and DUP07 were analyzed at a 25X dilution due to high levels of trichloroethene.

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
WHGLTA801-WG03	No qualification necessary	--	--	--	--
DUP07	No qualification necessary	--	--	--	--

**Appendix IX Volatile Organic Compounds**  
 SW-846 Method 8260B  
 USEPA Level III Review

Site NAS Fort Worth JRB

SDG #: 203960

Laboratory: STL-Chicago

Date: 08.27.01

HydroGeoLogic, Inc. Reviewer: Kimberly Evers

Project: AFC001-26CE

Client Sample ID	Laboratory Sample ID	Analytical Batch	Matrix
WHGLTA050-WG03	203960-1	25674	Water
WHGLTA051-WG03	203960-2	25674	Water
WHGLTA004-WG03	203960-3	25674	Water
EB061501	203960-4	25674	Water
TB061501	203960-5	25674	Water

Note: These samples were only tested for TCE. The only compounds that are being evaluated are TCE and those relevant compounds used for data validation.

Sample Delivery and Condition - The samples arrived at the laboratory in acceptable condition and temperature, and properly preserved. Proper custody was documented. No qualification required.

Holding Times - All samples were analyzed within the required holding times for preserved water samples. No qualification required.

GC/MS Tuning - The initial calibration and sample analytical sequences were all performed within 12 hours of an acceptable MS tune. No qualification required.

Initial Calibration - The initial calibration had acceptable average RRFs for all SPCCs. The mean %RSD for all analytes was below 15%; all compound %RSDs were <30%. Compounds with a %RSD <15% are quantified using relative standard deviation. Those with %RSD >15% are quantified using the calibration curve. All calibration curves were evaluated and found to have  $r^2 > 0.995$  and no qualification is required.

Continuing Calibration - Two continuing calibration verifications (CCVs), one run on 06/28/01 and one run on 06/29/01, are associated with this SDG. All SPCCs had CCRFs in control. All CCC %Ds were <20%; all other compound %Ds were in control.

Surrogates - All surrogate recoveries were within established control limits. No data required qualification.

Laboratory Control Samples - All %R results for both batch LCSs were in control with the exception of ethylbenzene, m&p-xylenes and o-xylenes which had %Rs greater than the upper control limit. None of the environmental samples in this data package were being analyzed for these compounds and no qualification is necessary.

724 429.

MS/MSD - Matrix Spike/Matrix Spike Duplicate analyses were not performed in this sample batch. No qualification required.

Internal Standard Performance - All internal standards met area and retention time criteria. No qualification necessary.

Method Blanks - Both method blanks were free from contamination. No qualification necessary.

Equipment and Trip Blanks - Trip blank TB061501 and EB061501 are associated with these samples. Both the trip blank and the equipment blank were free from contamination. No qualification necessary.

Field Duplicates - No duplicate pairs were submitted with this SDG. No qualification necessary.

Compound Quantitation - The TCE results reported for samples WHGLTA050-WG03, WHGLTA051-WG03 and WHGLTA004-WG03 were analyzed at a 25 fold dilution due to high levels detected in the original analysis.

Qualification Summary Table

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
WHGLTA050-WG03	No qualification necessary				
WHGLTA051-WG03	No qualification necessary				
WHGLTA004-WG03	No qualification necessary				

Trichloroethene  
SW8260B  
USEPA Level III Review

Site: Naval Air Station Fort Worth JRB, Texas	SDG # 204138
Laboratory: STL-Chicago	Date 09 03.01
HydroGeoLogic, Inc Reviewer Ken Rapuano	

Client Sample ID	Laboratory Sample ID	Matrix
WHGLTA052-WG03	204138-001	Water

Sample Delivery and Condition - The sample arrived at the laboratory in acceptable condition and temperature. Proper custody (internal and external) was documented. No qualification required.

Holding Times - The sample was analyzed within the required holding time for preserved water samples, no qualification is necessary.

GC/MS Tuning - All BFB tunes associated with initial and continuing calibrations were in control. No qualification necessary.

Initial Calibration - The initial calibrations had an acceptable %RSDs for TCE. All SPCCs had acceptable mean RRF values, and all CCCs had acceptable %RSD values. No qualification necessary.

Continuing Calibration - The continuing calibration had the %D in control for TCE. All CCC %Ds and SPCC RRFs were in control. No qualification necessary.

Surrogates - All surrogate recoveries were in control, no qualification necessary.

Laboratory Control Samples - All LCS results were in control, no qualification is necessary.

MS/MSD - An MS/MSD was not performed in association with this SDG, no qualification is necessary.

Internal Standards - All four ISs were in control for retention time and peak area for the sample analysis. No qualification necessary.

Method Blanks - The associated method blank was free from contamination; no qualification is necessary.

Field Blanks - Equipment blank EB062601 (results located in data package 204136) contained 0.22 F µg/L TCE. The action level is 1.1 µg/L. The sample concentration is >> the action level and no qualification is necessary. Trip blank TB062601 (results located in data package 204136) were free from contamination. No qualification necessary.

Field Duplicates - No field duplicates were submitted with this data package. No qualification necessary.

Compound Quantitation - The sample was analyzed at a 25x dilution because of the elevated level of TCE. The MDL and reporting limit are adjusted accordingly.

724 431

Qualification Summary Table

No data require qualification.

**Metals**  
SW-846 6010B/7000A Series  
USEPA Level III Review

Site: Naval Air Station Fort Worth JRB, Texas      SDG #: 204981  
Laboratory: STL-Chicago      Date: 11/19/01  
HydroGeoLogic, Inc. Reviewer: Ken Rapuano      Project: AFC001-26CC

Client Sample ID	Laboratory Sample ID	Matrix
THGLAOC1905-02	204981-1	Soil
IDW081501*	204981-2	Soil
EB081501	204981-3	Water

\* This sample was analyzed for disposal purposes only, and does not need validation to the DQOs presented in the NASFW Basewide QAPP.

Sample Delivery and Condition - The samples arrived at the laboratory preserved, and in acceptable condition and temperature. Proper custody (internal and external) was documented. No qualification required.

Holding Times - All samples were analyzed within the required holding times for preserved soil samples. No qualification required.

Calibration - The initial and continuing calibration verification standards had acceptable recoveries. No qualification required.

Method and Calibration Blanks - The preparation blank and associated CCBs showed contamination above the MDL for cadmium (0.3 µg/L), leading to an action level of 0.15 mg/kg, chromium (0.3 mg/kg), leading to an action level of 1.5 mg/kg, and zinc (0.8 mg/kg) leading to an action level of 4.0 mg/kg. The associated results for these elements were greater than the associated action levels and no qualification is necessary.

The preparation blanks and CCBs associated with the soil sample had negative baseline drift for silver. The highest associated blank values is -1.5 µg/L for silver, leading to an action level of 0.75 mg/kg. The silver result in sample number THGLAOC1905-02 was non-detect and should be UJ qualified at the MDL.

Equipment Blanks - The equipment blank associated with this sample is EB081501. This equipment blank was contaminated with zinc (6.9 µg/L), leading to an action level of 3.45 mg/kg. The associated sample result is greater than the action level and no qualification is necessary.

ICP Interference Check Sample - All %Rs were in control. No qualification necessary.

ICP Serial Dilution - No serial dilution performed. No qualification necessary.

Laboratory Control Samples - All LCSs had acceptable recoveries. No qualification required.

GFAA Recovery Tests - The recovery test was below the LCL for selenium and thallium in sample THGLAOC1905-02. All of the affected selenium and thallium results are non-detect and should be UJ qualified.

Matrix Spike Analyses - A matrix spike/matrix spike duplicate was not analyzed with this data package. No qualification is necessary.

Laboratory Duplicates - A laboratory duplicate was not analyzed with this data package. No qualification necessary.

Field Duplicates - No field duplicate is associated with the sample in this SDG and no qualification is necessary.

Compound Quantitation - All analytes reported below the PQL are reported as F qualified detections. The laboratory performed the analysis for lead at a 10x dilution due to the elevated concentration. The laboratory performed the analysis for selenium at a 5x dilution due to interferences in the sample.

Qualification Summary Table

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
THGLAOC1905-02	Selenium	0.76	U	0.76	UJ
	Silver	0.064	U	0.064	UJ
	Thallium	0.18	U	0.18	UJ

**Appendix IX SVOCs**  
**SW8270C**  
**USEPA Level III Review**

Site Naval Air Station Fort Worth JRB, Texas

SDG # 204981

Laboratory STL-Chicago

Date 11 14 01

HydroGeoLogic, Inc. Reviewer. Kimberly Evers

Project Number AFC001-26CC

Client Sample ID	Laboratory Sample ID	Lab Batch	Matrix
THGLAOC1905-02	204981-1	31873	Soil
THGLAOC1905-02	204981-1	35356	SPLP Extract
EB081501	204981-3	31874	Water

Sample Delivery and Condition - The samples arrived at the laboratory in acceptable condition and temperature. Proper custody (internal and external) was documented. No qualification required.

Holding Times - All samples were extracted and analyzed within the required holding times for soil samples.

GC/MS Tuning - All DFTPP tunes associated with initial and continuing calibrations were in control. No qualification necessary

Initial Calibration - 08.09.01 and 09.07.01. The average mean %RSD for all analytes was below 15%, all compound %RSDs were <30%. Several compounds with %RSD >15% are quantified using the calibration curve. All calibration curves were evaluated and found to have  $r^2 > 0.990$ , with the following exceptions:

08.09.01 (31873): N-Nitrosodimethylamine had  $r^2 < 0.990$ . The associated result should be R qualified

08.09.01 (31873): 1,2-Dichlorobenzene had  $r^2 < 0.990$ . The associated result should be R qualified.

08.09.01 (31873): 4-Nitroquinoline-1-oxide had  $r^2 < 0.990$ . The associated result should be R qualified.

09.07.01 (35356): 4-Nitroquinoline-1-oxide had  $r^2 < 0.990$ . This compound is not reported in the sample associated with this batch number. No qualification necessary.

Continuing Calibration - Two continuing calibration verifications (CCVs) are associated with the samples in this SDG. One was run on 08.11.01 (31873) and the other was run on 09.11.01 (35356). All CCC %Ds and SPCC RRFs were in control. The CCV had the %Ds within the 25% control limit for all compounds with the following exceptions

09.11.01 (35356): Benzyl alcohol had a %D of 58.08%. This compound is not reported in the sample associated with this batch number. No qualification necessary.

09.11.01 (35356): 2,4-Dimethylphenol had a %D of 28.58%. This compound is not reported in the sample associated with this batch number. No qualification necessary.



09.11.01 (35356) Methyl methanesulfonate, listed in Appendix A of the project QAPP, had a %D that did not meet the %D requirements; however, no corrective action is required for this compound. No qualification necessary

09 11.01 (35356) 1,4-Dioxane had a %D of 74.39%. This compound is not reported in the sample associated with this batch number. No qualification necessary

09 11 01 (35356) 2-Picoline, listed in Appendix A of the project QAPP, had a %D that did not meet the %D requirements; however, no corrective action is required for this compound. No qualification necessary.

09 11.01 (35356) Pentachloronitrobenzene, listed in Appendix A of the project QAPP, had a %D that did not meet the %D requirements; however, no corrective action is required for this compound. No qualification necessary.

09 11 01 (35356) Hexachloropropene had a %D of 25.43%. This compound is not reported in the sample associated with this batch number. No qualification necessary.

09.11 01 (35356) p-Phenylenediamine, listed in Appendix A of the project QAPP, had a %D that did not meet the %D requirements; however, no corrective action is required for this compound. No qualification necessary

Surrogates - All surrogate recoveries were in control with the exception of the surrogate terphenyl-d14 for the SPLP analysis of THGLAOC1905-02, which was below the LCL. The %R for this compound was above 10% and no qualification is necessary.

Laboratory Control Samples - The LCSs associated with the analytical results for all samples are in control for all compounds. No qualification necessary.

Note: The LSC associated with the equipment blank does not require validation and no qualification is necessary

MS/MSD - A matrix spike/matrix spike duplicate was performed on soil sample THGLAOC1905-02. All %Rs were in control with the exception of a low %R of phenanthrene in the MS and MSD, and a low %R of fluoranthene and chrysene in the MSD. The associated detections of phenanthrene, fluoranthene and chrysene should be J qualified in the parent sample. The calculated RPDs were in control with the exception of 2,4-dinitrophenol, phenanthrene, fluoranthene, pyrene, benzo(a)anthracene, chrysene, benzo(b)fluoranthene, benzo(k)fluoranthene, benzo(a)pyrene, indeno(1,2,3-cd)pyrene and benzo(g,h,i)perylene. The associated detections of phenanthrene, fluoranthene and chrysene have already been J qualified in the parent sample due to a low %R in the MS or MSD. The associated 2,4-dinitrophenol result is non-detect and no qualification is necessary. The associated pyrene, benzo(a)anthracene, benzo(b)fluoranthene, benzo(k)fluoranthene, benzo(a)pyrene, indeno(1,2,3-cd)pyrene and benzo(g,h,i)perylene detections should be J qualified.

Internal Standards - All six ISs were in control for retention time and peak area with the exception of perylene-d12 in the soil sample THGLAOC1905-02. The associated dibenzo(a,h)anthracene detection should be J qualified in sample THGLAOC1905-02. The associated detections of benzo(b)fluoranthene, benzo(k)fluoranthene, benzo(g,h,i)perylene, and benzo(a)pyrene have already been J qualified in sample THGLAOC1905-02 due to a failure to meet QC RPD requirements in the MS/MSD.

Method Blanks - The method blank associated with samples in this SDG was free from contamination. No qualification is necessary.

Field Blanks - The equipment blank, EB081501, associated with the samples was free from contamination and no qualification is necessary.

Field Duplicates - No field duplicate is associated with samples in this SDG. No qualification is necessary.

Compound Quantitation - No discrepancies were reported in this data package.

Qualification Summary Table

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
THGLAOC1905-02 (Soil)	N-Nitrosodimethylamine	110	U	110	R
	1,2-Dichlorobenzene	90	U	90	R
	Phenanthrene	2100	No flag	2100	J
	Fluoranthene	3500	No flag	3500	J
	Pyrene	3600	No flag	3600	J
	Benzo(a)anthracene,	2000	No flag	2000	J
	Chysene	2000	No flag	2000	J
	Benzo(b)fluoranthene	2200	No flag	2200	J
	Benzo(k)fluoranthene	1400	No flag	1400	J
	Benzo(a)pyrene	1800	No flag	1800	J
	Indeno(1,2,3-cd)pyrene	1100	No flag	1100	J
	Dibenzo(a,h)anthracene	430	No flag	430	J
	Benzo(g,h,i)perylene	1300	No flag	1300	J
	4-Nitroquinoline-1-oxide	1400	U	1400	R

**Appendix IX Volatile Organic Compounds**  
 SW-846 Method 8260B  
 USEPA Level III Review

Site NAS Fort Worth JRB

SDG#: 204981

Laboratory: STL-Chicago

Date: 11.12.01

HydroGeoLogic, Inc. Reviewer: Kimberly Evers

Project AFC001-26CC

Client Sample ID	Laboratory Sample ID	Lab Batch	Matrix
THGLAOC1905-02	204981-1	29259	Soil
IDW081501*	204981-2	29259	Soil
EB081501	204981-3	29040	Water
TB081501	204981-4	29040	Water

\* Sample IDW081501 is included in this SDG but does not require validation

Sample Delivery and Condition - The samples arrived at the laboratory in acceptable condition and temperature, and properly preserved. Proper custody was documented. No qualification is necessary

Holding Times - All samples were analyzed within the required holding time for soil samples and no qualification is necessary

GC/MS Tuning - The initial calibration and sample analytical sequences were all performed within 12 hours of an acceptable MS tune. No qualification required

Initial calibration - The initial calibration associated with the soil samples had acceptable average RRFs for all SPCCs. The mean %RSD for all analytes was below 15% in both calibrations, all compound %RSDs were <30%. Compounds with a %RSD <15% are quantified using the calibration curve. All calibration curves were evaluated and found to have  $r^2 > 0.990$  with the exception of bromomethane, iodomethane and acetone, which had  $r^2 < 0.990$ . All associated bromomethane, iodomethane and acetone results in THGLAOC1905-02 should be R qualified

Note: The initial calibration from 07.05.01 is associated with the equipment and the trip blank and does not require validation. No qualification necessary.

Continuing Calibration - Two continuing calibration verification (CCV) are associated with this SDG. One was run on 08.17.01 (29040) and one was run on 08.20.01 (29259). All SPCCs had CCRFs in control. All CCC %Ds were <20%, all other %Ds were in control with the following exception:

29259: 1,2-Dibromo-3-chloropropane had a %D of 34.45%. All associated results should be R qualified.

Note: The CCV run on 08.17.01 is associated with the equipment blank and the trip blank and does not require validation. No qualification necessary

Surrogates - All surrogate recoveries were within established control limits and no qualification is necessary.

Laboratory Control Samples - All %R results for the LSC associated with batches 29259 met established control limits and no qualification is necessary.

Note: The LCS associated with the equipment blank and the trip blank does not require validation and no qualification is necessary

MS/MSD - A matrix spike/matrix spike duplicate was not analyzed with this data package. No qualification necessary.

Internal Standard Performance - All internal standards met area and retention time criteria. No qualification necessary

Method Blanks - Both method blanks were free from contamination. No qualification necessary.

Trip Blanks - Trip blank TB081501 and equipment blank EB081501 are associated with the samples in this SDG. The equipment blank and the trip blank were free of contamination with the exception of 1 µg/L of chloromethane in the trip blank. The associated result is non-detect and no qualification is necessary

Field Duplicates - No duplicate pairs were submitted with this data package and no qualification is necessary.

Compound Quantitation - No discrepancies.

Qualification Summary Table

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
THGLAOC1905-02	Bromomethane	3	U	3	R
	Iodomethane	4	U	4	R
	Acetone	4	U	4	R
	1,2-Dibromo-3-chloropropane	1	U	1	R

**Metals**  
 SW-846 6010B/7000A Series  
 USEPA Level III Review

Site: Naval Air Station Fort Worth JRB, Texas      SDG #: 205075  
 Laboratory: STL-Chicago      Date 11/20/01  
 HydroGeoLogic, Inc. Reviewer: Ken Rapuano      Project: AFC001-26CC

Client Sample ID	Laboratory Sample ID	Matrix
BHGLAOC1905-01	205075-1	Soil
BHGLAOC1905-02	205075-2	Soil
BHGLAOC1905-03	205075-3	Soil
EB082001	205075-8	Water

**Sample Delivery and Condition** - The samples arrived at the laboratory preserved, and in acceptable condition and temperature. Proper custody (internal and external) was documented. No qualification required.

**Holding Times** - All samples were analyzed within the required holding times for preserved soil samples. No qualification required.

**Calibration** - The initial and continuing calibration verification standards had acceptable recoveries. No qualification required.

**Method and Calibration Blanks** - The preparation blank and associated CCBs showed contamination above the MDL for chromium (0.3 mg/kg), leading to an action level of 1.5 mg/kg, tin (1.6 mg/kg), leading to an action level of 8.0 mg/kg, vanadium (3.8 µg/L), leading to an action level of 1.9 mg/kg, and zinc (5.8 mg/kg), leading to an action level of 29 mg/kg. The associated results for chromium and vanadium were greater than the associated action levels and no qualification is necessary. All soil samples had detections of tin and zinc are below the associated action levels, and these detections are qualified U as laboratory artifacts.

The preparation blanks and CCBs associated with the soil samples had negative baseline drift for the following elements:

**Beryllium.** The highest associated blank value is -0.047 mg/kg, leading to an action level of 0.235 mg/kg. All beryllium results for soil samples are above the action level and no qualification is necessary.

**Antimony.** The highest associated blank value is -0.4 mg/kg, leading to an action level of 2.0 mg/kg. All antimony results for soil samples are non-detect and should be qualified UJ.

**Silver.** The highest associated blank value is -0.1 mg/kg, leading to an action level of 0.5 mg/kg. All silver results for soil samples are non-detect and should be qualified UJ.

**Equipment Blanks** - The equipment blank associated with this sample is EB082001. This equipment blank was contaminated with zinc (8.0 µg/L), leading to an action level of 4.0 mg/kg. The associated sample results are greater than the action level, but have already been qualified U as laboratory artifacts due to method blank contamination; no additional qualification is necessary.

ICP Interference Check Sample - All %Rs were in control No qualification necessary.

ICP Serial Dilution - No serial dilution performed. No qualification necessary.

Laboratory Control Samples - All LCSs had acceptable recoveries. No qualification required.

GFAA Recovery Tests - The recovery test for antimony was above the UCL for all three soil samples All of the affected antimony results are non-detect and should be UJ qualified The recovery tests for selenium and thallium were below the LCL (but above 10%) for all three soil samples. All of the affected selenium and thallium results are non-detect and should be UJ qualified

Matrix Spike Analyses - A matrix spike/matrix spike duplicate was not analyzed with this data package No qualification is necessary

Laboratory Duplicates - A laboratory duplicate was not analyzed with this data package. No qualification necessary

Field Duplicates - No field duplicate is associated with the sample in this SDG and no qualification is necessary

Compound Quantitation - All analytes reported below the PQL are reported as F qualified detections The laboratory performed the analysis for lead at a 10x dilution due to the elevated concentration The laboratory performed the analysis for selenium at a 5x dilution due to interferences in the sample

Qualification Summary Table

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
BHGLAOC1905-01	Antimony	0.23	U	0.23	UJ
	Selenium	0.19	U	0.19	UJ
	Silver	0.080	U	0.080	UJ
	Thallium	0.23	U	0.23	UJ
	Tin	1.7	F	1.7	U
	Zinc	27.3	--	27.3	U
BHGLAOC1905-02	Antimony	0.21	U	0.21	UJ
	Selenium	0.18	U	0.18	UJ
	Silver	0.075	U	0.075	UJ
	Thallium	0.21	U	0.21	UJ
	Tin	1.8	F	1.8	U
	Zinc	16.3	F	16.3	U

724 441

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
BHGLAOC1905-03	Antimony	0.17	U	0.17	UJ
	Selenium	0.14	U	0.14	UJ
	Silver	0.059	U	0.059	UJ
	Thallium	0.17	U	0.17	UJ
	Tin	1.5	F	1.5	U
	Zinc	13.9	F	13.9	U

**Appendix IX SVOCs**  
**SW8270C**  
**USEPA Level III Review**

Site: Naval Air Station Fort Worth JRB, Texas

SDG #: 205075

Laboratory: STL-Chicago

Date: 11.19.01

HydroGeoLogic, Inc. Reviewer: Ken Rapuano

Project Number: AFC001-26CC

Client Sample ID	Laboratory Sample ID	Lab Batch	Matrix
BHGLAOC1905-01	205075-1	30589/33348	Soil
BHGLAOC1905-02	205075-2	30589/33348	Soil
BHGLAOC1905-03	205075-3	30589/33348	Soil
EB082001	205075-8	30208	Water

Sample Delivery and Condition - The samples arrived at the laboratory in acceptable condition and temperature. Proper custody (internal and external) was documented. No qualification required.

Holding Times - All samples were extracted and analyzed within the required holding times for soil samples; however, each soil sample was re-extracted 24 days outside the 14-day holding time. The re-extracted batch (batch 33348) is rejected and no further validation is performed based on the QC results for that batch. The original results from batch 30589 should be used for all soil samples.

GC/MS Tuning - All DFTPP tunes associated with initial and continuing calibrations were in control. No qualification necessary.

Initial Calibration - 07.27.01 and 09.21.01. All SPCC mean RRFs were above 0.050 and all CCC %RSDs were less than 30%. The average %RSD for all analytes was below 15%; all compound %RSDs were <30%. No qualification necessary.

Note that the Form VI calibration summary (pp. 99-106) shows average RRFs and %RSDs for all compounds; however, several compounds are listed on the raw calibration summary reports (pp. 193-208) as being quantitated using linear, weighted linear, or power functions. The  $r^2$  values shown on pp. 193-208 are in control for all affected compounds except 1,2-dichlorobenzene and 4-nitroquinoline-1-oxide. The CCV and LCS are in control for 1,2-dichlorobenzene using either linear response or weighted linear response, and as this compound is not detected in any sample, it is the judgment of the validator that sufficient initial calibration control is demonstrated for this compound and no qualification is necessary. The CCV and LCS are not used to control 4-nitroquinoline-1-oxide results (it is a compound listed in Appendix A of the NASFW Basewide QAPP), and this compound also needs no qualification as initial calibration control is shown for linear response.

Continuing Calibration - The continuing CCV associated with the samples in this SDG had all CCC %Ds and SPCC RRFs in control. The CCV had the %Ds within the 25% (30% for selected compounds) control limit for all compounds (50% for those compounds listed in Appendix A). No qualification necessary.

Surrogates - All surrogate recoveries were in control. No qualification is necessary.



Laboratory Control Samples - The LCSs associated with the analytical results for all samples are in control for all compounds, with the exception of a low %R for benzyl alcohol. All associated results for this compound should be rejected and qualified R.

MS/MSD - No matrix spike/matrix spike duplicate was in association with the soil samples in this data package. No qualification necessary.

Internal Standards - Each sample had all six ISs in control for retention time and peak area. No qualification necessary.

Method Blanks - The method blank associated with samples in this SDG was free from contamination. No qualification is necessary.

Field Blanks - The equipment blank, EB082001, associated with the samples was free from contamination and no qualification is necessary.

Field Duplicates - No field duplicate is associated with samples in this SDG. No qualification is necessary.

Compound Quantitation - No discrepancies were reported in this data package.

Qualification Summary Table

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
BHGLAOC1905-01	Benzyl alcohol	120	U	120	R
BHGLAOC1905-01 (reanalysis)	All results	MDL	U	MDL	RX
BHGLAOC1905-02	Benzyl alcohol	110	U	110	R
BHGLAOC1905-02 (reanalysis)	All results	MDL	U	MDL	RX
BHGLAOC1905-03	Benzyl alcohol	120	U	120	R
BHGLAOC1905-03 (reanalysis)	B2EHP	290	F	290	RX
	All other results	MDL	U	MDL	RX

**Appendix IX Volatile Organic Compounds**  
**SW-846 Method 8260B**  
**USEPA Level III Review**

Site: NAS Fort Worth JRB

SDG#: 205075

Laboratory: STL-Chicago

Date: 10/30/01

HydroGeoLogic, Inc. Reviewer: Kimberly Evers

Project: AFC001-26CC

Client Sample ID	Laboratory Sample ID	Lab Batch	Matrix
BHGLAOC1905-01	205075-1	30398	Soil
BHGLAOC1905-02	205075-2	30265	Soil
BHGLAOC1905-03	205075-3	30265	Soil
BHGLAOC1906-02*	205075-4	30398	Soil
BHGLAOC1906-03*	205075-5	30398	Soil
BHGLAOC1907-03*	205075-6	30265	Soil
DUP082001*	205075-7	30398	Soil
EB082001	205075-8	31000	Water
TB082001	205075-9	31000	Water

\* Analyzed for Trichloroethene only

**Sample Delivery and Condition** - The samples arrived at the laboratory in acceptable condition and temperature, and properly preserved. Proper custody was documented. No qualification is necessary.

**Holding Times** - All samples were analyzed within the required holding time for soil samples and no qualification is necessary.

**GC/MS Tuning** - The initial calibration and sample analytical sequences were all performed within 12 hours of an acceptable MS tune. No qualification required.

**Initial calibration** - The initial calibration associated with samples BHGLAOC1905-2, BHGLAOC1905-3 and BHGLAOC1907-3 had acceptable average RRFs for all SPCCs. The mean %RSD for all analytes was below 15%; all compound %RSDs were <30%. Compounds with a %RSD <15% are quantified using the calibration curve. All calibration curves were evaluated and found to have  $r^2 > 0.990$  and no qualification is necessary with the exception of bromomethane, iodomethane and acetone which had an  $r^2 < 0.990$ . All associated bromomethane, iodomethane and acetone results in samples BHGLAOC1905-2 and BHGLAOC1905-3 should be R qualified. These compounds are not reported for sample BHGLAOC1907-03.

The initial calibration associated with samples BHGLAOC1905-1, BHGLAOC1906-2 and BHGLAOC1906-3 had acceptable average RRFs for all SPCCs. The mean %RSD for all analytes was below 15%, all compound %RSDs were <30%. Compounds with a %RSD <15% are quantified using the calibration curve. All calibration curves were evaluated and found to have  $r^2 > 0.990$  and no qualification is necessary.

Note. The initial calibration performed on 08/29/01 is associated with the equipment and trip blank and does not require validation. No qualification is necessary.

Continuing Calibration - Three continuing calibration are associated with this SDG. One was run on 08/28/01 (30265), one was run on 08/29/01 (30398) and one was run on 09/02/01 (31000). All SPCCs had CCRFs in control. All CCC %Ds were <20%; all other %Ds were in control with the following exceptions:

30265: 1,2-dibromo-3-chloropropane had a %D of 28.41%. All associated results should be R qualified.

30265: Acrolein, listed in Appendix A of the QAPP, had a %D that did not meet the %D requirements; however, no corrective action is required for this compound.

30265: Iodomethane had a %D of 25.60%. All associated results should be R qualified.

30398: Chloromethane had a %D of 32.90%. All associated results should be R qualified.

30398: Bromomethane had a %D of 72.67%. All associated results should be R qualified.

30398: Chloroethane had a %D of 34.11%. All associated results should be R qualified.

30398: 1,2-dibromo-3-chloropropane had a %D of 25.16%. All associated results should be R qualified.

30398: Pentachloroethane had a %D of 45.02%. All associated results should be R qualified.

Note: The continuing calibration verification on 09/02/01 is associated with the equipment and trip blank and does not require validation. No qualification necessary.

Surrogates - All surrogate recoveries were within established control limits with the exception of a high %R for dibromofluoromethane in sample number BHGLAOC1906-03. All detection in this sample should be J qualified.

Laboratory Control Samples - All %R results for the LSCs associated with batches 30265, 30398 and 31000 met established control limits with the exception of a high %R for bromomethane and chloroethane in the LCS associated with batch 30398. All associated results in samples BHGLAOC1905-01, BHGLAOC1906-02, BHGLAOC1906-03 and DUP082001 for bromomethane and chloroethane have already been R qualified due to a failure to meet acceptance criteria in the CCV associated with these samples.

Note: The LCS associated with the equipment blank and the trip blank does not require validation and no qualification is necessary.

MS/MSD - A matrix spike/matrix spike duplicate was not analyzed with this data package. No qualification necessary.

Internal Standard Performance - All internal standards met area and retention time criteria with the exception of sample BHGLAOC1906-03. All internal areas were below the 50% acceptance limits. The associated detection of TCE should be J qualified.

Method Blanks - All method blanks were free from contamination. No qualification necessary.

Trip Blanks - Trip blank TB082001 and equipment blank EB082001 were free of contamination and no qualification is necessary.

Field Duplicates - Field duplicate DUP082001 is associated with sample BHGLAOC1907-03. No detections are reported in either member of this duplicate pair. No qualification is necessary.

Compound Quantitation - No discrepancies.

#### Qualification Summary Table

Note - The laboratory provides informational codes in a column in the report page called flags. Those codes are removed and replaced with the appropriate qualifier

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
BHGLAOC1905-01	Chloromethane	1	U	1	R
	Bromomethane	3	U	3	R
	Chloroethane	2	U	2	R
	1,2-dibromo-3-chloropropane	1	U	1	R
	Pentachloroethane	6	U	6	R
BHGLAOC1905-02	Bromomethane	3	U	3	R
	Iodomethane	3	U	3	R
	Acetone	4	U	4	R
	1,2-dibromo-3-chloropropane	1	U	1	R
BHGLAOC1905-03	Bromomethane	3	U	3	R
	Iodomethane	3	U	3	R
	Acetone	14	No flag	14	R
	1,2-dibromo-3-chloropropane	1	U	1	R
BHGLAOC1906-02	No qualification necessary				
BHGLAOC1906-03	Trichloroethene	8	No flag	8	J
BHGLAOC1907-03	No qualification necessary				
DUP082001	No qualification necessary				

**Metals**  
SW-846 6010B/7000A Series  
USEPA Level III Review

Site: Naval Air Station Fort Worth RB, Texas      SDG #: 205104  
Laboratory: STL-Chicago      Date: 11.26.01  
HydroGeoLogic, Inc. Reviewer: Ken Rapuano      Project: AFC001-26CC

Client Sample ID	Laboratory Sample ID	Matrix
BHGLAOC1908-01	205104-1	Soil
BHGLAOC1908-02	205104-2	Soil
BHGLAOC1908-03	205104-3	Soil
BHGLSWMU1919-02*	205104-4	Soil
BHGLSWMU1919-03*	205104-5	Soil
BHGLSWMU1924-01*	205104-7	Soil
BHGLSWMU1924-02*	205104-8	Soil
BHGLSWMU1924-03*	205104-9	Soil
BHGLSWMU1924-04*	205104-10	Soil
BHGLSWMU1924-05*	205104-11	Soil
EB082101	205104-16	Water

\* Analyzed only for a sample-specific abbreviated list of metals

Sample Delivery and Condition - The samples arrived at the laboratory in acceptable condition and temperature. Proper custody (internal and external) was documented. No qualification required.

Holding Times - All samples were analyzed within the required holding times for soil samples. No qualification required.

Calibration - The initial and continuing calibration verification standards had acceptable recoveries. No qualification required.

Method and Calibration Blanks - The preparation blank and associated CCBs showed contamination above the MDL for **chromium** (0.3 mg/kg), leading to an action level of 1.5 mg/kg; **tin** (1.6 mg/kg), leading to an action level of 8.0 mg/kg; **vanadium** (3.8 µg/L), leading to an action level of 1.9 mg/kg, and **zinc** (5.8 mg/kg), leading to an action level of 29 mg/kg. All associated results for chromium and vanadium were greater than the associated action levels and no qualification is necessary. All associated tin and zinc results are below the associated action levels, and these detections are qualified U as laboratory artifacts.

The preparation blanks and CCBs associated with the soil samples had negative baseline drift for the following elements:

**Beryllium.** The highest associated blank value is -0.047 mg/kg, leading to an action level of 0.235 mg/kg. All beryllium results for soil samples are above the action level and no qualification is necessary.

**Antimony** The highest associated blank value is -0.4 mg/kg, leading to an action level of 2.0 mg/kg. The non-detect in sample BHGLAOC1908-01 should be qualified UJ. All other associated antimony results should retain the F-qualifier.

**Silver** The highest associated blank value is -0.1 mg/kg, leading to an action level of 0.5 mg/kg. All associated silver results for soil samples are non-detect and should be qualified UJ.

**Equipment Blanks** - The equipment blank associated with this sample is EB082101. This equipment blank was contaminated with zinc (6.9 µg/L), leading to an action level of 3.45 mg/kg. The associated sample results are greater than the action level, but have already been qualified U as laboratory artifacts due to method blank contamination, no additional qualification is necessary.

**ICP Interference Check Sample** - All %Rs were in control. No qualification necessary.

**ICP Serial Dilution** - A serial dilution was performed on sample BHGLSWMU1924-02. Vanadium did not meet the 10 %D criterion. All associated vanadium results are less than 5x the PQL and no qualification is necessary.

**Laboratory Control Samples** - All LCSs had acceptable recoveries. No qualification required.

**GFAA Recovery Tests** - The recovery test for antimony was above the UCL for samples BHGLAOC1908-02 and BHGLAOC1908-03. The antimony result for sample BHGLAOC1908-02 should retain its F-qualifier. The antimony result for sample BHGLAOC1908-03 is a non-detect and should be UJ qualified. The recovery tests for selenium were below the LCL (but above 10%) for samples BHGLAOC1908-01, BHGLAOC1908-02, BHGLAOC1908-03. All of the affected selenium results are non-detect and should be UJ qualified. The recovery tests for thallium were below the LCL (but above 10%) for samples BHGLAOC1908-02 and BHGLAOC1908-03. All of the affected thallium results are non-detect and should be UJ qualified.

**Matrix Spike Analyses** - A matrix spike/matrix spike duplicate was performed on sample BHGLSWMU1924-02. The matrix spike had high recoveries for arsenic and vanadium, and the MS/MSD pair had high RPDs for arsenic and vanadium. Both these elements should retain the F-qualifier in the parent sample. No qualification is necessary.

**Laboratory Duplicates** - A laboratory duplicate was not analyzed with this data package. No qualification necessary.

**Field Duplicates** - No field duplicate is associated with the samples in this SDG and no qualification is necessary.

**Compound Quantitation** - All analytes reported below the PQL are reported as F-qualified detections. The laboratory performed analyses for lead at a 10x or 20x dilutions due to the elevated concentrations in the samples.

Qualification Summary Table

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
BHGLAOC1908-01	Selenium	0.20	U	0.20	UJ
	Silver	0.082	U	0.082	UJ
	Tin	1.6	F	1.6	U
	Zinc	20.3	F	20.3	U
BHGLAOC1908-02	Selenium	0.18	U	0.18	UJ
	Silver	0.075	U	0.075	UJ
	Thallium	0.21	U	0.21	UJ
	Tin	1.9	F	1.9	U
	Zinc	25.5	F	25.5	U
BHGLAOC1908-03	Antimony	0.24	U	0.24	UJ
	Selenium	0.20	U	0.20	UJ
	Silver	0.084	U	0.084	UJ
	Thallium	0.24	U	0.24	UJ
	Tin	2.1	F	2.1	U
	Zinc	16.7	F	16.7	U
BHGLSWMU1919-02	No qualification necessary				
BHGLSWMU1919-03	No qualification necessary				
BHGLSWMU1924-01	No qualification necessary				
BHGLSWMU1924-02	No qualification necessary				
BHGLSWMU1924-03	No qualification necessary				
BHGLSWMU1924-04	No qualification necessary				
BHGLSWMU1924-05	No qualification necessary				

**Appendix IX SVOCs**  
**SW8270C**  
**USEPA Level III Review**

Site Naval Air Station Fort Worth JRB, Texas

SDG #: 205104

Laboratory: STL-Chicago

Date: 11.26.01

HydroGeoLogic, Inc. Reviewer: Ken Rapuano

Project Number: AFC001-26CC

Client Sample ID	Laboratory Sample ID	Matrix
BHGLAOC1908-01	205104-1	Soil
BHGLAOC1908-02	205104-2	Soil
BHGLAOC1908-03	205104-3	Soil
BHGLSWMU1919-04*	205104-6	Soil
BHGLSWMU1924-03*	205104-9	Soil
BHGLSWMU1926-04*	205104-14	Soil**
EB082101	205104-16	Water

\* Analyzed only for a sample-specific abbreviated list of SVOCs

\*\* The chain of custody requests an SPLP extract and analysis for this sample, these were not performed

Sample Delivery and Condition - The samples arrived at the laboratory in acceptable condition and temperature. Proper custody (internal and external) was documented. No qualification required.

Holding Times - All samples were extracted and analyzed within the required holding times for soil samples; however, each soil sample was re-extracted 22 days outside the 14-day holding time. The re-extracted batch (batch 33348) is rejected and no further validation is performed based on the QC results for that batch. The original results from extraction batch 30833 should be used for all soil samples.

GC/MS Tuning - All DFTPP tunes associated with initial and continuing calibrations were in control. No qualification necessary.

Initial Calibration - 07.27.01 and 09.21.01: All SPCC mean RRFs were above 0.050 and all CCC %RSDs were less than 30%. The average %RSD for all analytes was below 15%; all compound %RSDs were <30%. No qualification necessary.

Note that the Form VI calibration summary (pp. 131-138) shows average RRFs and %RSDs for all compounds; however, several compounds are listed on the raw calibration summary reports (pp. 224-239) as being quantitated using linear, weighted linear, or power functions. The  $r^2$  values shown on pp. 224-239 are in control for all affected compounds except 1,2-dichlorobenzene and 4-nitroquinoline-1-oxide. The CCV and LCS are in control for 1,2-dichlorobenzene using either linear response or weighted linear response, and as this compound is not detected in any sample, it is the judgment of the validator that sufficient initial calibration control is demonstrated for this compound and no qualification is necessary. The CCV and LCS are not used to control 4-nitroquinoline-1-oxide results (it is a compound listed in



Appendix A of the NASFW Basewide QAPP), and this compound also needs no qualification as initial calibration control is shown for linear response.

Continuing Calibration - The continuing CCV associated with the samples in this SDG had all CCC %Ds and SPCC RRFs in control. The CCV had the %Ds within the 25% (30% for selected compounds) control limit for all compounds (50% for those compounds listed in Appendix A). No qualification necessary.

Surrogates - All surrogate recoveries were in control. No qualification is necessary.

Laboratory Control Samples - The LCSs associated with the analytical results for all samples are in control for all compounds, with the exception of a low %R for benzyl alcohol. All associated results for this compound should be rejected and qualified R.

MS/MSD - A matrix spike/matrix spike duplicate was performed on sample BHGLSWMU1919-04. All %Rs and RPDs were in control. No qualification necessary.

Internal Standards - Each sample had all six ISs in control for retention time and peak area, with the exception of the peak area of IS naphthalene-d8 in sample BHGLSWMU1926-04. No SVOCs associated with this IS are reported for this sample. No qualification necessary.

Method Blanks - The method blank associated with samples in this SDG was free from contamination. No qualification is necessary.

Field Blanks - The equipment blank, EB082101, associated with the samples was free from contamination and no qualification is necessary.

Field Duplicates - No field duplicate is associated with samples in this SDG. No qualification is necessary.

Compound Quantitation - Compounds detected below the PQL are reported qualified F.

#### Qualification Summary Table

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
BHGLAOC1908-01	Benzyl alcohol	120	U	120	R
BHGLAOC1908-01 (reanalysis)	All results	MDL	U	MDL	RX
BHGLAOC1908-02	Benzyl alcohol	120	U	120	R
BHGLAOC1908-02 (reanalysis)	All results	MDL	U	MDL	RX
BHGLAOC1908-03	Benzyl alcohol	120	U	120	R
BHGLAOC1908-03 (reanalysis)	All results	MDL	U	MDL	RX
BHGLSWMU1919-04	No qualification necessary.				
BHGLSWMU1924-03	No qualification necessary.				
BHGLSWMU1926-04	No qualification necessary.				

**Appendix IX Volatile Organic Compounds**  
 SW-846 Method 8260B  
 USEPA Level III Review

Site. NAS Fort Worth JRB

SDG# 205104

Laboratory: STL-Chicago

Date. 11.20 01

HydroGeoLogic, Inc Reviewer: Ken Rapuano

Project: AFC001-26CC

Client Sample ID	Laboratory Sample ID	LCS/Method Blank Batch	Matrix
BHGLAOC1908-01	205104-1	30381	Soil
BHGLAOC1908-02	205104-2	30381	Soil
BHGLAOC1908-03	205104-3	30381	Soil
BHGLSWMU1919-03*	205104-5	30381	Soil
BHGLSWMU1919-04*	205104-6	30845	Soil
BHGLSWMU1924-03*	205104-9	30871	Soil
BHGLSWMU1925-03*	205104-12	30871 & 30662	Soil & Extract
BHGLSWMU1926-03*	205104-13	30871 & 30662	Soil & Extract
BHGLSWMU1926-04*	205104-14	30871/30861 & 30662	Soil & Extract
BHGLSWMU1927-04*	205104-15	30871 & 30662	Soil & Extract
EB082101	205104-16	30789	Water
TB082101	205104-17	30789	Water

\* Analyzed for selected VOCs only

**Sample Delivery and Condition** - The samples arrived at the laboratory in acceptable condition and temperature, and properly preserved. Proper custody was documented. No qualification is necessary.

**Holding Times** - All samples were analyzed within the required holding time for soil samples and no qualification is necessary

**GC/MS Tuning** - The initial calibration and sample analytical sequences were all performed within 12 hours of an acceptable MS tune, with one exception. The SPLP extract for sample BHGLSWMU927-04 was injected 12 hours and 4 minutes after the BFB tuning standard, and the matrix spike of the SPLP extract of sample BHGLSWMU1925-03 was injected 12 hours and 40 minutes after the BFB tuning standard. In the judgment of the validator, this is a minor discrepancy and no qualification is required.

**Initial Calibration** - Several ICal runs are reported in this data package. The QC issues associated with each one are discussed below:

pp. 148-150 This initial calibration is associated with the trip and equipment blanks, and no qualification is performed based on this calibration.

pp. 314-316: This initial calibration is associated with all soil analyses except the dilution of sample BHGLSWMU1926-04. Not all target analytes are included on the Form VI summary, and the raw calibration data on pp. 317-329 were used to supplement this Form. [The laboratory resubmitted revised ICal pages to correct this deficiency after the data review was complete.] This calibration had acceptable average RRFs for all SPCCs and %RSDs for all CCCs. The mean %RSD for all analytes was below 15%; all compound %RSDs were <30%. Some compounds with a %RSD >15% are quantified using the calibration curve. All calibration curves were evaluated and found to have  $r^2 > 0.990$ . No qualification is necessary.

pp. 401-403: This initial calibration is associated only with QC samples and is not evaluated. No qualification necessary.

pp. 552-554: This initial calibration is associated with all SPLP extract analyses. The only target compounds are benzene, toluene, and acrylonitrile. This calibration had acceptable average RRFs for all SPCCs and %RSDs for all CCCs. The mean %RSD for all analytes was below 15%; all target compound %RSDs were below 30%. No qualification necessary.

pp. 657-659: This initial calibration is associated only with the diluted analysis of toluene in soil sample BHGLSWMU1926-04. Therefore, only the SPCCs and CCCs (note that toluene is a CCC) results, and total average %RSD, are subject to review for this ICal. This calibration had acceptable average RRFs for all SPCCs and %RSDs for all CCCs. The mean %RSD for all analytes was below 15%; the toluene %RSD was below 30%. No qualification necessary.

Continuing Calibration - Each CCV was evaluated for SPCC RRFs, CCC %Ds, and target analyte %Ds < 25%. Compounds listed in Appendix A of the QAPP have an advisory %D requirement of 50%, with no qualification or corrective action if this requirement is not met.

pp. 747-749 and 755: This continuing calibration is associated with the soil analyses of samples BHGLAOC1908-01, -02, and -03, and BHGLSWMU1919-03. SPCCs and CCCs met criteria. The following compounds did not meet %D criteria: chloromethane, chloroethane, bromomethane. All associated results should be R qualified. The 1,2-dibromo-3-chloropropane %D was 25.2%. This exceedence is considered by the validator to be nominal and this compound should not be qualified.

pp. 760-762: This initial calibration is associated with all SPLP extract analyses. The only target compounds are benzene, toluene, and acrylonitrile. All SPCCs, CCCs, and target compounds met criteria and no qualification is necessary.

pp. 788-790 and 795: These CCVs are not associated with environmental samples and were not evaluated.

pp. 788-790 and 795: This continuing calibration is associated with the soil analyses of samples BHGLSWMU1924-03, BHGLSWMU1925-03, BHGLSWMU1926-03, BHGLSWMU1926-04 (original analysis only), and BHGLSWMU1927-04. The only analyte analyses associated with this CCV are for BTEX, acrylonitrile, acetone, MEK, and MIBK. SPCCs, CCCs, and target compounds met criteria, with the exception of acetone. The acceptance criterion for this compound is advisory only. No qualification necessary.

pp. 798-799: This continuing calibration is associated with the soil analysis of sample BHGLSWMU1919-04. The only analyte analysis associated with this CCV is acetone. SPCCs, CCCs, and acetone met criteria. No qualification necessary.

pp. 805-807: This continuing calibration is associated with the diluted soil analysis of sample BHGLSWMU1926-04. The only analyte analysis associated with this CCV is toluene. SPCCs and CCCs (toluene is a CCC) met criteria. No qualification necessary.

Surrogates - The original and diluted analysis of sample BHGLSWMU1926-04 and the analysis of sample BHGLSWMU1927-04 had one or more surrogate recoveries above the UCL. All detections associated with these sample analyses should be J qualified.

Laboratory Control Samples - For the LCS associated batch 30381, the %R was above the UCL for bromomethane and chloroethane. The results for these compounds have already been rejected in this batch and no additional qualification is necessary. All %R results for the LCSs associated with batches 30662, 30845, 30861, and 30871 met established control limits. No qualification necessary.

Note: The LCS associated with the equipment blank and the trip blank (batch 30789) and some QC samples (30836) do not require review.

MS/MSD - A matrix spike/matrix spike duplicate was performed on the soil fraction of sample BHGLSWMU1919-04, and a matrix spike (no MSD) was performed on the SPLP fraction of sample BHGLSWMU1925-03. All recoveries and RPD were in control. No qualification necessary.

Internal Standard Performance - All internal standards met area and retention time criteria with the exception of the original analysis of sample BHGLSWMU1926-04. All internal standard areas were below the 50% acceptance limit for this analysis. The detection of benzene should be J qualified in this sample.

Method Blanks - All method blanks and extraction blanks were free from contamination. No qualification necessary.

Note: The method blanks associated with the equipment blank and the trip blank (batch 30789) and some QC samples (30836) do not require review.

Trip Blanks - Trip blank TB08201 contained 1 µg/L methylene chloride, and equipment blank EB082101 contained 19 µg/L acetone. These detections caused action levels of 5 µg/kg for methylene chloride and 95 µg/kg for acetone. All associated detections of the affected compounds that are below the action level should be qualified U as artifacts.

Field Duplicates - No field duplicate was submitted with this data package. No qualification is necessary.

Compound Quantitation - No discrepancies noted. Some compounds are reported from secondary dilutions with appropriate adjustment to MDLs and RLs.

#### Qualification Summary Table

Note - The laboratory provides informational codes in a column in the report page called flags. Those codes are removed and replaced with the appropriate qualifier.

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
BHGLAOC1908-01	Chloromethane	1	U	1	R
	Bromomethane	3	U	3	R
	Chloroethane	2	U	2	R

724.455

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
	Acetone	8	—	8	U
BHGLAOC1908-02	Chloromethane	0.9	U	0.9	R
	Bromomethane	3	U	3	R
	Chloroethane	1	U	1	R
BHGLAOC1908-03	Chloromethane	0.9	U	0.9	R
	Bromomethane	3	U	3	R
	Chloroethane	1	U	1	R
BHGLSWMU1919-03	No qualification necessary				
BHGLSWMU1919-04	No qualification necessary				
BHGLSWMU1924-03	Acetone	6	—	6	U
BHGLSWMU1925-03	No qualification necessary				
BHGLSWMU1926-03	No qualification necessary				
BHGLSWMU1926-04	Benzene	52	—	52	J
	Toluene (original result)*	value	E	value	EX
	Toluene (diluted result)	8200	—	8200	J
BHGLSWMU1927-04	No qualification necessary				

\* This result is not reported on the hardcopy.

**Appendix IX SVOCs**  
**SW8270C**  
**USEPA Level III Review**

Site: Naval Air Station Fort Worth JRB, Texas

SDG #: 205132

Laboratory: STL-Chicago

Date: 11.28.01

HydroGeoLogic, Inc. Reviewer: Ken Rapuano

Project Number: AFC001-26CC

Client Sample ID	Laboratory Sample ID	Batch	Matrix
BHGLSWMU1923-03*	205132-1	33924 & 33925	Soil & Extract
BHGLSWMU1923-04*	205132-2	33924 & 33925	Soil & Extract
BHGLSWMU1928-03*	205132-3	33924 & 33925	Soil & Extract
BHGLSWMU1928-06*	205132-6	33924 & 33925	Soil & Extract
BHGLSWMU1929-01	205132-8	33924	Soil
BHGLSWMU1929-02	205132-9	33924	Soil
BHGLSWMU1929-03	205132-10	33924	Soil
BHGLSWMU1929-04	205132-11	33924	Soil
DUP006	205132-12	33924	Soil
BHGLAOC1909-02**	205132-14	33924	Soil
BHGLAOC1910-01**	205132-15	33924	Soil
BHGLAOC1910-02**	205132-16	33924	Soil
BHGLAOC1910-03**	205132-17	33924	Soil
EB082201	205132-18	33926	Water

\* Analyzed only for a sample-specific abbreviated list of SVOCs.

\*\* The chain of custody request for "SVOCs/PAHs" is ambiguous; the laboratory provided a full-suite of Appendix IX analyses.

Sample Delivery and Condition - The samples arrived at the laboratory in acceptable condition and temperature. The chain of custody did not specify analyses for the equipment blank. The laboratory correctly analyzed this blank for Appendix IX SVOCs. Proper custody (internal and external) was documented. No qualification required.

Holding Times - All samples were extracted and analyzed within the required holding times for soil samples. No qualification required.

GC/MS Tuning - All DFTPP tunes associated with initial and continuing calibrations were in control. No qualification necessary.

Initial Calibration - 07.27.01 and 09 07 01: This ICal is associated with all SPLP analyses in this SDG. The only target analyte is bis(2-ethylhexyl)phthalate. All SPCC mean RRFs were above 0.050 (the hexachlorocyclopentadiene mean RRF was calculated to be 0.364) and all CCC %RSDs were less than 30%. The average %RSD for all analytes was below 15%; the B2EHP %RSD was <30%. No qualification necessary.

07.27.01 and 09 21.01. This ICal is associated with all soil sample analyses in this SDG. All SPCC mean RRFs were above 0.050 and all CCC %RSDs were less than 30%. The average %RSD for all analytes was below 15%; all compound %RSDs were <30%, with the exceptions of 1,2-dichlorobenzene and 4-nitroquinoline-1-oxide. All associated results for these two compounds are rejected and qualified R.

Continuing Calibration - 09.11 01 This CCV is associated with all SPLP analyses in this SDG. The only target analyte is bis(2-ethylhexyl)phthalate. All SPCC RRFs were above 0.050 and all CCC %Ds were less than 20%. The B2EHP %D was <25%. No qualification necessary.

09 24 01: This CCV is only associated with the equipment blank and was not reviewed.

10.03.01: This CCV is associated with all soil samples in this SDG. All CCC %Ds and SPCC RRFs are in control. The CCV had the %Ds within the 25% (30% for selected compounds) control limit for all compounds (50% for those compounds listed in Appendix A), with the exceptions of the %Ds for benzoic acid and benzo[k]anthracene. All associated results for these compounds are rejected and are qualified R.

Surrogates - The SPLP extracts of samples BHGLSWMU1923-04, BHGLSWMU1928-03, and BHGLSWMU1928-06 had a %R for base/neutral surrogate terphenyl-*d*14 below the LCL but above 10% (the SPLP extract of BHGLSWMU1923-04 also had a %R for the acid surrogate 2-fluorophenol). No qualification is necessary, as two surrogates are in control for each fraction. All surrogate %Rs were in control for environmental soil samples. No qualification necessary.

Laboratory Control Samples - The LCSs associated with the analytical results for all soil samples and SPLP extracts are in control for all compounds. No qualification is necessary.

MS/MSD - A matrix spike/matrix spike duplicate was performed on sample BHGLAOC1910-01. All %Rs and RPDs were in control, with the exceptions of low %Rs for 2,4-dimethylphenol, 4-chloroaniline, 4-nitrophenol, pentachlorophenol, 3, 3'-dichlorobenzidine in the MS and/or MSD. There were no detections of these compounds in the parent sample, and these compounds should be qualified UJ. There were several compounds with %Rs above the UCL and/or RPDs greater than the precision control limit. There were no detections of the affected compounds in the parent sample and no qualification is necessary.

Internal Standards - Each sample had all six ISs in control for retention time and peak area. No qualification necessary.

Method Blanks - The method blanks associated with samples in this SDG were free from contamination. No qualification is necessary.

Field Blanks - The equipment blank, EB082201, associated with the samples was free from contamination and no qualification is necessary.

Field Duplicates - Sample DUP006 is a field duplicate of sample BHGLSWMU1929-02. There are no detections of target compounds in either member of this duplicate pair. No qualification is necessary.

Compound Quantitation - Compounds detected below the PQL are reported qualified F.

Qualification Summary Table

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
BHGLSWMU1923-03 (soil and SPLP)	No qualification necessary				
BHGLSWMU1923-04 (soil and SPLP)	No qualification necessary				
BHGLSWMU1928-03 (soil and SPLP)	No qualification necessary				
BHGLSWMU1928-06 (soil and SPLP)	No qualification necessary				
BHGLSWMU1929-01	1,2-Dichlorobenzene	97	U	97	R
	Benzoic acid	190	U	190	R
	Benzo[k]anthracene	130	U	130	R
	4-Nitroquinoline-1-oxide	1600	U	1600	R
BHGLSWMU1929-02	1,2-Dichlorobenzene	96	U	96	R
	Benzoic acid	190	U	190	R
	Benzo[k]anthracene	130	U	130	R
	4-Nitroquinoline-1-oxide	1500	U	1500	R
BHGLSWMU1929-03	1,2-Dichlorobenzene	100	U	100	R
	Benzoic acid	210	U	210	R
	Benzo[k]anthracene	140	U	140	R
	4-Nitroquinoline-1-oxide	1700	U	1700	R
BHGLSWMU1929-04	1,2-Dichlorobenzene	98	U	98	R
	Benzoic acid	190	U	190	R
	Benzo[k]anthracene	130	U	130	R
	4-Nitroquinoline-1-oxide	1600	U	1600	R
DUP006	1,2-Dichlorobenzene	98	U	98	R
	Benzoic acid	190	U	190	R
	Benzo[k]anthracene	130	U	130	R
	4-Nitroquinoline-1-oxide	1600	U	1600	R



Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
BHGLAOC1909-02	1,2-Dichlorobenzene	90	U	90	R
	Benzoic acid	180	U	180	R
	Benzo[k]anthracene	120	U	120	R
	4-Nitroquinoline-1-oxide	1400	U	1400	R
BHGLAOC1910-01	1,2-Dichlorobenzene	96	U	96	R
	Benzoic acid	190	U	190	R
	2,4-Dimethylphenol	250	U	250	UJ
	4-Chloroaniline	140	U	140	UJ
	4-Nitrophenol	410	U	410	UJ
	Pentachlorophenol	210	U	210	UJ
	3,3'-Dichlorobenzidine	130	U	130	UJ
	Benzo[k]anthracene	130	U	130	R
	4-Nitroquinoline-1-oxide	1500	U	1500	R
BHGLAOC1910-02	1,2-Dichlorobenzene	93	U	93	R
	Benzoic acid	180	U	180	R
	Benzo[k]anthracene	120	U	120	R
	4-Nitroquinoline-1-oxide	1500	U	1500	R
BHGLAOC1910-03	1,2-Dichlorobenzene	100	U	100	R
	Benzoic acid	200	U	200	R
	Benzo[k]anthracene	140	U	140	R
	4-Nitroquinoline-1-oxide	1600	U	1600	R

**Appendix IX SVOCs**  
**SW8270C**  
**USEPA Level III Review**

Site: Naval Air Station Fort Worth JRB, Texas

SDG#. 207066

Laboratory: STL-Chicago

Date: 1.11.02

HydroGeoLogic, Inc. Reviewer: Ken Rapuano

Project: AFC001-26CC (AFC01-026-10)

Client Sample ID	Laboratory Sample ID	Matrix
EB120501	207066-2	Water
BHGLAOC1911-02 <sup>†</sup>	207066-3	Soil
BHGLAOC1912-02	207066-6	Soil
BHGLAOC1912-03	207066-7	Soil
DUP02*	207066-8	Soil
DUP03*	207066-9	Soil
DUP04	207066-10	Soil
BHGLSWMU1935-02*	207066-11	Soil
BHGLSWMU1936-02*	207066-13	Soil
BHGLSWMU1936-03*	207066-14	Soil

<sup>†</sup> Mis-identified on the chain of custody. The correct sample ID is BHGLAOC1911-03.

\* Analyzed only for a sample-specific abbreviated list of SVOCs

**Sample Delivery and Condition** - The samples arrived at the laboratory in acceptable condition and temperature. Proper custody (internal and external) was documented. No qualification required.

**Holding Times** - All samples were extracted and analyzed within the required holding times for soil samples. No qualification necessary.

**GC/MS Tuning** - All DFTPP tunes associated with initial and continuing calibrations were in control. No qualification necessary.

**Initial Calibration** - 12.17.01 and 1.2.02: All SPCC mean RRFs were above 0.050 and all CCC %RSDs were less than 30%. The average %RSD for all analytes was below 15%; all compound %RSDs were <30%. Those compounds calibrated to a linear relationship or curve had  $r^2$  values > 0.990.

**Continuing Calibration** - The continuing CCV associated with the samples in this SDG had all CCC %Ds and SPCC RRFs in control. The CCV had the %Ds within the 25% (30% for selected compounds) control limit for all compounds listed in Section 7 of the QAPP. The %Ds were all less than 50% for those compounds listed in Appendix A of the QAPP. No qualification necessary.

Surrogates - All surrogate recoveries were in control. Note that the samples from SWMU 19 (including DUP02 and DUP03) were not analyzed for the acid fraction and only base/neutral surrogates are reported for these samples. No qualification is necessary.

Laboratory Control Samples - The LCSs associated with the analytical results for all samples are in control for all compounds, with the exception of a high %R for di-n-octyl phthalate. All associated results for this compound are non-detects and no qualification is necessary.

MS/MSD - A matrix spike/matrix spike duplicate was performed on sample BHGLAOC1912-02. All %Rs and RPDs were in control. No qualification necessary.

Internal Standards - Each sample had all six ISs in control for retention time and peak area. No qualification necessary.

Method Blanks - The method blank associated with samples in this SDG was free from contamination. No qualification is necessary.

Field Blanks - The equipment blank, EB120501, associated with the samples was free from contamination and no qualification is necessary.

Field Duplicates - There are three parent sample/field duplicate pairs in this SDG. BHGLSWMU1935-02/DUP02, BHGLSWMU1936-02/DUP03, and BHGLAOC1911-02/DUP04. There were no target compound detections in either member of duplicate pairs BHGLSWMU1935-02/DUP02 and BHGLSWMU1936-02/DUP03. No qualification is necessary.

Duplicate pair BHGLAOC1911-02/DUP04 had multiple detections, which are compared in the table below

Analyte	BHGLAOC1911-02	DUP04	RPD	Acceptable?
Naphthalene	82 F	75 U	NA	Yes
Acenaphthene	130 F	62 U	NA	Yes
Fluorene	270 F	170 F	NA	Yes
Phenanthrene	1600	550	98	No
Anthracene	230 F	86 U	NA	Yes
Fluoranthene	2100	1100	63	No
Pyrene	1300	1200	8	Yes
Benzo[a]anthracene	650	640	2	Yes
Chrysene	740	720	3	Yes
bis(2-Ethylhexyl)phthalate	130 U	160 F	NA	Yes
Benzo[b]fluoranthene	670	910	30	Yes
Benzo[k]fluoranthene	470	620	28	Yes
Benzo[a]pyrene	580	820	34	No
Indeno[1,2,3-cd]pyrene	310 F	500	NA	No
Dibenzo[a,h]anthracene	130 U	170 F	NA	Yes
Benzo[g,h,i]perylene	300 F	520	NA	No

Where unacceptable precision was found, the affected results are qualified J in each member of the duplicate pair (those data points qualified F retain this qualifier).

Compound Quantitation - Compounds detected below the PQL are reported qualified F.

Qualification Summary Table

Note - The laboratory provides informational codes in a column in the report page called flags. Those codes are removed and replaced with the appropriate qualifier

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
BHGLAOC1911-02 (the correct sample ID is BHGLAOC1911-03)	Phenanthrene	1600	--	1600	J
	Fluoranthene	2100	--	2100	J
	Benzo[a]pyrene	580	--	580	J
BHGLAOC1912-02	No qualification necessary				
BHGLAOC1912-03	No qualification necessary				
DUP02	No qualification necessary.				
DUP03	No qualification necessary.				
DUP04	Phenanthrene	550	--	550	J
	Fluoranthene	1100	--	1100	J
	Benzo[a]pyrene	820	--	820	J
	Indeno[1,2,3-cd]pyrene	500	--	500	J
	Benzo[g,h,i]perylene	520	--	520	J
BHGLSWMU1935-02	No qualification necessary				
BHGLSWMU1936-02	No qualification necessary				
BHGLSWMU1936-03	No qualification necessary.				

**Selected Volatile Organic Compounds**  
 SW-846 Method 8260B  
 USEPA Level III Review

Site: NAS Fort Worth JRB

SDG#: 207066

Laboratory: STL-Chicago

Date 1.11.02

HydroGeoLogic, Inc Reviewer: Ken Rapuano

Project AFC001-26CC (AFC01-026-10)

Client Sample ID	Laboratory Sample ID	LCS/Method Blank Batch	Matrix
TB120501*	207066-1	40893	Water
EB120501*	207066-2	40893	Water
BHGLAOC1913-02	207066-4	42265	Soil
BHGLAOC1913-03	207066-5	42275	Soil
DUP02	207066-8	42275	Soil
DUP03	207066-9	42275	Soil
BHGLSWMU1935-02	207066-11	42275	Soil
BHGLSWMU1935-03	207066-12	42275	Soil
BHGLSWMU1936-02	207066-13	42275	Soil
BHGLSWMU1936-03	207066-14	42268 (med/high level)	Soil

\* Analyzed for the full Appendix IX list of VOCs

Sample Delivery and Condition - The samples arrived at the laboratory in acceptable condition and temperature, and properly preserved. Proper custody was documented. No qualification is necessary.

Holding Times - All samples were analyzed within the required holding time for soil samples and no qualification is necessary.

GC/MS Tuning - The initial calibration and sample analytical sequences were all performed within 12 hours of an acceptable MS tune, with one exception. A laboratory standard labeled 'ICALSPIKE' was injected 19 hours and 5 minutes after the BFB tuning standard run on instrument GCL7. In the judgment of the validator, this is a minor discrepancy and no qualification is required.

Initial Calibration - Two ICal runs are reported in this data package. The QC issues associated with each one are discussed below:

pp. 93-105. This initial calibration is associated with the trip and equipment blanks, and no qualification is performed based on this calibration.

pp. 248-260: This initial calibration is associated with the soil analysis of sample BHGLSWMU1936 -03. Not all target analytes are included on the Form VI summary, and the raw calibration data were used to evaluate data. This calibration had acceptable average RRFs for all SPCCs and %RSDs for all CCCs. The mean %RSD for all analytes was below 15%, all target compound %RSDs were <30%. One target compound, acetone, had a %RSD >15% and was quantified using a calibration curve. The calibration curve was found

to have  $r^2 < 0.990$ ; the laboratory re-evaluated the calibration data, but was not able to fit a curve with  $r^2 > 0.990$ . The corresponding acetone result is rejected and qualified R.

pp. 352-364: This initial calibration is associated with all soil sample analyses in this SDG except BHGLSWMU1936-03. This calibration had acceptable average RRFs for all SPCCs and %RSDs for all CCCs. The mean %RSD for all analytes was below 15%; all target compound %RSDs were below 30%. One target compound, acetone, had a %RSD > 15% and was quantified using a calibration curve. The original calibration curve was found to have  $r^2 < 0.990$ ; the laboratory re-evaluated the calibration data and was able to achieve  $r^2 > 0.990$  by changing the form of the curve. The laboratory submitted revised acetone data and no qualification is necessary.

Continuing Calibration - Each CCV was evaluated for SPCC RRFs, CCC %Ds, and target analyte %Ds < 25%. Compounds listed in Appendix A of the QAPP have an advisory %D requirement of 50%, with no qualification or corrective action if this requirement is not met.

pp. 420-422: This continuing calibration is associated with the soil analyses of sample BHGLSWMU1936-03. All SPCCs, CCCs, and target compounds met criteria and no qualification is necessary.

pp. 429-431: This initial calibration is associated with all soil sample analyses with the exceptions of BHGLAOC1913-02 and BHGLSWMU1936-03. All SPCCs, CCCs, and target compounds met criteria and no qualification is necessary.

pp. 436-438: This initial calibration is associated with the soil sample analysis of BHGLAOC1913-02. All SPCCs, CCCs, and target compounds met criteria and no qualification is necessary.

Surrogates - All samples in this SDG showed acceptable surrogate recoveries with one exception. Sample BHGLSWMU1936-03 had two surrogate recoveries above the UCL. The sample was reanalyzed with similar results. The laboratory reported only the 'best' analysis for this sample. All detections associated with this sample analysis should be J qualified.

Laboratory Control Samples - All %R results for the LCSs associated with batches 42265, 42268, and 42275 met established control limits. No qualification necessary.

Note: The LCS associated with the equipment blank and the trip blank (batch 40893) does not require review.

MS/MSD - No matrix spike/matrix spike duplicate was performed on the soil samples in this SDG. No qualification necessary.

Internal Standard Performance - All internal standards met area and retention time criteria with the exception of the reported analysis of sample BHGLAOC1913-02. The area of internal standard 1,4-dichlorobenzene-d4 was below the 50% acceptance limit for this analysis. The only analyte requested for this sample is trichloroethene, which is not quantified using this IS. No qualification is necessary.

Method Blanks - All method blanks and extraction blanks were free from contamination. No qualification necessary.

Note: The method blanks associated with the equipment blank and the trip blank (batch 40893) does not require review.

Trip Blanks - Trip blank TB120501 was free from contamination, equipment blank EB120501 contained 1 µg/L methylene chloride. This compound is not a requested analyte for any sample in this SDG and no qualification is necessary.

Field Duplicates - DUP02 is a field duplicate of sample BHGLSWMU1935-02, DUP03 is a field duplicate of sample BHGLSWMU1936-02. All results in the DUP03/BHGLSWMU1936-02 pair met precision criteria. No target compounds were detected in the DUP02/BHGLSWMU1935-02 pair. No qualification necessary.

Compound Quantitation - No discrepancies noted. Sample BHGLSWMU1936-03 was analyzed using the medium/high level method with methanol dilution due to high levels of non-target compounds present in the sample. This resulted in the MDLs and reporting limits for this sample to be elevated by a factor of approximately 20 fold. Sample BHGLAOC1913-02 was submitted without sufficient volume for the laboratory to determine the percent solids in the sample and calculate a dry weight correction for the wet weight results. The results for this sample are biased low, possibly by as much as 35% (assuming approximately 75% solids), and the result is qualified with a J

Qualification Summary Table

Note - The laboratory provides informational codes in a column in the report page called flags. Those codes are removed and replaced with the appropriate qualifier

Sample ID	Analyte	Lab Val	Lab Qual	HGL Val	HGL Qual
BHGLAOC1913-02	Trichloroethene	51	--	51	J
BHGLAOC1913-03	No qualification necessary				
DUP02	No qualification necessary				
DUP03	No qualification necessary				
BHGLSWMU1935-02	No qualification necessary				
BHGLSWMU1935-03	No qualification necessary				
BHGLSWMU1936-02	No qualification necessary				
BHGLSWMU1936-03	Acetone	28	U	28	R



# TAB

*APPENDIX H*

---

**APPENDIX H**  
**METES AND BOUNDS**

STATE OF TEXAS  
TARRANT COUNTY

INDUSTRIAL SOLID WASTE  
CERTIFICATION OF CLOSURE/REMEDATION  
AREA OF CONCERN 19

KNOW ALL MEN BY THESE PRESENTS THAT:

Pursuant to the Rules of the Texas Natural Resource Conservation Commission (TNRCC) pertaining to Industrial Solid Waste Management, this document is hereby filed in the Deed Records of Tarrant County, Texas in compliance with the recordation requirements of said rules:

I

The Department of the Air Force has performed closure/remediation of the land described herein. A copy of the Notice of Registration No. 65004, including a description of the facility, is attached hereto and is made part of this filing. A list of the known waste constituents, including known concentrations in soil, which have been left in place is attached hereto and is made part of this filing. Further information concerning this matter may be found by an examination of company records or in the Notice of Registration No. 65004 files, which are available for inspection upon request at the central office of the TNRCC in Austin, Texas.

The TNRCC derives its authority to review the closure/remediation of this tract of land from the Texas Solid Waste Disposal Act, § 361.002, Texas Health and Safety Code, Chapter 361, which enables the TNRCC to promulgate closure and remediation standards to safeguard the health, welfare and physical property of the people of the State and to protect the environment by controlling the management of solid waste. In addition, pursuant to the Texas Water Code, § 5.012 and § 5.013, Texas Water Code, Annotated, Chapter 5, the TNRCC is given primary responsibility for implementing the laws of the State of Texas relating to water and shall adopt any rules necessary to carry out its powers and duties under the Texas Water Code. In accordance with this authority, the TNRCC requires certain persons to provide certification and/or recordation in the real property records to notify the public of the conditions of the land and/or the occurrence of remediation. This deed certification is not a representation or warranty by the TNRCC of the suitability of this land for any purpose, nor does it constitute any guarantee by the TNRCC that the remediation standards specified in this certification have been met by the Department of the Air Force.

## II

**Parcel "B-1"**

Being a tract of land situated in the John M. Shreeve Survey, Abstract No. 1456 within the Naval Air Station Fort Worth Joint Reserve Base (formerly known as Carswell Air Force Base), Tarrant County, Texas, said tract of land also being a portion of a boundary resurvey prepared by Baird, Hampton & Brown, Inc. of Fort Worth, Texas, dated January 14, 1998 and filed with the Air Force Base Conversion Agency and Westworth Redevelopment Authority, said tract of land being described by metes and bounds as follows:

BEGINNING at a set 5/8 inch capped iron rod stamped "BHB INC" having a State Plane Coordinate (North Central Zone, NAD 83) of Northing: 6963043.31; Easting: 2296164.36, for the northeast and beginning corner of tract being described, from which a 5/8 inch aluminum capped iron rod found stamped "N-13" at the Point of Beginning of the area labeled "ENVIRONMENTAL AREA" on said resurvey, bears north 48 degrees 59 minutes 47 seconds west, a distance of 108.32 feet and a 5/8 inch aluminum capped iron rod found stamped "N-12", shown on the West line of said "ENVIRONMENTAL AREA" of said boundary resurvey, bears south 07 degrees 02 minutes 26 seconds west, a distance of 685.13 feet; thence south 00 degrees 12 minutes 09 seconds east, a distance of 283.38 feet to a 5/8" capped iron rod set marked "BHB INC"; thence south 84 degrees 23 minutes 22 seconds west, a distance of 346.98 feet to a 5/8" capped iron rod set marked "BHB INC"; thence north 19 degrees 26 minutes 29 seconds east, a distance of 336.44 feet to a 5/8" capped iron rod set marked "BHB INC"; thence north 89 degrees 59 minutes 17 seconds east, a distance of 232.33 feet to the point of beginning and containing 85798 square feet or 1.969 acres more or less, as surveyed by Steven W. Hughes, Registered Professional Land Surveyor during the month of 2002.

The basis of bearings for this description is the NAD 83 (1986) State Plane Coordinate System for North Central Texas, Zone 4202, US Feet. All bearings shown are based on grid bearings. All distances shown are ground distances in US Feet. Parcel "B-1" is depicted in Exhibit "B-1".

**Parcel "B-2"**

Being a tract of land situated in the John M. Shreeve Survey, Abstract No. 1456 within the Naval Air Station Fort Worth Joint Reserve Base (formerly known as Carswell Air Force Base), Tarrant County, Texas, said tract of land also being a portion of a boundary resurvey prepared by Baird, Hampton & Brown, Inc. of Fort Worth, Texas, dated January 14, 1998 and filed with the Air Force Base Conversion Agency and Westworth Redevelopment Authority, said tract of land being described by metes and bounds as follows:

BEGINNING at a set 5/8 inch capped iron rod stamped "BHB INC" having a State Plane Coordinate (North Central Zone, NAD 83) of Northing: 6963113.19; Easting: 2296037.66, for the northeast and beginning corner of tract being described, from which a 5/8 inch aluminum capped iron rod found stamped "N-13" at the Point of Beginning of the area labeled

"ENVIRONMENTAL AREA" on said resurvey, bears north 88 degrees 29 minutes 25 seconds east, a distance of 44.97 feet and a 5/8 inch aluminum capped iron rod found stamped "N-12", shown on the West line of said "ENVIRONMENTAL AREA" of said boundary resurvey, bears south 03 degrees 15 minutes 44 seconds east, a distance of 751.07 feet; thence south 20 degrees 34 minutes 00 seconds west, a distance of 71.80 feet to a 5/8" capped iron rod set marked "BHB INC"; thence north 88 degrees 11 minutes 49 seconds west, a distance of 23.36 feet to a 5/8" capped iron rod set marked "BHB INC"; thence north 19 degrees 30 minutes 05 seconds west, a distance of 35.46 feet to a 5/8" capped iron rod set marked "BHB INC"; thence north 61 degrees 18 minutes 42 seconds east, a distance of 68.87 feet to the point of beginning and containing 1999 square feet or 0.045 of an acre more or less, as surveyed by Steven W. Hughes, Registered Professional Land Surveyor during the month of 2002.

The basis of bearings for this description is the NAD 83 (1986) State Plane Coordinate System for North Central Texas, Zone 4202, US Feet. All bearings shown are based on grid bearings. All distances shown are ground distances in US Feet. Parcel "B-2" is depicted in Exhibit "B-2".

Volatile Organic Compound (VOC) contaminated soil in Parcel "B-1" and Semi-volatile Organic Compound (SVOC) contaminated soil in Parcel "B-2" meets non-residential (i.e., industrial/commercial) criteria, in accordance with the TNRCC's requirements in 30 Texas Administrative Code, §335.555, which mandates that the closure/remedy be designed to eliminate substantial present and future risk such that no post-closure care or engineering or institutional control measures are required to protect human health and the environment. Future land use is considered suitable for non-residential (i.e., industrial/commercial) purposes in accordance with risk reduction standards applicable at the time of this filing. Future land use is intended to be non-residential.

In accordance with the requirements for Standard 2 cleanups where the closure/remedy is based upon non-residential soil criteria, the current owner has undertaken actions as necessary to protect human health or the environment in accordance with the rules of the TNRCC.

724-472

**Maximum Concentrations of Soil Contaminants Left in Place  
Area of Concern 19**

<b>Analytical Method</b>	<b>Analyte</b>	<b>Maximum Concentration (mg/kg)</b>
<b>VOCs</b>		
SW8260B	Trichloroethene	0.051 J
<b>SVOCs</b>		
SW8270C	Anthracene	0.38
SW8270C	Benzo(a)anthracene	2
SW8270C	Benzo(a)pyrene	1.8
SW8270C	Benzo(b)fluoranthene	2.2
SW8270C	Benzo(g,h,i)perylene	1.3
SW8270C	Benzo(k)fluoranthene	1.4
SW8270C	bis(2-Ethylhexyl)phthalate	0.66
SW8270C	Chrysene	2
SW8270C	Dibenz(a,h)anthracene	0.43
SW8270C	Fluoranthene	3.5
SW8270C	Indeno(1,2,3-c,d)pyrene	1.1
SW8270C	Phenanthrene	2.1
SW8270C	Pyrene	3.6

## III

STATE OF TEXAS  
TARRANT COUNTY

The owner of the site is Department of the Air Force, and its address is Headquarters Air Force Center of Environmental Excellence (AFCEE)/Environmental Restoration Division (ERD), 3207 Sidney Brooks, Brooks Air Force Base, Texas 78235-5363

EXECUTED this the 26th day of April, 2002.

Department of the Air Force

*Michael R Dodyk*

Michael R. Dodyk, P.E.  
Environmental Restoration Team Chief

BEFORE ME, on this the 26th day of April, 2002, personally appeared Michael R. Dodyk, Environmental Restoration Team Chief, Air Force Center for Environmental Excellence, United States Air Force, known to me to be the person and agent of said government agency whose name is subscribed to the foregoing instrument, and he acknowledged to me that he executed the same for the purposes and in the capacity therein expressed.

GIVEN UNDER MY HAND AND SEAL OF OFFICE, this the 26th day of April, 2002.

*Billy Van-Deren*  
BILLY VAN-DEREN

Notary Public in and for the State of Texas, of Tarrant County




6 May 2003

My Commission Expires

Exhibit Showing  
85,798 Square feet in the  
John M. Shreeve Survey  
Abstract No. 1456  
NAS Fort Worth JRB

## EXHIBIT "B-1"

John M. Shreeve Survey  
Abstract No. 1456



Baird, Hampton & Brown, Inc.  
Engineering & Surveying

309 W 7th St, Ste 500 Ft Worth, TX 76102 Tel (817)338-1277 Fax (817)338-9245 E-Mail mail@bhbinc.com

DRAWN BY JPW

CHECKED BY BHB


BHB PROJECT 2002 300 027

DATE April 23, 2002



Exhibit Showing  
1,999 Square feet in the  
John M. Shreeve Survey  
Abstract No. 1456  
NAS Fort Worth JRB

EXHIBIT "B-2"



John M. Shreeve Survey  
Abstract No. 1456

Sketch showing to the best of my knowledge and belief an accurate  
delineation of field survey and office computations performed by me or  
under my supervision

Steven Hughes  
Registered Professional  
Land Surveyor No. 4717

0 30' 60'

GRAPHIC SCALE IN FEET

DRAWING SCALE: 1" = 30'



Baird, Hampton & Brown, Inc.  
Engineering & Surveying

309 W 7th St, Ste 500 Ft Worth, TX 76102 Tel (817)338-1277 Fax (817)338-9245 E-Mail mail@bhbinc.com

DRAWN BY: JPW

CHECKED BY: BHB

BHB PROJECT 2002 300 027

DATE April 23, 2002

**FINAL PAGE**

**ADMINISTRATIVE RECORD**

**FINAL PAGE**